

CHANGE }

No. 1 }

HEADQUARTERS
DEPARTMENT OF THE ARMY
WASHINGTON, DC, 8 January 1982

**Organizational Maintenance Manual
CRANE-SHOVEL, TRUCK MOUNTED; 3/4 CUBIC YARD;
20 TON; WITH CLAMSHELL, DRAGLINE, AND BACKHOE
ATTACHMENTS; G.E.D. (HARNISCHFEGER CORP MODEL M320T2)
NSN 3810-00-151-4431**

TM 5-3810-294-20, 5 April 1974, is changed as follows:

Page iv, following number 2-72 add the following:

2-72.1 Air cleaner service 2-84.

Page v, following number 2-105 add the following:

2-105.1 Adjusting front and rear drum brakes. 2-110.

2-105.2 Location of chains and chain shafts . . 2-110.

Page 1-1.

Paragraph 1-4 line 1. Change "TM 7480-90-1" to "TM 740-90-1".

Paragraph 1-5 is superseded as follows.

1-5. Reporting Errors and Recommending Improvements

You can help improve this manual. If you find any mistakes or if you know of a way to improve the procedures, please let us know. Mail your letter or DA 2028 (Recommended Changes to Publications and Blank Forms) direct to: Commander, US Army Tank-

Automotive Command, ATTN: DRSTA-MBP, Warren, MI 48090. A reply will be furnished to you.

Page 2-3, paragraph 2-4e(3). Following subparagraph (3) add.

CAUTION

When reeving a three or more part line, position the cable outside the boom point cable guards. This will prevent the cable dragging on the inside rear of the guards.

Page 2-25, paragraph 2-10a. Warning is superseded as follows.

WARNING

Do not transport crane with the clamshell bucket, the dragline attachments, or the piledriver front end installed.

Page 2-26, Section V is superseded as follows.




FIG 3





FIG 4



Distorted Cross-Sections of Beams under Flexure.

Drawn by G Baker after Saint Venant

Table 2.1. Organizational Preventive Maintenance Checks and Services (CRANE)

Item No.	Interval						ITEM TO BE INSPECTED Procedure
	Q-Quarterly S-Semiannually		A-Annually B-Biennially		H-Hours MI-Miles		
							<p>NOTE</p> <p>PERFORM OPERATOR/CREW PMCS PRIOR TO OR IN CONJUNCTION WITH ORGANIZATIONAL PMCS.</p>
1	•						<p>FUEL TANK, LINES, AND FITTINGS</p> <p>Inspect lines and fittings for leaks. Tighten loose fittings. Replace damaged lines or fittings (para 2-79).</p>
2	•						<p>RADIATOR</p> <p>Tighten mounting clamps and connections if necessary, making sure no leaks are apparent. The correct cap pressure rating is 4 psi. Replace cracked or damaged hose. Replace a leaking or faulty radiator (para 2-74).</p>
3	•						<p>V-BELTS</p> <p>Inspect for worn, frayed, or cracked belts. Adjust as required (fig. 2-85).</p>
4	•						<p>BATTERIES</p> <p>Check electrolyte level and specific gravity (1.285-1.300) using hydrometer. Check tightness of connections. Fill to 3/8-inch above the plates. In freezing weather, run engine for 30 minutes after adding water. Clean vent hole in filler caps before installing (para 2-53).</p>
5	•						<p>HOOK ROLLERS</p> <p>Inspect hook rollers for wear and proper adjustment. Maximum allowable clearance between rollers and lower side of roller path is 1/16-inch. Replace severely worn rollers (para 2-111).</p>
6	•						<p>GANTRY</p> <p>Inspect for cracks, worn sheaves, and improper lubrication (para 2-65).</p>
7	•						<p>BOOM AND/OR JIB</p> <p>Inspect visually for damage, including cracks, breaks, and general condition. Repair or replace damaged boom or jib sections (para 2-37).</p>
8	•						<p>REAR DRUM DRIVE CHAIN, REVERSING CHAIN, SHOVEL CROWD CHAIN, AND HORIZONTAL SWING SHAFT CHAIN</p> <p>Inspect for wear. Replace chain if worn excessively (para 2-110).</p>
9	•						<p>LIGHTS</p> <p>Inspect lights for loose cables, mountings, cracked lens, and proper operation. Repair or replace defective lamps or bulbs (para 2-51).</p>
10	•						<p>ENGINE CLUTCH</p> <p>Inspect and adjust if necessary (para 2-101).</p>
11	•						<p>FRONT DRUM CLUTCH</p> <p>Check operation; adjust if necessary. Check lining thickness; if band is worn to within 1/16-inch of rivet heads at point of most wear, install new band (para 2-106).</p>
12	•						<p>FRONT DRUM BRAKE</p> <p>Check operation; adjust if necessary. If band is worn to within 1/16-inch of rivet heads at point of most wear, install new band (para 2-106).</p>
13	•						<p>REAR DRUM CLUTCH</p> <p>Check operation; adjust if necessary. If band is worn to within 1/16-inch of rivet heads at point of most wear, install new band (para 2-105).</p>
14	•						<p>REAR DRUM BRAKE</p> <p>Check operation; adjust if necessary. If band is worn to within 1/16-inch of rivet heads at point of most wear, install new band (para 2-105).</p>
15	•						<p>BOOM HOIST CLUTCH</p> <p>Check operation; adjust if necessary. If band is worn to within 1/16-inch of rivet heads at point of most wear, install new band (para 2-108).</p>
16	•						<p>BOOM HOIST BRAKE</p> <p>Check operation; adjust as necessary (para 2-112).</p>

Page 2-84, paragraph 2-78.

Subparagraph *b* is superseded as follows.

b. Removal. Refer to figure 2-72 and remove the air cleaner.

Subparagraphs *c* and *d* are added as follows.

c. Service. Refer to figure 2-72.1 and service the air cleaner.

d. Replacement. Refer to figure 2-72 and replace the air cleaner.

620.1123
163
v. 2 p. 1

Cambridge :

PRINTED BY C. J. CLAY, M.A. AND SONS,
AT THE UNIVERSITY PRESS.

Figures 2-105.1 and 2-105.2 are added as follows.




Figure 2-105.1. Adjusting front and rear drum brakes.

Man hat aber erst angefangen die Gesetze der Elasticität in ihrem ganzen Umfange zu studiren; bei jedem Schritte stösst man in diesen Untersuchungen auf neue Eigenschaften der elastischen Körper; je weiter man vorgeht desto mehr Verwickelung. Bei solchen Umständen ist wohl in diesem Augenblick keine völlig abgeschlossene Arbeit über irgend eine Eigenschaft der elastischen Körper möglich.

Kupffer.


I cannot doubt but that these things, which now seem to us so mysterious, will be no mysteries at all; that the scales will fall from our eyes; that we shall learn to look on things in a different way—when that which is now a difficulty will be the only common-sense and intelligible way of looking at the subject.

Lord Kelvin.

Works of this nature form, as it were, the principal fund of the science property of mankind, the *interest* of which we may turn to further profit. We might compare them to a capital invested in land. Like the soil, of which landed property consists, the knowledge stored up in these catalogues, lexicons, etc., may have but slender attractions for the vulgar, the man unacquainted with the subject can have no idea of the labour and cost at which the soil has been prepared; the work of the husbandman appears to him terribly toilsome, tedious and clumsy. But although the work of the lexicographer and physical science cataloguer calls for the same painful and persevering industry as the labour of the husbandman, we must not therefore hastily assume that the work itself is of an inferior character, or that it is as dry and mechanical as it at first appears when we have the catalogue or lexicon ready printed before us. For it is necessary in such compilations that all the isolated facts should be selected by careful observation, and afterwards tested and compared with one another, the essential sifted from the unessential,—and all this it is plain, he only can efficiently accomplish who has clearly conceived the end and aim of his work, and the scope and method of the branch of science which it concerns; but for such an one each minute detail will have its own peculiar interest from its position in relation to the whole science of which it is a part. Were it not so, such work would indeed be the worst kind of mental drudgery it were possible to conceive.

von Helmholtz.

- STEP 1. LOOSEN LOCKNUTS (4) WHICH SECURE ADJUSTING BOLTS (4).
- STEP 2. TURN ADJUSTING BOLTS OUT OF CONTACT WITH CLUTCH BANDS. CLUTCH BANDS MUST BE CENTERED IN CLUTCH DRUM. USE ADJUSTING BOLTS (4) AND A FEELER GAGE TO CENTER CLUTCH. BANDS. TIGHTEN LOCKNUTS.
- STEP 3. LOOSEN LOCKNUT ON CYLINDER ROD.
- STEP 4. TURN CYLINDER ROD OUT UNTIL A PULL OF 15 TO 20 POUNDS ON A SPRING SCALE IS NEED TO ENGAGE THE CLUTCH. TIGHTEN LOCKNUT.



NOTE: ONLY STEPS 3 AND 4 ABOVE ARE NECESSARY TO ADJUST FOR LINING WEAR. USE COMPLETE PROCEDURE ONLY WHEN CLUTCH HAS BEEN REMOVED AND REPLACED. TA072310

Figure 2-107. Adjusting front and rear drum clutch.

said that without a thorough study of their writings, it is impossible to be an accomplished elastician, or to follow without great difficulty the drift of modern elastical research. Their memoirs and treatises form the frame, which the Editor had hoped he might be able to fill up by briefer accounts of the discoveries due to, perhaps, less distinguished but none the less useful workers in the same field. This process of filling up is only completed for the years 1850-60, but the Editor ventures to think that the reader of his Chapter XI. will be surprised at the wealth of material, theoretical, technical and physical, which was brought to light in that decade. Many facts have been discovered, more, perhaps, rediscovered since 1860, but till the last few years it may be doubted whether any period has been more fruitful of genuine progress in the science of elasticity than these ten years.

The number of the memoirs included in this volume by no means measures the work of preparation it has involved. The study and analysis of many memoirs not included in its contents had to be undertaken. But the chief task has been the verification of the analysis of all the more important mathematical memoirs. In some cases the whole of this analysis has been *novο*, occasionally with different results. As ^{proofs} of this I may cite Resal's researches on the figure of earth, the whole of Winkler's work on the strained form of links of chains, and Lord Kelvin's analysis of the strains produced by the tides in an elastic earth. In all the work of verification, not only of others' analysis but of my own, I have had the most self-sacrificing and devoted assistance from Mr. C. Chree of King's College, Cambridge. Without his aid not only would this volume have been much longer delayed, but I veritably shudder to think of the blunders which would certainly have escaped my unaided revision. My thanks are due to him, not as to a mere friendly proof-reader, but as to one whose cooperation in the task of editing has given the volume the major portion of any freedom from error it may possess. I trust that many serious

- STEP 1. LOOSEN LOCKNUTS WHICH SECURE ADJUSTING BOLTS.
- STEP 2. TURN ADJUSTING BOLTS OUT OF CONTACT WITH CLUTCH BAND. CLUTCH BAND MUST BE CENTERED IN CLUTCH DRUMS. USE ADJUSTING BOLTS AND A FEELER GAGE TO CENTER CLUTCH BAND. TIGHTEN LOCKNUTS.
- STEP 3. LOOSEN LOCKNUT ON CYLINDER ROD.
- STEP 4. TURN CYLINDER ROD OUT UNTIL A PULL OF 15 TO 20 POUNDS ON A SPRING SCALE IS NEEDED TO ENGAGE THE CLUTCH. TIGHTEN LOCKNUT ON CYLINDER ROD.

NOTE: ONLY STEPS 3 AND 4 ABOVE ARE NECESSARY TO ADJUST FOR LINING WEAR. USE COMPLETE PROCEDURE ONLY WHEN CLUTCH HAS BEEN REMOVED AND REPLACED.




Figure 2-115. Adjusting boom hoist clutch.

Clebsch's *Treatise*—arises chiefly from two causes. In the first place Dr Todhunter omitted all memoirs dealing with the physical or technical branches of our subject, and more than a third of the present volume will be found to deal with physical or technical problems. In the second place a still larger portion of the work falls beyond the period to which Dr Todhunter had carried his researches. On this point I may, perhaps, be permitted to refer to the remarks I have made in the preface to *The Elastical Researches of Barré de Saint-Venant*, and content myself here with citing from them the following words :

...it has seemed to me that the best memorial to the first Cambridge historian of mathematics would be that the last history bearing his name should have the widest possible sphere of usefulness. That usefulness will, I am firmly convinced, be best obtained by its comprehensive character, by its attempt to be a *Repertorium* of elasticity rather than an *Historique Abrégé* of its purely mathematical side.

For the Index to the present volume I alone am responsible. In a work of this comprehensive character a complete and systematic index is a first necessity. To prepare it is a duty which experience has taught me no one can fulfil so efficiently as the writer of a book.

Lastly, I have to express the great sense of the indebtedness I feel to the Syndics of the University Press for the patience with which they have submitted to the delay in the publication of this History, and the kindness with which they have permitted these volumes to grow so much beyond my original estimate. Should the reader complain that the work after all remains a fragment, then the blame must fall on the shoulders of the Editor, who much underestimated the extent of his material and overestimated his own powers, when he reported to the Syndics nine years ago on the original manuscript.

KARL PEARSON.

UNIVERSITY COLLEGE, LONDON.

June 7, 1893.

Table 4-1. Organizational Preventive Maintenance Checks and Services (CARRIER)

Item No.	Interval						ITEM TO BE INSPECTED Procedure
	Q	S	A	B	H	MI	
							<p>NOTE</p> <p>PERFORM OPERATOR/CREW PMCS PRIOR TO OR IN CONJUNCTION WITH ORGANIZATIONAL PMCS.</p>
1	•						<p>TRANSMISSION AIR FILTER</p> <p>Monthly, remove drain plug and blow out accumulated sediment. Quarterly, or each 400 operating hours, replace the element.</p>
2	•						<p>FUEL LINES AND FITTINGS</p> <p>Inspect fuel lines for leaks and tighten loose connections. Replace defective lines and fittings (para 4-39).</p>
3	•						<p>RADIATOR</p> <p>Fill to 3/4-inch above baffle plate. Replace cracked or worn hose. Tighten all mounting clamps and connections (fig. 4-12 and 4-13).</p>
4	•						<p>ENGINE DRIVE BELTS</p> <p>Adjust as required. Replace worn or frayed belts (para 4-47).</p>
5	•						<p>BATTERIES</p> <p>Check electrolyte level and specific gravity (1.285-1.300) using hydrometer, and check tightness of connections. Fill to 3/8-inch (approx) above the plates. In freezing weather, run the engine for 30 minutes after adding water. Clean vent hole in filler caps before installing caps. Replace a cracked or leaking battery (para 4-26).</p>
6	•						<p>SERVICE BRAKES</p> <p>Remove wheel. Inspect brake lining and replace brake shoes if lining is within 1/16-inch of rivets (para 4-80).</p>
7		•					<p>ENGINE CLUTCH</p> <p>Adjust if necessary (para 4-67).</p>
8	•						<p>LIGHTS</p> <p>Inspect lights for loose cables mountings, cracked lens, and proper operation. Repair or replace defective lamps or bulbs.</p>

Page 4-18. Following paragraph 4-38b(2). Add the following:

b.1. Refer to paragraph 2-78 for servicing of air cleaner.

Page A-1.

Paragraph A-5. Change "TM 9-1870-1" to "TM 9-2610-200-20".

Paragraph A-6. Change "TB 740-93-2" to "TB 740-97-2" and "TB 740-93-1" to "TM 740-90-1".

Page B-11, group 3101, column (3)H. Change "F" to "O".

Page B-21.

Group 3201, column (3)A. Add "O" to indicate maintenance function and "1.5" to indicate time standard.

Group 3202.

Column (3)A. Add "O" to indicate maintenance function and "1.5" to indicate time standard.

Column (3)H. Change "F" to "O".

TECHNICAL MANUAL }
 No. 5-3810-294-20 }

HEADQUARTERS
 DEPARTMENT OF THE ARMY
 WASHINGTON, D. C., 5 April 1974

ORGANIZATIONAL MAINTENANCE MANUAL

CRANE-SHOVEL, TRUCK MOUNTED; 3/4 CUBIC YARDS;

20 TON; WITH CLAMSHELL, DRAGLINE AND BACKHOE

ATTACHMENTS; G.E.D. (HARNISCHFEGER CORP MODEL

M320T2)

(HARNISCHFEGER CORP MODEL M320T2)

FSN 3810-151-4431

	Paragraph	Page
PART ONE. CRANE (REVOLVING FRAME)		
CHAPTER 1. INTRODUCTION		
Section I. General	1-1	1-1
II. Description and data	1-6	1-1
CHAPTER 2. ORGANIZATIONAL MAINTENANCE INSTRUCTIONS		
Section I. Service upon receipt of material	2-1	2-1
II. Movement to a new worksite	2-10	2-25
III. Repair parts, special tools, and equipment	2-12	2-25
IV. Lubrication instructions	2-15	2-25
V. Preventive maintenance checks and services	2-17	2-26
VI. Troubleshooting	2-19	2-27
VII. Radio interference suppression	2-21	2-30
VIII. Maintenance of shovel front attachment	2-25	2-31
IX. Maintenance of backhoe attachment	2-31	2-40
X. Maintenance of piledriver attachment	2-34	2-41
XI. Maintenance of crane, dragline, and clamshell attachments	2-36	2-41
XII. Maintenance of hull wiring harness	2-49	2-41
XIII. Maintenance of lights, batteries, and miscellaneous items	2-51	2-41
XIV. Maintenance of instrument control assembly	2-54	2-51
XV. Maintenance of horn, wiring, and tachometer gage	2-56	2-55
XVI. Maintenance of exhaust muffler and pipes	2-59	2-55
XVII. Maintenance of cab assembly	2-61	2-56
XVIII. Maintenance of gantry assembly	2-64	2-59
XIX. Maintenance of accessory items	2-66	2-60
XX. Maintenance of hydraulic system	2-69	2-62
XXI. Maintenance of engine cooling system	2-73	2-69
XXII. Maintenance of engine transmission assembly and propeller shaft	2-75	2-82
XXIII. Maintenance of engine fuel system	2-77	2-84
XXIV. Maintenance of engine cooling system accessories	2-85	2-92
XXV. Maintenance of engine electrical system	2-87	2-94
XXVI. Maintenance of engine assembly and mechanical accessories	2-94	2-102
XXVII. Maintenance of crane-shovel and earth working equipment	2-102	2-109
XXVIII. Maintenance of counterweight	2-115	2-137
XXIX. Maintenance of miscellaneous items	2-117	2-138

ERRATA.

PART I.

- p. 3, l. 5, from bottom *dele* reference to Hopkins.
- p. 26, l. 7, from top *for* $M = .843462\mu\tau\omega^2b^2/3$ *read* $M = .843462\mu\tau\omega 2b^2/3$.
- p. 68, l. 2, from top *for* ω on left-hand side of equation *read* w .
- p. 79, l. 19, *for* $a_r = du/dr$ *read* $u_r = du/dr$.
- „ footnote *for* co-latitude *read* latitude.
- „ „ „ in first body-stress equation of sphere *read* $2\hat{r}$ *for* $2r$.
- p. 113, l. 13, *for* neutral line *read* neutral axis.
- p. 114, l. 4 of footnote, *for* central axis *read* central line.
- p. 125, l. 2, *for* S_0/G *read* S_0/μ .
- p. 244, *add* to footnote: see, however, our Art. 410.
- pp. 379-81. Phillips's analysis for the case of a doubly built-in girder has been shown by Bresse and Saint-Venant to be in error: see our Arts. 382 and 540. ll. 3 and 4, p. 380, and the footnote p. 381, must be modified in this sense. Arts. 552-4 were written at a very different date to Arts. 381 and 540, and the facts stated in the latter had escaped me.

LIST OF ILLUSTRATIONS

Part One—Crane (Revolving Frame)

Number	Title	Page
1-1	Truck-mounted crane, model 320T2, with crane attachment, front three-quarter view, and shipping dimensions	1-2
1-2	Truck-mounted crane, model M320T2, with crane, attachment, rear three-quarter view	1-3
1-3	Crane engine	1-5
1-4	Crane (revolving frame) wiring diagram	1-6
2-1	Separately packed components	2-2
2-2	Alternator and water pump belt tension adjustment	2-3
2-3	Cribbing prepared for boom assembly and installation	2-4
2-4	Connecting boom sections	2-4
2-5	Installing boom foot pins	2-5
2-6	Boom backstop installation (sheet 1 of 2)	2-5
2-6	Boom backstop installation (sheet 2 of 2)	2-5
2-7	Crane boom angle indicator installation	2-5
2-8	Guy cables, installation (sheet 1 of 2)	2-6
2-8	Guy cables, installation (sheet 2 of 2)	2-6
2-9	Boom hoist line reeving	2-7
2-10	Securing cable to drum	2-8
2-11	Main hoist line reeving	2-9
2-12	Tagline winder installation	2-10
2-13	Fairlead installation	2-11
2-14	Dragline reeving diagram	2-12
2-15	Assembling piledriver lead sections	2-13
2-16	Piledriver lead and adapter installation	2-14
2-17	Piledriver reeving diagram	2-15
2-18	Cribbing prepared for backhoe boom assembly, installation and removal	2-15
2-19	Backhoe auxiliary gantry suspension reeving	2-16
2-20	Backhoe digging cable reeving	2-17
2-21	Backhoe hoist cable reeving	2-18
2-22	Shovel drum lagging	2-19
2-23	Installation crowd sprocket lagging	2-20
2-24	Crowd chain tightener	2-21
2-25	Cribbing shovel boom assembly	2-22
2-26	Shovel boom installation	2-22
2-27	Crowd and retract cable reeving	2-23
2-28	Digging hoist cable reeving	2-24
2-29	Boom hoist cable reeving	2-25
2-30	Dipper trip cable reeving	2-30
2-31	Radio interference suppression resistor and capacitor removal and replacement	2-32
2-32	Adjusting saddle block	2-33
2-33	Rake angle and retract cable adjustment	2-34
2-34	Dipper trip cable adjustment	2-35
2-35	Dipper latch bar adjustment	2-36
2-36	Crowd chain idler sprocket	2-36
2-37	Crowd chain direction and travel viewed from above while entering drive sprocket in crowd out direction	2-37
2-38	Chain repair and replacement	2-38
2-39	Dipper trip wiring diagram	2-39
2-40	Dipper trip magneto switch removal	2-40
2-41	Shovel dipper removal and installation	2-41
2-42	Dipper teeth removal and replacement	2-42
2-43	Cable roller and boom point sheaves service	2-43
2-44	Cable guide rollers removal	2-43
2-45	Hook block	2-44
2-46	Bridle assembly, replace and repair	2-46
2-47	Jib and jib strut removal and replacement	2-47
2-48	Boom hoist cable lower spreader connection removal and replacement	2-47

Le travail dont nous venons de rendre compte, mérite des éloges à plus d'un titre: par les nombres et les résultats nouveaux qu'il offre aux arts industriels, il constate, une fois de plus, l'importance de la théorie de l'équilibre d'élasticité; par l'emploi de la méthode mixte, il indique comment les ingénieurs, qui veulent s'appuyer sur cette théorie, peuvent utiliser tous les procédés actuellement connus de l'analyse mathématique; par ses tables, ses épures, et ses modèles en relief¹, il donne la marche qu'il faut nécessairement suivre, dans ce genre de recherches, pour arriver à des résultats immédiatement applicables à la pratique; enfin, par la variété de ses points de vue, il offre un nouvel exemple de ce que peut faire la science du géomètre, unie à celle de l'ingénieur. (p. 988.)

The report gives a succinct account of the memoir. A second account by Saint-Venant himself will be found in: *Notice sur les travaux et titres scientifiques de M. de Saint-Venant*, Paris, 1858, pp. 19—31, and 71—80. This work together with one of the same title published in 1864, when Saint-Venant was again a candidate for the *Institut*, gives an excellent *résumé* of our author's researches previous to 1864. We shall refer to them briefly as *Notice I.* and *Notice II.*

[2.] The memoir itself is principally occupied with the torsion of *prisms*, a great variety of cross-sections being dealt with. This particular problem in torsion has been termed by Clebsch: *Das St. Venantsche Problem* (*Theorie der Elasticität*, S. 74), and in him we shall term it *Saint-Venant's Problem*. The memoir consists of thirteen chapters.

3. The first chapter occupies pp. 233—236; and gives an introductory sketch of the contents of the memoir. If the values of the shifts of the several points of an elastic body are given the stresses can be easily found by simple differentiation. But the inverse problem—to find the shifts when the stresses are given—has not been generally solved, because we do not yet know how to integrate the differential equations which present themselves. Saint-Venant accordingly proposes the adoption of a *mixed method* (*méthode mixte ou semi-inverse*), which consists in assuming a part of the shifts and a part of the stresses, and then determining by an exact analysis what the remaining shifts and the remaining

¹ Copies of these numerous models are at present deposited in the mathematical model cases at University College. They represent much better than the poor woodcuts of the original memoir the distortion of the various cross-sections.

Number	Title	Page
2-100	Full flow oil filter	2-106
2-101	Oil cooler and external oil lines, removal and replacement	2-107
2-102	Intake and exhaust manifolds, removal and replacement	2-108
2-103	Engine clutch adjustment	2-109
2-104	Not used	
2-105	Chain case	2-110
2-106	Control identification (sheet 1 of 2)	2-112
2-106	Control identification (sheet 2 of 2)	2-113
2-107	Adjusting front and rear drum clutch	2-114
2-108	Rear drumshaft brake band removal and replacement	2-115
2-109	Rear drumshaft clutch band removal and replacement	2-116
2-110	Adjusting reversing shaft clutch or horizontal swing shaft clutch	2-117
2-111	Reversing shift clutch or horizontal swing shaft clutch, removal or replacement	2-118
2-112	Boom hoist brake adjustment	2-119
2-113	Boom hoist clutch removal and replacement	2-120
2-114	Boom hoist brake band removal and replacement	2-122
2-115	Adjusting boom hoist clutch	2-124
2-116	Swing brake shoes, removal and replacement	2-125
2-117	Swing brake adjustment	2-126
2-118	Reversing shift chain, removal and replacement	2-127
2-119	Rear drum chain case removal and replacement	2-128
2-120	Rear drum drive chain removal and replacement	2-129
2-121	Horizontal swing shaft chain removal and replacement	2-130
2-122	Hook roller removal and replacement	2-131
2-123	Hook roller adjustment	2-132
2-124	Swing lock assembly adjustment, removal, and replacement	2-133
2-125	Boom hoist planetary pawls	2-134
2-126	Boom hoist drum, rear drum, and front drum safety pawl adjustment	2-135
2-127	Toggle linkage adjustment	2-136
2-128	Adjusting front and rear drum brake pedal return spring tension	2-137
2-129	Counterweight removal and replacement	2-138

Part Two—Carrier

3-1	Carrier engine	3-2
3-2	Carrier hydraulic steering system	3-3
3-3	Carrier air brake system	3-4
3-4	Carrier wiring diagram (sheet 1 of 2)	3-6
3-4	Carrier wiring diagram (sheet 2 of 2)	3-7
4-1	Radio interference suppression resistor and capacitor, removal and replacement	4-6
4-2	Engine control panel removal and replacement	4-8
4-3	Trailer coupling removal and replacement	4-10
4-4	Oil temperature sender removal and replacement	4-10
4-5	Water temperature sender, removal and replacement	4-10
4-6	Oil pressure sender removal and replacement	4-10
4-7	Horn button removal and replacement	4-11
4-8	Seat installation	4-12
4-9	Carrier cab assembly, exploded view	4-13
4-10	Engine hood assembly removal and replacement	4-14
4-11	Windshield wiper motor removal and replacement (sheet 1 of 2)	4-15
4-11	Windshield wiper motor removal and replacement (sheet 2 of 2)	4-16
4-12	Radiator removal and replacement	4-17
4-13	Thermostat housings, removal and replacement	4-17
4-14	Thermostat removal and replacement	4-18
4-15	Engine air cleaner, removal and replacement	4-19
4-16	Fuel tank removal and replacement	4-20
4-17	Fuel lines and fittings replacement and repair	4-21
4-18	Carburetor adjustment removal and replacement	4-21
4-19	Fuel filter service and fuel pump removal and replacement	4-22
4-20	Acceleration and throttle control, removal, replacement, and repair	4-23
4-21	Exhaust pipes and muffler removal and replacement	4-24
4-22	Engine belt and pulley arrangement, removal and replacement	4-25

Finally the strain is expressed for *small* shifts in terms of the shift-fluxions (pp. 246—8). There is reference in a footnote to the strain-values for *large* shifts (see our Art. 1618*).

(ε) We next pass to an analysis of stress on pp. 248—254. Stress is defined from the molecular standpoint as follows :

Nous appellerons donc en général *Pression*, sur un des deux côtés d'une petite face plane imaginée à l'intérieur d'un corps ou à la limite de séparation de deux corps, la résultante de toutes les actions des molécules situées de ce côté sur les molécules du côté opposé, et dont les directions traversent cette face ; toutes ces forces étant supposées transportées parallèlement à elles-mêmes sur un même point pour les composer ensemble. (p. 248.)

The reader will find it interesting to follow the evolution of the stress-definition by comparing this with Arts. 426*, 440*, 546*, 616*, 678—9* and 1563*.

From this definition Saint-Venant deduces Cauchy's theorems (see our Arts. 606* and 610*) and an expression for \overline{rr} . On p. 253 p_{rr} is erroneously printed for p_{rr} .

In a footnote to p. 254 a generalisation of the expression for \overline{rr} is obtained. Suppose x, y, z to be any three concurrent but non-rectangular lines, and let x', y', z' be lines normal respectively to the planes yz, zx, xy . Then in our notation :

$$\begin{aligned}\overline{rr} = & \frac{\cos rx'}{\cos xx'} \left(\widehat{xx} \frac{\cos r'x'}{\cos xx'} + \widehat{xy} \frac{\cos r'y'}{\cos yy'} + \widehat{xz} \frac{\cos r'z'}{\cos zz'} \right) \\ & + \frac{\cos ry'}{\cos yy'} \left(\widehat{yx} \frac{\cos r'x'}{\cos xx'} + \widehat{yy} \frac{\cos r'y'}{\cos yy'} + \widehat{yz} \frac{\cos r'z'}{\cos zz'} \right) \\ & + \frac{\cos rz'}{\cos zz'} \left(\widehat{zx} \frac{\cos r'x'}{\cos xx'} + \widehat{zy} \frac{\cos r'y'}{\cos yy'} + \widehat{zz} \frac{\cos r'z'}{\cos zz'} \right).\end{aligned}$$

The proof is easily obtained by the orthogonal projection of areas.

(ζ) Saint-Venant next proceeds to express the relations between stress and strain (pp. 255—262). It cannot be said that this portion of his work is so satisfactory as the later treatment in Moigno's *Statique* (see p. 268 *et seq.*) or the full discussion of the generalised Hooke's Law in his edition of *Clebsch* (pp. 39—41). In fact the linearity of the stress-strain relations is obtained in the text by assumption. *Admettons donc avec tout le monde que les pressions sont fonctions linéaires des dilatations et des glissements tant qu'ils sont très-petits* (p. 257). A long footnote (pp. 257—261) treats the matter from the standpoint of central intermolecular action. Appeal is made to Cauchy (*Exercices de mathématiques* t. iv. p. 2: see our Art. 656*) for the reduction of the 36 coefficients to 15. Saint-Venant, however,—consistent rari-constant elastician as he has always been—retains the multi-constant formulæ, remarking :

PART ONE CRANE (REVOLVING FRAME)

CHAPTER 1 INTRODUCTION

Section I. GENERAL

1-1. Scope

a. This manual contains instructions for the use of personnel to whom the Model M320T2 Truck-Mounted Crane is issued. It provides information on the maintenance services allocated to Organizational Maintenance by the Maintenance Allocation Chart (MAC).

b. This manual is divided into two parts. Part One primarily concerns maintenance of the crane (revolving frame) portion of the truck-mounted crane. Maintenance personnel should read the instructions provided in both parts of this manual before operating or servicing the equipment.

c. Numbers in parentheses on illustrations indicate quantity. Numbers preceding nomenclature callouts on illustrations indicate the preferred maintenance sequence.

1-2. Maintenance Forms and Records

Maintenance forms and records that you are required to use are explained in TM 38-750.

1-3. Destruction of Army Material to Prevent Enemy Use

Refer to TM 750-244-3 for procedures for destruction of equipment to prevent enemy use.

1-4. Administrative Storage

Refer to TM 7480-90-1 for information concerning administrative storage.

1-5. Reporting of Errors

You can improve this manual by calling attention to errors and by recommending improvements, using DA Form 2028 (Recommended Changes to Publications) or by letter, and mail directly to Commander, U.S. Army Mobility Equipment Command, ATTN: AMSME-MPP, 4300 Goodfellow Boulevard, St. Louis, Missouri, 63120. A reply will be furnished direct to you.

Section II. DESCRIPTION AND DATA

1-6. Description

A general description of the truck-mounted crane (figs. 1-1 and 1-2) and of its identification plates are in TM 5-3810-294-10. A more detailed description of specific components and assemblies is contained in the applicable sections of this manual. Detailed descriptions of the components of the truck-mounted crane are provided in the applicable maintenance paragraphs of this manual.

1-7. Identification and Tabulated Data

a. *Identification Plates.* Refer to TM 5-3810-294-10.

b. Tabulated Data.

(1) Crane

Manufacturer ----- Harnischfeger Corporation
Model ----- M320T2

(2) Crane engine (fig. 1-3)

Manufacturer ----- International Harvester
Company
Model ----- U-450
Ignition timing ----- Top dead center
Number of cylinders ----- 6
Horsepower ----- 92.5 net hp at 1800 rpm full
load
Intake valve tappet
clearance (hot) ----- 0.024-to-0.026 inch
Exhaust valve tappet
clearance (hot) ----- 0.024-to-0.026 inch
Displacement ----- 450.9 cubic inches

Substitute from (iii) in (i) and then the values so deduced in (ii). We obtain

$$\left. \begin{aligned} \widehat{xy} &= \left(\frac{f+e}{2} + \frac{f-e}{2} \cos 2\beta + h \sin 2\beta \right) \sigma_{xy'} \\ &\quad + \left(-\frac{f-e}{2} \sin 2\beta + h \cos 2\beta \right) \sigma_{xz'} \\ \widehat{xz} &= \left(\frac{f+e}{2} - \frac{f-e}{2} \cos 2\beta - h \sin 2\beta \right) \sigma_{xz'} \\ &\quad + \left(-\frac{f-e}{2} \sin 2\beta + h \cos 2\beta \right) \sigma_{xy'} \end{aligned} \right\} \dots\dots (iv).$$

Obviously, if we take $\tan 2\beta = \frac{2h}{f-e}$ we reduce this last pair of equations to

$$\left. \begin{aligned} \widehat{xy} &= f_1 \sigma_{xy'} \\ \widehat{xz} &= e_1 \sigma_{xz'} \end{aligned} \right\} \dots\dots\dots (v),$$

where f_1 and e_1 are roots of the quadratic $\mu^2 - (f+e)\mu + fe - h^2 = 0$.

Such is substantially Saint-Venant's reduction. It is obvious, however, that this result follows at once when a known problem as to the invariants of a conic is applied to the work-function.

(i) A remark as to isotropy on p. 272 may be reproduced as bearing on the uni-constant controversy:

Mais l'isotropie paraît rare. Non-seulement les corps fibreux, tels que bois, les fers étirés ou forgés, mais même les corps grenus ou vitreux, refroidis de la surface au centre après leur fusion, peuvent présenter des élasticités différentes en divers sens.

Saint-Venant refers to the experiments and remarks of Regnault, Savart and Poncelet already noted in our first volume: see Arts. 332*, 978* and 1227*.

(κ) On pp. 272—8 we have deductions of the body-stress equations, the body-shift equations and the surface-stress equations.

On p. 276 Saint-Venant deduces the body-shift equation for a planar distribution of elasticity such as he requires for his torsion problem.

He takes for the shears the expressions found in Equation (v) above, and for the traction \widehat{xx} perpendicular to the planar system the expression

$$\widehat{xx} = as_x + bs_y + cs_z + d\sigma_{yz} + e\sigma_{zx} + f\sigma_{xy},$$

with six independent constants. Substituting in the body-stress equation $\frac{d\widehat{xx}}{dx} + \frac{d\widehat{xy}}{dy} + \frac{d\widehat{xz}}{dz} = X$, and expressing the strain in terms of the shift-fluxions, he finds:




Figure 1-2 Truck-mounted crane, Model M320T2, with crane
attachment rear three-quarter view.

slides to be so small that their squares may be neglected. It is conceivable that in some materials before rupture and, possibly, before a dangerous set is reached, this might not be allowable.

(c) Our author begins by noticing that the proper limit to be taken for the stability of a material is a *stretch* and not a *traction* limit. He attributes to Mariotte¹ the first recognition of this fact "que c'est le degré d'extension qui fait rompre les corps" and remarks that although it is legitimate, and occasionally convenient, to take a traction limit given by $T = E\bar{s}$ where \bar{s} is the stretch-limit and E the stretch-modulus, T need not be the stress across any plane, whatever, at the point in question.

Et cette sorte de notation est sans inconvénient si l'on n'oublie pas que T représente simplement le produit $E\bar{s}$, ou la force capable de donner (aussi par unité superficielle) à ce même petit prisme supposé isolé, la dilatation limitée \bar{s} relative à sa situation dans le corps, mais qu'il ne représente que *quelquefois* et non *toujours* l'effort intérieur ou la pression supportée normalement par sa section transversale pendant qu'il fait partie du corps. (p. 280.)

This remark is all the more important as the distinction has been neglected by Lamé, Clebsch and more recent elasticians: see our Arts. 1013*, 1016* footnotes and 1567*.

(d) The stretch in any direction being given by the equation (i) above, we have next to ask what in an aeolotropic body is the distribution of limiting stretch? Saint-Venant having regard to equation (i) assumes it to be *ellipsoidal* in character; in other words he takes

$$\bar{s} = \bar{s}_x \cos^2 \alpha + \bar{s}_y \cos^2 \beta + \bar{s}_z \cos^2 \gamma,$$

where \bar{s}_x , \bar{s}_y , \bar{s}_z are three constants to be determined by experiment, and the axes of ellipsoidal distribution are chosen as those of co-ordinates. The condition of safety now reduces to the maximum value of s/\bar{s} being = or < 1. By the ordinary max.-min. processes of the Differential Calculus we obtain for s/\bar{s} the equation:

$$4\bar{s}_x\bar{s}_y\bar{s}_z\left(\frac{s}{\bar{s}} - \frac{s_x}{\bar{s}_x}\right)\left(\frac{s}{\bar{s}} - \frac{s_y}{\bar{s}_y}\right)\left(\frac{s}{\bar{s}} - \frac{s_z}{\bar{s}_z}\right) - \sigma_{yz}^2\bar{s}_x\left(\frac{s}{\bar{s}} - \frac{s_x}{\bar{s}_x}\right) \\ - \sigma_{zx}^2\bar{s}_y\left(\frac{s}{\bar{s}} - \frac{s_y}{\bar{s}_y}\right) - \sigma_{xy}^2\bar{s}_z\left(\frac{s}{\bar{s}} - \frac{s_z}{\bar{s}_z}\right) - \sigma_{yz}\sigma_{zx}\sigma_{xy} \dots (ii).$$


The roots of this equation are known to be real and we must have the greatest of them = or < 1.

Suppose the material is subject only to a sliding strain, then $s_x = s_y = s_z = \sigma_{zx} = \sigma_{xy} = 0$. Hence it follows that

$$\frac{s}{\bar{s}} = \frac{\sigma_{yz}}{2\sqrt{\bar{s}_y\bar{s}_z}}.$$

In other words if \bar{s} is the limit of s , then $2\sqrt{\bar{s}_y\bar{s}_z}$ is the limit of σ_{yz} , or gives the slide-limit. Let us represent it by $\bar{\sigma}_{yz}$.

¹ *Traité du mouvement des eaux*, sixième et troisième alinéa du second discours.



ME 3810-294-20/1-3

Figure 1-3. Crane engine.

semi-axes. Saint-Venant uses throughout his memoir a slightly different form. Let μ_1, μ_2 be slide-coefficients and S_1, S_2 the shears capable of producing the slides $\bar{\sigma}_{xy}$ and $\bar{\sigma}_{xz}$; then the condition of *non-rupture par glissement* (i.e. of no failure of linear elasticity) is expressed by

$$1 = \text{or} > \left(\frac{\mu_1 \sigma_{xy}}{S_1} \right)^2 + \left(\frac{\mu_2 \sigma_{xz}}{S_2} \right)^2.$$

The chapter concludes with a few general remarks on the physical characteristics of rupture by torsion.

[6.] The third chapter occupies pp. 288—99: it relates to the simple case of a prism on any base, whose terminal faces and sides are subjected to any uniform tractive loads. Lamé and Clapeyron in their memoir of 1828 (see our Art. 1011*) had treated the simple case of isotropy. Saint-Venant as an example of the *mixed* or *semi-inverse* method gives the solution for the case when there are three planes of elastic symmetry, the intersection x of one pair being parallel to the axis of the prism. He assumes that the tractions are constant and the shears zero throughout. This satisfies the body stress-equations; the constant values of the tractions are in this case given by the surface stress-equations. The stress-strain relations then give in terms of the elastic constants and the loads the values of the shift-fluxions. We thus arrive at a system of simple linear partial differential equations, whose solution is extremely easy. The complete solution gives for each shift a part proportional to the corresponding coordinate and a general integral which is only the resolved part of the most general displacement of the prism treated as a rigid body. On p. 292 Saint-Venant determines the value of the stretch-modulus when the tractive load on the sides of the prism is zero, and on p. 293 he considers the simple cases of (1) the axis of the prism being an axis of elastic symmetry, and (2) the material being isotropic: see our Art. 1066*. On p. 293 we have a remark that some writers have doubted the exactness of the above results, considering them only as plausible but not necessarily unique. Saint-Venant asserts that they are unique, which is undoubtedly true in this case, but I am not quite satisfied with the nature of his proof, for it would at first sight apply to any elastic body. It depends essentially on the following line of reasoning: Take any particular integrals of the equations of elasticity u_0, v_0, w_0 , put the shifts equal

CHAPTER 2

MAINTENANCE INSTRUCTIONS

Section I. SERVICE UPON RECEIPT OF MATERIAL

I. Inspecting and Servicing the Equipment

- a. Remove all exterior material used to protect truck-mounted crane during shipment.
- b. Remove all interior protective materials, including wrapping on the operator's seats, headlights, tail lights, flood lights, and the faces of instruments.
- c. Make a complete visual inspection of the crane and carrier to see that the required publications, tools, accessories, attachments, and repair parts are with the crane and carrier.
- d. Inspect the crane and carrier for missing parts, or damage which may have occurred during loading, shipment, or unloading. Inspect the crane and carrier engines, tires, revolving-frame machinery, glass panels, and instruments for damage.
- e. Inspect all separately packaged components for damage. See figure 2-1.
- f. Inspect carrier brakes and be sure brake shoes do not stick to brake drums.
- g. Replace any missing parts.

NOTE

Make certain that the crane and carrier have been deprocessed completely before servicing.

- h. Drain the engine crankcases and oil filters and refill to the operating level with oil of the type specified in the current lubrication order (LO).
- i. Remove all tape and wrappings from the engine crankcase breathers, intake and exhaust manifolds, crane engine transmission, breather, alternator, and clutches and brakes.
- j. Check the tension on the water pump and alternator drive belts and adjust, if necessary. Refer to figure 2-2.
- k. Check the level of the lubricant in the engine gear and chain housing and add lubricant of the type specified in the current LO, if necessary. Lubricate the reversing shaft drive chain.

l. Remove the tape or plugs from the air brake system safety valve and relay emergency valves. Close air reservoir drain cocks.

m. Remove wrappings from all machined surfaces and clean the surfaces to remove preservative coatings.

NOTE

If the LO specifies OE 10 for operation under prevailing temperature conditions, the preservative oil may be used until the first required oil change.

n. Remove the seals from the crane and carrier battery filler caps. Remove battery material and clean the preservative coating from the terminals. Fill the batteries with the separately packed electrolyte. Check the specific gravity of the electrolyte using a hydrometer. Check to see that all electrical switches are in the OFF position and then connect the battery cables.

o. Lubricate the entire crane in accordance with the current LO.

p. Make a final complete inspection of the entire machine, looking for leaks, loose electrical connections, loose or broken hoses and lines, or any other damage or unsafe condition.

2-2. Installation

a. Refer to TM 5-3810-294-10 for installation or setting-up instructions.

b. The use of separately packaged components illustrated in figure 2-1 is covered in this manual where they would logically be installed or used.

c. Refer to equipment conversion (para 2-3, below) for instructions to install the various working attachments available for use with the truck crane.

2-3. Equipment Conversion

a. The basic crane can be converted to various uses by changing front-end attachments. The converted crane may be referred to as a crane,

très-proches de ceux où agissent les forces (p. 299). We can perhaps, however, reach some conception of the field to which he supposes the influence to extend by paying attention to a footnote on p. 22 of *Notice I*.

Suppose the terminal of a prism subjected to any system of load statically equivalent to that distribution which produces the system of strains theoretically calculated. Impose upon the terminal two equal and opposite loads having the theoretical distribution. One of these will produce the theoretical strains, the other will be in statical equilibrium with the actual load distribution. The terminal is thus acted upon by two equivalent and opposite systems of force. These systems will produce certain small shifts in the end of the prism, and these shifts measure the extent to which the prism is influenced by the difference between the theoretical and practical distributions. Saint-Venant tells us in his footnote that the influence of forces in equilibrium acting on a small portion of a body extend very little beyond the parts upon which they act.

L'auteur a fait deux expériences de ce genre sous les yeux de l'Académie en lisant un de ses mémoires. Elles ont consisté simplement à pincer avec des tenailles un prisme de caoutchouc, et à dilater transversalement une lanière mince de même matière, en tirant ses bords en deux sens opposés. Tout le monde peut les répéter et voir que l'impression ou l'élargissement *ne se fait point sentir à des distances excédant la profondeur dans le premier cas et l'amplitude dans le second*.

The reader will find this matter still further treated of in the *Navier*, pp. 40—41 and the *Clebsch*, pp. 174—7. The principle is of first-class importance, as it is scarcely possible in a practical structure to ensure any given theoretical distribution of load. The terminals will generally take a form which lies beyond theoretical investigation and only the statical equivalent of the load system will be really ascertainable, e.g. the tractive load on a bar may be applied by means of a nut carrying a weight, the nut itself being supported by the thread of a screw cut on the bar.

[9.] Saint-Venant's fourth chapter deals with the problem of flexure by the *semi-inverse* process. The important results here first published were afterwards considered at greater length in the well-known memoir on flexure: see our Art. 69 *et seq.*




Figure 2-2. Alternator and water pump belt tension adjustment.

clamshell, dragline, piledriver, backhoe, or shovel. The various conversions are described in paragraphs 2-4 through 2-9.

b. When a conversion is anticipated, make certain that all required attachments, tools, blocking, a suitable lifting device, and maintenance personnel are available.

c. Before reeving any line, lay out the line so that there is no possibility of kinking during the reeving process. Refer to TM 5-3810-294-10 for information on handling and maintenance of cables.

NOTE

When wrapping new cable on a drum, wrap the cable slowly and make certain that the cable wraps evenly on the drum the first time.

2-4. Crane Conversion

a. *General.* The crane may be converted to crane operation by installing the crane front-end assembly. The following components are necessary for the equipment conversion: one 15-foot boom base section, one 15-foot point section, boom foot pins, boom guy cables, boom hoist

cable, boom backstops, hoist line, and hook block. The basic crane boom may be extended by installing boom inserts between the boom base section and the boom point section. The boom inserts are in 10-foot lengths and must be for the specific boom installed so that the connecting joints of the boom and insert match.

NOTE

Longer guy cables are necessary when the length of the boom is increased. Refer to cable specifications in TM 5-3810-294-10.

b. Boom Installation.

NOTE

To install the boom, a cribbing will be necessary to support the boom in a horizontal position. The cribbing must be high enough to bring the boom into position with the boom foot lugs on the revolving frame as shown in figure 2-3.

(1) Lift boom sections into place on cribbing.

(2) Refer to figure 2-4 and install the boom connection capscrews, lockwashers, and locknuts so that the boom base section, insert

between any two practical cases of flexure. It is just as reasonable or unreasonable to quarrel with Coulomb's torsion solution as with Saint-Venant's flexure results.

[10.] With regard to the uniqueness of the solution obtained by the semi-inverse method—supposing the theoretical shearing and tractive loads were applied to the terminals—Saint-Venant has some remarks on p. 307 which it is well to consider. After remarking that the shifts satisfy all the conditions and equations of the problem, he continues :

Et ils sont les seuls qui y satisfassent, car le problème des déplacements est complètement déterminé si, en donnant les pressions et tractions sur tous les points de la surface, on suppose fixes l'un des points du prisme (le point O), et les directions d'un élément linéaire et d'un élément plan qui y passent (un élément sur l'axe des z et un élément sur le plan yz) en sorte qu'il ne puisse y avoir ni translation ni rotation générale à ajouter aux déplacements provenant de la flexion. (p. 307.)

He then proceeds as on p. 294 to put the shifts equal to the particular solutions found plus additional unknown parts (u', v', w'), these latter he argues must be zero as they are shifts due to a zero system of loading as appears by the vanishing of the load terms from the equations on substitution. This sketch of a proof of the uniqueness of solution of the equations of elasticity has been adopted and expanded by Clebsch: see Kap. I. § 21 of his *Theorie der Elasticität*. I have suggested above that there is need of applying the proof with some caution: see Art. 6.

[11.] In treating the problem of flexure Saint-Venant assumes the longitudinal shifts and the lateral loading, hence he deduces the transverse shifts and the terminal loading. The values of the longitudinal shifts were doubtless suggested by the Bernoulli-Eulerian solution of the problem, but in this chapter they appear to arise very naturally from the consideration of the simpler case of uniform flexure, or the bendings of each longitudinal 'fibre' into a circular arc; see pp. 292—304.

Saint-Venant makes two generalisations of his problem. The first (p. 306) to the case when besides terminal shearing load, there is also terminal tractive load. It is necessary, however, to remark that when such load is negative, and the prism of con-




Figure 2-6. Boom backstop installation.
(Sheet 1 of 2)






Figure 2-6. Boom backstop installation. (Sheet 2 of 2)




Figure 2-8. Guy cables, installation (Sheet 1 of 2).

Then Saint-Venant assumes that $\int xz d\omega = -P$; and this leads to the value of K which he uses in this case: see p. 312 line 3 from the foot.

13. On p. 311 Saint-Venant says that $F = 0$, and $dF/dz = 0$, when $y = 0$ and $z = 0$. Suppose that h and k denote very small quantities; then the value of u at the origin being denoted by u_0 the value at a point very near the origin would be

$$u_0 + \left(\frac{du}{dy}\right)_0 h + \left(\frac{du}{dz}\right)_0 k.$$

Now $\left(\frac{du}{dy}\right)_0$ is zero since u is an even function of y , so that if we have $\left(\frac{du}{dz}\right)_0$ zero as well as u_0 then the value of u vanishes all over an element near the origin.

[14.] Pp. 316—318 are deserving of close attention; they give results which were partially published in the memoir of 1843 (see our Art. 1581*) and which followed up the suggestion of Persy: see our Art. 811*. Saint-Venant namely finds the plane of flexure when the load-plane does not coincide with the plane of one set of principal axes of the cross-sections.

Let Oz, Oy be the principal axes at O the centroid of any cross-section of area ω ; let κ_z, κ_y be the swing-radii about these axes, and ϕ, ψ the angles which the load and flexure planes make respectively with the plane through Oz and the axis of the prism. Then Saint-Venant easily shews that:

$$\tan \psi = \frac{\kappa_z^2}{\kappa_y^2} \tan \phi; \quad \frac{1}{\rho} = \frac{M}{E\omega} \sqrt{\frac{\cos^2 \phi}{\kappa_y^4} + \frac{\sin^2 \phi}{\kappa_z^4}},$$

where $1/\rho$ is the curvature, M the bending moment and E the longitudinal stretch-modulus¹.


Assuming that only longitudinal stretch produces danger, Saint-Venant deduces that if $s_0 = T_0/E$ be the limit of safe stretch then

$$M = \text{or} < \text{the minimum of } \frac{T_0 \omega}{z \frac{\cos \phi}{\kappa_y^2} + y \frac{\sin \phi}{\kappa_z^2}}.$$

For the rectangle ($2b \times 2c$) we have

$$M = \text{or} < \frac{4T_0 b^2 c^2}{3(b \cos \phi + c \sin \phi)},$$

¹ The first equation expresses geometrically that the plane of flexure is perpendicular to the diameter of the momental ellipse (neutral axis) conjugate to the plane of loading: see our Art. 171.



ME 3810-294-20/2-10

Figure 2-10. Securing cable to drum.

(5) Pull cable free of cable drum and boom point sheave and lay it out straight on ground.

(6) Roll cable into a coil and secure with wire. Label the cable for future use.

g. Unreeving the Boom Hoist Cable.

(1) Swing revolving frame so that the boom is over rear of carrier. Lower boom to horizontal position, level with carrier.

(2) Build up cribbing under boom as shown in figure 2-3.

(3) Lower boom to rest on cribbing and continue to slack off on boom hoist cable until upper spreader comes to rest on boom.

(4) Unspool boom hoist cable from drum. Remove wedge from cable drum socket and free cable.

(5) Disconnect cable dead-end at gantry and free cable. Refer to figure 2-9.

(6) Unreeve boom hoist cable from gantry spreader and upper spreader sheaves.

(7) Lay cable out straight on ground.

(8) Roll cable into coil and secure with wire. Label the cable for future use.

(9) Remove guy cables by removing cotter pins and pins from both ends of cables. Refer to figure 2-8.

(10) Using a suitable lifting device, lift upper spreader from crane boom.

h. Removing the Crane Boom.

(1) Unreeve hoist line and boom hoist line. Support boom on cribbing as shown in figure 2-3.

(2) Use wedges or hydraulic jack to relieve weight of boom on boom foot pins and remove pins. Refer to figure 2-5.

(3) Disconnect boom backstops from gantry A-frame and lay backstops on top of boom. Refer to figure 2-6.

(4) Drive carrier away from boom.

2-5. Clamshell Conversion

a. General. The crane may be converted to clamshell operation by installing the crane boom (para 2-4) and a clamshell bucket. The following components are necessary for equipment conversion: crane boom components (para 2-4), clamshell bucket, bucket holding and closing lines, tagline winder, and tagline.

NOTE

The crane hoist cable may be used for the bucket holding line, but if additional depth below ground level is desired, longer holding and closing lines must be installed. Refer to cable specifications in TM 5-3810-294-10.

b. Installation. Install the crane boom, backstops, and boom hoist cable as described in paragraph 2-4.

c. Reeving.

(1) Swing crane boom over clamshell bucket. Lower boom to approximately six feet above ground beside clamshell bucket.

(2) Reeve the closing line on clamshell around left boom point sheave and to rear hoist drum. Secure line to drum (fig. 2-10) and wrap sufficient line on drum to close clamshell bucket.

(3) Reeve the holding line around right boom point sheave and to front hoist drum. Secure line to drum and wrap line on drum until same number of turns are on both drums. Attach holding line loosely to clamshell bucket.

(4) Raise boom to working angle. Raise clamshell bucket, using both lines, until the second layer begins on rear (closing line) drum. The second layer should begin on the front drum at the same time. If it does not, adjust the point of attachment of holding line to bucket.

(5) Cut both lines and secure them to bucket.

d. Tagline Winder.

(1) Using a suitable lifting device, lift tagline winder into position between chords of boom base section, near upper end of section.

We will now sketch the method by which our author reaches the general equations of torsion.

[17.] The axis of torsion will be taken as axis of x ; the direction of torsion will be from the axis of y towards that of z . The area of a cross-section will be denoted by ω , and we shall write $\omega \kappa_x^2 = \int y^2 d\omega$, $\omega \kappa_y^2 = \int z^2 d\omega$, these being the sectional moments of inertia. The torsion referred to unit of length will be τ ; that is, if we draw the radius-vector of a displaced point in one section, and also that of the homologous point in a section at distance ξ from the first, then the second radius-vector makes with a parallel to the first an angle of which the circular measure is $\tau \xi$; this angle is measured from the axis of y to that of z . This language implies that the torsion is constant, but the meaning of τ , when it is not constant, will be assigned in the same manner as before at any point, provided we consider ξ as infinitesimally small.

The above definition of torsion leads us at once to the results :

$$dv/dx = -\tau z, \quad dw/dx = \tau y \dots\dots\dots (i).$$

The consideration that there is no lateral load gives for every point of a sectional contour the equation

$$\widehat{x}y \, dy - \widehat{x}z \, dz = 0 \dots\dots\dots (ii).$$

On p. 329 Saint-Venant fixes a point, line and elementary plane as in our Art. 10, and remarks that the total torsion between the terminal sections may be considerable provided each short element into which we may divide the prism by two cross-sections receives only a small distortion relative to itself, the length of the prism being great as compared with the linear dimensions of the section. The total shifts can then be obtained by summation from the solutions of the above equations for each short element.

Referring to the equations in our Art. 4 (θ) we easily obtain

$$\widehat{x}y = f_1 (du/dy - \tau z), \quad \widehat{x}z = e_1 (du/dz + \tau y) \dots\dots\dots (iii).$$

Whence if M be the moment of all the stresses on a cross-section about the axis of x ,


$$M = \int_0^\omega d\omega [e_1 (du/dz + \tau y) y - f_1 (du/dy - \tau z) z] \dots\dots\dots (iv).$$

It will be seen that this agrees with the old theory—which gave $M = e_1 \tau \int_0^\omega d\omega (y^2 + z^2)$,—only when $e_1 = f_1$ and $du/dz = du/dy$. This, since du/dx is assumed constant, amounts to $u = 0$, or the old theory that the cross-sections remain plane and perpendicular to the axis. Substituting in the equation of our Art. 4 (κ), and in (ii) above, we find for body and surface shift-equations :

$$\left. \begin{aligned} ad^2u/dx^2 + f_1 d^2u/dy^2 + e_1 d^2u/dz^2 + f d^2u/dxdy + e d^2u/dxdz \\ + (ey - fz) d\tau/dx \quad 0 \end{aligned} \right\} \dots (v).$$

$$e_1 (du/dz + \tau y) dy - f_1 (du/dy - \tau z) dz = 0$$

- STEP 1. UNREEVE TAGLINE (PARAGRAPH 2-5e).
- STEP 2. REMOVE U-BOLT.
- STEP 3. REMOVE MOUNTING BOLTS AND NUTS.



ME 3810-294-20/2-12

Figure 2-12. Tagline winder installation.

2-6. Dragline Conversion

a. General. The crane may be converted to dragline operation by installing the crane boom (para 2-4) and a dragline bucket. The following components are necessary for equipment conversion: crane boom components (para 2-4), drag bucket, bucket hoist and drag lines, and fairlead.

NOTE

The crane hoist cable may be used for the bucket hoist line, but if additional reach and depth are desired, a longer cable must be installed. Refer to cable specifications in TM 5-3810-294-10.


b. Installation and Reeving.

- (1) Install crane boom, backstops, and boom hoist cable as described in paragraph 2-4.
- (2) Install the fairlead (fig. 2-13).
- (3) Reeve the hoist cable over center boom point sheave and secure it to the rear drum. Secure remaining free end to cable socket on dump sheave chain (fig. 2-14).

NOTE

When inserting the cable end back into the cable socket, do not let it protrude on the opposite side more than one inch.

accompanying figure the contour lines of these surfaces of distortion are marked; broken lines denoting depressions.



The principal slide σ is given by

$$\sigma^2 = \sigma_{xy}^2 + \sigma_{xz}^2 = \left(\frac{2\tau}{b^2 + c^2} \right)^2 (b^4 z^2 + c^4 y^2) \dots\dots\dots (\text{iv}).$$

The *point dangereux* or *fail-point* is obtained by making $b^4 z^2 + c^4 y^2$ a maximum, thus it is at the extremity of the minor axis, i.e. is the point nearest to the axis of torsion.


From (iv) we obtain by means of our Art. 5 (f), if $S_1 = S_2 = S_0$:

$$S_0 = \text{or} > \mu\tau \frac{2b^2c}{(b^2 + c^2)} \dots\dots\dots (\text{v}),$$

whence it follows that $M = \text{or} < \frac{\pi b c^3 S_0}{2} \left(= \text{or} < \frac{2\omega \kappa_y^2 S_0}{c} \right) \dots\dots\dots (\text{vi}).$

The general appearance of the prism under torsion is given in the figures on the next page, the torsion being diagrammatically exaggerated.

[19.] There are one or two important points to be noticed in this chapter. In the first place Saint-Venant solves equation (vi) of Art. 17 by a series ascending in powers of y and z ; one term ($\alpha'yz$) suffices for the elliptic cross-section, he makes use of others later. Secondly he points out pp. 339—341 that his results agree with the theory of Coulomb only in the case of a circular section,



ME 3810-294-20/2-14

Figure 2-14. Dragline reeving diagram.

(11) Refer to figure 2-16 and install catwalk to foot of boom and the leads; adjust catwalk so the leads are vertical, and bolt catwalk sections together.

c. Removing the Piledriver.

(1) Lower hammer enough to allow slack in cable sling. Remove sling and move piledriver clear of cap.

(2) Remove bolts and nuts securing the catwalk sections. Raise boom enough to clear hammer and lower hammer to ground. Remove cable from hammer.

(3) Remove bolts securing catwalk to leads and boom and lower catwalk to ground.

(4) Lower leads to ground and slowly drive carrier forward; at same time, lower boom to the wood blocks.

(5) Remove piledriver lead adapters and leads as shown in figures 2-15 and 2-16. Secure pile lead adapters to leads.

(6) Remove boom hoist cable and boom (para 2-4).

2-8. Backhoe Conversion

a. General. The crane may be converted to backhoe front-end attachment. The following components are necessary for equipment conversion: backhoe boom, dipper handle, backhoe bucket, pitch brace, drag padlock sheave, hoist padlock sheave, gantry mast, boom foot pins, boom hoist cable, pull cable, and mast suspension cable.

b. Installation.

NOTE

To install the backhoe boom, a cribbing will be necessary to support the boom in a horizontal position. The cribbing must be high enough to bring the boom into position with the boom foot lugs on the revolving frame as shown in figure 2-18.

(1) With base of backhoe boom assembly cribbed up to height of boom foot lugs on revolving frame, swing revolving frame to face the rear of carrier. Carefully back carrier up to cribbed up boom so that the bores in boom foot lugs on revolving frame are aligned with bores

[20.] On pp. 341—343 we have, thirdly, a footnote on Cauchy's suggestions that the torsion τ should be made to vary transversally: see our Art. 684*. Saint-Venant shews that this would require,—at least in the case of a circular cross-section and an axis of elasticity coinciding with the axis of figure—a shearing load at each element of lateral surface. This is a supposition which could hardly be attained in any practical case.

[21.] Fourthly we have on pp. 342—345 a very concise and admirable consideration of the point referred to in our Art. 9; namely, the *practical* equivalence of statically equipollent systems of terminal loading at very short distances from the terminals.

Nos résultats relatifs à la torsion d'un prisme elliptique par des couples quelconques peuvent être adoptés au même titre et avec la même confiance qu'on adopte les formules, soit de l'extension simple, soit de la flexion par des forces latérales, et la formule plus analogue du cas de torsion des cylindres circulaires (p. 345).


In all these cases there is the same assumption as to the equivalence of the shifts produced by the theoretical and by the actual equipollent load systems.

[22.] Fifthly §§ 59 and 60 (pp. 346—7) may be noted. The first deduces from the equations $\int_0^{\omega} \widehat{xy} d\omega = \int_0^{\omega} \widehat{xz} d\omega = 0$ that the axis of torsion for the shifts assumed must coincide with the line of sectional centroids¹: see our Art. 181 (*d*). The second treats of the case of large torsional shifts, see our Art. 17, p. 18. Saint-Venant remarks that the values $v = -\tau xz$ and $w = \tau xy$ of our Art. 18, equation (i), no longer hold, but by an easy process of summation (p. 347) we find the new values:

$$\begin{aligned} v &= -z \sin \tau x - y(1 - \cos \tau x) \\ w &= y \sin \tau x - z(1 - \cos \tau x) \end{aligned}$$

[23.] Lastly we may note on p. 349 the general argument by which Saint-Venant would explain why the *fail-points* are those nearest and not farthest from the axis of torsion as in the old theory (*la théorie ordinaire*, S^t-V.). He points out that at the extremity of the major axis the slide produced by the distortion of the plane section is zero and so we have only the slide produced by the 'fibres becoming helical,' while at the extremity of the minor axis the two components of the slide both exist and compound, *operating* together. Hence generally we see how it is possible for the slide to be greater at the latter than the former point.

¹ This paragraph was cancelled in the copies of the memoir remaining in Saint-Venant's possession.



ME 3810-294-20/2-16

Figure 2-16. Piledriver lead and adapter installation.

(2) Release front cable drum brake and spool cable off drum. Remove cable wedge from drum socket and pull cable free of drum and cable guide sheave on boom.

(3) Remove wedge from dead-end socket on boom and pull cable free of padlock, guide sheave, and boom.

These equations can be solved by the assumption

$$v' = \sum A_m (e^{my} - e^{-my}) \sin mz$$


and the usual determination of the constants by Fourier's Theorem.

[27.] Saint-Venant obtains the following general results :

$$\begin{aligned}
 \text{(i)} \quad & \left\{ \begin{aligned} u &= \tau b c \left[-\frac{yz}{bc} + \frac{1}{2} \left(\frac{4}{\pi} \right)^2 \frac{c}{b} \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n-1)^2} \frac{\sinh \frac{(2n-1)\pi y}{2c}}{\cosh \frac{(2n-1)\pi b}{2c}} \sin \frac{(2n-1)\pi z}{2c} \right] \\ &= \tau b c \left[\frac{yz}{bc} - \frac{1}{2} \left(\frac{4}{\pi} \right)^2 \frac{b}{c} \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n-1)^2} \frac{\sinh \frac{(2n-1)\pi z}{2b}}{\cosh \frac{(2n-1)\pi c}{2b}} \sin \frac{(2n-1)\pi y}{2b} \right] \end{aligned} \right. \\
 \text{(ii)} \quad & \left\{ \begin{aligned} \widehat{xx} &= \widehat{yy} = \widehat{zz} = \widehat{yz} = 0, \\ \widehat{xy} &= -\mu \tau c \left\{ 2 \frac{z}{c} - \left(\frac{4}{\pi} \right)^2 \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n-1)^2} \frac{\cosh \frac{(2n-1)\pi y}{2c}}{\cosh \frac{(2n-1)\pi b}{2c}} \sin \frac{(2n-1)\pi z}{2c} \right\} \\ &= -\mu \tau c \left(\frac{4}{\pi} \right)^2 \frac{b}{c} \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n-1)^2} \frac{\sinh \frac{(2n-1)\pi z}{2b}}{\cosh \frac{(2n-1)\pi c}{2b}} \cos \frac{(2n-1)\pi y}{2b} \\ \widehat{xz} &= \mu \tau b \frac{c}{b} \left(\frac{4}{\pi} \right)^2 \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n-1)^2} \frac{\sinh \frac{(2n-1)\pi y}{2c}}{\cosh \frac{(2n-1)\pi b}{2c}} \cos \frac{(2n-1)\pi z}{2c} \\ &= \mu \tau b \left\{ 2 \frac{y}{b} - \left(\frac{4}{\pi} \right)^2 \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n-1)^2} \frac{\cosh \frac{(2n-1)\pi z}{2b}}{\cosh \frac{(2n-1)\pi c}{2b}} \sin \frac{(2n-1)\pi y}{2b} \right\} \end{aligned} \right. \\
 \text{(iii)} \quad & \left\{ \begin{aligned} M &= \mu \tau b c^3 \left\{ \frac{16}{3} - \left(\frac{4}{\pi} \right)^5 \frac{c}{b} \sum_{n=1}^{\infty} \frac{1}{(2n-1)^5} \tanh \frac{(2n-1)\pi b}{2c} \right\} \\ &= \mu \tau b^3 c \left\{ \frac{16}{3} - \left(\frac{4}{\pi} \right)^5 \frac{b}{c} \sum_{n=1}^{\infty} \frac{1}{(2n-1)^5} \tanh \frac{(2n-1)\pi c}{2b} \right\} \end{aligned} \right.
 \end{aligned}$$


[28.] It will be noted that Saint-Venant obtains in each case double values for his quantities which are unsymmetrical in b

¹ Saint-Venant puts \sinh for \cosh in the denominator here by a misprint (p. 368, equation 159).



ME 3810-294-20/2-18

Figure 2-18. Cribbing prepared for backhoe boom assembly, installation and removal.



ME 3810-294-20/2-19

Figure 2-19. Backhoe auxiliary gantry suspension reeving.

foot pin holes in boom with those in revolving frame.

(5) Install boom foot pin through left boom foot lug. Using a suitable lifting device, support boom foot drum in position and install boom foot pin through drum and right boom foot lug. Install boom foot pin retaining plates, capscrews, lockwashers, and nuts (fig. 2-26). Connect electrical line to dipper trip motor.

(6) Install crowd chain around front drum sprocket, boom foot drum sprocket, and over the chain tightener. Adjust chain (TM 5-3810-294-10).


c. Reeving Crowd Cable.

(1) Unroll and stretch crowd cable out on ground on right side of boom.

(2) Reeve one end of crowd cable under and around the bottom foot drum to right cable socket on drum and secure cable to drum as shown in figure 2-10.

(3) Reeve other end of crowd cable around front of right groove in shipper shaft roller, around dipper stick rope thimble, around front of left groove in shipper shaft roller, under and around boom foot drum to left cable socket on drum and secure cable to drum (fig. 2-27).

The values of u are calculated and given in a table on p. 377. The accompanying figures give the contour lines of the distorted cross-section and the boundaries of the cross-section as cutting the lateral faces of the distorted prism in elevation (diagrammatically exaggerated).



For numerical values we have,

$$M = .843462 \mu \tau \omega^2 b^2 / 3$$


$$= \text{or} < 1.66532 S_0 b^3.$$

$\sigma = 1.350630 b \tau$ is the maximum slide and occurs at the middle points of the sides of the cross-section, which are thus the *fail-points*. These values are all less than those obtained from the old theory.

[31.] On pp. 382—387 Saint-Venant refers to the experiments of Duleau¹ and Savart² as confirming his results. From Duleau's experiments on circular bars the mean value of μ obtained was 6,659,230,000 kilogs. but from his experiments on

¹ See our Art. 229*.

² See our Art. 334*.



ME 3810-294-20/2-21

Figure 2-21. Backhoe hoist cable reeving.

g. Reeving Shovel Dipper Trip Cable.

(1) Raise dipper off ground and crowd it out as far as it will go; then lower it to the ground.

(2) Unroll and stretch dipper trip cable out on ground on right side of boom.

(3) Reeve cable from trip lever on dipper stick, over small sheaves on shipper shaft, round dipper trip motor eccentric, around outside sheave on shipper shaft, and back to dead end on dipper stick (fig. 2-30).

h. Adjustments. Refer to TM 5-3810-294-10.

NOTE

Each adjustment must be made or checked before a machine converted to shovel operation is placed in service.

i. Unreeving Shovel Cables.

(1) To unreeve shovel dipper trip cable, remove cable clamp at dipper trip lever and dead end on dipper stick. Pull cable from drum and sheaves. Coil cable neatly and secure with wire. Label cable for future use.


(2) To unreeve boom hoist cable, hoist dipper up and crowd it out beyond boom point sheaves. Lower boom onto blocking (fig. 2-25). Unspool cable from drum. Remove cable wedge from cable drum socket and free cable. Pull cable free of drum and boom point sheaves and lay it out straight on ground. Roll cable into coil and secure with wire. Label cable for future use.

square sectioned bars it was only 5,636,625,000 on the old theory. Saint-Venant's however brings it up to 6,682,750,000, which may be considered in fair agreement with the result obtained from bars of circular section; especially when we remember the non-isotropic character which was inevitable in the iron bars of Duleau's experiments (see table p. 383). At any rate Saint-Venant's theory accounts for the greater part of the inferior resistance to torsion of square as compared with circular bars of equal sectional moment of inertia.

Some experiments on copper wires of square and circular cross-sections are tabulated on p. 386. Here the mean for the circular cross-section is $\mu = 4,174,825,000$; the old and the new theory give for μ the values 3,384,121,000 and 4,012,180,000; again to the advantage of the latter. The isotropy of these wires is however very questionable.

[32.] Saint-Venant deduces on pp. 387—391 the value of the numerical factor which occurs in M (see our Art. 30) by an algebraic expansion for u and a calculation after the manner of Fourier (*Théorie de la chaleur*, chap. III. art. 208, Eng. Trans. p. 137) of the indeterminate coefficients. It does not seem a very advantageous process. A remark on p. 397 as to the difference between *résistance à la rupture éloignée* and *rupture immédiate* is to the point. Saint-Venant remarks namely that experiments on the latter can throw little light on the mathematical theory of elasticity. At the same time it is regrettable that he should have retained the word *rupture* in reference even to the first limit. Some support, however, for his theory may even be derived, he thinks, from Vicat's experiments on rupture; see our Art. 731* and p. 398 of the memoir. For Vicat found that for *pierre calcaire*, *brique crue* and *plâtre* the moment of the forces required to break a prism of square cross-section and length at least twice the diameter was less than in the case of an infinitely short prism, i.e. a case where the plane section cannot be distorted. This result of Vicat is of great interest and would be well worth further experimental investigation.

[33.] We now come to the general case: *Cas d'un rapport quelconque des deux dimensions de la base* (pp. 398—413). Saint-Venant has calculated numerically all the particulars of the



- STEP 1. REFER TO PARAGRAPH 2-4 AND UNREEVE THE CABLES FROM FRONT AND REAR DRUMS. REFER TO FIGURE 2-23 AND REMOVE COTTER PIN, PIN AND REVERSING CHAIN.
- STEP 2. REMOVE CAPSCREWS (5) AND LOCKWASHERS (4). REFER TO FIGURE 2-22 AND REMOVE LAGGING BOLTS.
- STEP 3. REMOVE ROPE LAGGING FROM THE FRONT DRUM, AND REMOVE REVERSING SPROCKET HALVES (3) FROM THE LAGGING HALVES BY REMOVING CAPSCREWS (1) AND LOCKWASHERS (2).
- STEP 4. INSTALL REVERSING SPROCKET HALVES (3) ON CROWD SPROCKET LAGGING HALVES AND INSTALL THE CROWD SPROCKET LAGGING ON THE FRONT DRUM. INSTALL CAPSCREWS (5) AND LOCKWASHERS (4).

ME 3810-294-20/2-23

Figure 2-23. Installing crowd sprocket lagging.

and this maximum slide takes place at the centre of the longer side of the rectangular cross-section. (p. 410.)

$$(iii) \quad S_0 = \text{or} > \mu \gamma \tau c, \quad \text{hence}$$

$$M = \text{or} < \frac{\beta}{\gamma} b c^3 S_0 = M_0.$$

These complex analytical results are rendered practically of service by a table on pp. 559—60 of the memoir, the most serviceable portion of which we shall reproduce later. This table gives the values of β and of β/γ for magnitudes of the parameter b/c varying from 1 to 100, after which they become sensibly constant. We are thus able to determine M and its limit M_0 .

Saint-Venant, however, gives in footnotes empirical formulae which agree with less than 4 per cent. error with the above theoretical values. He appears to have reached them by purely tentative methods, but he holds that they satisfy all practical needs. They are

$$(iv) \quad \beta = \frac{16}{3} - 3 \cdot 36 \frac{c}{b} \left(1 - \frac{1}{12} \frac{c^4}{b^4} \right).$$


$$(v) \quad \frac{\beta}{\gamma} = \frac{8}{3} / \left(1 + \cdot 6 \frac{c}{b} \right) \quad \text{or, } M_0 = \frac{40 b^3 c^3}{15 b + 9 c} \cdot S_0.$$

{It should be noted that our $\sigma = g_x$, our $\beta = \mu$, our $\tau = \theta$, our $\mu = G$, our $S_0 = T_0$ of the memoir.}

[35.] On pp. 403—6 we have a further discussion of experiments of Duleau and Savart on the torsion of rectangular bars of iron, oak, *plâtre*, and *verre à vitre*, the paucity of the experiments, and the large variation in the values of the slide-moduli as obtained from Saint-Venant's formula do not seem to me very satisfactory. A series of experiments directly intended to test the torsion of rectangular bars for variations of the parameter c/b would undoubtedly be of considerable value.

[36.] We now reach Saint-Venant's ninth chapter which is entitled: *Torsion de prismes ayant d'autres bases que l'ellipse ou le rectangle*. It occupies pp. 414—454.

The chapter opens with an enumeration of the various forms of contour for which it is easy to integrate the equations of Art. 17. We will tabulate them on the next page.






ME 3810-294-20/2-25

Figure 2-25. Cribbing shovel boom assembly.

Solutions (3) and (5) are really identical. No. 4 has given rise to the solutions in terms of *conjugate functions*: see Thomson and Tait's *Natural Philosophy*, 2nd Ed. Part II. pp. 250—3.

[37.] In the present chapter Saint-Venant dismisses Nos. 1 and 2 on the ground that the resulting curves are very difficult to trace. He contents himself with two closed curves of the fourth degree and one of the eighth as given by No. 5. On pp. 421—434 he calculates and traces these curves at considerable length. The most practically valuable results are those obtained on p. 439.

We have there the following characteristic sections treated :



(a) The equation of the first curve is :

$$\frac{y^2 + z^2}{r_0^2} - 4 \frac{y^4 - 6y^2z^2 + z^4}{r_0^4} = .6 \quad (\text{Square with rounded angles}).$$

$$\omega = 2.0636r_0^2; \quad \omega\kappa^2 = .7174r_0^4 = 1.0586\omega^2/2\pi;$$

$$M = .5873\mu\tau r_0^4 = .8186\mu\tau\omega\kappa^2 = .8666\mu\tau\omega^2/2\pi.$$

(b) The equation to the second curve is :

$$\frac{y^2 + z^2}{r_0^2} - .5 \frac{y^4 - 6y^2z^2 + z^4}{r_0^4} = .5 \quad (\text{Square with acute angles}).$$

$$\omega = 1.7628r_0^2; \quad \omega\kappa^2 = .5259r_0^4 = 1.0634\omega^2/2\pi;$$

$$M = .4088\mu\tau r_0^4 = .7783\mu\tau\omega\kappa^2 = .8276\mu\tau\omega^2/2\pi.$$

(c) The equation to the third curve is, if $y = r \cos \phi$, $z = r \sin \phi$,

$$\frac{r^2}{r_0^2} - \frac{48}{49} \cdot \frac{16}{17} \frac{r^4 \cos 4\phi}{r_0^4} + \frac{12}{49} \cdot \frac{16}{17} \frac{r^8 \cos 8\phi}{r_0^8} - 1 = \frac{36}{49} \cdot \frac{16}{17}$$

(Star with four rounded points).

$$\omega = 1.2202r_0^2; \quad \omega\kappa^2 = .2974r_0^4 = 1.2551\omega^2/2\pi;$$

$$M = .15983\mu\tau r_0^4 = .5374\mu\tau\omega\kappa^2 = .6745\mu\tau\omega^2/2\pi.$$

We add to these the results for the circle and square.

(d) Circle: $M = \mu\tau\omega\kappa^2 = \mu\tau\omega^2/2\pi.$

(e) Square: $M = .84346\mu\tau\omega\kappa^2 = .88327\mu\tau\omega^2/2\pi.$





Figure 2-28. Dipper hoist cable reeving.

$\cdot 01857 \mu \tau \omega \kappa^2$, or the torsion of such a pair of cylinders round an intermediate axis is *only one fifty-fourth* of that given by the old




theory:—"Cela ne doit pas étonner, si l'on considère que le glissement est nul aux points $z=0$, $y=\pm b\sqrt{\frac{2}{3}}$ ou à très-peu près au centre de gravité de chaque orbe."

[39.] Saint-Venant on his pp. 441—9 discusses the contour-lines of the distorted cross-sections of our Art. 37. This he accomplishes by numerical tables in a footnote (pp. 441—3). Then he considers the maximum slides and *fail-points* of the same sections and finally the limiting values of the torsional couples. These values are as follows:

$$\begin{array}{lll} \text{For section (a) of Art. 37} & M_0 = \cdot 8269 \frac{\omega \kappa^2}{r_0} S_0 = \cdot 7094 \frac{\omega^{\frac{2}{3}}}{2\sqrt{\pi}} S_0. \\ \text{" (b) " } & M_0 = \cdot 85514 \frac{\omega \kappa^2}{r_0} S_0 = \cdot 6812 \frac{\omega^{\frac{2}{3}}}{2\sqrt{\pi}} S_0. \\ \text{" (c) " } & M_0 = \cdot 7285 \frac{\omega \kappa^2}{r_0} S_0 = \cdot 5695 \frac{\omega^{\frac{2}{3}}}{2\sqrt{\pi}} S_0. \end{array}$$

The reasoning by which Saint-Venant deduces the *fail-points* cannot be considered satisfactory. Indeed the statement as to the 'side of the triangle' and the deduction of the maximum slide on p. 444 are unsound. The same judgment must be passed on the process of p. 447, where the maximum slide for the section (c) is shewn to be on the contour. Thus Saint-Venant has *not demonstrated* his very general statement (237) on p. 448. The reader will however find little difficulty in proving the accuracy of Saint-Venant's *results* by casting the expressions on pp. 444 and 447 into other forms or by the ordinary processes of the Differential Calculus. In his edition of the *Leçons de Navier*, our author has recognised the defective reasoning of these pages and replaced them by more accurate arguments. (Cf. his § 31, pp. 308—310 and § 37, pp. 340—1: see our Art. 181 (e).)

[40.] In the concluding pages of this chapter Saint-Venant points out how the solutions of a number of other sections can be obtained. Thus we can take solutions like (3) of Art. 36 involving terms of the 12th and 16th degrees and so obtain curves equally symmetrical with regard to the axes of y and z .



ME 3810-294-20/2-30

Figure 2-30. Dipper trip cable reeving.

Section II. MOVEMENT TO A NEW WORKSITE

2-10. Dismantling for Movement

a. The crane can be transported readily as it is mounted on its own carrier. Instructions for transportation of crane with front end equipment attached are contained in TM 5-3810-294-10.

WARNING

Do not transport crane with the piledriver front-end installed.

b. When it is necessary to remove the front end equipment for movement to a new worksite, refer to the appropriate instructions (para 2-4 through 2-9).

2-11. Reinstallation after Movement

a. Refer to the appropriate instructions (para 2-4 through 2-9) to install front end equipment.

b. Refer to TM 5-3810-294-10 for installation or setting-up instructions.

Section III. REPAIR PARTS, SPECIAL TOOLS, AND EQUIPMENT

2-12. Tools and Equipment

Tools, equipment, and repair parts issued with or authorized for the crane are listed in the basic issue items troop installed or authorized list. Refer to TM 5-3810-294-10.

organizational level maintenance of the crane (revolving frame).

2-14. Maintenance Repair Parts

Repair parts and equipment are listed and illustrated in the repair parts and special tools list covering organizational maintenance for this equipment (TM 5-3810-294-20P).

2-13. Special Tools and Equipment

No special tools or equipment are required for

Section IV. LUBRICATION INSTRUCTIONS

2-15. General

General lubrication instructions are listed in TM 5-3810-294-10.

2-16. Detailed Lubrication Instructions

Refer to Lubrication Order (LO 5-3810-294-12).

Thus the form of the surface into which the originally plane cross-section becomes changed by torsion is easily understood. In the part between Oy and the perpendicular OL , we have u negative; in the part between OL and OB we have u positive; in the part between OB and yO produced through O we have u negative; in the next piece, which is vertically opposite to the piece between Oy and OL , we have u positive; and so on.

We have as usual the equations

$$\widehat{xy} = \frac{du}{dy} - \tau z, \quad \widehat{xz} = \frac{du}{dz} + \tau y;$$

these by (ii) of Art. 41 give

$$\widehat{xy} = -\tau \left(z + \frac{yz}{b} \right), \quad \widehat{xz} = \tau \left(y - \frac{y^2 - z^2}{2b} \right).$$

The moment of torsion by equation (iv) of Art. 17 is

$$M = \mu\tau \left\{ \int y^2 d\omega + \int z^2 d\omega + \frac{3}{2b} \int yz^2 d\omega - \frac{1}{2b} \int y^3 d\omega \right\}.$$

All these integrations are easily effected; for here if ξ denote any function of y and z , even in z , we have

$$\int \xi d\omega = 2 \iint \xi dy dz,$$

where we integrate for z from $z=0$ to $z = \frac{2b-y}{\sqrt{3}}$, and for y from $y=-b$ to $y=2b$. Thus we find that

$$\begin{aligned} \int z^2 d\omega &= \frac{3}{2} b^4 \sqrt{3}, \\ \int y^2 d\omega &= \frac{3}{2} b^4 \sqrt{3}, \\ \int yz^2 d\omega &= -\frac{3}{5} b^5 \sqrt{3}, \\ \int y^3 d\omega &= \frac{3}{5} b^5 \sqrt{3}. \end{aligned}$$

Then for the moment of inertia round the axis we have

$$\omega \kappa^2 = \int y^2 d\omega + \int z^2 d\omega = 3b^4 \sqrt{3} = \frac{\omega^2}{3\sqrt{3}}, \text{ for } \omega = 3b^2 \sqrt{3}.$$

Hence

$$M = \frac{3}{5} \mu \tau \omega \kappa^2 = \frac{\mu \tau \omega^3}{5\sqrt{3}}.$$

The new theory thus gives a value for M only $\cdot 6$ of that given by the old.

42. To find the greatest slide, Saint-Venant considers the side which is parallel to the axis of z ; then he says that along this side $y+b=0$, so that $\widehat{xy}=0$, and $\widehat{xz} = -\frac{3b^2 - z^2}{2b} \tau$. Thus the greatest value of \widehat{xz} is when $z=0$. Hence he tells us that the *fail-point* is on the boundary at the point which is nearest to the axis. The greatest value of the *glissement principal* is then $\frac{3b}{2}$; and to ensure safety we must have as before

$$S_0 = \text{or } > \frac{3}{2} \mu b \tau.$$

Table 2-1. Preventive Maintenance Checks and Services—Continued

M — Monthly Total man-hours required: 1.5		Q — Quarterly Total man-hours required: 26.4	
Interval and Sequence No.		Item to be inspected	Work Time (M/H)
M	Q	Procedure	
	10	REAR DRUM CLUTCH Check operation; adjust if necessary. If lining is worn to within 1/16-inch of rivet heads at point of most wear, install new lining (para 2-105).	2.5
	11	BOOM HOIST CLUTCH Check operation: adjust if necessary. If lining is worn to within 1/16-inch of rivet heads at point of most wear, install new lining (para 2-108).	2.5
	12	FRONT DRUM BRAKE Check operation; adjust if necessary. If lining is worn to within 1/16-inch of rivet heads at point of most wear, install new lining (para 2-106).	2.5
	13	REAR DRUM BRAKE Check operation; adjust if necessary. If lining is worn to within 1/16-inch of rivet heads at point of most wear, install new lining (para 2-105).	2.5
	14	BOOM AND/OR JIB Inspect visually for damage including cracks, breaks, and general condition. Replace damaged boom or jib sections (para 2-37).	2.0
	15	ENGINE CLUTCH Inspect, and adjust if necessary (para 2-101).	.5
	16	HOOK ROLLERS Inspect hook rollers for wear and proper adjustment. Maximum allowable clearance between hook rollers and lower side of roller path is 1/16-inch. Replace severely worn rollers (para 2-111).	3.0
	17	OPERATOR'S CAB Replace cracked glass or damaged door (para 2-62 and 2-61).	1.0
	18	LIGHTS Inspect lights for loose cables, mountings, cracked lens, and proper operation. Repair or replace defective lamps or bulbs (para 2-51).	1.5
	19	REAR DRUM DRIVE CHAIN, REVERSING CHAIN, SHOVEL CROWD CHAIN, AND HORIZONTAL SWING SHAFT CHAIN Inspect for wear. Replace chain if worn excessively (para 2-110).	1.0
	20	GANTRY Inspect for cracks, worn sheaves, and improper lubrication (para 2-65).	2.0

Section VI. TROUBLESHOOTING

2-19. General

a. This section contains troubleshooting information for locating and correcting trouble which may develop in the crane (revolving frame) that are within the scope of organizational maintenance. Each malfunction for an individual component, unit, or system is followed by a list of tests or inspections which will help you to determine probable causes of trouble and corrective actions to take. You should perform the tests/

inspections and corrective actions in the order listed.

b. This manual cannot list all malfunctions that may occur, nor all tests or inspections and corrective actions. If a malfunction is not listed or is not corrected by listed corrective actions, notify your supervisor.

2-20. Troubleshooting

Refer to table 2-2.

[46.] Thus in the case of the ellipse (pp. 455—8 of memoir), we must write for $\frac{y^2}{b^2} + \frac{z^2}{c^2} = 1$, $\frac{y'^2}{b^2/\mu_1} + \frac{z'^2}{c^2/\mu_2} = 1$. Thus we obtain at once the results :

$$u = -\frac{b^2/\mu_1 - c^2/\mu_2}{b^2/\mu_1 + c^2/\mu_2} \tau' y' z' = -\frac{b^2/\mu_1 - c^2/\mu_2}{b^2/\mu_1 + c^2/\mu_2} \tau y z.$$

$$\text{Similarly} \quad \widehat{xy} = -\frac{2\tau z b^2}{b^2/\mu_1 + c^2/\mu_2}, \quad \widehat{xz} = \frac{2\tau y c^2}{b^2/\mu_1 + c^2/\mu_2},$$

and

$$M = \frac{\pi b^3 c^3 \tau}{b^2/\mu_1 + c^2/\mu_2} \text{ (see Art. 18).}$$

Saint-Venant remarks that with this inequality, the cross-section of a circular cylinder will be distorted by torsion. The elliptic prism however, for which the ratio of the semi-axes $b/c = \sqrt{\mu_1/\mu_2}$, will retain undistorted cross-sections although under torsion (p. 456). Saint-Venant in the course of the chapter again refers to relations of this kind (p. 462), but it is obvious that such are extremely unlikely to occur in practice.

It must be noted that the 'fail-limit' (*condition de non-rupture*, pp. 456—7) now takes another form, namely that of our Art. 5 (*f*),

$$1 = \text{or} > \left(\frac{\mu_1 \sigma_{xy}}{S_1} \right)^2 + \left(\frac{\mu_2 \sigma_{xz}}{S_2} \right)^2.$$

From this we find at once

$$(b^2/\mu_1 + c^2/\mu_2)^2 = \text{or} > 4\tau^2 (b^4 z^2/S_1^2 + c^4 y^2/S_2^2).$$

We have then to find the maximum value of the right-hand side. It is easily seen to be on the contour of the cross-section, and at the extremities of the minor or major axis according as b/c is $>$ or $<$ S_1/S_2 . In the first case we find that the limiting value of M is given by

$$M_1 = \frac{\pi b c^2}{2} S_1.$$

[47.] Saint-Venant devotes pp. 458—460 to describing the changes which must be made in the general solutions of our Art. 36 in order to adapt them to this case of unequal slide-moduli. They follow easily from our Art. 45. On pp. 460—8 he treats at some length the case of the prism with rectangular cross-section. The results are the same as those of our Art. 27, provided we re-

place the ratios $\frac{c}{b}$ and $\frac{b}{c}$ where they occur in our formulæ by

$\frac{c}{b} \sqrt{\frac{\mu_1}{\mu_2}}$ and $\frac{b}{c} \sqrt{\frac{\mu_2}{\mu_1}}$ respectively, and the exponentials

$e^{\pm \frac{(2n-1)\pi y}{2} \frac{y}{c}}$ and $e^{\pm \frac{(2n-1)\pi z}{2} \frac{z}{b}}$ by $e^{\pm \frac{(2n-1)\pi y}{2} \frac{y}{c} \sqrt{\frac{\mu_2}{\mu_1}}}$ and $e^{\pm \frac{(2n-1)\pi z}{2} \frac{z}{b} \sqrt{\frac{\mu_1}{\mu_2}}}$ respectively.

Table 2-2. Troubleshooting—Continued

MALFUNCTION	TEST OR INSPECTION	CORRECTIVE ACTION
	Step 2.	Check for clogged oil filter. Replace oil filter (para 2-98).
	Step 3.	Check for oil too thin due to dilution or too light a grade used. Drain crankcase and refill with proper oil (para 2-86).
8. HIGH OIL PRESSURE		
	Step 1.	Oil too heavy. Drain crankcase and refill with proper oil (para 2-96).
	Step 2.	Check for defective oil pressure gage on engine control panel. Replace oil pressure gage (para 2-54).
9. EXCESSIVE OIL CONSUMPTION		
	Step 1.	Check oil lines for leaks at connections. Tighten loose connections (para 2-98).
	Step 2.	Check for poor quality or wrong grade of oil. Drain crankcase and refill with proper oil (para 2-96).
10. ENGINE LACKS POWER		
	Step 1.	Fuel pump not operating properly. Refer to paragraph 2-84 and test fuel pump. Replace defective pump.
	Step 2.	Check for dirty or faulty carburetor. Clean or replace carburetor (para 2-83).
	Step 3.	Check for faulty spark plugs. Replace plugs (para 2-91).
	Step 4.	Check for burned, pitted, or sticking ignition points. Replace points (para 2-90).
11. BATTERIES DISCHARGE WITH ENGINE RUNNING		
		Check for loose alternator V-belt or faulty alternator. Adjust V-belt tension or replace faulty alternator. (para 2-88).
12. LIGHTS FAIL		
	Step 1.	Check for defective or burned out lamps. Replace lamps (para 2-51).
	Step 2.	Check for defective wiring. Repair or replace wiring (para 2-50).
	Step 3.	Check for defective switch. Replace switch (para 2-55).
	Step 4.	Check for faulty ground. Clean ground terminals
13. REVOLVING FRAME TEETERS		
		Check hook rollers for improper adjustment. Adjust hook rollers (para 2-111).
14. HEATER MOTOR INOPERATIVE		
	Step 1.	Check wiring. Replace faulty wiring (para 2-68).
	Step 2.	Check heater blower motor. Replace defective motor.
15. HEATER DELIVERS COLD AIR		
	Step 1.	Check for stuck thermostat. Replace defective thermostat.
	Step 2.	Check for blocked heater hose. Repair or replace hose.
	Step 3.	Check for air lock in water line to heater. Disconnect heater hose and drain line until air block is bled from system.
	Step 4.	Check for dirt on outside of coil. Remove cover and clean outside of coil.
	Step 5.	Check for sediment in inside of coil. Remove input and output hoses and flush coil with suitable solvent.
16. HEATER DOES NOT DELIVER AIR		
	Step 1.	Check for inoperative heater motor. Refer to malfunction 14 above.

gives the value of β , where $M = \beta \mu_1 \tau b c^3$ is the value of the torsional couple. The third and fourth columns give the maximum slides by means of the coefficients γ_1 and γ_2 where $\sigma_1 = -\gamma_1 c \tau$ and $\sigma_2 = \gamma_2 b \tau$. The fifth and sixth columns give the maximum value M_0 of M by means of the tabulated values of β/γ_1 and $\frac{\beta}{\gamma_2} \frac{c^2}{b^3} \frac{\mu_1}{\mu_2}$, where $M_1 = \left(\frac{\beta}{\gamma_1}\right) b c^3 S_1$ and $M_2 = \left(\frac{\beta}{\gamma_2} \frac{c^2}{b^3} \frac{\mu_1}{\mu_2}\right) b^2 c S_2$. M_0 is to be taken equal to the lesser of M_1 and M_2 .

[48.] Pages 468—9 of this chapter suggest the modifications which must be made in the results obtained for prisms of other cross-sections, when μ_1 differs from μ_2 ; while on p. 470 we have a simple proof that in this case at corners and angles which project there is no slide, or the intersection of the lateral faces at such corners remains normal to the cross-section.

[49.] Saint-Venant's eleventh chapter deals with the torsion of hollow prisms (pp. 471—6).

In this case we have to satisfy the surface shift-equation

$$\mu_2 (du/dz + \tau y) dy - \mu_1 (du/dy - \tau z) dz = 0 \quad \dots\dots\dots(i)$$

on two surfaces. If then we form a family of surfaces satisfying this equation and give to the arbitrary constant which appears on the right-hand side two different values we shall obtain the two boundaries of a hollow prism satisfying all the required conditions.

For example :

$$(a) \quad u = -\frac{b^2/\mu_1 - c^2/\mu_2}{b^2/\mu_1 + c^2/\mu_2} \tau y z$$

satisfies the body shift-equation. Substituting in (i) we have on integration

$$c^2 y^2 + b^2 z^2 = \text{constant}.$$

Giving the constant different values we obtain a system of similar and similarly placed ellipses. Thus we find for a hollow elliptic cylinder formed by the ellipses $(2b \times 2c)$ and $(2b' \times 2c')$

$$M = \tau \left\{ \frac{\pi b^3 c^3}{b^3/\mu_1 + c^3/\mu_2} - \frac{\pi b'^3 c'^3}{b'^3/\mu_1 + c'^3/\mu_2} \right\} = \frac{\tau \pi b^3 c^3}{b^2/\mu_1 + c^2/\mu_2} \left\{ 1 - \left(\frac{b'}{b} \right)^4 \right\}.$$

(b) In the rectangular section

$$u = -\tau y z + \sum A_m \sinh(m y / \sqrt{\mu_1}) \sin(m z / \sqrt{\mu_2}),$$

where

$$A_m = \tau \frac{b c}{2} \left(\frac{4}{\pi} \right)^3 \frac{c}{b} \sqrt{\frac{\mu_1}{\mu_2}} \frac{(-1)^{n-1}}{(2n-1)!} \operatorname{sech}(mb/\sqrt{\mu_1})$$


and

$$m = \frac{(2n-1)\pi}{2} \sqrt{\frac{\mu_2}{c}}.$$

Table 2-2. Troubleshooting—Continued

ALFUNCTION	TEST OR INSPECTION	CORRECTIVE ACTION
	Step 2.	Check for clogged oil filter. Replace oil filter (para 2-98).
	Step 3.	Check for oil too thin due to dilution or too light a grade used. Drain crankcase and refill with proper oil (para 2-86).
HIGH OIL PRESSURE		
	Step 1.	Oil too heavy. Drain crankcase and refill with proper oil (para 2-96).
	Step 2.	Check for defective oil pressure gage on engine control panel. Replace oil pressure gage (para 2-54).
EXCESSIVE OIL CONSUMPTION		
	Step 1.	Check oil lines for leaks at connections. Tighten loose connections (para 2-98).
	Step 2.	Check for poor quality or wrong grade of oil. Drain crankcase and refill with proper oil (para 2-96).
1. ENGINE LACKS POWER		
	Step 1.	Fuel pump not operating properly. Refer to paragraph 2-84 and test fuel pump. Replace defective pump.
	Step 2.	Check for dirty or faulty carburetor. Clean or replace carburetor (para 2-83).
	Step 3.	Check for faulty spark plugs. Replace plugs (para 2-91).
	Step 4.	Check for burned, pitted, or sticking ignition points. Replace points (para 2-90).
2. BATTERIES DISCHARGE WITH ENGINE RUNNING		
		Check for loose alternator V-belt or faulty alternator. Adjust V-belt tension or replace faulty alternator. (para 2-88).
3. LIGHTS FAIL		
	Step 1.	Check for defective or burned out lamps. Replace lamps (para 2-51).
	Step 2.	Check for defective wiring. Repair or replace wiring (para 2-50).
	Step 3.	Check for defective switch. Replace switch (para 2-55).
	Step 4.	Check for faulty ground. Clean ground terminals.
4. REVOLVING FRAME TEETERS		
		Check hook rollers for improper adjustment. Adjust hook rollers (para 2-111).
HEATER MOTOR INOPERATIVE		
	Step 1.	Check wiring. Replace faulty wiring (para 2-68).
	Step 2.	Check heater blower motor. Replace defective motor.
5. HEATER DELIVERS COLD AIR		
	Step 1.	Check for stuck thermostat. Replace defective thermostat.
	Step 2.	Check for blocked heater hose. Repair or replace hose.
	Step 3.	Check for air lock in water line to heater. Disconnect heater hose and drain line until air block is bled from system.
	Step 4.	Check for dirt on outside of coil. Remove cover and clean outside of coil.
	Step 5.	Check for sediment in inside of coil. Remove input and output hoses and flush coil with suitable solvent.
HEATER DOES NOT DELIVER AIR		
	Step 1.	Check for inoperative heater motor. Refer to malfunction 14 above.

By a simple analysis Saint-Venant finds its absolute magnitude for a *right-circular* cylinder of radius a . Take a fibre at distance r from the axis and let us consider the element PP' of it between two planes at unit distance. Suppose owing to torsion that the two planes approach each other by a quantity η and let $P'N$ be the perpendicular from the new position of P' on the cross-section through P ,



$$PP' = \sqrt{P'N^2 + PN^2} = \sqrt{(1-\eta)^2 + \tau^2 r^2} \\ = 1 - \eta + \frac{\tau^2 r^2}{2} \text{ nearly.}$$

Saint-Venant takes for PP' the quantity

$$(1-\eta)\sqrt{1 + \tau^2 r^2} \\ = 1 - \eta + \frac{\tau^2 r^2}{2},$$

but I do not think he obtains the first expression very rigorously. He has practically the same value in the *Leçons de Navier* (pp. 240—1).

The traction in the fibre will now be given by

$$Ed\omega \left(\frac{\tau^2 r^2}{2} - \eta \right),$$

where E is the longitudinal stretch-modulus. The quantity $-\eta$ must be determined by the condition that the total traction is zero, or

$$\int_0^a 2\pi r dr E \left(\frac{\tau^2 r^2}{2} - \eta \right) \sin P'PN = 0.$$

Since
$$\sin P'PN = \frac{1-\eta}{1-\eta + \frac{\tau^2 r^2}{2}} = 1 - \frac{\tau^2 r^2}{2}$$

it may be put $= 1$ in the integral.

We find $\frac{\tau^2 a^4}{4} = a^2 \eta$, giving $\eta = \frac{\tau^2 a^2}{4}$, a result which agrees with Saint-Venant's; our analysis thus proves that η is of the *second order* in τ .

Further we have for the total-moment of these tractions about the axis

$$M = \int_0^a 2\pi r dr E \left(\frac{\tau^2 r^2}{2} - \frac{\tau^2 a^2}{4} \right) \cos I'PN \times r \\ = E\pi\tau^3 \int_0^a r^3 dr \left(r^2 - \frac{a^2}{2} \right), \text{ since } \cos I'PN = \tau r; \\ = \frac{E\pi a^3}{24} (\tau a)^3.$$

Section VIII. MAINTENANCE OF SHOVEL FRONT ATTACHMENT

2-25. General

a. This section contains instructions for service, adjustment, repair and replacement of the shovel front attachment and components.

b. Use a crane or other adequate lifting device for removing and installing components.

2-26. Shovel Front Attachment

a. *Service.* The shovel front must be lubricated at the periodic intervals listed in the current lubrication order (LO 3810-294-12). When removed from the machine, all exposed finished surfaces must also be lubricated as often as required to prevent damage due to rust and corrosion. If possible, the entire attachment should be placed inside a suitable dry building, preferably on wooden blocking. The shovel front should be cleaned with cleaning solvent. Paint the shovel boom as required to prevent rust and corrosion. (Refer to TM 9-213.)

b. *Adjustments.* Each of the following adjustments must be checked after every 40 hours of shovel operation. Adjust only if necessary.

(1) *Saddle block adjustment.* Shims and wear plates are used to adjust the clearance between the dipper stick and the saddle block wear plates as shown in figure 2-32. The desired minimum clearances between wear plates and saddle blocks are 1/64-inch at each location. Adjustment is mandatory when clearance reaches 1/16-inch at any point illustrated. Use the following procedure for adjustment:

(a) Support the dipper stick in horizontal position, using the hoist line.

(b) Divide the dipper stick into three approximately equal lengths, using chalk marks or paint.

(c) Move the dipper stick back and forth a few times to make sure it is free in the saddle blocks and in its normal operating condition.

(d) Position the dipper stick so that the outer third of the dipper stick, as measured by the chalk or paint marks, is located in the saddle block. Measure the clearance between the wear plates on each side of the dipper stick and the dipper stick. Record the measured distance.

(e) Measure the clearance between the top of the dipper stick and the wear plate at each end of the saddle block and record the measured distance.

(f) Repeat steps (d) and (e) above for each of the other two marked sections of the

dipper stick, each time recording the measurements.

(g) Loosen wear plate bolts and insert shims beneath the wear plates until the clearance between the dipper stick and the wear plates is approximately 1/64-inch at the thickest point of the dipper stick. Adjust both top and side clearances in this manner.

NOTE

Shims are slotted so they may be tapped into place without removing wear plates.

(2) *Crowd chain adjustment.* Adjust for crowd chain wear as illustrated in figure 2-24. Total midspan chain slack at top of chain must be maintained at approximately 1/4-inch.

(3) *Rake angle adjustment.* Refer to figure 2-33 and adjust the dipper pitch braces in accordance with type of material being moved and working conditions. In general, pin the pitch brace in hole 1 for easy digging and low bank cuts. Pin the brace in hole 2 for medium or average soil conditions and bank heights, and in hole 3 for hard digging, high banks, and when grading the area.

(4) *Retract cable tension adjustment.* Refer to figure 2-34 and adjust retract cable tension.

(5) *Dipper trip cable adjustment.* This adjustment should not be necessary unless the dipper trip cable wears or stretches. Therefore, the cable should be inspected to determine that it is safe for further use before it is adjusted. Refer to figure 2-34 and adjust the dipper trip cable tension.

(6) *Dipper latch bar adjustment.* The dipper latch bar must be adjusted to move forward into the opening in the dipper latch as latch bar wear occurs. Refer to figure 2-35 and adjust the dipper latch bar.

c. *Shovel Front Replacement.* Refer to paragraph 2-9 for removal or replacement of the shovel front attachment.

2-27. Idler Sprocket Replacement

a. Inspect sprockets for wear or other defects. Replace a badly worn or defective sprocket to prevent excessive chain wear.

b. Refer to figure 2-36 and remove or replace the idler sprocket assembly by removing the attaching bolts.

2-28. Crowd Chain

a. *Replacement.* The crowd chain may be opened at any point for chain replacement. The

longitudinal stretch. Thus we find as safe-stretch limit

$$(i) \dots 1 = \text{maximum of } \frac{1-\eta_1}{2} \frac{E_1}{T_1} s_x + \sqrt{\left(\frac{1+\eta_1}{2} \frac{E_1}{T_1} s_x\right)^2 + \left(\frac{\mu \sigma_x}{S}\right)^2}.$$

We take the positive sign of the radical, because if $\sigma_x = 0$ we should have the alternative between $\frac{E_1}{T_1} s_x$ and $-\eta_1 \frac{E_1}{T_1} s_x = \frac{E_1}{T_1} s_y$, and the former will be considered the greater (Saint-Venant, p. 484).

Case (2). A like equation is obtained, if, without supposing an axis of elasticity, two out of the three slide components vanish at a *fail-point*.

Case (3). This is a case of approximation, Saint-Venant supposes σ_{yz} to be zero; but $-s_y/\bar{s}_y$ and $-s_z/\bar{s}_z$ without being equal to differ but slightly, and he then takes them equal to $\eta_2 \frac{s_x}{\bar{s}_x}$ 'une certaine moyenne entre ces deux rapports.' Thus he replaces $(s/\bar{s} - s_y/\bar{s}_y) (s/\bar{s} - s_z/\bar{s}_z)$ by $(s/\bar{s} + \eta_2 s_x/\bar{s}_x)^2$ and divides out all the terms by the same factor. We thus reach the equation

$$\left(\frac{s}{\bar{s}} - \frac{s_x}{\bar{s}_x}\right) \left(\frac{s}{\bar{s}} + \eta_2 \frac{s_x}{\bar{s}_x}\right) - \frac{\sigma_{xy}^2}{\bar{\sigma}_{xy}^2} - \frac{\sigma_{xz}^2}{\bar{\sigma}_{xz}^2} = 0,$$

and obtain for the safe-stretch condition

(ii) ... 1 = maximum of

$$\frac{1-\eta_2}{2} \frac{E_1}{T_1} s_x + \sqrt{\left(\frac{1+\eta_2}{2} \frac{E_1}{T_1} s_x\right)^2 + \left(\frac{\mu_1 \sigma_{xy}}{S_1}\right)^2 + \left(\frac{\mu_2 \sigma_{xz}}{S_2}\right)^2}.$$

Here η_2 is given, I think, most satisfactorily by the arithmetic mean

$$\frac{1}{2} \left(\frac{s_y}{\bar{s}_y} + \frac{s_z}{\bar{s}_z} \right) = -\eta_2 \frac{s_x}{\bar{s}_x}.$$


Now if $s_y = -\eta s_x$, and $s_z = -\eta' s_x$,

$$\begin{aligned} \eta_2 &= \frac{1}{2} \left(\eta \frac{\bar{s}_x}{\bar{s}_y} + \eta' \frac{\bar{s}_x}{\bar{s}_z} \right) \\ &= 2 \left(\eta \frac{1}{\bar{\sigma}_{xy}^2} + \eta' \frac{1}{\bar{\sigma}_{xz}^2} \right) \bar{s}_x^2 : \text{ see our Art. 5 (d),} \\ &= 2 \left\{ \eta \left(\frac{\mu_1}{S_1} \right)^2 + \eta' \left(\frac{\mu_2}{S_2} \right)^2 \right\} \frac{T_1^2}{E_1^2}. \end{aligned}$$

This result gives a constant value for η_2 and appears to agree with Saint-Venant's note on *Clebsch*, p. 275. I do not think the value given for ϵ'_1 (= our η_2) on p. 485 of the memoir is quite satisfactory.

It will be noted that in all three cases the resulting quadratic is practically of the same form and the condition may for all three be thrown into a somewhat different shape, namely, transposing and squaring we find

$$(iii) \dots \left(1 - \frac{E_1 s_x}{T_1}\right) \left(1 + \eta_2 \frac{E_1}{T_1} s_x\right) - \left(\frac{\mu_1 \sigma_{xy}}{S_1}\right)^2 - \left(\frac{\mu_2 \sigma_{xz}}{S_2}\right)^2 - \text{or} > 0.$$



ME 3810-294-20 2-33

Figure 2-38. Rake angle and retract cable adjustment.

easiest point will be at the boom foot drum sprocket, since the chain is accessible and supported by the sprocket. To open the chain, chisel off the cotter pin (fig. 2-36) and drive out the chain connecting pin at the point shown. To re-install the pin, wrap the chain around the two sprockets as shown. Make sure the chain points in the direction shown in figure 2-37. Then support the chain on one side with a heavy hammer or steel plate while installing the connecting pin and a new cotter pin.

b. *Repair.* If a single section of unworn chain should break, refer to figure 2-38 and repair the chain by replacing the broken link.

2-29. Dipper Trip Motor Magnetic Switch and Wire Leads

a. Refer to the dipper trip wiring diagram, figure 2-39. When the shovel attachment is in-

stalled, the dipper trip pushbutton switch is mounted on a bracket on the front drum clutch lever. If closing the dipper trip pushbutton will not actuate the dipper trip mechanism, first check the batteries (para 2-53).

b. Refer to figure 2-40 and replace the dipper trip motor magnetic switch and wire leads.

2-30. Dipper and Dipper Teeth Replacement

a. *Dipper Replacement.* Refer to figure 2-41 and remove or replace the shovel dipper.

b. *Dipper Tooth Replacement.* Drive out the attaching pins and replace dipper teeth.

NOTE

Dipper teeth can be kept sharp in service by regularly reversing them, top for bottom, as they wear. However, when teeth are worn to about one third their original length, they must be replaced.

The expressions (v) of course are only true for these exceptional sections, which can never occur in pure torsion as sections of danger, while in practical cases of flexure combined with torsion or slide they are frequently found to be specially strengthened (e.g. built-in ends).

[56.] We will now enumerate the examples Saint-Venant gives of the above condition of safety.

Case (1). Consider a rectangular prism (cross-section $2b \times 2c$) subjected only to a force P parallel to the axis of z (or side $2c$). Let the built-in terminal of the prism be so fixed that it can be distorted by flexure. Then if the length of the prism be a , and $2c$ be much greater than $2b$, we have

$$\begin{aligned}\mu_2 \sigma_{xx} &= \frac{3}{2} \frac{P}{\omega} \left(1 - \frac{z^2}{c^2}\right), & P_x = P_y = 0, \\ \sigma_{xy} &= 0, & Es_x = Paz \left/ \frac{\omega c^3}{3} \right.;\end{aligned}$$


so that, *granting uniconstant isotropy*, $S = \frac{4}{5} T$, $\eta = \frac{1}{4}$, and thus the equation (i) of our Art. 53 becomes

$$1 = \text{maximum of } \frac{3Pa}{T\omega c} \left[\frac{3}{8} \frac{z}{c} + \frac{5}{8} \sqrt{\frac{z^2}{c^2} + \left(\frac{c}{a}\right)^2 \left(1 - \frac{z^2}{c^2}\right)^2} \right].$$

Saint-Venant gives a table of the values of the quantity between square brackets for values of $z/c = 0$ to 1, and for values of $2c/a$ (depth to length) from 3 to 6. From this table the following results may be drawn. So long as $2c/a < 3.05$ the *fail-point* lies on the surface of the prism where $z/c = 1$, or at that point *where there is no slide*. If then the ratio of depth to length be < 3.05 , the prism's resistance is just that of flexure without consideration of slide. If on the other hand $2c/a > 3.05$ the maximum passes abruptly to the points for which $z/c = .2$ about, and approaches more and more to those for which $z = 0$. But this latter point lies on the *neutral-axis*, or it must be *slide* and not *flexure* which produces the failure. When $2c/a = 3.2$ we may calculate the resistance either from flexure or transverse slide, but after $2c/a = 4$, it is the slide alone which is of importance. Similar conclusions Saint-Venant tells us may be obtained for a circular section (radius r); in this case the fail-point passes abruptly when $2r/a = 4.3$ from $z = r$ to $z = .2r$ about.

The reader who bears in mind Vicat's attack upon the mathematical theory of elasticity (see our Arts. 732^a—733') will find that the above remarks satisfactorily explain Vicat's experimental results.

Case (2). This is that of a prism (length $2a$, section $2b \times 2c$) terminally supported and centrally loaded. Here the section of greatest strain suffers no distortion. If the load P be in the direction of



ME 3810-294-20 2-35

Figure 2-35. Dipper latch bar adjustment.

I shall have something to say of these experiments when dealing with Morin's *Résistance des matériaux*, 1853 : see our Chap. xi.

Case (4). This case gives the calculation of the 'solid of equal resistance' for a bar built-in at one end and acted upon at the other by a non-central load perpendicular to its axis, i.e. combined flexure and torsion. Saint-Venant supposes uni-constant isotropy and neglects the flexural slides. His final equation is

$$2 \frac{T\pi r^3}{P} = 3x + 5\sqrt{x^2 + k^2}.$$

Here P is the load acting on an arm k , and r is the sectional radius at distance x from the loaded terminal. (p. 504.)

Case (5). An axle terminally supported has weight Π and carries two heavy wheels (ϖ and ϖ') upon which act forces, whose moments about the axle are equal and whose directions are perpendicular to the axle. We have thus another case of combined flexure and torsion, which is dealt with as before.

[57.] The next case treated by Saint-Venant is of greater complexity; it occupies pp. 507—18 of the memoir. It is the investigation of combined flexural and torsional strain in rectangular prisms ($2b \times 2c$), and possesses considerable theoretical interest. In practice also the non-central loading of beams of rectangular section must be a not infrequent occurrence.


Case (6). Saint-Venant in his treatment does not suppose the elasticity round the prismatic axis to be isotropic, but takes the general case of two slide-moduli, supposing, however, that $b\sqrt{\mu_2} > c\sqrt{\mu_1}$.

He neglects also the flexural slide-components. Let the torsional slide-components be given by $\sigma_1 = -\gamma_y \tau$ and $\sigma_2 = \gamma_z \tau$ for $z/c = 1$ and $y/b = 1$ respectively. τ must be eliminated by means of the relation $M'' = \beta \mu_1 \tau b c^3$. If ϕ be the angle the plane of the flexural load makes with the plane through the prismatic axis and the axis of y , and M' the flexural moment at section x , we easily obtain for the stretch s_x the value

$$\begin{aligned} s_x &= \frac{3M'}{4Ebc} \left(\frac{z \cos \phi}{c^3} + \frac{y \sin \phi}{b^3} \right) \\ &= (\text{for } z = c) \frac{3M'}{4bc^3} E \left(\cos \phi + \frac{c}{b} \frac{y}{b} \sin \phi \right) \\ &= (\text{for } y = b) \frac{3M'}{4bc^3} E \left(\frac{z}{c} \cos \phi + \frac{c}{b} \sin \phi \right). \end{aligned}$$

Let us substitute these values in equation (ii) of our Art. 53. Taking these expressions alternately for the sides $2b$ and $2c$ we obtain :

$$\begin{aligned} 1 &= \text{maximum} \frac{1 - \eta_2}{2T'} \frac{3M'}{4bc^3} \left(\cos \phi + \frac{c}{b} \frac{y}{b} \sin \phi \right) \\ &\quad + \sqrt{\left[\frac{1 + \eta_2}{2T'} \frac{3M'}{4bc^3} \left(\cos \phi + \frac{c}{b} \frac{y}{b} \sin \phi \right) \right]^2 + \left(\gamma_y \frac{M''}{\beta b c^3} \right)^2}, \end{aligned}$$



- STEP 1. PLACE THE CHAIN ON STEEL PLATE WITH BUSHING BENEATH PIN. BUSHING MUST HAVE HOLE LARGER THAN PIN, AND MUST BE LONG ENOUGH TO ALLOW PIN TO MOVE.
- STEP 2. STRIKE THE PIN VERY SHARPLY. HIT IT HARD. THIS WILL DRIVE THE PIN FROM THE CHAIN, WHILE CUTTING OFF COTTER PIN.
- STEP 3. INSTALL NEW PIN AND DRIVE COTTER PIN IN PLACE. DO NOT FILE DOWN PINS TO AID IN INSTALLING. PRESS FITS ARE NEEDED FOR CHAIN LIFE.

ME 3810-294-20/2-38

Figure 2-38. Chain, repair and replacement.

(2) c so much less than b that $c/b \cdot \tan \phi$ may be neglected as compared with 1, i.e. the case of a 'plate' (pp. 511—2).

(3) Prism on square base, when $\tan \phi = 0$, $= \frac{1}{2}$, $= 1$, and $=$ anything whatever when there is a non-distorted section for section of least safety (pp. 512—4). The fail-points are also determined.

(4) Prism on rectangular base for which $b = 2c$, when $\tan \phi = 0$, $= \frac{1}{2}$, $= 1$, $= 2$, $= \infty$, and $=$ anything whatever when there is a non-distorted section for that of least safety (pp. 514—518). The fail-points are also determined.

[59.] On pp. 518—22 we have the treatment of a prism on elliptic base subjected at the same time to flexure and torsion. Saint-Venant only works this out numerically for the case of uni-constant isotropy and when $\tan \phi = \infty$.


It is found that after a certain value of the ratio of torsional to flexural couple, the fail-point leaves the end of the major axis (through which the flexural load-plane passes¹) and traverses the quadrant of the ellipse till it reaches the end of the minor axis (p. 522).

[60.] We now turn to Saint-Venant's final chapter (pp. 522—558). This consists of three parts: § 135 *Résumé général*; § 136 *Récapitulation des formules et règles pratiques* and § 137 *Exemples d'applications numériques*.

In the first article there is little to be noted. A reference is made on p. 528 to the models of M. Bardin shewing the *gauchissement* of the cross-section to which we have previously referred. Saint-Venant also mentions the visible distortion of the cross-sections obtained by marking them on a prism of caoutchouc and then subjecting it to torsion.

In the general recapitulation of formulae we have some results not in the body of the memoir, as on p. 536 (d_1) where the flexural slides for the prism whose base is the curve $\left(\frac{y}{b}\right)^4 + \left(\frac{z}{c}\right)^2 = 1$ are cited from the memoir on flexure: see our Art. 90. So again on p. 546 for the flexural slides of other cross-sections. The best *résumé*, however, of formulae as well as numbers for both flexure and torsion is undoubtedly to be found in Saint-Venant's *Leçons de Navier* to which we shall refer later. The last section § 137 contains some instructive numerical examples of Saint-Venant's treatment of combined strain.

¹ Saint-Venant terms this *sollicité de champ*. When the load-plane is perpendicular to this the prism is *sollicité à plat*.



- STEP 1. DISCONNECT ELECTRICAL LEADS.
- STEP 2. REMOVE CAPSCREWS AND LOCKWASHERS.
- STEP 3. REMOVE MAGNETIC SWITCH.

ME 3810-294-20/2-40

Figure 2-40. Dipper trip magnetic switch, removal.

[64.] In the same volume of the same Journal, pp. 220—1, are particulars of the memoir on the Flexure of Prisms communicated to the *Société Philomathique*.

[65.] In the same volume of this Journal, pp. 396—398, is another communication of Saint-Venant's to the *Société Philomathique* (July 8, 1854). This deals with the formulæ for the flexure of prisms and for their strength, when the cross-section does not possess inertial isotropy. It gives the general equations and treats specially the case of a rectangular cross-section: see the *Leçons de Navier*, pp. 52—58 and our Arts. 1581*, 14 and 171.

A final paragraph to the paper points out that the resistance to torsion varies more nearly inversely than directly as the axial moment of inertia: see our Art. 290.

[66.] On pp. 428—31 of the same volume of the same Journal Saint-Venant communicates to the *Société Philomathique* (July 8 and October 21, 1854) the results obtained from the stretch-condition of strength. These results were afterwards published in the memoir on Torsion: see our Arts. 53 *et seq.*

[67.] Volume 23 of the same Journal, pp. 248—50. Further results of the memoir on *Torsion* communicated to the *Société Philomathique* (April 12 and May 12, 1855), notably the case of a prism on an equal-sided triangular base: see our Arts 40—2.

[68.] The same volume of the same Journal, pp. 440—442. *Diverses considérations sur l'élasticité des corps, sur les actions entre leurs molécules, sur leurs mouvements vibratoires atomiques, et sur leur dilatation par la chaleur.* An account of a memoir presented October 20, 1855, to the *Société Philomathique* containing general remarks on the rari-constant theory of intermolecular action. The expression for the velocity of sound on p. 441 *b* should be $\sqrt{\frac{3G-p}{\rho}}$ and not $\sqrt{\frac{3G+p}{\rho}}$: see *L'Institut*, Vol. 24, p. 215. Saint-Venant refers to the labours of Newton, Ampère and others on this subject: see our Art. 102. He points out that in order to explain heat by translational vibrations, the second differential of the function which expresses the law of intermolecular force must be *positive*: see our Arts. 268 and 273.

Dipper Assembly Pitch Adjustment. Refer to paragraph 2-8d and adjust the backhoe pitch.

Repair and Replacement.

- 1) Inspect sheaves and sheave bushings. Replace faulty sheaves or sheave bushings as indicated in paragraph 2-8.
- 2) Inspect all parts for wear, defects, or damage of any type, and repair or replace defective parts.
- 3) Replace side cutters if they are dull or damaged.
- 4) Refer to paragraph 2-8 for removal or replacement of backhoe front attachment or components.

Dipper Assembly

General. The dipper assembly consists of the dipper, dipper teeth, side cutters, attaching pins and bushings, and bracket assembly, block, and link assembly. The dipper is attached to the handle and pitch brace assembly. It is actuated by pull cables through the bracket assembly, and link assembly.


Removal.

- 1) Lower dipper to rest on blocks, then disconnect drag cable from bracket assembly, block, and link assembly.
- 2) Remove cotter pins and washers from handle and pitch brace pins. Remove handle and pitch brace pins and remove dipper and bracket assembly, block, and link assembly from handle.

Cleaning, Inspection and Repair.

- 1) Clean parts and attaching hardware with cleaning solvent.
- 2) Inspect parts and attaching hardware for damage and wear.
- 3) Inspect teeth and side cutters for wear and damage.
- 4) Inspect bracket assembly, block, and link assembly for worn or damaged links, broken

- STEP 1. DRIVE OUT PIN AND PIN KEEPER.
- STEP 2. INSTALL NEW TEETH.
- STEP 3. IF NECESSARY, DRIVE OUT ADAPTER KEEPER AND REPLACE.



ME 3810-294-20/2-42

Figure 2-42. Dipper teeth, removal and replacement.

pins, and missing parts. Inspect sheaves and bushings for wear and damage.

(5) Repair or replace damaged, worn, or missing parts.

d. Dipper Teeth Replacement. Dipper teeth must be replaced when they are worn to about one third their original length. Refer to figure 2-42 and replace dipper teeth.

Section X. MAINTENANCE OF PILEDRIVER ATTACHMENT

General

Maintenance of the piledriver attachment consists of service, inspection, repair, and replacement.

Use a crane or other adequate lifting device for removing and installing components.

Piledriver Rig

Service. Keep the piledriver rig clean, well

painted, and keep machined surfaces lubricated in accordance with LO 5-3810-294-12.

b. Repair. Inspect the piledriver rig for faulty welds, bent lacings, or other damage to structural members. Any damaged item which affects structural strength must be repaired or replaced.

c. Replacement. Refer to paragraph 2-7 for replacement of the piledriver rig.

on *Torsion* had given the outlines of the true theory of flexure: see our Arts. 9—13.

[71.] The third section (pp. 98—101) is entitled: *Objet et sommaire de ce memoire*. Saint-Venant here indicates that he intends to use the semi-inverse method (see our Art. 3) to test how far the Bernoulli-Eulerian formulae:

$$\begin{cases} \text{Traction} = Ez/\rho, \\ \text{Bending moment} = E\omega\kappa^2/\rho, \\ \int z d\omega = 0, \end{cases}$$

(see our Arts. 20*, 65*, 75*, etc.)

are correct, when consideration is paid to the influence of slide. There is also a succinct account of the contents of Sections 4—32 of the memoir.


[72.] Sections 4—12 (pp. 101—120) contain an elementary sketch of the general theory of elasticity. Saint-Venant wrote three other such sketches, namely (i) in the memoir on *Torsion* (see our Art. 4); (ii) in the *Leçons de Navier* (see our Art. 190); and (iii) for Moigno's *Statique* (see our Arts. 224—9). This sketch falls between (i) and (ii). It adopts rari-constancy and bases it upon intermolecular action being central and a function of central distance only. This rari-constancy Saint-Venant holds to be without doubt true for bodies of 'confused crystallisation' such as are used for the materials of construction (p. 108). At the same time for the sake of the 'weaker brethren,' and as it does not increase the difficulty of solving the elastic equations, he adopts multi-constant formulae.

[73.] As a specimen of the mode of treatment, we reproduce his proof of the equality of the cross-stretch and direct-slide coefficients, i.e. in our notation $|xxyy| = |xyxy|^1$.

We have to shew that the coefficient of s_y in $\widehat{xx} =$ the coefficient of σ_{xy} in \widehat{xy} .

Suppose all the strain-components zero except s_y and σ_{xy} and these to be constant for all points of the body. Suppose the central distance of two molecules m', m'' to have length r , and projections x, y, z on the coordinate axes before strain. After strain x and z remain unchanged, but y will be increased by ys_y owing to the stretch and $x\sigma_{xy}$ owing to

¹ See the footnote to our Art. 116.



- STEP 1. REMOVE COTTER PIN AT EITHER END.
- STEP 2. REMOVE EXTERNAL WASHER AT END COTTER PIN WAS REMOVED.
- STEP 3. PRESS ROLLER PIN OUT FROM END COTTER PIN WAS REMOVED. REMOVE SPACERS AND GUIDE ROLLERS.

ME 3810-294-20/2-44

Figure 2-44. Cable guide rollers, removal.

2-41. Bridle Assembly Service, Replacement, and Repair

a. *General.* The bridle assembly contains the sheaves for the boom hoist cable and provides the point of attachment for boom guy cables. The bridle assembly is sometimes called the spreader assembly.

b. *Removal.* Refer to paragraph 2-4 and remove the bridle assembly.

c. *Service and Repair.* Refer to figure 2-46. Clean and inspect sheave bushings for signs of wear or damage and replace damaged bushings. Inspect sheaves for wear, grooving, or cracks, and replace worn or damaged sheaves. Inspect sheave pins for wear or scoring and smooth small rough points with a fine file or emery cloth. Replace severely worn or scored pins. Clean sheaves with solvent, removing all old lubricant. Inspect lubrication fittings and make sure




Figure 2-45. Hook block.

that passages are open and have been receiving the lubricant.

NOTE

A properly grooved sheave has smooth side walls and the groove is only slightly wider than the cable. Use a light layer of lubricant when reinstalling pins, bushings, and other fitted parts. Be sure lubrication fittings are properly installed and line up with grease holes.

d. *Installation.* Refer to paragraph 2-4d and install the bridle assembly.

2-42. Clamshell and Dragline Bucket Service, Replacement, and Repair

a. *Service.* The bucket must be kept clean and wear points must be kept lubricated in accordance with LO 5-3810-294-12.

b. *Replacement.*

(1) *Clamshell bucket.* Refer to paragraph 2-5 for removal and installation of the clamshell bucket.

(2) *Dragline bucket.* Refer to paragraph 2-6 for dragline bucket removal and installation.

(3) *Bucket teeth.* When teeth are worn to about one third of their original length, drive out the attaching pins and replace bucket teeth (fig. 2-42).

NOTE

Dragline bucket teeth can be reversed, top for bottom, to equalize wear and keep them sharp during operation.

(4) *Dump cable.* Replace dump cable when it is frayed or worn.

(5) *Sheave bushings.* Replace sheave bushings and sheaves as described in paragraph 2-41c.

[75.] Section 13 (pp. 121—123) deals with Poisson and Cauchy's method of treating the problem of flexure by expanding the stresses as positive integral algebraic functions of the co-ordinates of the point on the cross-section referred to axes in the cross-section: see our Arts. 466* and 618* (footnote). This method Saint-Venant admits had served for the departure of his own researches (p. 99), and he deals more gently with it here (p. 124) than he does in his later work. The assumption of the possibility of the expansion in a convergent series is a very dangerous one, and leads in the case of torsion to very erroneous results: see our Arts. 1626* and 191 (or *Lçons de Navier*, footnote pp. 621—7).

[76.] In §§ 14—17 (pp. 125—36) Saint-Venant gives the general solution of the problem of flexure, carefully stating his assumptions and once integrating his equations. He reduces the solution to the determination of a single function F , which can be chosen to suit a great variety of cross-sections. I will reproduce as briefly as possible the matter of these sections.

[77.] Taking a portion of a weightless prism between two cross-sections Saint-Venant proposes to determine its state of equilibrium after it has been subjected to flexure on the following suppositions:

(i) The character of a certain portion of the shifts and strains is assumed; namely, the axis of the prism, or the right line joining the centroids of the cross-sections, is supposed to become a plane curve (*elastic line* here one with the *neutral line*), and further the stretches of the longitudinal 'fibres' vary in a uniform manner with their distances from each other measured parallel to the plane of the elastic line.

Let x be the direction of the line of centroids before flexure and let the origin be its fixed extremity (see (iii)), and let xz be the plane of flexure (or of the elastic line), then the above condition is analytically represented by

$$s_x = Cz + C' \dots\dots\dots (1),$$

where C and C' are constants for the cross-section.

(ii) The character of a certain portion of the stresses is assumed; namely, it is supposed that the fibres exercise no mutual *traction* upon each other, or that their mutual action is solely of the nature of shear. Further, on the terminal cross-sections there is supposed to be no tractive loading.

2-43. Fairlead, Service and Replacement

a. Service.

(1) Inspect for excessive grooving of fairlead sheaves or rollers.

(2) Lubricate in accordance with LO 5-3810-294-12.

b. Replacement.

(1) The fairlead is mounted on a bracket located on the front of the revolving frame. Use a suitable lifting device for removal and installation.

(2) Refer to figure 2-13. Remove nuts, lockwashers, and U-bolts, and remove fairlead. Replace fairlead as described in steps 1 and 2 of figure 2-13.

2-44. Boom Jib Mast, Service and Replacement

a. *General.* The boom jib mast is also called the jib strut and is used to support the jib when a jib is in use.

b. *Jib and Jib Strut Service.* Service for the jib and jib strut is the same as for the crane boom. Refer to paragraph 2-37a and service the jib and jib strut.

c. *Jib and Jib Strut Replacement.* Refer to figure 2-47 and replace the jib and jib strut.

2-45. Cable Replacement

a. *General.* To replace either the front or the rear drum load cable, place the drum brake for the cable to be removed in the brake released position.

b. Replacement of Load Cables.

(1) Lower the hook block to the ground or to suitable blocking.

(2) Loosen the cable clamp at the cable dead end. This may be at the boom point or the hook block, depending on the number of parts of line in use.

(3) Manually unreeve the hook block (fig. 2-11).

(4) Raise the boom to any convenient height so that the line hangs downward. One man can then pull the cable off the drum. When the cable end is reached, refer to figure 2-10 and remove the cable wedge from the drum lagging.

(5) To install the new cable, place the new cable reel beneath the boom point sheaves.

(6) Run the end of the new cable over the boom point sheaves to the correct main drum.

(7) Refer to figure 2-10 and install the new cable wedge in the drum, being careful that

the cable goes over the top of the rear drum, or beneath the front drum.

(8) Carefully and slowly spool the new cable on the selected drum, using the proper drum clutch lever. As this is done, one man should tap the new cable into place on the drum with a soft hammer.

(9) A second man should maintain some drag on the new cable reel so the cable is under tension.

(10) A third man operates the proper drum clutch lever to wind the cable on the drum.

c. Replacement of Boom Hoist Cable.

(1) Provide adequate wooden blocking to support the boom.

(2) Lower boom until it is supported on blocking as illustrated in figure 2-3.

(3) Pay off more cable until the upper spreader lies on the boom.

(4) Refer to figure 2-48 and disconnect the boom hoist cable from the lower spreader.

(5) Release the boom hoist pawl and the boom hoist brake (TM 5-3810-294-10).

(6) Unreeve the boom hoist line and pull it from the boom hoist drum.

NOTE

The boom hoist drum may be used to pay the line off the drum under power if the operator desires. When this is done, one man standing on the ground must pull the cable out of the cab.

(7) Refer to figure 2-10 and remove the cable wedge to complete removal of the cable.

(8) Position the new cable reel close to the upper spreader and near the boom.

(9) Starting at the center (equalizer) sheave of the upper spreader, reeve the boom hoist cable back to the dead end on the lower spreader as shown in figure 2-48.

(10) Pull the rest of the cable off the new cable reel and reeve the other half of the boom hoist cable back to the boom hoist drum, as shown in figure 2-9.

(11) Install new cable wedge in the boom hoist drum as shown in figure 2-10.

(12) Carefully and slowly spool the new cable on the boom hoist drum. As this is done, one man should tap the new cable into place with a soft hammer.

2-46. Pulleys (Boom Point Sheaves) Service and Replacement

a. *General.* Boom point sheaves are illustrated in figure 2-49. They provide low friction pivot points for load cable movement.

If we now turn to the body stress-equations we find they reduce to

$$\left. \begin{aligned} \frac{d\widehat{xy}}{dy} + \frac{d\widehat{xz}}{dz} &= -\frac{z}{\omega\kappa^2} \frac{dM}{dx} \\ \frac{d\widehat{xy}}{dx} &= 0, \quad \frac{d\widehat{xz}}{dx} = 0 \end{aligned} \right\} \dots\dots\dots(11),$$

while the surface stress-equations reduce to the single one

$$\widehat{xz}dy - \widehat{xy}dz = 0 \dots\dots\dots(12).$$

The last two equations of (11) lead us by means of the last two of (7) to the conditions¹

$$\frac{d\sigma_{xy}}{dx} = 0, \quad \frac{d\sigma_{xz}}{dx} = 0,$$

or, to

$$\frac{d^2u}{dxdy} + \frac{d^2v}{dx^2} = 0, \quad \frac{d^2u}{dxdz} + \frac{d^2w}{dx^2} = 0.$$

Hence, putting for $du/dx = s_x$ its value $zM/E\omega\kappa^2$, we have, since M is supposed a function of x only,

$$\frac{d^2v}{dx^2} = 0, \quad -\frac{d^2w}{dx^2} = M/E\omega\kappa^2 \dots\dots\dots(13).$$

The first equation tells us that there is no curvature in the direction of y after flexure, the second that the curvature $\left(1/\rho = -\frac{d^2w}{dx^2}\right.$ for small shifts) in direction of z is equal to $M/E\omega\kappa^2$.

We thus obtain

$$M = E\omega\kappa^2/\rho, \quad s_x = z/\rho, \quad \widehat{xz} = Ez/\rho \dots\dots\dots(14),$$

the formulae of the Bernoulli-Eulerian theory, here deduced without its invalid assumptions (i.e. that the cross-sections remain plane and normal to the strained fibres).

[80.] The first equation of (11) shews that if M is variable or in other words the curvature changes, the stresses \widehat{xy} , \widehat{xz} and therefore the slides σ_{xy} , σ_{xz} cannot be zero, or it involves the contradiction of the Bernoulli-Eulerian assumptions.

Further differentiating the same equation with regard to x , we deduce by the second and third equations of (11) the result

$$\frac{d^2M}{dx^2} = 0 \dots\dots\dots(15),$$

or M must be of the linear form in x ,

$$= P(a - x) \dots\dots\dots(16),$$

¹ Provided the relation $e/h'' = h'''/f$ does not hold between the elastic constants.

b. Service. Clean the boom point sheaves and lubricate in accordance with LO 5-3810-294-12.

c. Replacement.

(1) Refer to figure 2-49 and remove boom point sheaves.

(2) Reverse sequence of steps in figure 2-49 to install sheaves.

2-47. Backstop Assembly, Replacement

a. General. Boom backstops are provided strictly as a means of giving an operator a visual way of telling when the boom has been raised to the maximum limit. They must never be used to prevent the boom from being raised too high.

b. Removal.

(1) Refer to figure 2-6(2). Remove cotter pins and backstop pins at gantry.

(2) Refer to figure 2-6(1). Remove cotter pins and backstop pins and remove boom backstop from boom.

c. Installation. Install boom backstop between the gantry and boom as shown in figure 2-6(1) and 2-6(2).

2-48. Angle Indicator, Replacement

a. Refer to figure 2-7. Remove nuts, lockwashers, and bolts and remove angle indicator.

b. Install angle indicator as shown in figure 2-7.



- STEP 1. LOWER BOOM TO SUITABLE SUPPORT.
- STEP 2. ENGAGE BOOM HOIST PAWL.
- STEP 3. REMOVE COTTER PIN AND PIN.
- STEP 4. REMOVE CABLE SOCKET AND PLACE ON NEW CABLE.
- STEP 5. INSTALL PIN AND COTTER PIN.

ME 3810-294-20 2-48

Figure 2-48. Boom hoist cable, lower spreader connection, removal and replacement.

These results follow by simple analytical work if we start with the value of u obtained from the equation $s_x = z/\rho = P(a-x)z/E\omega\kappa^2$ and then proceed to those of v and w given by the second and third equations of (8), the values so found being made to satisfy (11), etc.

[83.] Saint-Venant, however, does not deal in his special examples with this general case of elastic distribution; he assumes the material to have planes of elastic symmetry perpendicular to y and z , as well as perpendicular to x . We then have $h'' = h''' = h = k = l = h' = k' = l' = 0$, and clearly $\epsilon = 0$.

Further,

$$\widehat{xy} = f\sigma_{xy}, \quad \widehat{xz} = e\sigma_{xz}, \quad \sigma_{yz} = 0 \dots\dots\dots (20).$$

The equations (18) and (19) now become, if we take¹

$$f = \mu_1, \quad e = \mu_2,$$

$$\frac{\eta_1 f}{E} = \gamma_1, \quad \frac{\eta_2 e}{E} = \gamma_2.$$

$$\left. \begin{aligned} u &= P \frac{2ax - x^2}{2E\omega\kappa^2} z + F(y, z), & v &= -\gamma_1 P \frac{(a-x)}{\mu_1\omega\kappa^2} yz, \\ w &= \sigma_0 x + \frac{P(a-x)}{2\omega\kappa^2} \left(\frac{\gamma_1 y^2}{\mu_1} - \frac{\gamma_2 z^2}{\mu_2} \right) - P \frac{3ax^2 - x^3}{6E\omega\kappa^2} \end{aligned} \right\} \dots\dots (18'),$$

$$\left. \begin{aligned} \mu_1 \frac{d^2 F}{dy^2} + \mu_2 \frac{d^2 F}{dz^2} &= P \frac{1 - \gamma_1 - \gamma_2}{\omega\kappa^2} z \text{ throughout the section; } \\ F &= 0, \quad dF/dz = 0, \text{ when } y = z = 0; \end{aligned} \right\} \dots (19').$$

$$\left. \begin{aligned} \left(\frac{dF}{dy} + \gamma_1 \frac{Pyz}{\mu_1\omega\kappa^2} \right) dz + \mu_2 \left\{ \frac{dF}{dz} + \sigma_0 + \frac{P}{2\omega\kappa^2} \left(\frac{\gamma_2 z^2}{\mu_2} - \frac{\gamma_1 y^2}{\mu_1} \right) \right\} dy &= 0 \end{aligned} \right\}$$

over the contour of the cross-section.

[84.] The last section of general treatment (pp. 133—6) gives formulae for various quantities used for the special cases afterwards dealt with. Thus we note:

First, the values of the stresses:

$$\left. \begin{aligned} \widehat{xx} &= P \frac{(a-x)}{\omega\kappa^2} z, & \widehat{xy} &= \mu_1 \left(\frac{dF}{dy} + \gamma_1 \frac{Pyz}{\mu_1\omega\kappa^2} \right), \\ \widehat{xz} &= \mu_2 \left\{ \frac{dF}{dz} + \sigma_0 + \frac{P}{2\omega\kappa^2} \left(\frac{\gamma_2 z^2}{\mu_2} + \frac{\gamma_1 y^2}{\mu_1} \right) \right\} \end{aligned} \right\} \dots\dots (20').$$

It follows that

$$\sigma_{xz} = \widehat{xz}/\mu_2, \text{ or } = \sigma_0 \text{ for } y = z = 0,$$

that is the inclinations of all the cross-sections at their centres to the axis is the same and equals σ_0 .

¹ I have altered Saint-Venant's notation to correspond with that of our History, he puts for our $\left\{ \begin{smallmatrix} \mu_1 & \mu_2 & \gamma_1 & \gamma_2 & \omega\kappa^2 & \eta_1 & \eta_2 & \epsilon & \sigma_0 \end{smallmatrix} \right\}$.

- STEP 1. REMOVE SCREWS.
 STEP 2. REMOVE HEADLIGHT GUARD.
 STEP 3. REMOVE TWO SCREWS WHICH ATTACH HEADLIGHT CLAMP AND REMOVE HEADLIGHT.
 STEP 4. REPLACE HEADLIGHT, INSTALL LEAD LIGHT CLAMP AND SCREWS. INSTALL HEADLIGHT GUARD AS SHOWN.




Figure 2-50. Headlights, replacement.

lights furnished with this machine, both upper and carrier positions, is illustrated in figure 2-51. Refer to figure 2-51 and remove and replace any defective light component.

d. Repair. Refer to the schematic diagram of the upper wiring, figure 1-4, to isolate wiring problems. Refer to paragraph 2-50 for the method to be used for wiring harness repair.

2-52. Slave Cable Receptacles and Cables

a. General. Slave cable receptacles are provided for recharging batteries from an external

power source. They are provided with covers to prevent dirt and moisture from entering.

b. Replacement. Refer to figure 2-52 and remove and replace a faulty slave receptacle.

c. Slave Cables. Cables must be kept clean and must be inspected before each use to be sure they are not cut, worn, or damaged. A faulty cable could lead to short circuits which could damage the crane and the power source to which the cables are connected.

If $C = 0$ this represents a family of ellipses. If C be finite and we give various values to m we have curves symmetrical with regard to the axis of y , and symmetrical or not with regard to the axis of z according as $m/(1-m)$ is even or odd. Equation (25) can be thrown into a somewhat different form by assuming c to be the semi-axis of the curve in the direction of $\pm z$, and b the semi-axis in the direction y . Thus $y = 0, z = \pm c$, but for $z = 0, y = +b$ always, $= -b$ also if $m/(1-m)$ be treated as even.

In putting $y = 0, z^2 = c^2$ we find,

$$\sigma_0 = -\frac{mPc^2}{2\mu_2\omega\kappa^2} \dots\dots\dots (26).$$

Equation (25) now becomes :

$$\left(1 - \frac{1-2\gamma_1-m}{3m-2} \frac{\mu_2 b^2}{\mu_1 c^2}\right) \left(\frac{y}{b}\right)^{\frac{m}{1-m}} + \frac{1-2\gamma_1-m}{3m-2} \frac{\mu_2 b^2}{\mu_1 c^2} \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1.$$

Saint-Venant now proceeds (pp. 138—143) to discuss the various forms that can be taken by this system of curves. This discussion seems to me perhaps a little too brief. Thus, he says: Supposing $m/(1-m)$ to be treated as even, then it is sufficient and necessary in order that the curve may be closed,—and so capable of serving as a contour for a cross-section,—that z/c have a real value when $y/b = 1 - \chi$, χ being an extremely small positive quantity. This leads him to the condition that m must lie between

$$\frac{1-2\gamma_1}{1+\mu_1 c^2/(\mu_2 b^2)} \text{ and } 1.$$

[87.] We may note the following cases :

The *ellipse* ($2b \times 2c$) is obtained (not by putting $m/(1-m) = 2$ which leads to a logarithmic curve owing to the appearance of indeterminate forms, but) by making the coefficient of $y^{m/(1-m)}$ vanish. Thus we have

$$m = \frac{2\mu_1 c^2 + (1-2\gamma_1)\mu_2 b^2}{3\mu_1 c^2 + \mu_2 b^2}.$$

The *circle* (radius b) is obtained by putting $b = c$ or

$$m = \frac{2\mu_1 + (1-2\gamma_1)\mu_2}{3\mu_1 + \mu_2}.$$

The *false ellipse*, $\frac{y^4}{b^4} + \frac{z^2}{c^2} = 1$, is obtained by putting $m/(1-m) = 4$ in the case of isotropic material for which uni-constancy holds, or

$$\mu_2 = \mu_1, E/\mu_1 = 5/2 \text{ and } \gamma_1 = 1/10.$$

More generally we must take $m = 2\gamma_1 - 1$, for a similar curve in bodies with tri-planar elastic symmetry.

[88.] On pp. 139—40 Saint-Venant deals with and figures the

- | | | |
|---------------|----------------|--------------------|
| 1. Screw | 21. Nut | 41. Nut |
| 2. Bracket | 22. Floodlamp | 42. Bracket |
| 3. Socket | 23. Nut | 43. Screw |
| 4. Lamp | 24. Bracket | 44. Bracket |
| 5. Gasket | 25. Nut | 45. Nut |
| 6. Lens | 26. Bracket | 46. Lockwasher |
| 7. Screw | 27. Screw | 47. Bracket |
| 8. Nut | 28. Nut | 48. Nut |
| 9. Lockwasher | 29. Nut | 49. Lockwasher |
| 0. Base | 30. Lockwasher | 50. Plate |
| 1. Screw | 31. Bracket | 51. Screw |
| 2. Socket | 32. Washer | 52. Reel assembly |
| 3. Lamp | 33. Bracket | 53. Lamp assembly |
| 4. Ring | 34. Screw | 54. Lamp container |
| 5. Lens | 35. Gasket | 55. Screw |
| 6. Floodlamp | 36. Lens | 56. Plate |
| 7. Nut | 37. Screw | 57. Bracket |
| 8. Bracket | 38. Bulb | 58. Pushbutton |
| 9. Bracket | 39. Socket | |
| 20. Screw | 40. Floodlamp | |

Figure 2-51—Continued.




Figure 2-52. Slave receptacle, replacement.

2-53. Batteries

a. General. The batteries provide power for starting the engine, after which the alternator supplies required electrical power.

b. Test. Test the batteries with a hydrometer. If the specific gravity reads below 1.225, recharge the batteries. Retest with a hydrometer after charging. A fully charged battery should test between 1.280 and 1.300. Replace a battery that will not take or hold a charge. The difference in specific gravity between any two cells must not exceed 0.025. Remove battery filler caps and add distilled water to 3/8-inch above plates before recharging. Refer to tables 2-3 and 2-4.

Table 2-3. Battery Condition (Corrected to 80° F).

Specific gravity	Battery condition
1.280	Fully charged.
1.250	75% charged.
1.220	50% charged.
1.190	25% charged.
1.160	Almost discharged.
1.130	Discharged.

Table 2-4. Electrolyte Freezing Points

Specific gravity	Temperature ° F.
1.280	- 90
1.250	- 62
1.200	- 16
1.150	+ 5
1.100	+19

c. Replacement. Refer to figure 2-53 and replace faulty batteries or battery box components.

false ellipse for a uni-constant isotropic material ($m = 4/5$, $\gamma_1 = \gamma_2 = 1/10$); of the curve $m = 9/10$ (or $18/20$, considered as even), also for a uni-constant isotropic material—this curve approaches a rectangle of which the angles have been rounded off and the top and bottom hollowed out; and of $m = 1$ ($= 2/2$), the contour is here a quadrilateral formed by four curved lines. Then he proceeds to cases which have for practical purposes more definite contours, namely :

(i) *The ellipse.* Here, if $q = \mu_1 c^2 / \mu_2 b^2$, we have :

$$m = \frac{1 + 2q - 2\gamma_1}{1 + 3q};$$

$$\sigma_0 = -\frac{1 + 2q - 2\gamma_1}{1 + 3q} \frac{2P}{\mu_2 \omega}, \left[= -\frac{5c^2 + 2b^2}{3c^2 + b^2} \frac{4P}{5\mu \omega}, \text{ for uni-constant isotropy}; \right]$$

$$\widehat{xy} = \frac{4P}{\omega} \frac{q + 2\gamma_1}{1 + 3q} \frac{yz}{c^2}, \left[= \frac{4P}{5\omega} \frac{5c^2 + b^2}{3c^2 + b^2} \frac{yz}{c^2}, \text{ for uni-constant isotropy}; \right]$$

$$\widehat{xz} = -\frac{2P}{\omega} \frac{1 + 2q - 2\gamma_1}{1 + 3q} \left(1 - \frac{z^2}{c^2}\right) + \frac{2P}{\omega} \frac{1 - 6\gamma_1}{1 + 3q} \frac{y^2}{b^2},$$

$$\left[= -\frac{4P}{5\omega} \frac{5c^2 + 2b^2}{3c^2 + b^2} \left(1 - \frac{z^2}{c^2}\right) + \frac{4P}{5\omega} \frac{y^2}{3c^2 + b^2}, \text{ for uni-constant isotropy}; \right]$$

$$\delta = \frac{4Pl^3}{3E\omega c^2} \left\{ 1 + \frac{3(1 + 2q - 2\gamma_1)}{2(1 + 3q)} \frac{E}{\mu_2} \frac{c^2}{l^2} \right\},$$

$$\left[= \frac{4Pl^3}{3E\omega c^2} \left\{ 1 + \frac{15c^2 + 6b^2}{6c^2 + 2b^2} \frac{c^2}{l^2} \right\}, \text{ for uni-constant isotropy.} \right]$$

(ii) *The circle.* We have only to put $b = c$ in the above results.

[91.] We may note that the term to be added to the deflection owing to shear is generally about $3 \left(\frac{c}{l}\right)^2$ of that due to bending, if we deal with a uni-constant isotropic material (i.e. for circle $\frac{21}{8} \left(\frac{c}{l}\right)^2$, for false ellipse $3 \left(\frac{c}{l}\right)^2$, for rectangle with flattened angles $\frac{27}{8} \left(\frac{c}{l}\right)^2$, etc.). This represents the amount neglected in the ordinary theory. If in practice we may safely neglect an error of $1/100$ in the deflection, it follows that the ordinary theory will give sufficiently close practical results so long as the length of the beam is 8 or 9 times its diameter

[92.] On pp. 148—156 Saint-Venant goes through some most interesting work to trace the form of the distorted cross-sections. He traces these surfaces by means of level or contour lines for different ratios of x'/x'_0 [see equation (29')], that is by the trace of the surfaces on planes parallel to the tangent plane at the origin.

Section XIV. MAINTENANCE OF INSTRUMENT CONTROL ASSEMBLY

2-54. Engine Control Panel Replacement

a. General. Figure 2-54 illustrates the various control gages and instruments located on the control panel. Refer to TM 5-3810-294-10 for a description of the function of each.

b. Replacement. Refer to figure 2-54 and replace any damaged or faulty component of the control panel. Note that the panel is removable as a unit by removing the row of attaching fasteners around the edge of the panel.

CAUTION

Disconnect battery cables before working on the control panel.

2-55. Switches and Wiring, Replacement and Repair

a. Refer to the schematic wiring diagram of the upper wiring, figure 1-4, to isolate wiring problems.

b. Refer to paragraph 2-50 for the method to be used for wiring replacement or repair.

It may be remarked that the conception of these surfaces is much assisted by plaster-models, which exist for the case of the circular and square cross-sections (see below Art. 111).

[93.] Saint-Venant now passes to the discussion of the flexure of a beam of rectangular cross-section. This occupies pp. 156—168.

By the assumption

$$F(y, z) = \chi(y, z) + \frac{P(1 - \gamma_2)z^3}{6\mu_2\omega\kappa^2} - \frac{\gamma_1 P}{2\mu_1\omega\kappa^2} y^2 z. \dots\dots(30),$$

Saint-Venant reduces the equations of condition (19') for $F(y, z)$ to

$$\left. \begin{aligned} \mu_1 \frac{d^2 \chi}{dy^2} + \mu_2 \frac{d^2 \chi}{dz^2} &= 0 \text{ for all values of } y \text{ and } z, \\ \chi(-y, z) &= \chi(y, z) \text{ everywhere,} \\ \chi &= 0 \text{ and } d\chi/dz = 0 \text{ for } y = z = 0, \\ \frac{d\chi}{dz} &= -\sigma_0 - \frac{Pc^2}{2\mu_2\omega\kappa^2} + \frac{\gamma_1 P}{\mu_1\omega\kappa^2} y^2 \text{ for } z = \pm c \text{ and } y \text{ between } \pm b, \\ \frac{d\chi}{dy} &= 0 \text{ for } y = \pm b \text{ and } z \text{ between } \pm c. \end{aligned} \right\} \dots(31).$$

Here $2b$ and $2c$ are the horizontal and vertical (flexure plane) sides of the rectangle.

The first equation of (31) is satisfied by taking

$$\chi = \Sigma e^{qz} \left\{ A_q \cos \sqrt{\frac{\mu_2}{\mu_1}} qy + A'_q \sin \sqrt{\frac{\mu_2}{\mu_1}} qy \right\}. \dots\dots(32).$$

The sines must however disappear in virtue of the second equation, and since $\chi = 0$ when $y = z = 0$, we must have $A_q = -A_{-q}$ or,

$$\chi = \Sigma A_q (e^{qz} - e^{-qz}) \cos \sqrt{\frac{\mu_2}{\mu_1}} qy.$$

The condition $d\chi/dz = 0$ for $y = 0, z = 0$, shews us that a certain relation must hold among the coefficients A_q ; it will serve later to determine σ_0 .

The condition $d\chi/dy = 0$ for $y = \pm b$ will be satisfied if

$$q = \frac{n\pi}{b} \sqrt{\frac{\mu_1}{\mu_2}},$$

n being any whole number, and obviously it will be sufficient to deal only with positive whole numbers. For $n = 0$, we must introduce a term $A_0 (e^{0 \cdot z} - e^{-0 \cdot z})$ which gives us a quantity Kz .

Hence finally we may write:


$$\chi = Kz + \sum_1^{\infty} 2A_n \sinh \frac{n\pi z}{b} \sqrt{\frac{\mu_1}{\mu_2}} \cos n\pi y/b.$$

Section XV. MAINTENANCE OF HORN, WIRING, AND TACHOMETER DRIVE

2-56. Horn Replacement

a. General. The horn is used to warn personnel of machine movement which might endanger their safety.

b. Replacement. Refer to figure 2-55 and replace a defective horn switch. Refer to figure 1-4 for the upper machinery wiring diagram.



- STEP 1. REMOVE JAM NUTS
- STEP 2. REMOVE HORN SWITCH.
- STEP 3. REMOVE WIRING.

ME 3810-294-20/2-55

Figure 2-55. Horn switch and wiring, replacement.

2-57. Horn Wiring, Replacement and Repair

Refer to paragraph 2-50 for the method of replacing or repairing the horn wiring.

2-58. Tachometer and Drive

a. General. The tachometer is mounted on the engine control panel (fig. 2-54). It is cable driven from the tachometer drive (fig. 2-56).

b. Tachometer Removal and Replacement.

(1) Refer to figure 2-56 and disconnect the tachometer drive cable from the tachometer. Remove the tachometer from the control panel.

(2) Install tachometer on control panel and connect drive cable.



ME 3810-294-20 2-56

Figure 2-56. Tachometer drive cable.

Section XVI. MAINTENANCE OF EXHAUST MUFFLER AND PIPES

2-59. General

The exhaust muffler and pipes are illustrated in figure 2-57. Maintenance consists of inspection, removal, and replacement of defective muffler and pipes.

2-60. Exhaust Muffler and Pipes

a. Inspection. Inspect the muffler and exhaust pipes for cracks, breaks, or signs of deterioration.

b. Removal.

(1) Stop the engine and allow muffler and pipes to cool.

(2) Refer to figure 2-57 and remove nuts and bolts holding the guard to the supports.

(3) Remove nuts, lockwashers, and muffler clamps, and remove the muffler and exhaust elbow from the exhaust pipe.

(4) Remove capscrews, nuts, and lockwashers from the base of the exhaust pipe, and remove exhaust pipe and gasket.

$$v = -\gamma_1 \frac{P(l-x)}{\mu_1 \omega \kappa^2} yz,$$

$$\omega = -\frac{Pc^2}{2\mu_2 \omega \kappa^2} \left\{ 1 - \gamma_1 \frac{\mu_2}{\mu_1} \frac{2b^2}{3c^2} \left[1 - \frac{12}{\pi^2} \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{n^2} \operatorname{sech} \left(\frac{n\pi c}{b} \sqrt{\frac{\mu_1}{\mu_2}} \right) \right] \right\} x \\ - \frac{P}{2E\omega \kappa^2} \frac{3lx^2 - x^3}{3} + P \frac{l-x}{2\omega \kappa^2} \left(\frac{\gamma_1 y^2}{\mu_1} - \frac{\gamma_2 z^2}{\mu_2} \right),$$

$$\widehat{xy} = \frac{\gamma_1 P}{\omega \kappa^2} \frac{4b^2}{\pi^2} \sqrt{\frac{\mu_2}{\mu_1}} \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{n^2} \frac{\sinh \left(\frac{n\pi z}{b} \sqrt{\frac{\mu_1}{\mu_2}} \right) \sin \frac{n\pi y}{b}}{\cosh \left(\frac{n\pi c}{b} \sqrt{\frac{\mu_1}{\mu_2}} \right)},$$

$$\widehat{xz} = -\frac{Pc^2}{2\omega \kappa^2} \left(1 - \frac{z^2}{c^2} \right) \\ + \gamma_1 \frac{Pb^2}{3\omega \kappa^2} \frac{\mu_2}{\mu_1} \left\{ 1 - \frac{3y^2}{b^2} - \frac{12}{\pi^2} \sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{n^2} \frac{\cosh \left(\frac{n\pi z}{b} \sqrt{\frac{\mu_1}{\mu_2}} \right) \cos \frac{n\pi y}{b}}{\cosh \left(\frac{n\pi c}{b} \sqrt{\frac{\mu_1}{\mu_2}} \right)} \right\}.$$

Saint-Venant verifies these results by shewing that they satisfy the boundary equation $\widehat{xz} dy - \widehat{xy} dz = 0$ and the load-conditions $\int \widehat{xz} d\omega = -P$, $\int \widehat{xy} d\omega = 0$.

[96.] The next two sections 28 and 29 (pp. 164—8) are occupied with numerical, graphical and simpler algebraic expressions for the quantities which occur in the previous sections.

For σ_0 Saint-Venant obtains the following results when $\gamma_1 = \frac{1}{10}$:

When $\frac{c}{b} \sqrt{\frac{\mu_1}{\mu_2}} =$	$\frac{1}{4}$	$\frac{1}{2}$	$\frac{3}{4}$	1	1.25	1.5	2	2.5	3
$-\sigma_0 = \frac{Pc^2}{2\mu_2 \omega \kappa^2} \times$.67624	.84918	.90729	.94031	.96177	.97101	.98311	.98931	.99259

It is shewn that for all values of $c \sqrt{\mu_1} > b \sqrt{\mu_2}$ the sum-term in equation (35) may be omitted, or we can write

$$-\sigma_0 = \frac{3P}{2\mu_2 \omega} - \frac{\gamma_1 b^2}{c^2} \frac{P}{\mu_1 \omega}.$$

Further the deflection δ is then given by :

$$\delta = \frac{Pl^3}{3E\omega \kappa^2} \left(1 + \frac{3E}{2\mu_2} \frac{c^2}{l^2} - \eta_1 \frac{b^2}{l^2} \right)$$

since

$$\gamma_1 = \eta_1 \frac{\mu_1}{E}.$$

For the case of isotropy: $\eta_1 = \frac{1}{4}$, $E/\mu_1 = 5/2$, or

$$\delta = \frac{Pl^3}{3E\omega \kappa^2} \left(1 + \frac{15c^2}{4l^2} - \frac{b^2}{l^2} \right).$$




Figure 2-58. Cab door assembly, removal.

injury. Place masking tape on the piece of glass to be broken out to prevent flying glass. Remove the weatherstripping around the glass.

c. Installation.

(1) Start the rubber weatherstripping as shown in figure 2-59. Go all the way around the window and force the ends into place, touching each other.

(2) Install the glass in one of the lower corners of the new weatherstrip.

(3) Moisten the weatherstrip with soapy water.

(4) Insert a suitable locking tool similar to the one illustrated in figure 2-59 and pull it around the complete weatherstrip to lock the glass in place.

NOTE

Do not begin the locking operation at the butt joint of the weatherstrip. Be sure to avoid excessive force.

2-63. Operators Seat

Refer to figure 2-60 and remove and replace the operator's seat (Stand).

[100.] The final section of the memoir (§ 32, pp. 187—9) is entitled: *Conclusion. Observation générale pour le cas où le mode d'application et de distribution des forces extérieures vers les extrémités est différent de celui qui rend tout à fait exactes les formules auxquelles conduit la méthode mixte.*


This reiterates the principle of the practical equivalence in elastic effect of two surface distributions of load which are statically equivalent: see our Arts. 8 and 9.

101. *Sur les conséquences de la théorie de l'élasticité en ce qui regarde la théorie de la lumière. L'Institut*, Vol. 24, 1856, 32—34. The article adopts the view that much remains to be done to render the theory of Physical Optics satisfactory; it supports the views of Cauchy, especially with regard to the existence of a *third* ray as obtained by him in his discussion of what is termed *double* refraction. The article concludes thus:

Quoi qu'il puisse être de ces explications, que nous devons nous borner à soumettre aux physiciens et aux physiologistes, et bien que l'on puisse continuer sans doute de regarder le mouvement de la lumière dans les cristaux comme représenté *approximativement* par la surface d'onde du quatrième degré de Fresnel, nous pensons qu'il convient de ne plus passer sous silence les composantes longitudinales des vibrations pour éluder quelques difficultés dont elles sont le sujet, et que, pour rendre la théorie de la lumière exempte d'inexactitude logique, et provoquer pour l'avenir des recherches qui seront peut-être suivies d'importantes découvertes, il y a lieu de ne plus présenter les vibrations de l'éther, dans les milieux biréfringents, comme étant tout à fait parallèles aux divers plans tangents à la surface des ondes lumineuses qui s'y propagent.

102. *Sur la vitesse du son. L'Institut*, Vol. 24, 1856, 212—216. Newton obtained a certain expression for the velocity of sound which gives a result much smaller than that found by experiment. Laplace modified the formula, and thus obtained a result agreeing with experiment: see our Arts. 310* and 68. Saint-Venant is not satisfied with any investigation which has been given, even with the aid of the formulæ of the theory of elasticity. He says

On voit toujours, par ce qui précède, qu'il reste encore bien des choses à savoir sur la théorie du son, objet des recherches d'hommes tels que Newton, Lagrange, Euler, Laplace, Poisson et Dulong; qu'on ne doit



STEP 1. REMOVE PIN.
STEP 2. REMOVE SEAT.

ME 3810-294-20/2-60

Figure 2-60. Operator's seat, removal.

Section XVIII. MAINTENANCE OF GANTRY ASSEMBLY

2-64. General

The gantry provides the anchor for items required to support the boom.

2-65. Gantry Assembly

a. Inspection. Visually inspect the gantry for evidence of cracks, bends, or other damage. Check the condition of gantry sheaves, paying careful attention to cracks or excessive grooving.

Make sure that points which require lubrication have not been missed.

b. Removal.

(1) Refer to applicable paragraph (2-4 through 2-9) and remove the front end attachment.

(2) Remove boom backstops (para 2-47).

(3) Refer to figure 2-68 and remove sheet metal as required.

(4) Refer to figure 2-61 and remove the gantry assembly.

1857, pp. 204—8. This memoir was presented on August 10, 1857. It was referred to Poncelet, Lamé, Bertrand and Hermite. An extract by the author is given in the *Comptes rendus*. Some of the results of this memoir were communicated to the *Société Philomathique*, November 5, 1853 and January 21, 1854, and partially published in *L'Institut*, T. 22, 1854, pp. 61—3, under the title: *Solution du problème du choc transversal et de la résistance vive des barres élastiques appuyées aux extrémités*. This is a special case of the resilience problem experimentally investigated by Hodgkinson and theoretically by Cox: see our Arts. 939*, 942*, 999* and 1434—7*. Saint-Venant, however, does not like Cox neglect the vibrations of the bar, or assume that its form will be that of the elastic line for a beam which centrally loaded has the same central deflection. In the *Comptes rendus*, Saint-Venant gives some account of the history of both transverse and longitudinal impact problems, but Cox's memoir seems to have escaped him.

The following result is given in the *Comptes rendus*, p. 206:

$$y = V\tau \sum \frac{4}{m^3} \frac{\frac{\sin mx/l}{\cos m} - \frac{\sinh mx/l}{\cosh m}}{\sec^2 m - \operatorname{sech}^2 m + \frac{2}{m^2} P} \sin (m^2 t/\tau),$$

where the Σ refers to all the real and positive roots m of the equation

$$m (\tan m - \tanh m) = 2P/Q,$$


and the following is the notation used:

$2l$ = length of bar, P its weight, Q that of body striking the bar horizontally with velocity V at its mid-section, y is the horizontal displacement at distance x from one end and $\tau = \sqrt{P^3/(2gE\omega\kappa^2)}$.

[105.] Saint-Venant makes the following remark:

Du calcul tant numérique que graphique d'une suite de ces valeurs du déplacement y , on peut déduire la suite des formes très-variées prises par la barre heurtée; ce qui permet de modeler un relief en plâtre donnant la surface que décrirait cette barre supposée emportée transversalement d'un mouvement rapide, perpendiculaire au sens où elle oscille. Cette surface est très-ondulée à cause des oscillations provenant des second et troisième termes surtout de la série Σ (p. 206).

This surface in plaster of Paris was actually prepared under Saint-Venant's directions; and I have found a copy of it very useful for lecture purposes.



ME 3810-294-20 2-61A

Figure 2-61A. Heater, replacement.

and general principles of the subject, may do more harm than good to the student.

The fairly elementary treatment of the *Leçons de Navier* seems to me more advantageous (pp. 245—250). The treatment of the present paper is also reproduced in § 7 (pp. 250—2) of the same work.

[110.] *L'Institut*, Vol. 26, 1858, pp. 178—9. Further results on Torsion communicated to the *Société Philomathique* (April 24 and May 15, 1858) and afterwards incorporated in the *Leçons de Navier* (pp. 305—6, 273—4). They relate to cross-sections in the form of doubly symmetrical quartic curves and to torsion about an external axis: see our Arts. 49 (c), 182 (b), 181 (d), and 182 (a).


[111.] Vol. 27, 1860, of same Journal, pp. 21—2. Saint-Venant presents to the *Société Philomathique* the model *de la surface décrite par une corde vibrante transportée d'un mouvement rapide perpendiculaire à son plan de vibration*. Copies of this as well as some other of Saint-Venant's models may still be obtained of M. Delagrave in Paris and are of considerable value for class-lectures on the vibration of elastic bodies.

[112.] Vol. 28, 1861, of same Journal, pp. 294—5. This gives an account of a paper of Saint-Venant's read before the *Société Philomathique* (July 28, 1860). In this he deduces the *conditions of compatibility*, or the six differential relations of the types:

$$2 \frac{d^2 s_x}{dy dz} = \frac{d}{dx} \left(\frac{d\sigma_{xz}}{dy} + \frac{d\sigma_{xy}}{dz} - \frac{d\sigma_{yz}}{dx} \right)$$

$$\frac{d^3 \sigma_{yz}}{dy dz} = \frac{d^3 s_y}{dz^2} + \frac{d^3 s_z}{dy^2}$$

which must be satisfied by the strain-components. These conditions enable us in many cases to dispense with the consideration of the shifts. A proof of these conditions by Boussinesq will be found in the *Journal de Liouville*, Vol. 16, 1871, pp. 132—4. At the same meeting Saint-Venant extended his results on torsion to: (1) prisms on any base with at each point only one plane of symmetry perpendicular to the sides, (2) prisms on an elliptic base with or without any plane of symmetry whatever; see our Art. 190 (d).



ME 3810-294-20/2-62

Figure 2-62. Hydraulic system, schematic diagram.

b. Hydraulic Cylinder (Brake or Clutch).

(1) *General.* Clutch and brake hydraulic cylinders are identical. Start engine and position adjusting bolts in the desired position by intermittently engaging engine clutch.

(2) *Replacement.* Close the hydraulic reservoir shutoff valve shown in figure 2-63. Refer to figure 2-67 and replace a hydraulic cylinder. Use same procedure for each hydraulic brake and clutch cylinder.

2-72. Hydraulic Fluid Reservoir

a. General. The hydraulic fluid reservoir provides the storage space required for hydraulic fluid used in the crane control system. It also allows air trapped in the lines from the control stand beneath the operator's levers to vent from the system. It must be kept filled to the full mark at all times.

b. Service. Service consists of keeping the hydraulic reservoir full of clean fluid of the type specified in the lubrication chart.

c. Replacement. Refer to figure 2-63 and remove and replace the hydraulic fluid reservoir.

[115.] The following paragraphs describe the quadric distributions of elasticity with which Saint-Venant proposes to deal.

After describing the *amorphic* body or body of *confused-crystallisation*, such as a rolled metal plate, the elasticity of which varies in length, breadth and depth,—Saint-Venant continues :

Qu'on enroule en tuyau cylindrique cette plaque homogène rectangulaire non isotrope supposée mince, en dirigeant, par exemple, les génératrices dans le sens de sa longueur. *Elle ne cessera pas d'être homogène* ; mais l'égalité d'élasticité aux divers points n'aura pas lieu pour les directions parallèles entre elles. Il y aura égale élasticité suivant les rayons qui vont tous couper perpendiculairement l'axe du cylindre : ce sera l'élasticité dans le sens de l'épaisseur. Il y aura égale élasticité suivant les diverses tangentes aux cercles ayant leur centre sur cet axe. Il n'y aura que les élasticités égales suivant la longueur qui auront conservé des directions parallèles entre elles. (p. 298.)

We shall term this a cylindrical distribution of elastic homogeneity.

The following describes a spherical distribution :

Qu'on imagine maintenant une sphère solide pleine ou creuse, ou un corps de forme quelconque divisible en couches sphériques concentriques. Si la résistance ou la réaction élastique, pour mêmes déplacements de ses points, est partout égale dans le sens des rayons, et partout égale aussi dans certains sens perpendiculaires entre eux et aux rayons, ceux par exemple où se comptent les latitudes et les longitudes pour un équateur donné, la matière est homogène, mais *polairement*, ou d'une manière que nous pouvons appeler *sphéroidique* vu le rôle qu'y jouent les cônes de *latitude* ayant un axe déterminé, le même pour tous. (p. 298.)

Such distributions of elasticity are, Saint-Venant asserts,—and I hold him to be entirely right—the true explanation of the anomalies which occur in experiments on a variety of cast, rolled and forged bodies. Even granted that isotropy is bi-constant, it is certainly not scientific to seek by means of two constants to account for the divergency between uni-constant formulæ and experimental results on wires, plates, or cylindrical and spherical bodies. Physically it is obvious that the *working* of such bodies really produces in them varied distributions of elastic homogeneity, which bi-constant formulæ only serve to mask. The 'isotropic boilers' treated of by Lamé (see our Art. 1038*) or his 'isotropic piezometers' (see our Art. 1358*) have practically no existence (see our Arts. 332* and 1357*), and all elasticians can adopt Saint-

ME 3810-294-20/2-64 ①




Figure 2-64. Hydraulic hoses, fittings, and tubing, replacement. (Sheet 1 of 2).

three planes, or all the asymmetrical coefficients to vanish. In this case the types of traction and shear are :

$$\begin{aligned} (a) \quad \widehat{xx} &= as_x + f's_y + e's_z & \widehat{yz} &= d\sigma_{yz}, \\ \widehat{yy} &= f's_x + bs_y + d's_z & \widehat{zx} &= e\sigma_{zx}, \\ \widehat{zz} &= e's_x + d's_y + cs_z & \widehat{xy} &= f\sigma_{xy}. \end{aligned}$$

(See our Art. 78.)

(b) If the normal to the distribution-surface be the axis of x and the elasticity be isotropic in the tangent plane, we have also :

$$b=c, \quad e=f, \quad e'=f' \text{ and } b=2d+d'.$$

(c) If the material be *amorphous*, there is an *ellipsoidal* distribution of direct-stretch coefficients (see our Arts. 139 and 142), and we have

$$2d+d'=\sqrt{bc}, \quad 2e+e'=\sqrt{ca}, \quad 2f+f'=\sqrt{ab}.$$

(d) In the case of *rari-constant* elasticity, the dashed and undashed letters are equal. Thus for the amorphous body we have :

$$\begin{aligned} \widehat{xx} &= 3 \frac{ef}{d} s_x + fs_y + es_z & \widehat{yz} &= d\sigma_{yz}, \\ \widehat{yy} &= fs_x + 3 \frac{fd}{e} s_y + ds_z & \widehat{zx} &= e\sigma_{zx}, \\ \widehat{zz} &= es_x + ds_y + 3 \frac{de}{f} s_z & \widehat{xy} &= f\sigma_{xy}. \end{aligned}$$

(See, however, our Art. 313.)

[118.] Before we can apply these formulae to any given distribution of elasticity determined by curvilinear coordinates, it is necessary to find :

(1) Expressions for the above strain-components ($s_x, s_y, s_z, \sigma_{yz}, \sigma_{zx}, \sigma_{xy}$) corresponding to the elements of the three rectangular surface normals or intersection-traces in terms of the curvilinear coordinates.

(2) To express the body-stress equations in terms of curvilinear coordinates. Saint-Venant indicates in § 4 (pp. 306—12) two methods of attacking this problem, and compares them with Lamé's method (in the *Leçons*, 1852, § 77) which he terms "un procédé en quelque sorte *mixte*." The analysis of the problem does not probably admit of much simplification, and for practical purposes the general results of Lamé's treatise on Curvilinear Coordinates may well be assumed: see our Arts. 1150¹—3*.

In § 5 (pp. 312—18) and in § 9 (pp. 333—9) Saint-Venant obtains expressions for the strains and the body-stress equations in terms




Figure 2-65. Hydraulic cylinder, bleeding procedure.

Hence we find for the shifts

$$u = Cr\sqrt{\frac{b}{a}} + C'r - \sqrt{\frac{b}{a}} + \frac{d' - e'}{a - b} \gamma r, \quad v = 0, \quad w = \gamma z.$$

The stresses and strains can be at once deduced; they will contain constant terms in γ and powers of r of order $\pm \sqrt{\frac{b}{a}} - 1$. The constants C , C' and γ are to be determined from the surface conditions and the relation $p_0 \pi r_0^2 - p_1 \pi r_1^2 = 2\pi \int_{r_0}^{r_1} z r dr$ for total terminal tractive stress.

[121.] Saint-Venant considers various special cases:

- (1) $r_1 - r_0$ is a small thickness ϵ . (pp. 324—5.)
- (2) $a = b$. Here the solution changes its form, we have (p. 326):

$$u = C_1 r + C_1' / r + \frac{d' - e'}{2a} \gamma r \log r.$$

If $d' = e'$ the solution becomes that found by Lamé and Clapeyron, and applied by Lamé to Regnault's piezometers: see our Arts. 1012* and 1358*.

- (3) When there is an ellipsoidal distribution of elasticity and rari-constancy is assumed, i.e. when $a = 3ef/d$, $b = 3fd/e$, $c = 3de/f$. In this case

$$u = Cr^{d/e} + C'r^{-d/e} - d\gamma r / \{3f(d/e + 1)\}.$$

The values of the stresses are then easily determined, as well as those of C , C' and γ (p. 329).

The results contain *three independent elastic constants*, and they differ in the *form* of the r -index from those found for the case of isotropy. Hence we can explain by means of them as well as or better than by biconstant formulae the divergencies remarked by Regnault in his piezometer experiments.

[122.] A result is given on p. 331, which is worth citing. The constants d , e , f of the ellipsoidal distribution are not easy to determine by direct experiment. Let E_r , E_ϕ , E_z however be the three stretch moduli in directions r , ϕ , z , then we easily find that:

$$d = \frac{2}{3} \sqrt{E_\phi E_z}, \quad e = \frac{2}{3} \sqrt{E_z E_r}, \quad f = \frac{2}{3} \sqrt{E_r E_\phi}.$$

From equations 50 (p. 332) Saint-Venant might have deduced the criterion for failure arising first by lateral or first by longitudinal stretch. These equations are:

$$s_z = \frac{1}{4} \frac{2\sqrt{E_\phi} - \sqrt{E_z}}{E_z \sqrt{E_\phi}} \frac{p_0 - p_1}{\epsilon} r', \quad s_\phi = \frac{1}{8} \frac{8\sqrt{E_z} - \sqrt{E_\phi}}{E_\phi \sqrt{E_z}} \frac{p_0 - p_1}{\epsilon} r',$$

where $r_0 = r' - \frac{\epsilon}{2}$ and $r_1 = r' + \frac{\epsilon}{2}$, so that $r' = \frac{r_0 + r_1}{2}$, $r_1 - r_0 = \epsilon$.




Figure 2-67. Hydraulic cylinders, replacement.

Section XXI. MAINTENANCE OF COOLING SYSTEM

2-73. General

The cooling system consists of the radiator and hoses, lines, and fittings required to conduct coolant from the engine to the radiator and back to the engine to complete the cooling circuit. Drain valves are located on the lower radiator hose connection and at the right rear of the engine block to drain the radiator and block.

2-74. Radiator, Cap, and Hoses

a. Inspect. Visually inspect the radiator and hoses for leaks or damage.

b. Test. If a cap tester is available, test the radiator cap. The cap should retain 4 psi pressure. If cap tester is not available, and the cap is suspected of leaking, replace the cap.

c. Replacement. Before removing the radiator, open both coolant drain valves and drain the radiator and engine block. Then refer to figure 2-69 and remove and replace the radiator as follows.

(1) Refer to figure 2-68 and remove radiator shutters and sheet metal as required.

The important point in the piezometer problem is the dilatation of the spherical cavity. This is equal to $\frac{3u_0}{r_0}$

$$= \frac{3r_0^{n-\frac{3}{2}}}{r_1^{2n} - r_0^{2n}} \left\{ \frac{p_0 r_0^{n+\frac{3}{2}} - p_1 r_1^{n+\frac{3}{2}}}{(n-\frac{1}{2})\alpha + 2e'} + \frac{p_0 r_0^{\frac{3}{2}-n} - p_1 r_1^{\frac{3}{2}-n}}{(n+\frac{1}{2})\alpha - 2e'} r_1^{2n} \right\}.$$

We see that it involves *three* elastic coefficients, and is thus, even as an *empirical* formula, better adapted to satisfy *numerically* Regnault's experiments than Lamé's bi-constant isotropic formula obtained by putting $d' = e'$, $b = a$ and $n = 3/2$.¹ On the other hand it is physically more plausible. The constants reduce to *two*, if we suppose the body *amorphous* and of *rari-constant* elasticity ellipsoidally distributed. If we take $r_0 = r' - \epsilon/2$, $r_1 = r' + \epsilon/2$, we easily find for the mid-sphere of radius r' :

$$s_\phi = s_\psi = \frac{\alpha}{\alpha(b+d') - 2e'^2} \frac{(p_0 - p) r'}{2\epsilon},$$

or in the case just mentioned

$$s_\phi = s_\psi = \frac{3}{20d} \frac{(p_0 - p_1) r'}{\epsilon}.$$

But $E_\phi = \frac{5fd}{2e} = \frac{5d}{2}$ by Art. 117 (6) if there be tangential isotropy.

Hence finally:

$$s_\phi = s_\psi = \frac{3}{8E_\phi} \frac{(p_0 - p_1) r'}{\epsilon}.$$

[125.] The final section of the memoir is entitled: *Vase cylindrique terminé par deux calottes sphériques* (pp. 347—9). This treats a problem similar to that dealt with by Lamé in his *Note* of 1850: see our Art. 1038*. The mean lateral expansion of the spherical ends is made to take the same value as that of the cylindrical body by equating the expressions for s_ϕ obtained in our Arts. 122 and 124. Saint-Venant thus reaches a more general rule than that given by Lamé as a result of bi-constant isotropy. We have:

$$\frac{1}{8} \frac{8\sqrt{E_z} - \sqrt{E_\phi}}{E_\phi \sqrt{E_z}} \frac{r'}{\epsilon} = \frac{3}{8} \frac{1}{E_{\phi_1}} \frac{r'_1}{\epsilon_1}$$

where the subscript ₁ refers to the spherical portions of the surface.

Hence

$$\frac{\epsilon}{\epsilon_1} = \frac{r'}{r'_1} \times \frac{8/E_\phi - 1/\sqrt{E_z E_\phi}}{3/E_{\phi_1}}.$$

In the case of the two portions being of the same *isotropic* material, we have $E_\phi = E_z = E_{\phi_1}$, or

$$\frac{\epsilon}{\epsilon_1} = \frac{7}{3} \frac{r'}{r'_1}.$$

¹ In Lamé's notation $a = \lambda + 2\mu$ and $\nu' = \lambda$: see our Art. 1093*.

1. Canopy	32A. Panel assembly	65. Nut (9)
2. Hex capscrew (30)	33. Capscrew (8)	66. Flat washer (9)
3. Nut (30)	34. Backup strip	67. Lockwasher (9)
4. Lockwasher (30)	35. Rubber seal strap	68. Angle
5. Safety glass	36. Shim	69. Capscrew (7)
6. Weather strip	37. Machine screw (12)	70. Lockwasher (35)
7. Guide	38. Nut (8)	71. Nut (23)
8. Capscrew (17)	39. Flat washer (8)	72. Nut (18)
9. Nut (17)	40. Lockwasher (8)	73. Capscrew (18)
0. Lockwasher (17)	41. Mounting plate	74. Capscrew (28)
1. Rain gutter	42. Bracket	75. Nut (28)
2. Capscrew (8)	43. Capscrew	76. Lockwasher (23)
3. Nut (8)	44. Nut	77. Capscrew (7)
4. Lockwasher (8)	45. Flat washer	78. Nut (7)
5. Ball bearing (3)	46. Lockwasher	79. Lockwasher (7)
6. Washer (3)	47. Extension panel	80. Rear panel
7. Capscrew (4)	48. Mounting plate	81. Louver (6)
8. Cotter pin	49. Capscrew (9)	82. Louver bracket (6)
9. Lockwasher	50. Nut (9)	83. Positioning plate
0. Handle	51. Lockwasher (9)	84. Capscrew (2)
1. Latch	52. Capscrew (6)	85. Nut (2)
2. Handle	53. Flat washer (24)	86. Lockwasher (2)
3. Machine screw (2)	54. Lock washer (24)	87. Control lever
4. Lockwasher (2)	55. Rear side panel	88. Capscrew (2)
5. Capscrew (4)	56. Nut (11)	89. Nut (2)
6. Lock	57. Lockwasher (11)	90. Lockwasher (2)
7. Key	58. Capscrew (14)	91. Actuating arm
8. Safety glass	59. Lockwasher (14)	92. Capscrew (16)
9A. Door	60. Nut (14)	93. Shutter
9. Weather strip	61. Side panel	94. Capscrew (11)
0. Backup strip	62. Capscrew (23)	95. Operating rod
1. Rubber seal strap	63. Mounting bracket	96. Ball joint (2)
2. Roundhead machine screw (3)	64. Capscrew (9)	

Figure 2-68(1)—Continued

(2) Remove upper connection hoses and hose clamps (fig. 2-69).

(3) Remove all fan guard capscrews and lockwashers and remove fan guard.

(4) Remove lower connection hoses and hose clamps.

(5) Remove drain line hose clamps.

(6) Support the radiator so it can not fall and attach a suitable lifting device.

(7) Remove one nut and three washers from the mounting studs on each side.

(8) Remove radiator braces. One brace is on each side of the engine.

(9) Lift radiator until mounting studs clear the mounting brackets. Then remove the radiator through the rear of the cab where rain shutters and sheet metal have been removed.

(10) Replace by performing (1) through (9) in reverse order.

energy: see the footnote to our Art. 117. It is desirable to obtain a proof of the elastic formulae due to Cauchy without appealing to the principle of inter-molecular action being central and a function *only* of the distance.

Subscript letters attached to the shifts u , v , w denoting fluxions, the formulae are given by the types:

$$\left. \begin{aligned} \widehat{xx} &= \widehat{xx}_0 (1 + u_x - v_y - w_z) + 2\widehat{xy}_0 u_y + 2\widehat{xz}_0 u_z + \widehat{xx}_1 \\ \widehat{yz} &= \widehat{yz}_0 (1 - u_x) + \widehat{yz}_0 u_y + \widehat{yz}_0 v_z + \widehat{xz}_0 v_x + \widehat{xy}_0 w_x + \widehat{yz}_1 \end{aligned} \right\} \dots\dots(i),$$

where

$$\left. \begin{aligned} \widehat{xx}_1 &= |xxxx| s_x + |xyxy| s_y + |xxzx| s_z + |xxyz| \sigma_{yz} + |xxzx| \sigma_{zx} + |xxxy| \sigma_{xy} \\ \widehat{yz}_1 &= |yzxx| s_x + |yzxy| s_y + |yzzz| s_z + |yzyz| \sigma_{yz} + |yzxz| \sigma_{zx} + |yzxy| \sigma_{xy} \end{aligned} \right\} (ii),$$

while the type of resulting body-shift equation is:

$$\left. \begin{aligned} -\rho X &= \widehat{xx}_0 u_{xx} + \widehat{yz}_0 u_{yy} + \widehat{xz}_0 u_{zz} + 2\widehat{yz}_0 u_{yz} + 2\widehat{xz}_0 u_{zx} + 2\widehat{xy}_0 u_{xy} \\ &+ |xxxx| u_{xx} + |xyxy| u_{yy} + |xxzx| u_{zz} \\ &+ 2|xxxy| u_{yz} + 2|xxzx| u_{zx} + 2|xxxy| u_{xy} \\ &+ |xxxy| v_{xx} + |xyxy| v_{yy} + |xxyz| v_{zz} \\ &+ \{ |xyyz| + |xxyy| \} v_{yz} + \{ |xxyz| + |xxxy| \} v_{zx} + \{ |xxyy| + |xyxy| \} v_{xy} \\ &+ |xxzx| w_{xx} + |xyyz| w_{yy} + |xxzx| w_{zz} \\ &+ \{ |xxyz| + |xyyz| \} w_{yz} + \{ |xxzx| + |xxzx| \} w_{zx} + \{ |xxyz| + |xyyz| \} w_{xy} \end{aligned} \right\} (iii).$$

These results representing the most general equations of elasticity for small strains were originally given by Cauchy, as is implied in our Arts. 615*, 616*, 662*, 666*. He obtained them by calculating the stresses as the sums of intermolecular actions on the rari-constant hypothesis. Saint-Venant in this section proposes to deduce them from the principle of energy (by Green's method) in a manner which will satisfy multi-constant elasticians.

[130.] The proof attempted by Saint-Venant is not legitimate, because in the expression he takes for the work the linear term

$$\widehat{xx}_0 s_x + \widehat{yz}_0 s_y + \widehat{xz}_0 s_z + \widehat{yz}_0 \sigma_{yz} + \widehat{xz}_0 \sigma_{zx} + \widehat{xy}_0 \sigma_{xy}$$

occurs where s_x , s_y , s_z , σ_{yz} , σ_{zx} , σ_{xy} are stretches and slides. Assuming this term correct, which it is not, these ought to be expressed to the second power of the shift-fluxions as in our Art. 1622*, for we want the work to the second power. This Saint-Venant does not do, but treats the strains s and σ as if they were the quantities ϵ_x , ϵ_y , ϵ_z , η_{yz} , η_{zx} , η_{xy} of our Art. 1619*. This mistake was pointed out by Brill and Boussinesq, and is acknow-

There is a footnote referring to Sylvester's papers in *Camb. and Dublin Math. Journal*, Vol. VII. 1852, p. 76, and *Phil. Trans.* 1853, p. 543.

[133.] Suppose *symbolically* $\iota_{jklm} = \iota_{kilm} = \iota_{ljkim}$ to represent $|jklm|$, where j, k, l, m are any of the letters $xyz, x'y'z'$ etc. Further \widehat{r} \widehat{r} to represent the stress \widehat{rr} , and $\epsilon_r \epsilon_r$ or ϵ_r^2 to represent s_r , and finally $2\epsilon_r \epsilon_{r'}$ to represent $\sigma_{rr'}$. Let $c_{rr'}$ denote the cosine of the angle between the directions r, r' .

We are now able to reproduce in symbolic form the following well-known typical relations :

$$\widehat{rr} = \widehat{xx} c_{rx} c_{rx} + \widehat{yy} c_{ry} c_{ry} + \widehat{zz} c_{rz} c_{rz}$$

$$+ \widehat{yz} (c_{ry} c_{rz} + c_{rz} c_{ry}) + \widehat{zx} (c_{rx} c_{ry} + c_{ry} c_{rx}) + \widehat{xy} (c_{rx} c_{rz} + c_{rz} c_{rx}) \dots (\text{iv}),$$

$$s_x = s_x c_{xx}^2 + s_y c_{xy}^2 + s_z c_{xz}^2 + \sigma_{yx} c_{xy} c_{xx} + \sigma_{zx} c_{xz} c_{xx} + \sigma_{xy} c_{xx} c_{xy} \dots (\text{v}),$$

$$\sigma_{yz} = 2s_x c_{xy} c_{yz} + 2s_y c_{yy} c_{yz} + 2s_z c_{yz} c_{yz}$$

$$+ \sigma_{yx} (c_{xy} c_{yz} + c_{yz} c_{xy}) + \sigma_{zx} (c_{yz} c_{xz} + c_{xz} c_{yz}) + \sigma_{xy} (c_{yx} c_{yz} + c_{yz} c_{xy}) \dots (\text{vi}).$$

See our Arts. 659* and 663*.

(The last two are most readily obtained from the stretch-quadric of Art. 612* for axes $x'y'z'$, namely :

$$s_x x'^2 + s_y y'^2 + s_z z'^2 + \sigma_{yx} y'z' + \sigma_{zx} z'x' + \sigma_{xy} x'y' = \pm 1.$$

Substitute for x' its equivalent $xc_{xx} + yc_{xy} + zc_{xz}$ and similar quantities for y' and z' , then the coefficients of x^2 and yz will be s_x and σ_{yz} as given above.)

The symbolical forms are :

$$\widehat{xx} \text{ or } \widehat{yz} = \iota_{xx} \text{ or } \iota_{yz} \times (\iota_x \epsilon_x + \iota_y \epsilon_y + \iota_z \epsilon_z)^2 \dots (\text{vii}),$$

whence it follows from (iv) that

$$\widehat{rr} = (\iota_x c_{rx} + \iota_y c_{ry} + \iota_z c_{rz}) (\iota_x c_{rx} + \iota_y c_{ry} + \iota_z c_{rz}) \times (\iota_x \epsilon_x + \iota_y \epsilon_y + \iota_z \epsilon_z)^2 \dots (\text{viii}).$$

Further we have from (v) :

$$\epsilon_x \epsilon_x = (\epsilon_x c_{xx} + \epsilon_y c_{xy} + \epsilon_z c_{xz})^2$$

$$\epsilon_y \epsilon_z = (\epsilon_x c_{xy} + \epsilon_y c_{yy} + \epsilon_z c_{yz}) (\epsilon_x c_{xz} + \epsilon_y c_{zy} + \epsilon_z c_{zz}),$$

whence we can take

$$\epsilon_j = \epsilon_x c_{jx} + \epsilon_y c_{jy} + \epsilon_z c_{jz} \dots \dots \dots (\text{ix})$$

Put $j = x, y, z$ successively and substitute for $\epsilon_x, \epsilon_y, \epsilon_z$ in (viii), we have

$$\begin{aligned} \widehat{rr} &= (\iota_x c_{rx} + \iota_y c_{ry} + \iota_z c_{rz}) (\iota_x c_{rx} + \iota_y c_{ry} + \iota_z c_{rz}) \times \\ &\{ (\iota_x c_{xx} + \iota_y c_{xy} + \iota_z c_{xz}) \epsilon_x + (\iota_x c_{xy} + \iota_y c_{yy} + \iota_z c_{yz}) \epsilon_y \\ &\quad + (\iota_x c_{xz} + \iota_y c_{zy} + \iota_z c_{zz}) \epsilon_z \}^2 \dots \dots \dots (\lambda). \end{aligned}$$

But we may obviously also express \widehat{rr} in the form

$$\widehat{rr} = |r'r'| s_{rr'} + \dots + \dots$$

$$+ |r'y'z'| \sigma_{y'z'} + \dots + \dots$$

$$= \iota_r \iota_{r'} (\iota_x \epsilon_x + \iota_y \epsilon_y + \iota_z \epsilon_z)^2 \dots \dots \dots (\text{vi}).$$

40. Sliding door
41. Rubber strip
42. Handle
43. Machine screw (2)
44. Lockwasher (2)
45. Plate
46. Latch
47. Capscrew (4)
48. Lockwasher (48)
49. Cotter pin
50. Wing nut (4)
51. Lockwasher (4)
52. Bottom engine cover
53. Backup strip
54. Rubber seal
55. Machine screw (3)
56. Angle

57. Nut (16)
58. Lockwasher (16)
59. Capscrew (14)
60. Mounting plate
61. Bottom panel
62. Nut (14)
63. Lockwasher (14)
64. Ball bearing (2)
65. Flat washer (2)
66. Capscrew (8)
67. Nut (8)
68. Lockwasher (8)
69. Nut (2)
70. Lockwasher (2)
71. Machine screw (2)
72. Spring lock
73. Cover

74. Gasket (2)
75. Cover (2)
76. Rear Panel
77. Thumb screw
78. Bracket
79. Capscrew (9)
80. Nut (9)
81. Flat washer (9)
82. Lockwasher (9)
83. Capscrew (20)
84. Nut (20)
85. Flat washer (20)
86. Capscrew (7)
87. Nut (7)
88. Lockwasher (7)
89. Capscrew (22)
90. Nut (22)

Figure 2-68(4)—Continued

[136.] The relation (xiii) gives for $|rrrr|$ the value

$$|rrrr| = [(c_x c_{rx} + c_y c_{ry} + c_z c_{rz})^2]^{1/2} \dots\dots\dots (xvii),$$

or the direct stretch coefficient in direction r , (c_{rx}, c_{ry}, c_{rz}) , in terms of the system of elastic coefficients for the axes x, y, z .

If we put

$$x = c_{rx} / \sqrt[4]{|rrrr|}, \quad y = c_{ry} / \sqrt[4]{|rrrr|}, \quad z = c_{rz} / \sqrt[4]{|rrrr|},$$

and substitute, we obtain the surface

$$1 = \{ (c_x x + c_y y + c_z z)^2 \}^2,$$

which expanded gives us Rankine's *tasinomic* quartic :

$$1 = \left. \begin{aligned} & |xxxx| x^4 + |yyyy| y^4 + |zzzz| z^4 \\ & + 2 \{ |yyzz| + 2 |yzyz| \} y^2 z^2 + 2 \{ |zzxx| + 2 |zxzx| \} z^2 x^2 + 2 \{ |xxyy| \\ & \quad + 2 |xyxy| \} x^2 y^2 \\ & + 4 \{ |xxyz| + 2 |zxxz| \} x^2 yz + 4 \{ |yyzx| + 2 |xyyz| \} y^2 zx \\ & \quad + 4 \{ |zzxy| + 2 |yzxz| \} z^2 xy \\ & + 4 |yyyz| y^3 z + 4 |zzzy| z^3 y + 4 |zzzx| z^3 x + 4 |xxxx| x^3 z \\ & \quad + 4 |xxyy| x^3 y + 4 |yyyz| y^3 x \end{aligned} \right\} \quad (xviii).$$

This equation with its fifteen *homotatic* coefficients was first given by Haughton in his memoir of 1846. These 15 coefficients are the 15 coefficients of *rari-constancy* multiplied by the numbers 1, 6, 12 or 4, so that the expressions for the work, stresses etc., can on that hypothesis be given in terms of the coefficients of this equation.

Its fundamental property is that the direct-stretch coefficient in any direction varies inversely as the fourth power of the corresponding ray.

[137.] Paragraphs 10 and 11 together with the footnote pp. 359—62 reproduce results of Rankine and Haughton with regard to the nature of the elastic coefficients. Thus it is pointed out :

(i) That there are sixteen directions real or imaginary for which $|rrrr|$ is a maximum or minimum. These directions cut the *tasinomic* surface at right-angles, and possess the peculiarity that any stretch in their direction produces a *traction* only across a plane normal to their direction (pp. 356—7).

(ii) That if we take

$$|x'x'x'x'| + |x'x'y'y'| + |x'x'z'z'| = S_{x'},$$

or $S_{x'}$ equal to the sum of direct- and cross-stretch coefficients for the direction x' , then

$$S_{x'} = (c_x c_{x'x'} + c_y c_{x'y'} + c_z c_{x'z'})^2 (c_{xx'} + c_{yy'} + c_{zz'})$$

- | | | |
|------------------------|------------------------|--------------------------|
| 1. Cover | 19. Capscrew (2) | 37. Fastener (4) |
| 2. Fastener (16) | 20. Loop clamp (2) | 38. Plastic washer (4) |
| 3. Plastic washer (16) | 21. Bracket | 39. Cable cover |
| 4. Gasket set | 22. Bracket | 40. Capscrew (4) |
| 5. Dirt trough | 23. Bracket (2) | 41. Lockwasher (4) |
| 6. Cover | 24. Bracket (4) | 42. Cab cover |
| 7. Fastener | 25. Flat washer | 43. Machine screw (29) |
| 8. Plastic washer | 26. Flat washer | 44. Machine screw (4) |
| 9. Cover | 27. Boot clamp (8) | 45. Self-locking nut (4) |
| 10. Fastener (8) | 28. Gantry boot (2) | 46. Gasket assembly |
| 11. Plastic washer (8) | 29. Gantry boot (2) | 47. Cover |
| 12. Cover | 30. Cover (2) | 48. Capscrew |
| 13. Capscrew (4) | 31. Machine screw (16) | 49. Bracket |
| 14. Lockwasher (4) | 32. Gasket (2) | 50. Bracket |
| 15. Nut (4) | 33. Cover | 51. Floor plate |
| 16. Guard assembly (2) | 34. Capscrew (2) | 52. Machine screw (6) |
| 17. Fastener (2) | 35. Lockwasher (2) | 53. Flat washer (6) |
| 18. Plastic washer (2) | 36. Nut (2) | |

Figure 2-68(5)—Continued

[138.] Saint-Venant in the twelfth paragraph of this section of his memoir (pp. 360—5) treats the case in which the elastic material has three rectangular planes of symmetry. This reduces the 21 coefficients to nine, for all the stretch-slide coefficients and cross-slide coefficients (i.e. Rankine's *asymmetrical elasticities*) must now vanish.

Let a, b, c be the direct-stretch
 d, e, f „ direct-slide
 d', e', f' „ cross-stretch } coefficients.

Then the tasinomic surface (xviii) becomes :

$$1 = ax^4 + by^4 + cz^4 + 2(2d + d')y^2z^2 + 2(2e + e')z^2x^2 + 2(2f + f')x^2y^2 \dots \text{(xxii)}.$$

The maximum-minimum values of $|rrrr|$ are now sought and are found to lie in the three axial directions x, y, z , and in pairs of others lying in each plane yz, zx, xy , or 9 in all. The first three solutions are always real; the second six will be imaginary, since the ratio of their direction-cosines become imaginary, when

$$\left. \begin{matrix} 2d + d' \\ 2e + e' \\ 2f + f' \end{matrix} \right\} \text{ lie between } \left\{ \begin{matrix} b \text{ and } c \\ c \text{ and } a \\ a \text{ and } b \end{matrix} \right\} \text{ respectively} \dots \text{(xxiii)}.$$

Saint-Venant remarks that the conditions (xxiii) are those for the *gradual variation in one sense* of the stretch-coefficients in the three principal planes of elastic symmetry—a physical characteristic, he holds, probably possessed by all natural bodies.

[139.] In the following section we have the statement of the conditions for *ellipsoidal* elasticity, i.e. that the first three quantities of (xxiii) be respectively equal: (i) to the arithmetic, or (ii) to the geometric mean of the corresponding second three quantities of (xxiii). In either case the direct-stretch coefficient $|rrrr|$ can be represented by the ray of an ellipsoid. In the first case the direct-stretch coefficient varies as the inverse square of the ray of the ellipsoid:

$$1 = ax^2 + by^2 + cz^2;$$

and in the second case as the inverse fourth power of the ray of the ellipsoid:

$$1 = x^2 \sqrt{a} + y^2 \sqrt{b} + z^2 \sqrt{c}.$$

The practical application of this ellipsoidal distribution has been discussed by Saint-Venant in the annotated *Clebsch*: see our analysis of that work in Arts. 307 to 313.

[140.] The next two paragraphs (pp. 367—72) are occupied with an extension of Lamé's solution of the equations of elastic

1. Door stop
2. Strip
3. Hinge
4. Door assembly
5. Door jam
6. Cotter pin (2)
7. Handle (2)
8. Washer
- 8A. Screw
9. Cab door lock
- 9A. Lockwasher
10. Sleeve
11. Square
12. Capscrew (8)
13. Lockwasher (8)

14. Nut (8)
15. Capscrew (12)
16. Lockwasher (12)
17. Door jam
18. Capscrew
19. Capscrew (13)
20. Lockwasher (14)
21. Nut (14)
22. Door jam
23. Strip
24. Strip
25. Panel
26. Cable guard
27. Cable guard
28. Cover

29. Cover
30. Capscrew (2)
31. Lockwasher (2)
32. Front floor plate
33. Flat washer (5)
34. Machine screw (5)
35. Flat washer (6)
36. Machine screw (6)
37. Floor plate
38. Flat washer (6)
39. Machine screw (6)
40. Floor plate
41. Support

Figure 2-68(6)—Continued




Figure 2-69. Radiator, guard, and hoses, removal.

if a solution in terms of *direct and inverse potentials* is obtainable (pp. 372—4).

[142.] Hitherto the set of ellipsoidal conditions of the type

$$2d + d' = \sqrt{bc}$$

has been seen as one only of the number which satisfies the relations (xxiii). Saint-Venant now attempts to give it a far more important and special physical meaning. Namely, he proceeds to show that these relations hold exactly or very closely for bodies which originally isotropic have afterwards received a permanent strain unequal in different directions. He describes the bodies in question in the following terms :

En effet, dans les corps à cristallisation confuse tels que les métaux, etc., employés dans les constructions, où les molécules affectent indistinctement toutes les orientations, si les élasticités sont égales dans trois directions rectangulaires, elles doivent l'être en tous sens, car on ne voit aucune raison pour qu'elles soient plus grandes ou moindres dans les autres directions. Si les élasticités y sont inégales, cela ne peut tenir qu'à des rapprochements moléculaires plus grands dans certains sens que dans d'autres, par suite du forgeage, de l'étirage, du laminage, etc., ou des circonstances de la solidification. Calculons les grandeurs nouvelles que doivent prendre les coefficients d'élasticité dans un corps primitivement isotrope ainsi modifié (p. 374).


Bodies with 'confused crystallisation' Saint-Venant terms *amorphous solids*, and he now proceeds to show that within certain limits of aeolotropy, they possess an ellipsoidal distribution of elasticity. He assumes that the bodies have *rari-constant* elasticity.

[143.] Let s, s', s'' be the *principal stretches* of the permanent set given to the body, let $\rho_0, r_0, x_0, y_0, z_0$ be the density, distance between two elements, and its projections on the directions of the principal stretches before the isotropy is altered. Then if ρ, r, x, y, z be the value of these quantities after aeolotropy is produced, we have

$$\left. \begin{aligned} x &= x_0 (1 + s), & y &= y_0 (1 + s'), & z &= z_0 (1 + s'') \\ \rho &= \rho_0 / \{1 + s \cdot 1 + s' \cdot 1 + s''\} \end{aligned} \right\} \dots\dots (xxix).$$

Let $f(r)$ be the law of intermolecular action, and $F(r) = \frac{1}{r} \frac{d}{dr} \left\{ \frac{f(r)}{r} \right\}$, then we have, m being the mass of a molecule :

$$\left\{ \begin{array}{l} |xxx| \\ |yyy| \\ |xyx| \end{array} \right\} = \frac{\rho}{2} \sum m F(r) \left\{ \begin{array}{l} x^4 \\ y^4 \\ x^2 y^2 \end{array} \right\} \dots\dots (xxx).$$



ME 3810-294-20 '2-71

Figure 2-71. Propeller shaft, removal.

Hence we may equate like powers of α , β , γ on both sides. In the first relation by equating the coefficients of β^4 and again of $\alpha^2\beta^2$ we deduce the first of relations (xxx) and also

$$\sum m \chi(r_0) x_0^4 = 3 \sum m \chi(r_0) x_0^2 y_0^2,$$

or
$$c_4 = 3 c_{2,2} \dots\dots\dots(\text{xxxiv}).$$

In the second relation by equating the coefficients of $\alpha^4\beta^2$, $\alpha^4\gamma^2$, $\beta^4\gamma^2$ and $\beta^4\alpha^2$ we obtain the third of relations (xxx), as well as the new one

$$c_6 = 5 c_{4,2} \dots\dots\dots(\text{xxxv}).$$

By equating the coefficients of β^6 we reach the second of relations (xxx); and by equating those of $\alpha^2\beta^2\gamma^2$ the new one:

$$c_8 = 15 c_{2,2,2} \dots\dots\dots(\text{xxxvi}).$$

From these relations¹ among the c 's we have by multiplying out the first two expressions of (xxxii) and neglecting the products of s , s' , s'' ,

$$\begin{aligned} |xxxx| \times |yyyy| &= 9 \left\{ \frac{(1+s)^2(1+s')^2}{(1+s'')^2} c_{2,2}^2 + c_{2,2} c_{2,2,2} (6s + 6s' + 2s'') \right\} \\ &= 9 |xyxy|^2. \end{aligned}$$

This is the required type of relation on the hypotheses of *rari-constancy* and *small* permanent strain.


[144.] With regard to the latter assumption Saint-Venant remarks that the terms neglected can only produce very small errors:

...si l'on considère que les écrouissages et la trempe, qui changent très-sensiblement la ténacité et les coefficients d'élasticité, altèrent à peine la densité des corps. On peut d'ailleurs s'assurer, par un calcul, que les portions ainsi négligées de l'expression de $3|xyxy|$ sont constamment comprises entre les portions correspondantes de celles de $|xxxx|$ et $|yyyy|$, en sorte qu'en supposant même qu'elles altèrent légèrement les valeurs absolues de ces trois coefficients, elles n'altéreront pas sensiblement pour cela la relation de moyenne proportionnalité de $3|xyxy|$ entre $|xxxx|$ et $|yyyy|$, donnée par les termes du premier ordre en s , s' , s'' (p. 379).

The calculation mentioned is made by Saint-Venant in a footnote pp. 379—81.

The other assumption that rari-constancy holds for isotropy seems very approximately, if indeed not absolutely, true in the

¹ Saint-Venant obtains these relations among the c 's by appealing to a general principle given by Cauchy in his *Nouveaux Exercices*, Prague, 1835, p. 35. It amounts to replacing 4 or 6 in (xxxiii) by the general index $2n$ and then equating general terms.



ME 3810-294-20/2-73

Figure 2-73. Lines and fittings, removal.

to open the carburetor throttle valve, thus allowing more fuel to enter the engine. The additional fuel prevents the engine from slowing down, and the governor has maintained the engine at the desired speed, which is represented by the throttle setting.

b. Speed Governor Removal. Refer to figure 2-77 and remove the speed governor.

c. Speed Governor Replacement. Refer to figure 2-77 and install the speed governor.

d. Speed Governor Adjustment.

(1) Adjust the length of the linkage from the carburetor side of the cross-shaft shown in figure 2-76 as follows:

(a) Push throttle lever (fig. 2-75) forward so throttle lever (fig. 2-76) is against the low speed stop. Check linkage on opposite side of engine to be sure the carburetor throttle valve is closed.

(b) Move the throttle lever (fig. 2-75) fully back and see that throttle lever (fig. 2-76) is

against the high-speed stop. Full movement of the throttle lever (fig. 2-75) should result in full range movement of throttle lever (fig. 2-76). With throttle lever against highspeed stop, check to see that throttle valve is approximately full open.

(2) Run engine until normal operating temperature is obtained.

(3) Refer to paragraph 2-83b and adjust carburetor.

(4) Pull throttle lever (fig. 2-76) back to obtain high-idle speed (para 1-7).

(5) Apply load to engine sufficient to reduce engine speed to normal governed speed and determine if carburetor throttle lever is wide open. If the throttle lever is wide open, move governor linkage (fig. 2-76) slightly toward closed position and then release. Now the linkage must return the carburetor lever to the wide open position.

(6) Adjust high-speed stop screw (fig. 2-

On pp. 384—393 he shews that Green's conditions flow from the hypotheses with which he has started. He then proves :

(i) From the tasinomic relation that the stretch-coefficient is the same for every direction or

$$|x'x'x'| = |xxxx|.$$

Thus an equal stretch always produces the same element in the traction whatever its direction.

(ii) That the second set of Green's conditions are fulfilled for all axes, i.e.

$$|y'y'y'| = |z'z'z'| = 0, \text{ etc.}$$

(iii) That the conditions whose type is

$$|zzzz| = 2 |y'z'z'| + |y'y'z'|$$

are true for any change of rectangular axes.

(iv) That the third set of conditions of the type

$$|x'x'y'z'| + 2 |z'x'x'y'| = 0$$

are also true for any change of rectangular axes.

(v) That the reciprocal theorems are true, i.e. if any one of the relations in (i) to (iv) hold for all rectangular axes, then Green's fourteen conditions follow.

It will thus be noted that Green's conditions are not based upon any conception of direction in the body, if fulfilled for one set of rectangular axes they are fulfilled for all. So far as these conditions are concerned the body possesses isotropy of direction, i.e. there is nothing of the nature of crystalline axes, or *the peculiarity of the medium has no relation to direction in space*. This seems to me the element of isotropy in Green's conditions which Glazebrook misses, and which Saint-Venant overstates when he identifies it with absolute elastic isotropy. Glazebrook well points out that if we give a stretch s_x only we have the following system of stresses¹:

$$\begin{aligned} \widehat{xx} &= |xxxx| s_x, & \widehat{yz} &= |yzxz| s_x, \\ \widehat{xy} &= |xyyy| s_x, & \widehat{zx} &= 0, \\ \widehat{zz} &= |xxzz| s_x, & \widehat{zy} &= 0. \end{aligned}$$


Here we are at liberty to take the stretch in the direction of the axis

¹ By choosing as our axes the *orthotatic axes* we can reduce the stress-strain relations as given by Green to the following types :

$$\begin{aligned} \widehat{xx} &= a\theta - 2fs_y - 2es_z, \\ \widehat{yz} &= d\sigma_{yz}, \end{aligned}$$

where

$$\left. \begin{aligned} a &= |xxxx| = \text{same for all directions} \\ d &= |yzyz| \\ e &= |xxzx| \\ f &= |xyxy| \end{aligned} \right\} = \text{values for orthotatic axes of direct-slide coefficients,}$$




- STEP 1. BACK OFF HIGH AND LOW SPEED STOPS. PUSH ENGINE THROTTLE (FIGURE 2-75) FORWARD UNTIL THROTTLE LEVER CONTACTS LOW SPEED STOP. START ENGINE AND CHECK LOW IDLE SPEED. ADJUST LOW SPEED STOP UNTIL SPEED IS CORRECT. REFER TO PARAGRAPH 1-6.
- STEP 2. PULL THROTTLE (FIGURE 2-75) PULL BACK AND ADJUST HIGH SPEED STOP IN THE MANNER DESCRIBED ABOVE. CHECK ENGINE HIGH AND LOW IDLE SPEEDS AS LISTED IN PARAGRAPH 1-7.

ME 3810-294-20/2-76

Figure 2-76. Engine speed governor adjustment.

- STEP 1. DISCONNECT THROTTLE LINKAGE AT THROTTLE LEVER.
- STEP 2. REMOVE TUBE BY REMOVING COUPLING NUTS.
- STEP 3. REMOVE COTTER PIN AND WASHER AND REMOVE THROTTLE LEVER FROM CROSS-SHAFT.
- STEP 4. REMOVE THROTTLE CABLE CLAMP.
- STEP 5. REMOVE GOVERNOR BODY MOUNTING NUTS AND LOCKWASHERS.



ME 3810-294-20/2-77

Figure 2-77. Engine speed governor, removal.

place, il est impossible de ne point convenir que l'inégal rapprochement moléculaire en divers sens doit influer sur la grandeur des *élasticités directes* $|xxxx| = \overline{xx}/s_x$ comme elle influe bien certainement sur celle des autres élasticités, dites *latérales*, $|xyxy| = \overline{xx}/s_y$, ou *tangentielles*, $|xyxy| = \overline{xy}/\sigma_{xy}$, etc., puisque sans les inégalités au moins de celles-ci en divers sens, les formules ne donneraient pas de double réfraction. Un milieu ne peut être élastique et vibrant si ses parties n'agissent pas les unes sur les autres, et quelque soit le mode de leur action, il n'est pas possible d'imaginer qu'elles engendrent des élasticités directes parfaitement égales, lorsqu'il y a une inégalité de texture qui rend inégales les élasticités latérales ou tangentielles. (pp. 396—8.)

This argument seems to me of great weight (see, however, a point raised in our Art. 193 (1)), and would incline me to reject Green's conditions (especially when we remember that Green himself supposed the ether-density to vary in refracting media), even were there no other grounds for questioning his hypotheses.

[148.] Saint-Venant now proceeds to deduce the *exact* wave-surface of Fresnel on the supposition that the vibrations are not accurately in the wave-front. He does this on the lines of Cauchy's memoir of 1830, but he does not assume rari-constancy and in many respects his method is an improvement on Cauchy's. This leads him to the following inter-constant conditions; the structure of the ether being supposed to have three planes of symmetry and thus its elasticity to be represented by the nine constants of our Art. 117 (a):

$$\left. \begin{aligned} (b-d)(c-d) &= (d+d')^2, & (c-e)(a-e) &= (e+e')^2 \\ (a-f)(b-f) &= (f+f')^2 \\ (a-e)(b-f)(c-d) &+ (a-f)(b-d)(c-e) \\ &= 2(d+d')(e+e')(f+f') \end{aligned} \right\} \dots(\text{xxxix}).$$

If the relations (xxxix) are satisfied we shall have Fresnel's wave-surface. If we make $a=b=c$ we shall reduce these conditions to Green's, which are thus only a particular case of those of Cauchy and Saint-Venant. (pp. 398—406.)

[149.] On pp. 406—411 Saint-Venant demonstrates that the relations (xxxix) give practically the same results as the ellipsoidal distribution of (xxxvii). He supposes $d/d' = i$ and then solves the first equation of both sets (xxxix) and (xxxvii) for d ; let the values so obtained be respectively d_1 and d_2 . Then by a numerical

fuel will be caused by some factor other than the fuel pump.

(3) When testing the fuel pump, first see that there is adequate fuel in the tank.

(4) Disconnect the line from the fuel tank to the fuel pump at the pump and see that fuel flows freely. If it does, fuel is available at the fuel pump and the line to the tank is in good condition. Reconnect the line.

(5) Connect a pressure gage in the input fuel line at the carburetor as shown in figure 2-81. Be sure the length of the connecting hose is as shown and that all connections are leak proof.

(6) Start the engine and run it at 500 rpm. Stop the engine when the maximum fuel pressure has been read on the gage. If the pressure is below 3 1/2 psi or above 5 psi, replace the fuel pump.

c. Removal and Replacement. Refer to figure 2-82 and remove and replace a faulty fuel pump. Note that this fuel pump includes a sediment bowl.

NOTE

Before installing a new fuel pump, make sure it is in good condition. To do so, follow steps (1) through (4) below.

(1) Hold the fuel inlet and output openings closed with the fingers of one hand.

(2) Move the lever (fig. 2-82) up and down. The pump will create a feeling of suction and pressure as the lever is moved, if it is in good condition.

(3) When installed, if there is an air leak between the sediment bowl and the bowl gasket, the pump cannot draw fuel into the bowl. To fix, install new gasket and be sure the bowl seats firmly. Also tighten knurled nut beneath bowl.

(4) If the strainer bowl still does not fill, air may be trapped in lines to the pump. To fix, loosen bowl slightly so air can escape and blow into fuel-tank filler neck. This will force fuel into fuel pump bowl. Now tighten the bowl down securely.




Figure 2-79. Carburetor linkage.

2-84. Fuel Pump

a. General. The fuel pump is a mechanical type with offset filter. The suction side of the pump is connected to the fuel tank and the discharge side to the carburetor, where the fuel accumulates in the carburetor float bowl for use as required by engine demand.

b. Test.

NOTE

The following test will be used to determine if it is necessary to replace the fuel pump.

(1) If the pump supplies too little fuel the engine will not run at all, or will falter or misfire under load.

(2) If the pump supplies too much fuel (which is rare), fuel will drip from the carburetor or the engine will not idle smoothly. The engine will be hard to start. Usually, too much

case there will be a denominator of 720 terms in the constants, and Saint-Venant wisely contents himself with the case of three planes of symmetry and a 9-constant medium.

The conclusions drawn as to the nature of the quartic and its special reduction to an ellipsoid, are all treated with somewhat fuller detail in the annotated *Clebsch*, and we have accordingly discussed them in our analysis of that work: see our Arts. 308 to 310.

[152.] We may note that Saint-Venant (pp. 424—5) attempts to apply the ellipsoidal distribution of elasticity, which leads to the ellipsoidal distribution of stretch-modulus, i.e.

$$\frac{1}{\sqrt{E_r}} = \frac{c^2_{xr}}{\sqrt{E_x}} + \frac{c^2_{yr}}{\sqrt{E_y}} + \frac{c^2_{zr}}{\sqrt{E_z}},$$

to the case of *wood*. He appeals to Hagen's results (see our Art. 1229*) and compares Hagen's empirical formula

$$\frac{1}{E_r} = \frac{c^2_{xr}}{E_x} + \frac{c^2_{yr}}{E_y} \dots\dots\dots (\alpha)$$


with that given by the ellipsoidal distribution

$$\frac{1}{\sqrt{E_r}} = \frac{c^2_{xr}}{\sqrt{E_x}} + \frac{c^2_{yr}}{\sqrt{E_y}} \dots\dots\dots (\beta).$$

He shews the theoretical impossibility of Hagen's formula, arising from the fact that if $E_x = E_y$, E_r is not equal to them, and endeavours to shew by curves that (β) and (α) coincide within the limits of experimental error. By graphical representation of the curves it is seen that only the ellipsoidal distribution gives anything like a satisfactory theoretical as well as practical figure, and Saint-Venant concludes that, although proved for a different kind of medium (see our Arts. 142 and 144), it may be practically of use in the case of fibrous material like wood. Later Saint-Venant saw occasion to alter this opinion; he treats this important material very fully in the *Leçons de Navier* (pp. 817—25) and in the annotated *Clebsch* (pp. 98—110). Under the latter heading we shall discuss his more complete treatment of the subject: see our Arts. 308—310. The memoir ends with the *résumé* to which we have before referred.


[153.] *Sur la détermination de l'état d'équilibre des tiges élastiques à double courbure.* *Les Mondes*, Tome 3, 1863, pp. 568—575. This note was a contribution to the *Société Philomathique*, August 8, 1863; see also *L'Institut*, 1863, pp. 324—5.

Consider a rod of double curvature; let M_x , M_y , M_z be the



ME 3810-294-20/2-81

Figure 2-81. Checking fuel pump output pressure.



- STEP 1. STOP ENGINE. DISCONNECT FUEL LINES.
- STEP 2. REMOVE BOLTS AND LOCK-WASHERS. REMOVE FUEL PUMP WITH SEDIMENT BOWL AND GASKET FROM ENGINE.
- STEP 3. POSITION FUEL PUMP ON ENGINE WITH GASKET BETWEEN PUMP AND ENGINE. INSTALL BOLTS AND LOCK-WASHERS. RECONNECT FUEL LINES.
- STEP 4. LOOSEN KNURLED NUT AT THE BOTTOM OF BOWL, SWING BAIL ASIDE, AND REMOVE BOWL IF NECESSARY.
- STEP 5. WIPE OUT SEDIMENT BOWL WITH CLEAN CLOTH. INSTALL NEW GASKET ABOVE BOWL. POSITION

Figure 2-82. Fuel pump and fuel sediment bowl, removal and replacement.

This memoir draws attention to the point considered by Saint-Venant in his memoirs of 1843 and 1844; see our Arts. 1598* and 1603*; namely the importance of taking into consideration the 'angle of torsion' or angle between new and old osculating planes in dealing with the elastic equilibrium of wires of double-curvature. Saint-Venant brings out the importance by a good example, namely a curved wire turned upon itself so as to have the same curvature at each point of the central axis, but so that the naturally longest and shortest 'fibres' interchange places.

He points out that the stretch in a fibre distant z from the central axis is:

$$z \sqrt{1/\rho^2 - 2/\rho\rho_0 \cdot \cos \epsilon + 1/\rho_0^2},$$

where ρ, ρ_0 are the new and the primitive radii of curvature and ϵ the angle the new and old radii of curvature make with each other. In the example above referred to $\rho = \rho_0$ and $\epsilon = \pi$, so that the stretch becomes

$$2z/\rho_0.$$

Generally when $\rho = \rho_0$, the stretch equals

$$2z/\rho_0 \cdot \sin \frac{1}{2} \epsilon.$$

In conclusion Saint-Venant refers to the contributions of Poisson, Binet, Wantzel and himself to the subject: see for references.


[56.] *Mémoire sur les contractions d'une tige dont une extrémité a un mouvement obligatoire; et application au frottement de roulement sur un terrain uni et élastique: Comptes rendus*, T. 58, 1864, pp. 455—8.

This memoir was written in 1845, and is an attempt to apply the theory of elasticity to the phenomena of rolling friction. The chief results were published in the *Bulletin de la Société Philomathique* of June 21, 1845. The following conclusions are given in the *résumé* in the *Comptes rendus*:

On en déduit que le frottement de roulement sur un pareil sol est: 1° proportionnel à la pression; 2° en raison inverse du rayon du cylindre; 3° indépendant de sa longueur (ou de la largeur de jante, si c'est une roue); 4° proportionnel à la vitesse; 5° d'autant moindre que le terrain élastique est plus roide ou moins compressible.

Saint-Venant remarks:

Ces résultats sont d'accord avec un certain nombre d'expériences de



ME 3810-294-20/2-84

Figure 2-84. Water pump and fan replacement.

(3) Remove the capscrews and washers securing the fan and remove the fan. See figure 2-84.

(4) Remove the fan belts from the water pump pulley.

(5) Loosen hose clamps and remove hoses from the water pump.

(6) Remove the mounting bolts from the water pump and remove the pump from the engine. Remove pump gasket.

c. Installation. Refer to figure 2-84 and install the water pump as follows:

(1) Position the pump on the front of the crankcase and install the pump gasket and all mounting bolts.

(2) Install radiator (para 2-74c).

(3) Install fan belts on water pump pulley.

(4) Fasten radiator hose to water pump.

(5) Install the fan.

(6) Fasten the alternator bracket and adjust fan belt tension. See figure 2-85 for belt adjustment procedure and adjust belt tension.

(7) Fill the cooling system to the proper level with the correct coolant.

d. Service Water pump service consists of lubricating the pump shaft bearings in accordance with the current LO. At the same time, inspect the fan for bent or damaged blades. Replace the fan if necessary.

e. Guard Replacement. Refer to paragraph 2-74 and remove and replace damaged water pump fan guard.

f. Belt Adjustment and Replacement. Replacement of belts and belt adjustment are covered in paragraph 2-88.

Substitute in the above equation (1) and we obtain

$$\iint dy \, dz \left\{ \mu_1 \frac{du}{dy} \left(\frac{du}{dy} - \tau z \right) + \mu_2 \frac{du}{dz} \left(\frac{du}{dz} + \tau y \right) \right\} = 0.$$

Integrate this equation by parts in the usual way, and it becomes

$$\begin{aligned} \int u \left[\mu_1 \left(\frac{du}{dy} - \tau z \right) \cos (ny) + \mu_2 \left(\frac{du}{dz} + \tau y \right) \cos (nz) \right] ds \\ - \tau \iint u \left[\mu_1 \frac{d^2 u}{dy^2} + \mu_2 \frac{d^2 u}{dz^2} \right] dy \, dz = 0 \dots \dots \dots (2); \end{aligned}$$

here (ny) and (nz) denote the angles which the normal to the surface at the point (x, y, z) makes with the axes of y and z respectively; and ds is an element of the curve of intersection of the body by a plane at right angles to the axis of x .

If we equate to zero the term in brackets in the double integral we obtain the equation which must hold at every point of the interior; and if we equate to zero the term in brackets in the single integral we obtain the equation which must hold at every point of the surface.

But Saint-Venant does not explain why we must equate these terms separately to zero; that is, he does not explain why he breaks up equation (2) into *two* equations. Moreover the whole process borrows so much from the memoir on Torsion that it has

air of being an independent investigation.

St-Venant says:

Or la deuxième et la première parenthèse carrée, égales séparément à zéro...

by this he means the terms contained within the square brackets in (2). The English translation has very strangely "Now the squares of the second, and of the first parenthesis, each equated to zero,..."

[158.] A remark of Saint-Venant's on p. 809 may be cited:

Le calcul du potentiel de torsion a aussi, en lui-même, une valeur pratique; car les ressorts en hélice, qu'on oppose souvent à divers chocs, travaillent *presque* entièrement par la torsion de leurs fils, ainsi que je l'ai montré en 1843, et que l'ont remarqué, au reste, Binet dès 1814, M. Giulio en 1840, et récemment des ingénieurs des chemins de fer.

See our Arts. 175*, 1220*, 1382* and 1593—5*. The 1814 and the *récemment* (1864) mark the wide interval which too often separates theory from practice!

ground connection. Use an accurate voltmeter set on the 50-volt *dc* scale for this check. The ignition switch must be turned ON during this test. Full battery voltage of 24 volts should be shown. If no voltage is indicated, an open circuit between the battery and the alternator is indicated. Check battery cables, ignition switch, and wiring.

(2) With the ignition switch on, but the engine NOT started, check for full battery voltage from the ignition (IGN) lead of the alternator to ground. Full battery voltage must be indicated. It will be necessary to unplug the ignition (IGN) connector and check the male side with the voltmeter probe. Full battery voltage must be present at both alternator terminals in order for the machine to function properly.

CAUTION

Do not run the alternator with its output circuit open and the ignition lead energized. This will create extremely high voltages which will seriously damage the alternator. Never attempt to polarize this alternator. Always disconnect all alternator leads if welding is to be done on this unit.

e. Alternator Replacement. Refer to figure 2-85 and loosen alternator drive belts. Remove all electrical connections to the alternator. Support the alternator, remove the adjusting lock screw and remove the alternator mounting bolts, nuts, and lockwashers. Remove alternator. Install a new alternator and secure with mounting bolts, nuts, and lockwashers as shown in figure 2-85. Connect all electrical connections, and reinstall alternator-water pump drive belts. Adjust alternator-water pump belt tension as described in *b* above.

2-89. Starter Assembly

a. Starting Motor. The starting motor is designed for high torque, short use applications. It engages the flywheel ring gear, and is used to crank the engine until it starts. When the engine starts, the starter motor automatically disengages.

CAUTION

Never crank the engine for more than 30 consecutive seconds with the starter motor. If this does not start the engine wait at least two minutes before trying again.

(1) *Motor and solenoid test.* Before removing the motor make the following tests. Check the batteries (para 2-53) to make sure that the batteries are in good condition. Inspect all starting motor wiring for frayed insulation or other damage. Replace or repair damaged wiring. Inspect all connections to the starting motor, solenoid, magnetic switches, ignition switch, start pushbutton, and battery, including all ground connections. Clean and tighten defective connections. If the trouble is not found, connect a jumper wire around any switch or solenoid suspected of being defective. If the system functions properly using this method, replace the defective item. If none of the above has located the trouble, check the starting motor battery terminal, using a voltmeter adjusted for *dc* operation, and measure the battery voltage. If voltage is 22- to 24-volts, replace the starting motor.

(2) *Motor replacement.* Refer to figure 2-86 and remove and replace the starting motor.

b. Starting Motor Solenoid Replacement. Refer to figure 2-86 and remove the solenoid mounting capscrews. Refer to figure 2-87 and remove the starting motor solenoid.

c. Magnetic Switch Replacement.

(1) *General.* The magnetic switch shown in figure 2-88, sheet 2 is used to reduce the amount of current which must pass through the engine start switch. When energized, it energizes the starter solenoid, thus starting the engine.

(2) *Removal.* Refer to figure 2-88, sheet 2 and remove electrical leads, two mounting screws, and lockwashers. Remove the magnetic switch.

(3) *Installation.* Position magnetic switch as shown in figure 2-88, sheet 2, install screws and lockwashers, and attach electrical leads.

d. Reverse Polarity Relay.

(1) *General.* The reverse polarity relay contains a solid-state rectifier which prevents current from flowing through the engine starting circuit in the wrong direction. Refer to the wiring diagram of the relay in figure 2-88 and the engine wiring diagram, figure 1-4.

(2) *Testing.* With the relay removed from the engine, connect a 24 volt source to connector C (fig. 2-88). Then touch the relay case to ground. The polarities shown on the diagram must be observed. When this is done, the relay will be energized, and an audible "click" can be heard when the relay contacts close. If the contacts close, the relay is in good condition. If not, replace the relay.

li; the funeral discourses on Navier by Emmery and Girard, pp. li—liv: a bibliography of the works of Navier with copious remarks due to Saint-Venant, pp. lv—lxxxiii; the original prefaces to the editions of Navier's *Leçons* published in 1826 and 1833; pp. lxxxiv—xc; and finally Saint-Venant's *Historique abrégé des recherches sur la résistance et sur l'élasticité des corps solides*; pp. xc—cccxi.

[162.] The *Historique abrégé* is practically the only brief account of the chief stages of our science extant. Girard had written what was for his day a fair sketch of the *incunabula* (see our Art. 123*), but it remained for Saint-Venant, without entering into the analysis of the more important memoirs, to describe their purport and relationship. It fulfils a different purpose to our own history—for it makes no attempt to replace the more inaccessible memoirs—but as a model of how mathematical history should be written, we hold it to be unsurpassed, and can only regret that a recent French historian has not better profited by the example thus set¹.

We would especially recommend to the student of Saint-Venant's memoirs pp. clxxiii—xcxii, which treat of the relation of his own researches by means of the *semi-inverse* method to the work of his predecessors. The point we have referred to in our Art. 6, 8 and 9 is well brought out in relation to Lamé's proof of the right-six-face.

We will note one or two further points of the *Historique* in the following five articles.

[163.] On p. cxcviii in the footnote Saint-Venant gives the expression for the work-function in terms of the stresses when there is an *ellipsoidal* distribution of elasticity: see our Art. 144. He finds

$$W = \frac{1+i}{2(2+3i)} \left(\frac{\bar{x}\bar{x}}{a} + \frac{\bar{y}\bar{y}}{b} + \frac{\bar{z}\bar{z}}{c} \right)^2 + \frac{\bar{y}\bar{z}^2 - \bar{y}\bar{y}\bar{z}\bar{z}}{2bc} + \frac{\bar{x}\bar{z}^2 - \bar{z}\bar{z}\bar{x}\bar{x}}{2ca} + \frac{\bar{x}\bar{y}^2 - \bar{x}\bar{x}\bar{y}\bar{y}}{2ab},$$

where for isotropy $i = \lambda/\mu$ and $a^2 = b^2 = c^2 = \mu$.

¹ The essential feature of scientific history is the recognition of growth, the interdependence of successive stages of discovery. This evolution is excellently summarised in Saint-Venant's *Historique*. Our own 'history' is only a bibliographical repertorium of the mathematical processes and physical phenomena which form the science of elasticity, as a rule for the purpose of convenience chronologically grouped. M. Marie's *Histoire des sciences mathématiques* is a chronological biography, without completeness as bibliography or repertorium. Excellent fragments there are in it, but the same criticism applies to it.




Figure 2-87. Starting motor solenoid removal and replacement.

(5) Install new condenser and points, and adjust breaker points as follows: Turn the distributor shaft so that breaker arm rubbing point is on the high point of the breaker cam. Turn adjusting screw slightly until breaker point clearance is 0.022 inch, as measured by a round feeler gage. Tighten adjusting screw.

(6) Turn distributor shaft so breaker points are closed. Inspect breaker point alignment. Bend fixed point bracket so that points are aligned for full face contact. Recheck point gap and readjust if necessary.

(7) Install rotor.

c. Distributor Replacement and Adjustment.

(1) Wipe the cap and be sure all parts are clean and dry. Do not use degreasing compounds.

(2) Turn the engine crankshaft over to place the number one piston on top dead center of the compression stroke as shown in figure 2-80.

(3) Refer to figure 2-89 and place a drop of OE lubricating oil on the felt lubricant wick.

(4) Install the distributor in position on the engine. Be sure the distributor shaft tang engages the drive properly. Do not secure the manual advance (fig. 2-89) at this time.

(5) Place the distributor cap on the distributor and turn it until it drops into place. It will fit in only one position. Do not secure it with spring clips at this time.

(6) Trace the number one spark plug wire to its terminal in the cap. Raise the cap and determine if the rotor aligns with this same terminal. If the rotor does not align with this terminal, but instead aligns with the number six terminal, raise the distributor, disengaging the shaft tang, and rotate the shaft and rotor 180 degrees. Lower the distributor into the support again. This time install the advance arm lock-screw and secure finger tight.

(7) Be certain that the distributor cap is properly located on the distributor housing and that both mounting screws are tight.

CAUTION

If the distributor cap is incorrectly positioned on the distributor housing, it will usually result in a broken rotor when attempting to start the engine. The firing order is 1-5-3-6-2-4; and spark plug cables must be assembled in the distributor cap in this order in clockwise rotation as viewed from above the distributor.

(8) Disconnect the distributor vacuum advance line at the carburetor and close the fitting with a piece of tape.

d. Distributor Timing.

(1) Connect a stroboscopic timing light to the No. 1 spark plug. Some timing lights required connecting one lead to the spark plug terminal and the other to ground (parallel connection). Others require disconnecting the spark plug wire and connecting one of the timing light wires to the spark plug wire and the other wire to the spark plug terminal (series connection). Use white chalk to highlight the timing mark, figure 2-90.

(2) Start the engine and notice if the timing light is flashing. Each light flash should be fast and accurate, and the timing marks should be readily seen.

(3) When the engine is thoroughly warmed up and running at low idle speed (475-525 rpm), direct the timing light to the timing location on the fan drive pulley. The light should

He refers on this point to the experiments of Easton and Amos: see our Art. 1474*.

[165.] Pages ccxiv—xxiv deal with the problems of resilience and impact.

In the footnote p. ccxvii, there is an error in the integral of the equation $\frac{d^3z}{dt^3} = g \cos \alpha - \frac{g}{f} z$ there given. It should be

$$z = f \cos \alpha + V \sqrt{\frac{f}{g}} \sin \sqrt{\frac{g}{f}} t - f \cos \alpha \cos \sqrt{\frac{g}{f}} t.$$

The error was noted by Saint-Venant himself in a letter to the Editor of this History, August, 1885.

On p. ccxxii and footnote there should have been a reference to Homersham Cox with regard to the factor $k = 17/35$. His memoir of 1849 (see our Art. 1434*) seems to have escaped Saint-Venant's attention.

A further consideration of the effect of impact on bars when the vibrations are taken into account occurs on pp. ccxxxii—viii, and then follows (pp. ccxxxix—xlix) an account of Stokes' problem of the travelling load (see our Art. 1276*). Saint-Venant refers to the researches of Phillips and Renaudot, but his account wants bringing up to date by reference to more recent researches.

[166.] On pp. ccxlix—ccliii Saint-Venant refers to the rupture conditions given by Lamé and Clapeyron and again by Lamé for cylindrical and spherical vessels. It seems to me that he has not noticed here that these conditions are, on his own hypothesis of a *stretch* and not a *traction* limit, erroneous: see the footnotes to our Arts. 1013* and 1016*.

[167.] After an excellent and succinct account of the course of the investigations of Euler, Germain, Poisson, Kirchhoff &c. with regard to the vibrations of elastic plates (pp. ccliii—cclxxi) the *Historique* closes with two sections LXI. and LXII. (pp. cclxxi—cccxi) on the experiments made by technologists and physicists previously to 1864 on the elasticity and strength of materials. Good as these pages are, they are insufficient to-day in the light of the innumerable experiments of first-class importance made during the last




Figure 2-89. Distributor assembly removal, replacement and timing. (Sheet 1 of 2)

(8) The timing of the spark depends on the breaking of electrical contact at the breaker points. To assure accurate timing, make up a simple light circuit consisting of a 24 volt automotive light bulb with soldered-on leads or a socket with leads attached as shown in figure 2-91. Clip one lead to the lead to the movable breaker point and attach the other lead to ground. Turn the engine to TDC on the compression stroke for number one cylinder using timing marks shown in figure 2-90. Turn the ignition switch to the ON position. Rotate the distributor body (fig. 2-89) slightly to determine the point of breaker point opening, which will be the point where the light turns on. Tighten the hold down screws at the base of the distributor, making sure the body does not turn further. Reinstall distributor cap.

(9) Connect the distributor vacuum advance line to the carburetor.

2-91. Ignition Coil and Spark Plugs

a. General. The ignition coil has primary and secondary windings. The low voltage (24 volt) pulses from the distributor go to the primary

winding, where they cause a magnetic field to develop. When the distributor points open, this field collapses, inducing a very high voltage in the secondary winding. This high voltage is conducted to the engine spark plugs, via the high tension leads, to ignite the fuel in the combustion chamber.

b. Coil Testing. If a distributor ignition coil is thought to be defective, refer to figure 2-92 and disconnect electrical connections to the coil. Then test as follows.

(1) Check the continuity of the coil primary by connecting an ohmmeter across the primary terminals. The ohmmeter reading should be very low.

(2) Check the continuity of the coil secondary by connecting an ohmmeter across one primary terminal and the secondary terminal. The ohmmeter reading should be high.

(3) If no reading or an infinite reading is obtained, the coil is open or shorted, and should be replaced.

c. Coil Replacement. Remove the mounting screws, disconnect all electrical connections, and replace the ignition coil. Refer to figure 2-92.

cannot suppose the volume to diminish. We may, however, look at the matter thus :

Let ξ = the ratio of the slide-modulus to the dilatation coefficient ($= \mu/\lambda$), then (Vol. I. p. 885) :

$$\xi = \frac{3 - E/\mu}{E/\mu - 2}.$$

Hence, since ξ is necessarily positive, we must have $E/\mu > 2$ and < 3 (the mean of these gives the uni-constant hypothesis $E/\mu = 5/2$). But

$$\eta = \frac{E}{2\mu} - 1, \text{ or } \eta \text{ can only have values from } 0 \text{ to } \frac{1}{2}.$$

This proof holds only for an isotropic material. In the case of an aeolotropic material it does not seem obvious why a longitudinal stretch should not produce a negative dilatation. The ratio of dilatation to stretch

$$= \frac{s_x + s_y + s_z}{s_x} = 1 - \eta_1 - \eta_2,$$

and in the case of wood the values obtained for η_1, η_2 would seem to give this a negative value, for they are $> \frac{1}{2}$. Saint-Venant admits later this possibility: see his pp. 821—2. Hence any set of experiments which give values for $\eta > \frac{1}{2}$ may be taken to denote that the material in question is not isotropic and homogeneous.

On pp. 20—21 it is suggested that for some substances E may vary over the cross-section of a prism. Saint-Venant refers to the experiments on this point of Collet-Meygret and Desplaces: see our Chapter XI. He also regards Hodgkinson's experiments as leading to a like conclusion notwithstanding a special experiment to the contrary: see our Arts. 952* (iii), 1484* and references there. We thus have the formula

$$P_x = s_x \int E_x d\omega$$

put forward by Bresse, where P_x is the total traction in a prism stretched s_x in the direction of its axis x , and $(\int E_x d\omega)/\omega$ is the mean value of the stretch-modulus over the cross-section ω . For metals *coulés ou laminés*, where on the lateral faces there is a surface or *skin* change of elasticity, Saint-Venant would take:

$$P_x = s_x (E_0 \omega + \epsilon \chi),$$

χ étant le périmètre de la section supposée diminuée d'un à deux millimètres tout autour, afin de représenter le développement moyen de la croûte douée généralement de plus de roideur et de nerf que le reste :



Figure 2-92. Ignition coil, testing, removal, and replacement.

b. Test. Connect suppression lead to positive side of any battery. Place the tip of a light bulb on the negative terminal. Hold the other end of this lead against the metal side of the light bulb. If the light bulb illuminates, the lead is at least not an open circuit, and may be fit for further use. If the light does not come on, replace the lead. If an ohmmeter is available, the lead should test about 2,000 ohms per inch of length.

2-93. Sending Units

a. General. The sending units and associated lights and switches provide visual indications of developing trouble.

b. Oil Temperature Switch. Refer to figure 2-93. Disconnect electrical lead. Drain oil below the level of the switch, then unscrew and replace a faulty oil temperature switch.

c. Water Temperature Sender. Open radiator drain cocks and drain coolant level below the level of the water temperature sender. Then refer to figure 2-94; disconnect electrical leads and unscrew and replace the water temperature sender.

d. Oil Pressure Sender. Drain engine oil below the level of the pressure sender. Refer to figure 2-95; disconnect electrical leads and unscrew and replace a faulty oil pressure sender.




Figure 2-93. Oil temperature sender, removal and replacement.

est telle que le rapport T_0/E varie moins que y , l'équation sera, en désignant comme à l'ordinaire par y' la grandeur de l'ordonnée de cette fibre, et par E' , T'_0 , les valeurs correspondantes de E , T_0 ;

$$M_0 = \frac{E_0 T'_0 I}{E' y'} + \frac{e T'_0 i}{E' y'},$$

ou bien, C et c désignant deux constantes dépendant comme E_0 et e de la nature de la matière et de son mode de forgeage ou de fusion,

$$M_0 = C I/y' + c i/y'.$$

Saint-Venant calculates the value of M_0 for a rectangular section, and also deals with a similar expression for the case of the *wood* prism referred to above; see his pp. 117—8.

(g) In §§ 8—12 (pp. 22—26) the reader will find some account of the behaviour of a material under stress continued even to rupture. This account was doubtless for the time succinct and good, but there are several points which could only be accepted now-a-days with many reservations. For example the statement (§ 11): *Le calcul théorique est toujours applicable pour limiter les dilatations et établir les conditions de résistance à la rupture éloignée*—is one which requires much reservation. We have seen in Vol. I. p. 891 that a material may be in a state of ease and yet not possess linear elasticity for strains such as often occur in practice. Further that even when there is linear elasticity its limit can often be raised without *enervation* almost up to the yield-point, where one exists. Hence when Saint-Venant takes s_0 to be the stretch at which material ceases *de s'écrouir et commence à s'énerv*, *ce qui se manifeste par la marche des allongements persistants*, and puts $P_0 =$ or $< E\omega s_0$ as the safe tractive load—where E is the stretch-modulus and ω the sectional area—we find some difficulty in ascertaining what limit s_0 really represents. In most cases before enervation begins, *linear* elasticity will be long gone, and all the formula really can tell us is the stage at which *linear elasticity fails*; this fail-limit may be very far from the yield-point, and in some materials very far indeed from the elastic limit.

Saint-Venant refers to the 'fatigue' of a material due to repeated loading and to the question whether vibrations can change the molecular structure from fibrous to crystalline (see our Arts. 1429*, 1463* and 1464*). These are points on which we know to-day a good deal more than was accessible in 1857.



Figure 2-96. Checking and servicing engine oil pan.

the engine crankcase to bring the oil level to the FULL mark on the dipstick. Always shut the engine down for a few minutes before checking oil level. This will allow oil in the engine to return to the crankcase. Refer to figure 2-97 and drain the lubricating oil from the crankcase at the intervals prescribed in the current LO.

2-97. Rocker Arm/Tappet Inspection and Adjustment

a. *General.* Rocker arm adjustment is required when tappet noise increases noticeably. Basically, it is the clearance between the valve stem and the rocker arm which is adjusted.

b. *Adjustment.*

(1) Disconnect the high tension cable between the distributor cap and the coil, at the oil.

Figure 2-97. Draining engine oil pan.

(2) Remove the valve housing cover, figure 2-98.

(3) The piston must be on top dead center when adjusting valve stem to rocker arm clearance for that piston. Turn the crankshaft to place number one piston on top dead center, compression stroke. See that the ignition timing mark on the flange of the fan drive pulley is lined up with the timing pointer on the crankcase front cover as shown in figure 2-90.

(4) Refer to figure 2-99 and loosen the adjusting screw locknut on both the number one intake and exhaust valve levers.

(5) Adjust to the clearances shown in figure 2-99 using a feeler gage.

(6) Tighten both locknuts and recheck the clearances with the feeler gage.

(7) Crank the engine one third of a crankshaft revolution (120°) at a time, in the direction of normal rotation, and set the valve clearances for each cylinder in firing order sequence, which is 1-5-3-6-2-4.

(8) Replace the valve housing cover. Use a new cover gasket if necessary to obtain an oil tight seal.

(9) Reinstall the high tension cable on the ignition coil.

NOTE

Valve clearances must be correct or the valves will fail to rotate normally, which may cause premature exhaust valve failures.

[173.] Article IV. (pp. 86—186) is entitled: *Rupture par Flexion*.

This practically deals with the formula for the maximum moment

$$M_0 = \frac{T_0 \omega \kappa^2}{h},$$

where h is the distance of the 'fibre' most stretched from the neutral axis¹ and $\omega \kappa^2$ the sectional-moment of inertia about that axis. The question then arises: what is T_0 ? Saint-Venant holds that if T_0 be the stress at which *enervation* commences, we have in reality a condition for the safety of a permanent structure. This involves *the enervation-point being very close to the limit of linear elasticity*. In many materials this is certainly not the case, even were it possible to define exactly this enervation-point. We must treat the results of this article as applying only to the *fail-limit*, i.e. the failure of linear elasticity (p. 91). Saint-Venant indeed fully recognises that the formula does not give any condition for *immediate* rupture, and that no argument *against* the mathematical theory of 'perfect elasticity' can be drawn from experiments on absolute strength. He states clearly enough that for beams of various sections, for which $\omega \kappa^2/h$ retains the same value, T_0 varies with the form of the section and is greater than, even to the double of, the value obtained from pure traction experiments (this is the well-known 'crux' which the technicians raise against the mathematicians): see his pp. 90, 91. Yet it seems to me that even the extent to which he adopts the formula is not valid. It only gives the fail-limit, which in some cases, perhaps, may indicate *rupture éloignée*.

[174.] On pp. 95—101 our author treats of 'Emerson's paradox' or the existence of 'useless fibres'. In other words, the expression $\omega \kappa^2/h$ can be occasionally increased by cutting away projecting portions of ω .

We have the cases of beams of square, triangular and circular cross-sections fully treated, as well as that of the *croix d'équerre*.

¹ We use 'neutral axis' for the trace of the plane of unstrained 'fibres' on the cross-section, while we retain 'neutral line' for the succession of points in the plane of flexure through which pass real or imaginary elements of unstretched fibre. It will only coincide with the 'elastic line' or distorted central axis when there is no thrust.




Figure 2-99. Adjusting valve stem to rocker arm clearance.

(d) Disconnect the upper oil cooler pipe from the oil cooler.

(e) Disconnect the lower oil cooler pipe from the oil filter base.

(f) Remove the brackets at the upper end of the oil cooler.

(g) Remove the capscrews securing the lower end of the oil cooler to the crankcase. Remove the oil cooler.

(3) *Oil cooler service.* Immerse the oil cooler into a cleaning solvent to loosen sludge and foreign matter with compressed air. Be sure all passages are clean before replacing on engine.

NOTE

Improper maintenance of the cooling system or oil system are the most probable reasons for poor oil cooler performance.

(4) *Oil cooler replacement.* Refer to figure 2-101 and install the oil cooler as follows:

(a) Fasten the oil cooler to the engine. Bolt the bottom end to the crankcase and install the brackets at the top.

(b) Using a new gasket, fasten lower oil cooler pipe to the oil filter base.

(c) Using a new gasket, fasten the upper oil cooler pipe to the oil cooler.

(d) Connect water pump-to-oil cooler pipe to oil cooler.

(e) Install the ignition coil (para 2-91).

(f) Fill the cooling system.

(g) Fill the crankcase to the correct level.

(h) Run the engine for about ten minutes, stop the engine, and inspect for oil or water leaks.

d. *External Line Service and Repair.* The only repair possible for external oil lines is replacement of damaged lines or flange gaskets, and tightening loose connections. Refer to figure 2-101.

e. *Replacement.* Refer to figure 2-101 and replace any unserviceable parts.

2-99. Intake and Exhaust Manifolds

a. *General.* Intake and exhaust manifolds (fig. 2-102) provide fresh air for combustion and exhaust burned fuel.

b. *Inspection.* Inspect manifolds for cracks, breaks, signs of deterioration of gaskets, warping, or gas leaks.

c. *Removal.* Remove the exhaust manifold as follows:

(1) Stop engine. Refer to figure 2-80 and remove all throttle, choke, and other connections to the carburetor. Remove the carburetor.

(2) Refer to figure 2-72 and disconnect air hose from air cleaner to intake manifold.

(3) Disconnect the breather tube from the intake manifold, figure 2-102.

NOTE

Allow manifolds to cool before removal.

(4) Remove all capscrews fastening manifolds to cylinder heads and remove both the intake and exhaust manifolds from the engine. See figure 2-102.

(5) Remove capscrews which connect the two manifolds at the center and separate them. Separate the exhaust manifold into three parts by removing two expansion clamps.

d. *Replacement.*

(1) Refer to figure 2-102 and assemble intake and exhaust manifolds together using a

rupture stresses when the material sustains a tractive load in the transverse sense, η the stretch-squeeze ratio. Then :

$$\frac{T_{0,t}}{E_t} = \text{stretch in transverse direction due to } T_{0,t},$$

$$\frac{1}{\eta} \frac{T_{0,t}}{E_t} = \text{squeeze in longitudinal direction...},$$

$$E \frac{1}{\eta} \frac{T_{0,t}}{E_t} = \text{safe limit to negative traction in longitudinal direction.}$$

Thus we must have :

$$T''_0 = E \frac{1}{\eta} \frac{T_{0,t}}{E_t},$$

hence

$$\frac{T''_0}{T_0} = \frac{1}{\eta} \frac{E}{E_t} \frac{T_{0,t}}{T_0}.$$

Now by what precedes, Saint-Venant holds that we can legitimately replace $T_{0,t}/T_0$ by $T_{1,t}/T_1$, a ratio easily found from rupture experiments, thus :

$$\frac{T''_0}{T_0} = \frac{1}{\eta} \cdot \frac{E}{E_t} \cdot \frac{T_{1,t}}{T_1}.$$

In the case of isotropy $T_{1,t} = T_1$, $E = E_t$, and thus on the uniconstant hypothesis we should have $T''_0/T_0 = 1/\eta = 4$.

Saint-Venant finds from experiments of Wertheim and Chevandier, that for oak $T''_0/T_0 = 1.21$ or 1.08 ; for cast-metals he suggests 3, for stone 8 to 10, and for wrought iron 2. He holds the value 6 as obtained by Hodgkinson for cast-iron much too large to be prudently adopted, and discusses at some length Hodgkinson's experiments on the beam of strongest section : see our Art. 243*.


Finally we may note that on p. 115, he states that for different varieties of the same material it is more legitimate to take T_0 proportional to T of the formula of Art. 175, than to the stretch-modulus as some writers have done.

[177.] Pp. 122—171 are occupied with what is generally known as the comparative strength of beams of various sections—in reality it is the failure of linear elasticity and not *strength* with which we are dealing.

(a) On pp. 123—5 we have the fail-limit determined for cases of loading in planes of inertial asymmetry. The formula of our Art. 14 namely :

$$M_0 = \text{minimum of } \frac{T_0 \omega}{\frac{z \cos \phi}{\kappa_y^2} + \frac{y \sin \phi}{\kappa_z^2}},$$

we find repeated.



ME 3810-294-20/2-101

Figure 2-101. Oil cooler and external oil lines removal and replacement.

cross-sections. To begin with, they can hardly be taken as approximate for any material having a distinct yield-point; nor in the second place is it clearly stated how far they represent stress-strain relations for bodies whose elasticity is non-linear, or how far elastic-strain and set are to be treated as coexistent.

Saint-Venant after citing Hodgkinson's formulae (see our Art. 1411*) takes by preference the following for the positive and negative tractions p_1, p_2 at distances y_1, y_2 from the neutral axis of a beam under flexure :

$$p_1 = P_1 \left\{ 1 - \left(1 - \frac{y_1}{Y_1} \right)^{m_1} \right\}, \quad p_2 = P_2 \left\{ 1 - \left(1 - \frac{y_2}{Y_2} \right)^{m_2} \right\},$$

where P_1, P_2 are the tractions at distances Y_1, Y_2 from the axis, and m_1, m_2 are constants. On p. 177 traces of the curves for p in terms of y are given for values of m from 1 to 10, and they are compared with the curves obtained from Hodgkinson's formula.

It will be observed that the difficulty of stating exactly the physical relation between stress, elastic-strain and set is avoided by an assumption of this kind. There is, however, another assumption of Saint-Venant's which does not seem wholly satisfactory. He states it in the following words :

Observons d'abord que lorsque la dilatation d'une fibre a atteint sa limite, comme une faible augmentation qu'on lui fait subir produit la rupture ou bien fait décroître très-rapidement sa force de tension, il est naturel de regarder la courbe des tensions comme ayant à l'instant de la rupture sa tangente verticale ou parallèle à l'axe coordonné des y , d'autant plus que cet instant a été précédé d'une énérvation graduelle (pp. 180—1).

This paragraph assumes that for the material dealt with the rupture stress is an *absolute maximum*, but in several automatically drawn stress-strain relations which I have examined this does not appear to be the case (see Vol. I. p. 891), and at any rate in some materials it could only refer to the maximum stress *before stricture* and not to the rupture-stress.

On pp. 178—184 the case of a rectangle is treated at some length. Saint-Venant obtains general formulae on the supposition that the curves for negative and positive traction coincide at the origin, i.e. on the supposition that the stretch- and squeeze-moduli *for very small strains* are equal ($m_1 P_1 / Y_1 = m_2 P_2 / Y_2$). The limiting value of the bending moment is then calculated.


In § 3 various values are assumed for m_1 and m_2 ; in particular if $m_1 = m_2 = 1$, it is shewn that to make the initial stretch- and squeeze-moduli unequal is to *increase the resistance to rupture by flexure*.

(2) Pull the adjusting lock pin outward, using a suitable tool, and turn the adjusting yoke inward.

(3) Periodically check the pull required to

engage the clutch at the operator's lever. Adjust so that 42-to 44-pounds pull is required to engage the clutch.

(4) Replace the clutch hand hole cover.



ME 3810-294-20/2-103

Figure 2-103. Engine clutch adjustment.

Section XXVII. MAINTENANCE OF SHOVEL AND EARTH WORKING EQUIPMENT

2-102. General

In every case where clutches or brake bands are to be removed or replaced, safety requires that the load being supported by that clutch or brake be lowered to the ground. Specifically, always lower the boom to the ground when the boom hoist clutch or brake are to be worked upon. Lower the loads to the ground before working

on front or rear drum brakes or clutches. Secure the revolving frame from turning before working on the swing brake, swing brake lock, or anti-rotation device. Always lower attachments, including shovel fronts, backhoe fronts, clamshell and dragline buckets, booms and jibs, and piledriver or magnets to the ground or to proper supports to prevent any possible injury to personnel or damage to the machine.

one. Saint-Venant had only treated of this matter in the case of the elliptic section (§ 59 of the memoir on *Torsion*: see our Art. 22). A general proof is here given in a footnote.

(d) In § 15, pp. 264—7, we have a fuller treatment than occurs in the memoir on *Torsion* of eccentric torsion, or torsion about *any* axis parallel to the prismatic sides. Taking the equations of torsion for an isotropic material (equations vi. of Art. 17):

$$u_{yy} + u_{zz} = 0, \\ (u_x + \tau y) dy - (u_y - \tau z) dz = 0,$$

for which the origin lies on the axis of torsion, let us put $y' = y + \eta$, $z' = z + \zeta$ we find η and ζ being constants:

$$u_{y'y'} + u_{z'z'} = 0, \\ \{u_{x'} + \tau(y' - \eta)\} dy' - \{u_{y'} - \tau(z' - \zeta)\} dz' = 0.$$

These equations have for solution

$$u = u' - \tau(\xi y' - \eta z'),$$

where u' is the value of u when $\eta = \zeta = 0$, or in other words the shift when the torsion operates round an axis through the new origin. The shifts u' and u giving the distortions in the two cases differ only by

$$\tau(\xi y' - \eta z') = \tau(\xi y - \eta z),$$

or the two distorted surfaces are superposable by rotating the one through small angles $\tau\eta$ and $-\tau\zeta$ round the axes of y and z respectively.

Further $\left. \begin{aligned} u_x + \tau y &= u'_{x'} + \tau y' \\ \tau z &= u'_{y'} - \tau z' \end{aligned} \right\}$ or the slides determined for either axis are the same. Thus it follows that the torsional couple must be the same.

venant then shews how by placing two prisms of equal cross-section with corresponding lines parallel, and fixing their terminal faces so as to remain parallel after torsion about a mid-axis, we can obtain eccentric torsion. The torsional couple will be just double of that obtained from the simple torsion of either. Their axes it is true will be bent into helices, but the bending introduced is a small quantity of the *second order* in the torsion.

(e) In § 17 (pp. 268—71) we have an investigation of the maximum-slide and the fail-points. We cite the following passage:

Si σ_x^2 [σ_x = le plus grand glissement principal] croissait toujours de l'intérieur à l'extérieur de la section pour chaque direction, ce serait constamment sur son contour qu'il faudrait chercher les points dangereux. Mais nous savons qu'il y a souvent des points du contour où le glissement est nul, et il peut y avoir, dans l'intérieur, quelque point de maximum absolu de σ_x^2 (quoique cela ne se soit présenté dans aucun des exemples ci-après traités); et il n'est pas impossible que ce maximum excède toutes les valeurs de σ_x^2 relatives aux points du contour (p. 269).

2-108. Boom Hoist Brake and Clutch

a. General. The boom hoist brake is spring set-hydraulically released. Always lower the boom to the ground before adjusting or working on the brake or clutch.

b. Brake Band Removal.

(1) Refer to figure 2-125 and remove the boom hoist planetary pawls.

NOTE

The boom hoist brake band is removed as an assembly.

(2) Refer to figures 2-112 and 2-113 for views showing the band assembled. To remove the assembly, remove items 1 through 7 of figure 2-114. The entire assembly can then be removed to the bench for complete disassembly as shown. Unscrew the threaded end of the lower brake band from the adjusting rod to complete removal of the brake bands. Note that the phantom pin on figure 2-114 is welded to the revolving frame side frame and can not be removed.

c. Brake Adjustment. Refer to figure 2-112 and adjust the boom hoist brake. Be careful to prevent grease or other lubricant from contacting brake linings at any time.

WARNING

Always lower the attachment to the ground before attempting to adjust the boom hoist brake. Serious damage to the equipment or death or injury to personnel may otherwise result.

d. Clutch Removal and Replacement. Refer to figure 2-113 and remove or replace the boom hoist shaft clutch.

e. Clutch Adjustment. Refer to figure 2-106 and place the boom hoist clutch lever in the center (neutral) position. Refer to figure 2-115 and adjust the boom hoist clutch.

2-109. Swing Brake

a. General. The swing brake is used to hold the revolving frame from turning while the machine is being transported, or when it is desired to prevent the frame from turning. It is not used to stop the frame once it is in motion.

b. Replacement of Brake Shoes. Refer to figure 2-116 and remove or replace swing brake shoes. Engage the swing brake mechanical lock (para. 2-115) to prevent the frame from turning.

c. Service. Keep the mechanical components of the swing brake clean. Lubricate in accordance

with LO 5-3810-294-12. Keep locknuts tightened.

d. Adjust. Refer to figure 2-106 and place the swing brake lever in the released position. Refer to figure 2-117 and adjust the swing brake.

2-110. Drive Chains Replacement

a. General. The removal and replacement procedures for each drive chain are given in the following paragraphs.

b. Reversing Shaft Chain. Refer to figure 2-11 and remove the reversing shaft chain.

c. Rear Drum Chain. Refer to figure 2-119 and remove the rear drum chain case. Refer to figure 2-120 and remove the rear drum chain.

d. Horizontal Swing Shaft Chain. Refer to figure 2-121 and remove the horizontal swing shaft chains.

e. Shovel Crowd Chain. Refer to paragraph 2-28 for replacement of shovel crowd chain.

2-111. Hook Rollers

a. General. Hook rollers are provided to prevent the crane from tipping in relation to the truck. This prevents damage to the machine, while improving machine stability.

b. Removal. Refer to figure 2-122 and remove hook rollers. There is a single hook roller at the front of the revolving frame as shown in figure 2-122. A double hook roller of identical design is used at the rear of the revolving frame. Removal and replacement procedures are the same.

c. Adjustment. Refer to figure 2-123 and adjust hook rollers if clearance between rollers and roller path exceeds 1/16 inch. Items shown in figure 2-122 are also identified on figure 2-123 for clear understanding.

2-112. Swing Lock Assembly

a. General. The swing lock assembly mechanically prevents the revolving frame from moving in relation to the carrier.

b. Adjustment. Remove deck plates as required to obtain access to the swing lock assembly. Refer to figure 2-68. Refer to figure 2-124 and adjust the swing lock assembly.

c. Removal. Refer to figure 2-124 and remove the cotter pins and pins identified to remove the swing lock assembly.

2-113. Pawls

a. General. Safety pawls are provided for the front drum, the rear drum, and the boom hoist drum. The purpose of the safety pawls is to prevent the load on the front or rear drum load

By taking $\alpha_2 = -1/\sqrt{2}$, $\alpha_4 = 2(\sqrt{2} - 1)/b^2$ and the constant $= 0$, we obtain an isosceles triangle having for base a portion of the hyperbola $y^2 = b^2/4 + (\sqrt{2} - 1)^2 z^2$ and for sides lines making with the bisector of the base angles whose tangent $= \sqrt{2} - 1$. The length of the bisector from vertex to hyperbolic base is then $b/2$. The torsion takes place round an axis through the *vertex*. Saint-Venant finds approximately,

$$M = .56702 \mu \tau \omega \kappa^2.$$

This value agrees very closely with that of the equilateral triangle: see our Art. 41.

[183.] Pages 372—460 deal with the conditions for resistance to *rupture éloignée* under simultaneous torsion and flexure. Most of this matter had already been given in Chapters XII. or XIII. of the memoir on *Torsion* or in the memoir on *Flexure*: see our Arts. 50—60 and 90—8. One or two points may be noticed:

(a) In the memoir on *Torsion* Saint-Venant when seeking for the fail-limit neglects as a rule the flexural slides (see our Art. 56, Case (iii) etc.). Here he commences with an investigation of the values of these slides. The approximate methods of Jouravski and Bresse for obtaining the slide in a beam of small breadth are con-
 Chapter XI.), and are applied to the rectangle,
 s-sections. A footnote gives the value of the
 the same approximate manner for an isosceles triangle.
 See pp. 391—8. But the expressions thus obtained are not exact, and in a considerable number of cases differ sensibly from the real values, especially when the section has a measurable breadth perpendicular to the load plane. The expressions found by Jouravski and Bresse give the *total* shear upon a strip of unit-breadth taken on a section of the beam perpendicular to both the cross-section and the load plane, but they do not determine how such shear is transversely distributed, still less the magnitude of the maximum slide on the cross-section. Saint-Venant then proceeds as in the memoir on *Flexure* to deduce exact expressions for the flexural slides (pp. 399—414). The notation used differs from that in the original memoir. The reader will find the two notations placed side by side in the footnote, p. 405. The treatment in the *Leçons de Navier* is shorter and not nearly so complete as

- | | | |
|--------------------------------------|---|---------------------------------------|
| 1. Swing clutch lever | 10. Boom hoist drum pawl control | 19. Engine oil pressure warning light |
| 2. Front drum clutch lever | 11. Front drum pawl control | 20. Engine temperature gage |
| 3. Rear drum clutch lever | 12. Rear drum pawl control | 21. Engine temperature warning light |
| 4. Boom hoist clutch and brake lever | 13. Engine clutch lever | 22. Starter button (engine) |
| 5. Engine throttle control | 14. Horn button (or dipper trip switch) | 23. Ignition switch |
| 6. Swing brake lever | 15. Light switches | 24. Engine tachometer |
| 7. Rear drum brake pedal | 16. Engine fuel tank level gage | 25. Choke control |
| 8. Front drum brake pedal | 17. Voltmeter | 26. Rain shutter lever |
| 9. Swing brake lock control | 18. Engine oil pressure gage | |

Figure 2-106 (1) Continued




Figure 2-106. Control identification. (Sheet 2 of 2)

line from being accidentally dropped. All of these pawls should be kept engaged at all times that a load is being suspended aloft, and the boom hoist safety pawl should be engaged at all times, except when lowering the boom. The boom hoist planetary pawls, figure 2-125, are both manually and automatically operated. These pawls are operated by manual linkage attached to the engine clutch control. When the engine clutch is engaged, the pawls are engaged by automatically operated friction shoes, which allow the operator to drive the boom downward, rather than lower it by gravity. However, this machine is designed so that a load on either the front or rear drum can be lowered by gravity, with the engine clutch disengaged, by allowing the weight of the load to pull the machinery backward. If the friction shoes were not disengaged from their mating surface during this type of load lowering, the boom would be lifted as the load was lowered. Therefore, linkage has

been provided, as illustrated in figure 2-125, to pull the friction shoes out of contact with the boom hoist drum when the engine clutch is disengaged. This will allow a load on either load line to be lowered by gravity, without changing boom angle.

b. Adjustment. Refer to figure 2-126 and adjust safety pawls. Refer to figure 2-125, and see that the friction shoes are out of contact with their friction surface when the engine clutch is disengaged. Note that the length of the rod bolt can be changed. This adjustment is properly made at the time of manufacture and should not be changed. Do not disassemble or adjust the linkage shown in figure 2-125 unless parts are damaged and must be replaced. If this is the case, always see that the pawl friction shoes are disengaged from contact with their mating surface on the drum when the engine clutch is disengaged and that they make firm contact with the friction surface of the drum when the engine clutch is engaged.

2-114. Machinery Mechanism Controls

a. Control Levers and Pedals.

(1) *Service.* Lubrication and cleaning is required for control levers and pedals. Refer to LO 5-3810-294-12.

(2) *Adjust.* No adjustments should be required. However, stopscrews (adjusting screws) are furnished to limit the fore and aft movement of all control levers and pedals, as illustrated in figure 2-127. Adjust only the spring return tension on front and rear drum brake pedals and make this adjustment only after carefully checking front and rear drum brake adjustment. Refer to figure 2-128.

b. Toggle Lever Linkage. The front drum clutch lever, the rear drum clutch lever, the boom hoist clutch lever, and the swing brake lever are designed to "toggle in". Figure 2-127 illustrates the principle of operation of toggle linkage which must be understood to adjust such linkage. When the linkage moves from the neu-

gular cross section ($b \times c$) for which b is much greater than c . Here the approximate values of the slides before the linear limit is passed are:

$$\sigma_{xy} = -2\tau z, \quad \sigma_{xz} = \frac{2c^2\mu_1}{b^2\mu_2} \tau y.$$

These results may be deduced from Art. 46 by replacing the elongated rectangle by its inscribed ellipse and neglecting c^2/μ_2 as compared with b^2/μ_1 . See also Table I. p. 39, and Art. 47.

He assumes that after the linear limit is passed:

$$\widehat{xy} = -Q' \left\{ 1 - \left(1 - \frac{z}{h} \right)^m \right\}, \quad \widehat{xz} = Q'' \left\{ 1 - \left(1 - \frac{y}{k} \right)^n \right\}.$$

Hence, since for small slides or small values of z and y , $\widehat{xy} = \mu_1 \sigma_{xy}$ and $\widehat{xz} = \mu_2 \sigma_{xz}$, we must have:

$$-\mu_1 2\tau = -\frac{Q'm}{h}; \quad \mu_2 \frac{2c^2\mu_1}{b^2\mu_2} = \frac{Q''n}{k}.$$

These give,
$$Q''_2 = Q'_1 \frac{m}{n} \frac{c^2}{b^2} \frac{k}{h}.$$

Further, since the fail-points are the mid-points of the much longer side b , the rupture points are taken there also. Thus it is necessary that:

$$d\widehat{xy}/dz = 0, \quad \widehat{xy} = S' \text{ when } z = c/2.$$

It follows that $h = c/2$ and $Q' = S'$, the *absolute* shearing strength in direction of y .

To proceed further Saint-Venant assumes that the slide σ_{xz} always remains much less than the slide σ_{xy} , so that for the former it is sufficient to retain the linear strain form, we have thus

$$\widehat{xz} = Q''ny/k = S'm \frac{c}{b} \cdot \frac{2y}{b},$$

together with
$$\widehat{xy} = -S' \left\{ 1 - \left(1 - \frac{2z}{c} \right)^m \right\}.$$


It easily follows that

$$M_1 = bc^2 S' \left(\frac{m}{6} + \frac{2^{m-1}m}{(m+1)(m+2)} \right).$$

Cases (b) and (c) confirm the law of the cube stated in (a). Such formulae, although by no means satisfactory from the theoretical standpoint, are yet useful as suggesting lines for future experiment.

[185.] Pages 469—77 (§ 62) contain a useful discussion of the various methods of determining the elastic and fail-point constants, especially in the case of prisms whose material is transversely aeolotropic. Saint-Venant (p. 471) adopts the result given in Art. 5. d. of our account of the memoir on *Torsion*, $\bar{\sigma}_{yz} = 2\sqrt{\bar{s}_y \bar{s}_z}$, to obtain a

- STEP 1. LOWER LOAD ON FRONT OR REAR DRUM LINE TO GROUND.
- STEP 2. REMOVE ADJUSTING NUT AND ADJUSTING BOLT.
- STEP 3. REMOVE COTTER PIN AND UPPER BRAKE BAND PIN. THESE PINS ARE REACHED FROM BEHIND REAR DRUM. REMOVE UPPER BRAKE BAND.
- STEP 4. REFER TO FIGURE 2-67 AND REMOVE LOWER BRAKE BAND COTTER PIN AND PIN THROUGH HAND HOLE.
- STEP 5. REMOVE SPRING ADJUSTING NUT AND JAM NUT. SLIDE LOWER BRAKE BAND AROUND DRUM AND REMOVE LOWER BRAKE BAND.
- STEP 6. REMOVE FRONT DRUM BRAKE BAND IN SAME MANNER.



ME 3810-294-20 '2-108

Figure 2-108. Rear drumshaft brake band, removal and replacement.

terminals (*encastrements*) may be noted. Poncelet remarks that for a cantilever we may suppose two forces, whose resultant is equal and opposite to that of the load, to act at the built-in end. These forces—whose points of application are very close, one on the upper and one on the lower surface of the beam—are very great and alter the surfaces of the built-in beam and the surrounding material, so that the elastic line at this end is not horizontal, but takes a certain inclination varying as the terminal moment directly and inversely as the *profondeur de l'encastrement*. Small as this inclination is, it affects sensibly the experimental accuracy of the theoretical results based on the perfect horizontality of the elastic line at the built-in end. This was noted by Vicat: see our Art. 733*. Saint-Venant holds that careful experiments ought to be made to determine its influence.


[189.] Appendix II. is entitled: *Sur les conditions de l'exactitude mathématique des formules tant anciennes que nouvelles d'extension, de torsion, de flexion avec ou sans glissement.—Démonstration synthétique de ces formules quand on suppose ces conditions remplies*. This appendix contains first an easy refutation of Lamé's ill-judged sneer at the *procédés hybrides, mi-analytiques, et mi-empiriques ne servant qu'à masquer les abords de la véritable science*: see our Arts. 1162* and 3. Saint-Venant shews that his methods have precisely the same validity as those adopted in the cases of simple traction, of the old theories of flexure, and of torsion for a circular cylinder. In the sequel he demonstrates afresh the torsion and flexure equations. He starts from an axiom and definitions involving the hypothesis of central intermolecular action as a function of the central distance only. The appendix occupies pp. 520—541.

[190.] Appendix III. contains a complete theory of elasticity for aeolotropic bodies so far as the establishment of the general equations of elasticity and the usual formulæ of stress and strain are concerned. It occupies pp. 541—617. Proceeding from central intermolecular action, Saint-Venant on pp. 556—9 reduces the 36 constants of the stress-strain relations to 15. We may note one or two points of interest:

(a) § 23 (pp. 562—74) with its long footnote is specially worthy of the reader's attention. Saint-Venant obtains expressions for the

- STEP 1. LOOSEN LOCKNUTS ON ADJUSTING SCREWS.
 STEP 2. REFER TO FIGURE 2-32 AND ENGAGE THE SWING CLUTCH LEVER.
 STEP 3. BACK OFF ON ALL ADJUSTING SCREWS UNTIL THERE IS A 0.020 INCH GAP BETWEEN HEADS OF ADJUSTING SCREWS AND CLUTCH SHOES. TIGHTEN LOCKNUTS AND RECHECK GAP.

NOTE: MAKE ABOVE ADJUSTMENT FOR FIRST ONE CLUTCH SHOE AND THEN THE OTHER. BE SURE CLUTCH SHOES DO NOT DRAG.



ME 3810-294-20/2-110

Figure 2-110. Adjusting reversing shaft clutch or horizontal swing shaft clutch.

in the forward position until the operator pulls it back, past the toggle point, to the neutral (center) position. It is important that only the four levers which are designed for toggle linkage action,

and which are listed in this paragraph, be allowed to "toggle in". Refer to figure 2-127 and adjust toggle linkage.

footnote before referred to. He makes some remarks on the Navier-Poisson controversy, and refers to a paper of his own published in 1844 on Boscovich's system: see our Arts. 527* and 1613*.

(b) On p. 587 the remark is made that the stress-strain relations, the body stress-equations and the body strain-equations remain true whatever be the amount of the shifts in space provided the *relative* shifts of adjacent parts or the strain-components are small. In this case, however, the values to be given to the strains in terms of the shifts are those of our Art. 1618*. The ordinary shift-equations of elasticity hold only for small portions of an elastic body, when the total shifts are not small. Hence they cannot be directly applied to large torsional or flexural shifts. The whole treatment on pp. 587—92 is good, and better than that of the memoir of 1847: see our Art. 1618*.

(c) Saint-Venant points out that it is not sufficient to find values of the stress-components which satisfy the body and surface stress-equations. There are also certain *conditions of compatibility* between the strain components deduced from these stresses which also must be satisfied: see our Art. 112.

These equations hold for *all values of the shifts*, provided the strains remain small, i.e. if they take the forms given in our Art. 1618*.

(d) Pp. 603—17 contain a direct investigation of Saint-Venant's torsion and flexure equations from the general equations of elasticity. In both cases the method adopted assumes a given distribution of stress and deduces the corresponding shift-equations.

In dealing with torsion Saint-Venant supposes a single plane of elastic symmetry perpendicular to the axis of torsion, and starts from formulae for the shears of the form


$$\dot{\gamma} = f\sigma_{xy} + h\sigma_{zx}, \quad \dot{z}x = e\sigma_{zx} + h'\sigma_{xy},$$

where e and h are supposed unequal. See our Art. 4 (θ) on the memoir on *Torsion*. He deduces the general torsional equations, which now contain four constants, and solves them for the case of the ellipse. The discussion does not seem to me of much value, as all elasticians, multi- or rari-constant, would agree that $h = h'$, in which case by a change of axes we can take $h = h' = 0$: see the same Article. In the case of an elliptic contour a direct analysis gives:

$$M = \frac{4\tau\omega}{1/\mu_1\kappa_1^2 + 1/\mu_2\kappa_2^2 + (1/\kappa_1^2 - 1/\kappa_2^2)(1/\mu_2 - 1/\mu_1)\sin^2\alpha},$$

where α is the angle between the direction in which the slide-modulus is μ_1 and the axis of the ellipse about which the swing-radius is κ_1 . The reader must note that μ_1 and μ_2 are not the same constants as in Art. 46 of our discussion of the memoir on *Torsion*, where we supposed 'the principal axes of elasticity' to coincide with the principal axes of the elliptic section.

[191.] The fourth Appendix occupies pp. 617—45 and contains a careful comparison of Saint-Venant's theory of Torsion with the



- STEP 1. LOWER ATTACHMENT TO GROUND.
- STEP 2. PLACE SUITABLE ROD IN HOLE IN PUSHROD.
- STEP 3. TURN PUSHROD TO COMPRESS SPRING. TURN UNTIL SPRING IS REDUCED IN LENGTH TO 4-5/8" AS SHOWN.

ME 3810-294-20 2-112

Figure 2-112. Boom hoist brake adjustment.

Lamé have deduced the linearity of the stress-strain relation without any appeal to experiment or any statement of physical fact or any axiom of intermolecular action: see Saint-Venant's pp. 660—5 and our Arts. 553*, 614*, 928*, 1051* and 1164* footnote.

(b) On pp. 665—676 we have a long and careful numerical examination of the experiments of Regnault on piezometers of copper and brass. In general they accord with the uni-constant theory, or at least better with that than with Wertheim's (see our Art. 1319*). This is followed by some remarks on Wertheim's and Clapeyron's experiments on caoutchouc. The former found $\frac{\mu}{\lambda} = -\frac{1}{4}$ to $\frac{3}{4}$, and the latter $\frac{\mu}{\lambda} = \frac{1}{2.202}$: see our Art. 1322* and Chapter XI. Results so discordant as these lead Saint-Venant to remark that neither uni- nor bi-constant isotropy, nor

même des formules linéaires quelconques, ne sont pas applicables au caoutchouc, liquide coagulé ou épaissi plutôt que solidifié, et d'une nature en quelque sorte intermédiaire entre les fluides et les solides (p. 678).

(c) Pages 679—89 are occupied with a criticism of Wertheim's hypothesis, that $2\mu = \lambda$, and with the results of his experiments. Saint-Venant points out the great probability of a want both of homogeneity and of isotropy in the cylinders used by Wertheim (see our Art. 1343*) and he examines analytically the ratio of longitudinal to transverse stretch-moduli, when such isotropy is not presupposed. We shall return to some of Saint-Venant's arguments when examining Wertheim's later memoirs.

(d) On pp. 689—705 we have a consideration of Cauchy's hypothesis of 1851: see our Art. 681*, namely, that it is possible if a body be crystalline that:

les coefficients des déplacements et de leurs dérivées dans les équations d'équilibre intérieur ne sont plus des quantités constantes, mais deviennent des fonctions périodiques des coordonnées (p. 689).

In other words we arrive at stress-strain relations in which the 36 constants are *not* connected by 21 relations. Saint-Venant conducts a new investigation (pp. 697—706) with fairly simple analysis. The turning point of rari- or multi-constancy for such regularly crystallised bodies is then seen to lie in the legitimacy of bringing stretches like s'_x outside certain summations of the form

$$\sum_x R \cos^3(rx) \cdot s'_x, \quad \sum_x R \cos(rx) \cos^2(rz) \cdot s'_z,$$

and replacing them by their mean values s_x, s_z . Here s_x is the mean value of s'_x for all the atoms under consideration, and we may replace s'_x by s_x if the body is *isotropic* or possesses *confused crystallisation*. On the other hand in regularly crystallised bodies, there may be terms in s'_x periodic in the coordinates and we cannot replace s'_x by s_x and bring the mean stretch outside the summation. Hence we have not the 21 relations between the coefficients fulfilled. Saint-Venant

D

D

D

that, in whatever direction we take x' , the same stretch $s_{x'}$ will produce a traction $\widehat{x'x'}$ of the same intensity. Such an equality seems opposed to our ideas on the nature of bodies endowed with double refraction. The arguments used to support the improbability of this relation are identical with those of the memoir of 1863 and have been cited in our Art. 147.

[194.] While recognising the weight of Saint-Venant's reasoning in this Appendix and in the memoir of 1863, and admitting the difficulty of conceiving a double-refracting medium to obey such conditions as those given by Green, we have yet to notice a point with regard to the arguments Saint-Venant advances. A distinction must be drawn between an isotropic body held by external pressures in an aeolotropic state of *elastic strain*, and a body also primitively isotropic which has received *set* of different intensity in different directions. In the former case the initial stresses may enter into the elastic constants (as in our Art. 129) and so affect the elasticity in different directions. In the latter it would *appear* as if the molecules must be brought in some directions nearer together and so the direct stretch coefficients be affected and varied. But is this experimentally the fact? If a bar of metal be taken and stretched beyond the elastic limit, so that it receives set, it is found that its *stretch-modulus*, which is certainly a function of the direct stretch-coefficients remains nearly constant. Now this set may be of two kinds, first: a set occurring far below the yield-point, which is often little more than a removal of an initial state of strain due to the working: and secondly, a set which denotes a large change in the relative molecular positions and can occur after the yield-point has been reached. If it can be shewn that the stretch-modulus remains nearly constant notwithstanding one or both of these sets, it would be interesting to investigate experimentally whether such is also true for the slide-moduli and the cross-stretch coefficients before we condemn Green entirely.

Experiments on simple traction and torsion of *large bars* before and after very sensible set would throw light on this matter.

[195.] Saint-Venant further remarks that Green's conditions are not *necessary* in order that we may obtain exactly Fresnel's wave-surface. Saint-Venant in a foot-note gives a fairly easy

- | | | |
|-------------------|-------------------|-------------------------|
| 1. Brake cylinder | 8. Capscrew | 15. Spring |
| 2. Pin, cotter | 9. Washer, flat | 16. Washer, brake |
| 3. Lockwasher | 10. Lockwasher | 17. Pushrod |
| 4. Capscrew | 11. Nut | 18. Bracket |
| 5. Lockwasher | 12. Rod, threaded | 19. Brake band assembly |
| 6. Screw | 13. Spacer | |
| 7. Guard | 14. Washer, flat | |

Figure 2-114 — Continued

technical expediency, but principles going to the base of our knowledge of matter,—such as our *proofs* of the equation of energy and the application of the laws of motion to inter-molecular action.


[197.] Pages 742—46 are occupied with a review of Clausius' memoir of 1849: see our Art. 1398*. It is only necessary to remark here that recent experiments would, we think, have removed Saint-Venant's doubt as to the existence of elastic after-strain in metals (p. 745). The appendix concludes with a *résumé* of all the arguments brought forward in favour of rari-constancy (pp. 746—62).

[198.] The *Appendice complémentaire* is chiefly occupied with an examination of the elastical researches of Rankine, Clebsch and Kirchhoff, which Saint-Venant tells us had not then been properly studied in France. We note one or two points:

(a) In § 78 (pp. 764—7) Saint-Venant cites experiments of Morin to prove the linearity of the stress-strain relation. These experiments are really not conclusive, and I especially distrust the results cited for cast-iron. For elastic strains of such magnitude as occur in structures, the stress-strain relation for this material is certainly *not* linear. Nor again can arguments drawn from wires reduced to a state of ease serve the purpose Saint-Venant has in view of demonstrating the linearity and perfect elasticity of all materials for small strains.

(b) § 80 (pp. 771—4) treats of what Saint-Venant terms *l'état dit naturel ou primitif*. This is the state of no internal stress. It is used as a means of deducing the uniqueness of the solution of the elastic equations. If there be no body force or surface load the internal stresses are all zero, and *vice-versâ*. I have already had occasion to remark on the caution with which this principle must be accepted: see our Arts. 6 and 10. The arguments of this section do not seem to me very convincing.

(c) On pp. 783—86 the reader will find some interesting notes and valuable historical references on the origin of the terms *potential* and *potential function*.



ME 3810-294-20/2-116

Figure 2-116. Swing brake shoes removal and replacement.

SECTION IV.

*Memoirs of 1864—1882.**Impulse, Plasticity, etc.*

[200.] *Compléments au Mémoire lu le 10 août 1857 sur l'impulsion transversale et la résistance vive des barres, verges ou poutres élastiques.*

Comptes rendus, T. LX. 1865, pp. 42—47 and pp. 732—35, T. LXI. 1865, pp. 33—37 and T. LXII. 1866, pp. 130—134. These extracts of additions to the memoir of 1857 (see our Arts. 104—8) are all more fully developed in the annotated *Clebsch*: see our Arts. 342 *et seq.*

[201.] *Note sur les pertes apparentes de force vive dans le choc des pièces extensibles et flexibles, et sur un moyen de calculer élémentairement l'extension ou la flexion dynamique de celles-ci: Comptes rendus*, T. LXII. 1866, pp. 1195—99.

This note suggests the application of the principle of virtual displacements and of the hypothesis that dynamical strain is of the same form as statical strain to the problem of impact. Saint-Venant apparently considers that in his papers of 1865—66 he had been the first to adopt this method, but as we have seen it is really due to Cox: see our Art. 1434*. The discussion in this *Note* appears in a more consistent form in the annotated *Clebsch*: see our Art. 368. It is Saint-Venant's great service to have shewn that the accurate and approximate methods agree fairly closely, and *why* they agree. Cox's method gives a result which is almost the same as that given by taking the term involving the principal vibration only. This point is well brought out in the concluding paragraphs of the *Note*, pp. 1198—9.

[202.] *Démonstration élémentaire: (1°) de l'expression de la vitesse de propagation du son dans une barre élastique; (2°) des formules nouvelles données, dans une communication précédente, pour le choc longitudinal de deux barres: Comptes rendus*, Tome

WRENCH BLOCK

COVER PLATE

CAPSCREWS (18)
LOCKWASHERS (18)
AND NUTS (18)

ME 3810-294-20/2-118


Figure 2-118. Reversing shaft chain removal and replacement.

rods of the same material and section. He concluded that the impulse terminated whenever the two bars had not the same speed at their impellent terminals. This, as we shall see, is not true, and the conclusion vitiated some of Cauchy's results, the analysis of which does not appear to have been published.

Poisson in the second edition of the *Traité de Mécanique* (1833, Vol. II. pp. 331—47) also attacked the problem supposing his rods of the same material and cross-section. He used a double condition for separation, namely, not only that the bar which precedes shall have a greater speed at the impelled terminal than that which follows, but that the squeeze in both at the impellent terminals shall be simultaneously zero. This condition led Poisson to the singular conclusion that two unequal bars would never separate. He had forgotten that physically they can never sustain a stretch at the impellent terminals. In fact Cauchy's condition of excess of speed in the preceding bar is insufficient, and Poisson's additional one of no squeeze is superabundant. The true condition is clearly excess of speed at a time when there is zero squeeze at the impellent terminals, which can never sustain a stretch. It will also be necessary to shew that the bars thus separated are separated for good, and do not, owing to their vibrations, come again into contact.

[205.] Saint-Venant's method of treatment is to investigate the vibrations of a bar, of which the initial condition is given by zero stretch throughout, and by speeds constant for each of the several parts into which the rod may be supposed divided. The first instant at which a zero stretch at the section between any two of these parts is accompanied by an excess speed in the terminal of the preceding section marks a disunion if the parts are not those of a continuous rod. In this manner Saint-Venant shews that if two bars of the same section and material are in impact the shorter takes ultimately and uniformly, while losing all strain, the initial speed of the longer.

This result was stated by Cauchy in 1826. Saint-Venant refers to the elementary proof of it given by Thomson and Tait in §§ 302—304 of their *Treatise on Natural Philosophy* which in 1867 was in the press. His notice had been drawn to this proof by an article in *The Engineer* (February 15, 1867) due to Rankine




ME 3810-294-20 2-120


Figure 2-120. Rear drum drive chain removal and replacement.

Unequal speeds occur again when $t = 2a_2/k$, and now the upper bar has a negative squeeze, $j = -(V_1 - V_2)/2k$ at the

CASE $2a_1 < a_2$.



CASE $a_1 < a_2 < 2a_1$.



impelled terminal. Hence the solution no longer holds, and we have to treat each bar from this epoch as a distinct one. The bar a_1 moves obviously without strain and with the speed V_2 which the bar a_2 initially had. To deal with the bar a_2 , we have to distinguish two cases. Let us suppose:

- (1) $2a_1 < a_2$. We have to enquire how a bar of which a



**STEP 1. SOLID BLOCKING
BETWEEN REVOLVING
FRAME AND CARRIER AT
OPPOSITE END OF REVOLV-
ING FRAME.**


**STEP 2. REMOVE RETAINER PLATE
CAPSCREWS, RETAINER
PLATE, COTTER PIN, AND
PIN.**

STEP 3. REMOVE HOOK ROLLER.


ME 3810-294-20 2-122

Figure 2-122. Hook rollers, removal and replacement.

points of the rods, the dotted lines give the points at which the size of the rods changes abruptly. They corre-



lapping lines of the previous diagrams. Saint-Venant points at which velocity and squeeze change abruptly. It is hardly necessary to add that the squeeze of the rods are for diagrammatic purposes justly exaggerated.



The separation of the two rods is discussed in Saint-Venant's sixth paragraph, the fifth having been devoted to a verification by means of the solution in trigonometrical series of the general results of the fourth paragraph: see pp. 262—269 of the memoir.

[209.] The seventh paragraph (pp. 278—86) is entitled; *Conséquences.—Force vive translatrice perdue dans le choc des deux*




Figure 2-126. Boom hoist drum, rear drum, and front drum safety pawl adjustment.

of the impulse is proportional to the length of one of the rods and independent of the area of the cross-section. These results do not agree with Hamburger's experiments (*Untersuchungen über die Zeitdauer des Stosses elastischer cylindrischer Stäbe: Inaugural-Dissertation*, Breslau 1885, pp. 23—27). Hamburger finds that the duration is a function of the velocity of impact, which contradicts Saint-Venant's results.

[211.] The second part of Saint-Venant's memoir is entitled: *Choc de deux barres dont les sections et les matières sont différentes.*

The first paragraph (§ 8, pp. 286—98) gives in a double form the solution of the problem of the motion of two contiguous rods:

1° in trigonometrical series. This result Saint-Venant had obtained in an earlier memoir: see our Arts. 107 and 200. He adds the solution for beams in the form of truncated cones as given in the *Comptes rendus*, LXVI.; see our Art. 223. He remarks of these solutions:

Au mémoire cité, complément de ceux que j'ai présentés depuis 1857 et qui vont être imprimés au *Journal de l'École Polytechnique*, on trouvera le développement de cette solution, à laquelle il convient de recourir quelquefois même pour les barres prismatiques, comme nous verrons plus loin, notamment quand une des deux parties a une section relativement fort grande, une longueur fort petite ou une résistance élastique considérable; suppositions qui poussées plus loin encore, permettent de réduire l'une des deux parties ou barres à une masse étrangère parfaitement dure, pouvant être venue heurter l'autre barre supposée libre aussi, ce qui constitue un problème dont la solution directe, a été présentée en 1865 (*Comptes rendus*, T. LXI., p. 33: see our Arts. 200 and 221).

2° in finite terms. This solution is somewhat lengthy, but is accompanied by diagrammatic representations of speed and squeeze of the same character as in the simpler case when the bars have equal cross-sections and sound-velocities. It is of a more complex nature, however, in particular the sloping lines become more numerous and change their slope abruptly at the horizontal line which marks the contiguous terminals: see p. 297 of the memoir.

[212.] The general solution is applied to the special case of the impact of two rods where initially the squeeze is zero throughout

STEP 1. REMOVE PLATE IN FRONT OF OPERATOR'S CAB AS SHOWN.
 STEP 2. TIGHTEN NUTS TO ADJUST PEDAL RETURN SPRING TENSION. (SEE SECTION 2-115.)



NOTE: CHECK ADJUSTMENT OF FRONT AND REAR DRUM BRAKES BEFORE ADJUSTING PEDAL SPRING TENSION.

ME 3810-294-20 2-128

Figure 2-128. Adjusting front and rear drum brake pedal return spring tension.

Section XXVIII. MAINTENANCE OF COUNTERWEIGHT

2-115. General

The counterweight is mounted on the revolving frame assembly. It will normally be removed only if the mounting bolts are damaged.

2-116. Counterweight Removal and Installation

CAUTION

Proceed slowly and carefully when removing or installing the counterweight, since severe damage can be caused by improper handling.

a. Install two eyebolts and a suitable lifting sling in the tapped holes provided in the top of the counterweight, and lift the counterweight into position on the two locating pins on the deck of the carrier. The locations of the pins are shown in figure 2-129. Use the crane boom and main hoist line to lift the counterweight.

b. Remove the eyebolts and stow them in the tool box.

c. Swing the revolving frame so that the rear of the revolving frame is positioned over the

$$U_1 = V_2 + \left(\frac{m_1 k_1 - m_2 k_2}{m_1 k_1 + m_2 k_2} \right)^n \left\{ 1 - \frac{2m_2 k_2}{m_1 k_1 + m_2 k_2} \left(\frac{\tau_2}{\tau_1} - n \right) \right\} (V_1 - V_2),$$

$$U_2 = V_2 + \frac{M_1}{M_2} (V_1 - U_1).$$

where the value for U_1 on the right of the value for U_2 must be substituted from the first expression.

[214.] It will be observed that these formulae are again widely removed from those of the ordinary theory. They have been tested by Voigt for the velocities U_1 and U_2 of rebound, and by Hamburger for the duration of the impact. Neither find a really sufficient experimental accordance. Voigt attributes the discrepancy to the hypothesis adopted for the contiguous terminals, and considers that the rods cannot, while the contiguous terminals are in contact, be replaced by a single rod. He proposes a new theory, which introduces an elastic couch of some indefinite material (*Zwischenschicht*) between the terminals. This in a limiting case reduces the expressions for U_1 and U_2 to those of the ordinary theory, which in the same case agrees fairly with the results of experiment. In the general case, however, he has neither sufficiently specialised his hypotheses nor worked out his analytical results, so that we are unable to form any but the vaguest comparison of theory and experiment. His constants are unknown functions of material and of cross-section, and there seems no means of determining their form: see our discussion of his memoir later. A good test of Saint-Venant's theory might be made by experimenting in a vacuum and so removing a portion of Voigt's couch. I am inclined to think the discrepancy has more to do with thermal effect than with the couch of air, and that we ought to seek for results corresponding to those of the ordinary theory not when the coefficient of elastic impact is taken as unity, or the 'elasticity perfect,' but when it has a value differing from unity and so allowing for a loss of energy by heat. The problem ought not to be impossible with the aid of Duhamel's thermo-elastic equations.

[215.] In the twelfth paragraph (pp. 336—342) it is shewn that the bars after separating at time $t = 2\tau_1$, or $= 2\tau_2$ as the case may be, do not again come into contact. The thirteenth paragraph represents by diagrams similar to the figure on our p. 142 the motion

b. *Replacement.* Refer to paragraph 2-45 for cable replacement. Refer to c below when it is necessary to shorten a cable.

c. *Cutting Cable to Proper Length.* When cutting cable, seizings must be placed on each side of the point where the cable will be cut. On

preformed cable, one seizing on each side of the cut is enough. On non-preformed cable less than 7/8-inch diameter, two seizings are to be used. On non-preformed cable over 7/8-inch diameter, three seizings are recommended. Use abrasive cutting tools, wire cutters, or blade action tools or flame cutters.

The energy lost is then represented by

$$M_1 \{2a - (1 + M_1/M_2) a^2\} \frac{1}{2} (V_1 - V_2)^2.$$

Since there must always be a loss of energy, it is necessary that

$$a < \frac{2M_2}{M_1 + M_2}.$$

Saint-Venant shews from the values of a in the various cases referred to in Art. 213 that this is always true (pp. 361—355).

The coefficient of dynamic elasticity e as investigated by Newton (*Principia*, Ed. *Princeps*, p. 22) has probably relation to the energy lost not only in vibrations, but also in the form of heat. To make Newton's formula agree with the above, it is necessary to take $a = \frac{M_2}{M_1 + M_2} (1 + e)$, supposing for a moment Newton's laws to hold for rods and that the energy lost is *principally vibrational, not thermal*. This gives us, for example in *Case (ii)* of Art. 213,

$$1 + e = 2 \frac{m_1 a_1 + m_2 a_2}{m_1 k_1 + m_2 k_2} \cdot \frac{k_2}{a_2}.$$

Thus if the rods were of different materials, it is difficult to see how e could be independent of *their masses*, which Newton proved for the impact of spherical bodies. Further in the case of equal rods of the same material e would always equal unity. This again is not true for most bodies. Hence we are driven to conclude either that the amount of thermal energy generated is generally of importance or that the conditions at the surface of impact adopted by Saint-Venant are not satisfactory. It would be interesting to make experiments for a material for which e is nearly unity, the rods being of equal cross-section and the same material, and then endeavour to ascertain by varying their masses whether there was any change in e . Haughton's experiments seem to indicate that e is not constant but a function of the velocity of impact; this does not suggest Saint-Venant's form, but it is interesting as pointing out a want of constancy in this coefficient: see our Arts. 1523* and also 941*, 1183*.

[218.] In his sixteenth paragraph (pp. 355—373) Saint-Venant proceeds to give an elementary proof of the formulae of Art. 213. This proof does not involve differential or integral processes, but it seems to me that, while luminous and suggestive to the reader of the previous analysis, it would not in the more complex cases be of equal value to the student who approached in this manner

PART TWO CRANE CARRIER

CHAPTER 3 INTRODUCTION

Section I. GENERAL

3-1. Scope

a. This part of the manual gives organizational level maintenance instructions for proper care of the carrier portion of the machine. Maintenance personnel shall be thoroughly familiar with both crane and carrier maintenance procedures as described in this manual before attempting service or maintenance of this machine.

b. Refer to paragraph 1-1 for detailed instructions for the use of this manual.

3-2. Maintenance Forms and Records

Maintenance forms and records that you are required to use are explained in TM 38-750.

3-3. Destruction of Army Material to Prevent Enemy Use

Refer to TM 750-244-3 for procedures for destruction of equipment to prevent enemy use.

3-4. Administrative Storage

Refer to TM 740-90-1 for information concerning administrative storage.

3-5. Reporting of Errors

Refer to paragraph 1-5 for instructions.

Section II. DESCRIPTION AND DATA

3-6. Description

A general description of the crane and information pertaining to the identification plates are contained in TM 5-3810-294-10. A more detailed description of specific components and assemblies is contained in the applicable sections of this manual. Detailed descriptions of the components of the carrier are provided in the applicable maintenance paragraphs of this manual.

3-7. Identification and Tabulated Data

a. *Identification.* All identification plates for the carrier are located, identified, and illustrated in TM 5-3810-294-10.

b. *Tabulated Data.*

(1) *Carrier.*

Manufacturer Harnischfeger
Model M320T2

(2) *Carrier engine* (see fig. 3-1).

Manufacturer International Harvester
Company
Model UV-549
Number of cylinders 8

Horsepower 201 net hp at 2800 rpm
full load
Displacement 549 cubic inches
Gage compression 145 psi at 200 rpm
Firing order 1-3-7-3-6-5-4-2
Ignition timing Top dead center
Governed speed (high idle) .. 2800 \pm 10 rpm
Low idle speed 450 \pm 50 rpm
Maximum oil pressure
(above 1500 rpm) 50-to 55-pounds per square
inch
Minimum oil pressure
(idling) 15-to 20-pounds per square
inch
Intake and exhaust valve
tappet clearance Engine equipped with
hydraulic valve lifters.
Tappet clearance adjust-
ments not required.
Electrical system 24 volts, negative ground
Spark plug gap 0.028-to 0.033-inch
Distributor point gap 0.017 inch

(3) *Fuel, water, oil, and grease capacities, carrier.*

Engine fuel tank 75 gallons
Cooling system 40 quarts
Crankcase 12 quarts including filter

in which a_2/k_2 , or the time sound takes to traverse the second bar, is an exact multiple n of the time a_1/k_1 it takes to traverse the first bar :

$$\left. \begin{aligned} U_1 &= V_2 + \left(\frac{1-r}{1+r} \right)^n (V_1 - V_2), \\ U_2 &= V_2 + \frac{M_1}{M_2} \left\{ 1 - \left(\frac{1-r}{1+r} \right)^n \right\} (V_1 - V_2), \end{aligned} \right\} \dots\dots\dots (i),$$

where,
$$r = \frac{M_2}{M_1} \frac{a_1 k_2}{a_2 k_1} < 1.$$

Now if the impelling bar is infinitely short or infinitely hard (if $a_1 = 0$ or $k_1 = \infty$), the number $n \left(= \frac{M_2}{M_1} \frac{1}{r} \right)$ will be infinitely great, hence it follows that :

$$\left(\frac{1-r}{1+r} \right)^{1/r} = e^{-2},$$

and the formulae (i) become :

$$\begin{aligned} U_1 &= V_2 + (V_1 - V_2) e^{-2M_2/M_1}, \\ U_2 &= V_2 + M_1/M_2 \cdot (1 - e^{-2M_2/M_1}) (V_1 - V_2). \end{aligned}$$

[222.] Saint-Venant also shews in this memoir how to obtain from the results of his previous memoir the velocity and squeeze of each bar at each instant of the impact. Thus :

(1°) For the impelling bar. From $t = 0$ to $2a_2/k_2$,

$$\begin{aligned} \text{velocity} &= V_2 + (V_1 - V_2) e^{-M_2/M_1 \cdot k_2 t/a_2}, \\ \text{squeeze} &= 0. \end{aligned}$$

(2°) For the impelled bar. First from $t = 0$ to a_2/k_2 :

$$\text{From } x = 0 \text{ to } k_2 t, \begin{cases} \text{velocity} = V_2 + (V_1 - V_2) e^{-M_2/M_1 \cdot (k_2 t - x)/a_2}, \\ \text{squeeze} = (V_1 - V_2)/k_2 \cdot e^{-M_2/M_1 \cdot (k_2 t - x)/a_2}. \end{cases}$$

$$\text{From } x = k_2 t \text{ to } a_2, \begin{cases} \text{velocity} = V_2, \\ \text{squeeze} = 0. \end{cases}$$


Secondly from $t = a_2/k_2$ to $2a_2/k_2$:

From $x = 0$ to $2a_2 - k_2 t$ the velocity and squeeze have the same values as previously from $x = 0$ to $k_2 t$.

From $x = 2a_2 - k_2 t$ to a_2 ,

$$\begin{cases} \text{velocity} = V_2 + (V_1 - V_2) \{ e^{-M_2/M_1 \cdot (k_2 t - x)/a_2} + e^{-M_2/M_1 \cdot (k_2 t + x - 2a_2)/a_2} \}, \\ \text{squeeze} = (V_1 - V_2)/k_2 \cdot \{ e^{-M_2/M_1 \cdot (k_2 t - x)/a_2} - e^{-M_2/M_1 \cdot (k_2 t + x - 2a_2)/a_2} \}. \end{cases}$$

This gives the whole state of the bars up to the end of the impact or until $t = 2a_2/k_2$.



ME 3810-294-20/3-2

Figure 3-2. Carrier hydraulic steering system.

[224.] *Leçons de mécanique analytique*, par M. l'Abbé Moigno. *Statique*. Paris, 1868. The last two *Leçons* of this work, the twenty-first and twenty-second, pp. 616—723, contain a general theory of elasticity by Saint-Venant. This is the fourth such general theory that we have from his pen, the former three being respectively in the memoir on *Torsion*, in that on *Flexure*, and in the *Leçons de Navier*: see our Arts. 4, 72, and 190. Saint-Venant's treatment is in the main a modified and improved form of that of the second, third and fourth years of Cauchy's *Exercices de mathématiques*; that is to say it starts from the molecular definition of stress (p. 617). After a very full analysis of stress and strain we reach the general elastic equations. The hundred odd pages form one of the best introductions to the subject of elasticity, though they naturally contain no new results. We may refer to one or two points.

[225.] Saint-Venant rejects like Lamé that definition of stress across a plane, which considers stress as the force necessary to retain the plane in equilibrium if it were to become rigid (footnote p. 619). This apparently simple definition conveys, he holds, no exact notion and its simplicity is a pure delusion. In other words he insists upon the importance of the molecular-definition of stress: see Lamé's *Leçons sur l'élasticité*, § 5, and our Arts. 1051* and 1164*.

[226.] The well-known theorems of Cauchy and the equations to his ellipsoids are reproduced with short proofs: see our Arts. 603*—12*. We may note also on p. 630 a demonstration of Hopkins' theorem: see our Art. 1368*. Relations for change of direction of stretch and slide, such as those of our Art. 133, are given on pp. 644—5. Saint-Venant remarks that these relations were first given by Lamé in 1851, but that he assumes that the *shifts are small*; the proof given by Saint-Venant holds for any shifts, provided the relative shifts, i.e. the local strains, are small.

[227.] On pp. 652—3 Saint-Venant states as a Lemma and proves the principle of linearity of the stress-strain relations, i.e. the generalised Hooke's Law. The proof appeals to the rari-constant hypothesis. The reader will remember that there is an unjustifiable assumption often made in the proof of the generalised Hooke's law by Green's method: see our Art. 928*. We may note

- | | | |
|-----------------------------|-------------------------------------|--------------------------------------|
| 3. E-3 brake valve | 25. PP-1 Valve (choke vent) | 37. TU-FLO air compressor |
| 4. Reservoir (service) | 26. AS-1 Control valve | 38. Slack adjuster |
| 5. TC-2 Brake valve | 27. SV-1 Valve (with choke fitting) | 39. Slack adjuster |
| 6. Stoplight switch | 28. SD-3 Brake chamber | 40. HV-4 Drain valve |
| 7. Low pressure indicator | 29. TW-1 Control valve | 41. Reservoir (park) |
| 8. Relay emergency valve | 30. Coupling body | 42. Low pressure indicator buzzer |
| 9. PR-2 Pressure protection | 31. Air horn | 43. Brake chamber |
| 0. Emergency tag | 32. Wiper control | 44. Limiting and quick-release valve |
| 1. Service tag | 33. Windshield wiper | 45. Slack adjuster |
| 2. Dummy coupling | 34. Air gauge | 46. Slack adjuster |
| 3. Dummy coupling | 35. Junction block (manifold) | 47. Mechanical release yoke |
| 4. Clamping stud | 36. Cut-out cock | 48. Reservoir (emergency) |

Figure 3-3 — Continued

memoir of 1859: see our Chap. XI. It is pointed out that if Navier's error of taking $(r_1 - r)f'(r)$ instead of $f(r) + (r_1 - r)f'(r)$ for $f(r_1)$ be avoided, and if the summations be not replaced by integrals, then Poisson's objection to the application of the Calculus of Variations to molecular problems falls to the ground (p. 719): see our Arts. 266* and 446*. Finally there is an account of Green's process and an unfavourable criticism of his theory of double refraction (pp. 719—23): see our Arts. 147 and 193.


[230.] *Formules de l'élasticité des corps amorphes que des compressions permanentes et inégales ont rendus hétérotropes. Journal des mathématiques, Tome XIII. 1868, pp. 242—254.* In his memoir of 1863 Saint-Venant has shewn on the rari-constant hypothesis that the ellipsoidal distribution of elasticity holds for aeolotropic, but amorphous bodies, i.e. bodies such as the metals, whose primitive isotropy has been altered by a permanent strain, which has not converted their elements into crystals; such a permanent strain for instance as would be produced by the processes of rolling, forging, etc. This ellipsoidal distribution he has applied to explain the phenomena of double refraction, without adopting exact transversality of vibration, but obtaining without approximation Fresnel's wave-surface. The ellipsoidal conditions are of two kinds:

$$\text{or, } \left. \begin{array}{ll} \text{(i) a group of the type } 2d + d' = \sqrt{bc} \\ \text{(ii) } \text{,,} \text{,,} \text{,,} \text{ } 2d + d' = \frac{1}{2}(b + c) \end{array} \right\} \dots\dots\dots \text{(i).}$$

If the differences of the direct-stretch coefficients $(b - c, c - a, a - b)$ are so small that their squares may be neglected, these two groups of conditions are identical; this is probably the case in the metals used for construction, and in doubly-refracting media: see our Arts. 142—7. The conditions by which Saint-Venant would replace Green's relations—the Cauchy-Saint-Venant conditions as we have termed them—amount to an ellipsoidal distribution of elasticity (see our Art. 149), but this distribution Saint-Venant has only discussed on the basis of rari-constant equations. Boussinesq in a memoir entitled: *Mémoire sur les ondes dans les milieux isotropes déformés*, which immediately precedes the present memoir (pp. 209—241 of the same volume) has deduced the Cauchy-Saint-Venant conditions for double refraction on the basis of the ellipsoidal distribution without any appeal to

ME 3810-294-20/3-4 (2)

Figure 3-4. Carrier wiring diagram. (sheet 2 of 2)



This involves, as an identity true for all values of ϵ and ϵ' , the further results

$$a = 2\delta + \delta', \quad m = 2r + p, \quad l + m = 4s + 2q.$$

Whence we easily find generally :

$$\begin{aligned} b + c &= 2a + (\epsilon' + \epsilon'')(l + m) + 2m\epsilon, \\ &= 2(2\delta + \delta') + 2(\epsilon' + \epsilon'')(2s + q) + 2(2r + p)\epsilon, \\ &= 2(2d + d'), \end{aligned}$$

or

$$2d + d' = \frac{1}{2}(b + c),$$

the type of ellipsoidal condition for the second group. It will be identical with the group of type $(2d + d') = \sqrt{bc}$, when we may neglect the squares of the differences of a, b, c , or quantities like $(l - m)^2(\epsilon - \epsilon')^2$. Hence the ellipsoidal conditions have been deduced on a hypothesis very probable in character and not opposed to multi-constancy.

[232.] The memoir concludes by noting that to the stress-strain relations (ii) subject to the inter-constant relations (i), we must add terms of the type :

$$\begin{array}{ccc} \widehat{xx}_0(1 + u_x - v_y - w_z) & \text{to } \widehat{xx}, \\ \widehat{xx}_0 v_x + \widehat{yy}_0 w_y & \text{to } \widehat{yz}, \end{array}$$

if there be an initial stress $\widehat{xx}_0, \widehat{yy}_0, \widehat{zz}_0$ symmetrical with regard to the planes of symmetry of the primitive strain. Saint-Venant appeals for these to his memoir of 1863, but as we have seen he has really only proved them there for rari-constancy (see our Art. 129).

[233.] *Calcul du mouvement des divers points d'un bloc ductile, de forme cylindrique, pendant qu'il s'écoule sous une forte pression par un orifice circulaire; vues sur les moyens d'en rapprocher les résultats de ceux de l'expérience: Comptes rendus, LXVI. 1868, pp. 1311—24.* This memoir deals only with the motion of the parts of a ductile mass, and does not take into consideration the stresses which produce those motions. Its methods thus approach those of hydrodynamics rather than of elasticity; it belongs as Tresca's own theory, to which it refers, to the pure kinematics of deformation. A report drawn up by Saint-Venant on Tresca's communications to the Academy immediately precedes the above memoir (pp. 1305—11). It deals with and criticises Tresca's pure kinematic theory.

Memoirs by Saint-Venant treating of the flow of a ductile solid or of a liquid out of a vessel will be found in the *Comptes rendus*, LXVII. 1868, pp. 131—7, 203—211, 278—282 and LXVIII. 1869, pp. 221—237, 290—301. They cannot be considered to fall in any way under the title of the elasticity or even the *strength* of materials.

CHAPTER 4

MAINTENANCE INSTRUCTIONS

Section I. SERVICE UPON RECEIPT OF MATERIAL

4-1. Inspecting and Servicing the Equipment

Refer to paragraph 2-1 for instructions.

4-2. Installation

Refer to TM 5-3810-294-10 for installation instructions.

Section II. MOVEMENT TO A NEW WORKSITE

4-3. Dismantling for Movement

Refer to paragraph 2-10 for dismantling instructions.

4-4. Reinstallation after Movement

Refer to paragraph 2-11 for reinstallation instructions.

Section III. REPAIR PARTS, SPECIAL TOOLS, AND EQUIPMENT

4-5. Tools and Equipment

Refer to paragraph 2-12 for tools and equipment.

4-7. Maintenance Repair Parts

Refer to TM 5-3810-294-20P.

4-6. Special Tools and Equipment

Special tools required to maintain the carrier are listed in Section III of Appendix B.

Section IV. LUBRICATION INSTRUCTIONS

4-8. General

Refer to TM 5-3810-294-10 for general lubrication information.

4-9. Detailed Lubrication Instructions

Refer to Lubrication Order, LO 5-3810-294-12.

Section V. PREVENTIVE MAINTENANCE CHECKS AND SERVICES

4-10. General

To insure that the carrier is ready for operation at all times, it must be inspected systematically so that defects may be discovered and corrected before they result in serious damage or failure. The necessary preventive maintenance checks and services to be performed are listed and described in paragraph 4-11. The item numbers indicate the sequence of minimum inspection requirements. Defects discovered during operation of the unit will be noted for future correction, to be made as soon as operation has ceased. Stop

operation immediately if a deficiency is noted during operation which would damage the equipment if operation were continued. All deficiencies and shortcomings will be recorded together with the corrective action taken on DA Form 2404 at the earliest possible opportunity.

4-11. Preventive Maintenance Checks and Services

See table 4-1 for a tabulated listing of preventive maintenance checks and services.

This note merely refers to E. Mathieu's discussion of the potential of the second kind

$$\phi = \iiint f(\alpha, \beta, \gamma) \sqrt{(x-\alpha)^2 + (y-\beta)^2 + (z-\gamma)^2} d\alpha d\beta d\gamma,$$

by means of which the equation $\nabla^2 \nabla^2 \phi = 0$ can be solved. This equation occurs in the treatment of an isotropic solid. Saint-Venant notices the form

$$\phi = \iiint f(\alpha, \beta, \gamma) \sqrt{\frac{(x-\alpha)^2}{A} + \frac{(y-\beta)^2}{B} + \frac{(z-\gamma)^2}{C}} d\alpha d\beta d\gamma,$$

which solves the equations of elasticity when there is an ellipsoidal distribution of elasticity: see our Arts. 140-1.

Saint-Venant speaks highly of Cornu's memoir of 1869 and its bearing on the constant-controversy: see our Articles below on that physicist's work.

[236.] *Preuve théorique de l'égalité des deux coefficients de résistance au cisaillement et à l'extension ou à la compression dans le mouvement continu de déformation des solides ductiles au delà des limites de leur élasticité: Comptes rendus, LXX. 1870, pp. 309—11.*

The object of this note is to prove the equality between the coefficient of resistance to slide and the coefficient of resistance to stretch or squeeze, when both slide and stretch are plastic.

Saint-Venant takes a right six-face of edges a, b, c , and supposes the two faces $a \times b$ to be subjected to shearing forces in direction of a which produce a plastic slide-set $\sigma \times c$, so that the limit of elasticity is passed. If K' be the force necessary per unit of area, the work expended in producing this set is

$$K'ab \times \sigma \times c,$$

or, it equals $K'\sigma$ per unit of volume.

Now this same slide-set could have been produced by diagonal stretch and squeeze of magnitude $\sigma/2$: see our Art. 1570*. Let us take the right six-face abc and divide it up into others of the same breadth b , but of length a' and height c' making angles of 45° with a and c and having their end-faces $a' \times c'$ in the faces $a \times c$. In order to produce set-stretch it is necessary to apply to the faces bc' a traction given by Kbc' and to the faces ba' a negative traction given by Kba' , where K is the coefficient of resistance to both stretch and squeeze. Hence to produce a stretch of $\sigma/2$ and a squeeze of $\sigma/2$ parallel to a' and c' respectively, we require work equal to

1. ENGINE WILL NOT CRANK

- Step 1. Test batteries.
Replace defective batteries (para 4-26).
- Step 2. Check starter relay.
Replace defective relay (para 4-50).

2. ENGINE CRANKS BUT WILL NOT START

- Step 1. Check for open primary ignition circuit.
Tighten primary lead at distributor (para 4-51). Clean dirty ignition points; replace defective points (para 4-51). Repair open ignition switch circuit (para 4-51).
- Step 2. Check for grounded primary ignition circuit.
If insulator on primary lead is cracked, replace lead (para 4-54). Adjust ignition points (para 4-51). Replace defective capacitor (para 4-51).
- Step 3. Check for faulty secondary ignition circuit.
Clean spark plug cable terminals. If cable insulation is broken or cracked, replace cable (para 4-53). Clean dirty spark plugs; replace defective plugs (para 4-53). If distributor cap is cracked, replace cap (para 4-51). If rotor is cracked or rotor contact arm broken, replace rotor.
- Step 4. Check fuel pump.
Replace faulty fuel pump (para 4-41).
- Step 5. Check carburetor adjustment.
Adjust carburetor (para 4-40).

3. ENGINE MISFIRES

- Step 1. Check spark plugs for fouled plug or cracked porcelain.
Clean or replace plugs (para 4-53).
- Step 2. Check for burned or pitted ignition points.
Replace points (fig. 4-51).
- Step 3. Check for incorrect ignition point gap.
Adjust points (para 4-51).

4. ENGINE IDLES ROUGH

- Step 1. Check carburetor adjustment.
Adjust carburetor (para 4-40).
- Step 2. Check ignition point gap for gap too narrow or much too wide.
Adjust points (para 4-51).
- Step 3. Check intake manifold for leaks.
Repair or replace defective manifold (para 4-56).

5. ENGINE FAILS TO REACH OPERATING TEMPERATURE

- Step 1. Check for thermostat stuck open or removed from vehicle.
Replace defective thermostat (para 4-36).
- Step 2. Check for defective temperature sending unit or engine control panel gage.
Replace defective unit (para 4-24 or 4-20).

6. ENGINE OVERHEATS

- Step 1. Check for loose water pump V-belt.
Adjust V-belt (para 4-47).
- Step 2. Check water pump.
Replace defective water pump (para 4-46).
- Step 3. Check for collapsed or clogged hoses.
Replace hoses (para 4-36).
- Step 4. Check for defective thermostat.
Replace thermostat (para 4-36).
- Step 5. Check for clogged or leaky radiator.
Replace radiator (para 4-35).

[238.] The error in question was really indicated in our first volume (see Art. 1619*), namely that the true relations between the strains, s_x , σ'_{yz} and the shift-fluxions are in their most general form of the types¹:

$$\left. \begin{aligned} s_x + \frac{1}{2} s_x^2 &= u_x + \frac{1}{2} (u_x^2 + v_x^2 + w_x^2) \\ \sigma'_{yz} (1 + s_y) (1 + s_z) &= v_z + w_y + u_y u_z + v_y v_z + w_y w_z \end{aligned} \right\} \dots (i),$$

but that these are not the values taken by Saint-Venant in his memoirs of 1847 and 1863: see our Arts. 1622* and 130. Accordingly Saint-Venant's attempt to deduce Cauchy's equations from a multi-constant hypothesis is erroneous.

The full value of the potential energy is

$$\left. \begin{aligned} \phi &= \phi_0 + \widehat{x x_0} (s_x + \frac{1}{2} s_x^2) + \dots + \dots \\ &\quad + \widehat{y z_0} \sigma'_{yz} (1 + s_y) (1 + s_z) + \dots + \dots \\ &\quad + \phi_1 \end{aligned} \right\} \dots \dots \dots (ii),$$

as Boussinesq had pointed out, and not

$$\phi = \phi_0 + \widehat{x x_0} s_x + \dots + \dots + \widehat{y z_0} \sigma'_{yz} + \dots + \dots + \phi_1,$$

as assumed in the memoir of 1863 (see our Art. 130). But the expression (ii) *has been deduced only from molecular considerations on the vari-constant hypothesis*. The fact is that we can on the multi-constant hypothesis expand ϕ in linear and quadratic terms of the strain-components $\epsilon_x, \epsilon_y, \epsilon_z, \eta_{yz}, \eta_{zx}, \eta_{xy}$ of our Art. 1619*, as Green in fact did (*Collected Papers*, pp. 298–9), but we cannot determine to what extent the resulting coefficients are functions of the initial stress-components. This apparently requires us also to make some molecular assumption.

[239.] Starting with expression (ii) for the potential energy, we should arrive at the equations of Cauchy (as Saint-Venant had done in his memoir of 1863 by a double self-correcting error), but we must renounce the hope of arriving at (ii) on the simple assumption of a generalised Hooke's Law. We may note one or two further points in the first part of the memoir:

(a) To the second order of small quantities,

$$\left. \begin{aligned} s_x &= u_x + \frac{1}{2} (v_x^2 + w_x^2) \\ \sigma_{yz} &= v_z + w_y + u_y u_z - v_y w_y - v_z w_z \end{aligned} \right\} \dots \dots \dots (iii).$$

This was first noticed by Brill: see p. 279 of Saint-Venant's memoir.

¹ σ'_{yz} differs from the σ_{yz} of our Art. 1621*, it being the *cosine* and not the *cotangent* of the slide-angle. See Saint-Venant's definition of slide in Art. 1564*.

16. INCORRECT AIR BRAKE SYSTEM PRESSURE

- Step 1. Check compressor.
Replace defective compressor (para 4-90).
- Step 2. Check governor pressure range setting.
Adjust governor (para 4-90).

17. BRAKES GRAB OR VEHICLE TENDS TO TURN WHEN BRAKES ARE APPLIED

- Step 1. Check for improper brake adjustment.
Adjust brakes (para 4-80).
- Step 2. Check for worn brake linings.
Replace brake shoes (para 4-80).

18. INCORRECT ALTERNATOR VOLTAGE

- Check alternator.
Replace faulty alternator (para 4-49).

19. LIGHTS FAIL

- Step 1. Check for defective or burned out lamps.
Replace lamps (para 2-51).
- Step 2. Check for defective wiring.
Repair or replace wiring (para 2-55).
- Step 3. Check for defective switch.
Replace switch (para 2-55).
- Step 4. Check for faulty ground.
Clean ground terminals (foldout 3-4).

20. POWER STEERING IS "SPONGY" AND MAKES "GROANING" SOUND

- Step 1. Check for low fluid level.
Add fluid (para 4-70)
- Step 2. Check power steering pump.
Replace faulty pump (para 4-70)

21. HARD STEERING (VEHICLE MOVING)

- Check for clogged filter.
Clean filter or replace reservoir (para 4-70).

22. HARD STEERING (VEHICLE STANDING STILL)

- Step 1. Check for loose or glazed pump belt.
Adjust or replace belt (para 4-47).
- Step 2. Check for worn tires
Replace badly worn tire (para 4-87)

Section VII. RADIO INTERFERENCE SUPPRESSION

4-14. General Methods Used to Obtain Proper Suppression

Essentially, suppression is obtained by providing a low resistance path to ground for stray currents. The methods used include shielding the ignition wires, grounding with bonding straps, and using capacitors and resistors.

4-15. Interference Suppression Components

The primary suppression components are those whose primary function is to suppress radio interference. On this machine, the primary inter-

ference suppression components are the 0.025 microfarad capacitor mounted on the side of the ignition coil and the 0.450 - 0.475 ohm resistor illustrated in figure 4-1.

4-16. Replacement of Suppression Components

Refer to figure 4-1 and replace the radio interference suppression resistor and capacitor. Refer to figure 4-32 and replace secondary radio suppression components, which are spark plug lead and the lead from the distributor to the ignition coil.

$$\begin{aligned}
& + \frac{1}{2r_0^2} \left[\left(\frac{dw_0}{dx_0} x_0 + \frac{dw_0}{dy_0} y_0 + \frac{dw_0}{dz_0} z_0 \right)^2 \right. \\
& \quad + \left(\frac{dv_0}{dx_0} x_0 + \dots + \dots \right)^2 \\
& \quad \left. + \left(\frac{dw_0}{dx_0} x_0 + \dots + \dots \right)^2 \right] \\
& - \frac{1}{2r_0^2} \left[x_0^2 \frac{dw_0}{dx_0} + y_0^2 \frac{dv_0}{dy_0} + \dots + x_0 y_0 \left(\frac{dw_0}{dy_0} + \frac{dv_0}{dx_0} \right) \right]^2 \\
& \quad + \frac{1}{2r_0} \left(x_0^2 \frac{d^2 w_0}{dx_0^2} + \dots \right),
\end{aligned}$$

$$\frac{d}{dr} \left(\frac{f(r)}{r} \right) = \frac{d}{r_0 dr_0} \left(\frac{f(r_0)}{r_0} \right) + (r - r_0) \frac{d}{dr_0} \frac{1}{r_0} \frac{d}{dr_0} \left(\frac{f(r_0)}{r_0} \right) + \dots,$$

$$\begin{aligned}
\rho &= \frac{\rho_0}{\left(1 + \frac{dw_0}{dx_0}\right) \left(1 + \frac{dv_0}{dy_0}\right) \left(1 + \frac{dw_0}{dz_0}\right) - \frac{dv_0}{dz_0} \frac{dw_0}{dy_0} - \frac{dw_0}{dx_0} \frac{dv_0}{dz_0} - \frac{dw_0}{dy_0} \frac{dv_0}{dx_0} + \dots} \\
&= \rho_0 (1 - s_{x_0} - s_{y_0} - s_{z_0}),
\end{aligned}$$

if we suppress squares and products.

Substituting in Equation (vii) and remembering that

$$|x^4|_0 \text{ or } |y^2 z^2|_0 \text{ or } |y^3 z|_0 \text{ or } |x^2 y z|_0 = \frac{\rho_0}{2} \Sigma m \frac{d}{r_0 dr_0} \left\{ \frac{f(r_0)}{r_0} \right\} \{x_0^4 \text{ or } y_0^2 z_0^2 \text{ or } y_0^3 z_0 \text{ or } x_0^2 y_0 z_0\},$$

we obtain the typical results :

$$\begin{aligned}
|x^4| &= |x^4|_0 (1 - 3u_{x_0} - v_{y_0} - w_{z_0}) + 4 (|x^3 y|_0 u_{y_0} + |x^2 z|_0 u_{z_0}), \\
|y^2 z^2| &= |y^2 z^2|_0 (1 - u_{x_0} + v_{y_0} + w_{z_0}) + 2 (|yz^3|_0 v_{z_0} + |xy^2 z|_0 w_{x_0} + |xy^2 z|_0 w_{x_0} + |y^3 z|_0 w_{y_0}), \\
|y^3 z| &= |y^3 z|_0 (1 - u_{x_0} + 2v_{y_0}) + 3 (|y^2 z^2|_0 v_{z_0} + |xy^2 z|_0 w_{x_0}) + (|xy^3|_0 w_{x_0} + |y^4|_0 w_{y_0}), \\
|x^2 y z| &= |x^2 y z|_0 (1 + u_{x_0}) + 2 (|xy^2 z|_0 u_{y_0} + |xy^2 z|_0 u_{z_0}) + |x^3 z|_0 v_{x_0} + |x^2 z^2|_0 v_{z_0} + |x^3 y|_0 w_{x_0} \\
&\quad + |x^2 y^2|_0 w_{y_0}.
\end{aligned}$$

Here u_{x_0}, \dots denote $dw_0/dx_0, \dots$, and since the stresses $\widehat{xx}_0, \widehat{yz}_0$ are given functions of $u_{x_0}, v_{y_0}, \dots, u_{z_0}, \dots$ etc., we can express the new coefficients $|x^4|, \dots$ in terms of the old $|x^4|_0, \dots$ and the initial stresses. These results are obviously only a more general case of the formulae of our Art. 616*. The following pages 297—304 are concerned with other modes of looking at these results or expressing the stresses in terms of them.

[241.] Let us take as a special case that of a bar of primitively isotropic material subjected to a traction \widehat{xx} , there being an initial traction \widehat{xx}_0 . We have

$$s_{x_0} = \widehat{xx}_0/E_0, \quad s_{y_0} = s_{z_0} = -s_{x_0}/4.$$

Further, if $|x^2 y^2|_0 = \lambda = \mu$, then $|x^4|_0 = 3\lambda$ and $E_0 = 5\lambda/2$.




Figure 4-1 Radio interference suppression resistor and capacitor, removal and replacement.

Section VIII. MAINTENANCE OF CARRIER CAB ELECTRICAL SYSTEM AND MISCELLANEOUS ITEMS

4-18. General

a. This section contains instructions for maintenance of the carrier cab wiring harness, engine control panel switches, gages and lamps, lights, sending units, horn, batteries, and miscellaneous items.

b. The carrier has a 24-volt, negative-ground, electrical system. Refer to figure 3-4 for the schematic wiring diagram.

WARNING

Always disconnect battery cables before working on electrical components.

4-19. Wiring Harness

Refer to paragraph 2-50 for wiring harness repair.

4-20. Engine Control Panel Switches, Gages and Lamps

a. *General.* Figure 4-2 illustrates the control gages and instruments available to the operator. Refer to TM 5-3810-294-10 for description and function of each.

b. *Replacement.* Refer to figure 4-2 for location of a damaged or faulty component on the control panel.

CAUTION

Always disconnect battery cables before working on the control panel.

4-21. Slave Cable Receptacles and Cables

Refer to paragraph 2-52 for slave cable replacement and repair.

[242.] In Tome xv. of the *Journal de Liouville*, 1870, there are two articles by Saint-Venant, but they refer to a matter which I have thought it well to treat as lying outside our field, namely the stability of masses of loose earth. The history of the memoirs in question may be briefly referred to. Maurice Lévy in 1867 had presented to the Academy a memoir entitled: *Essai sur une théorie rationnelle de l'équilibre des terres fraîchement remuées, et ses applications au calcul de la stabilité des murs de soutènement* (published in the *Journal de Liouville* T. XVIII. 1873, pp. 241—300). This memoir had been referred to a committee including Saint-Venant for report. The report appeared in the *Comptes rendus*, T. LXX. 1870, pp. 217—28, and was reprinted in Vol. xv. of the *Journal*, pp. 237—49. Lévy as well as the committee appear to have been ignorant of Rankine's memoir: *On the Stability of Loose Earth* (*Phil. Trans.* 1857, pp. 9—27) which had contained most of Lévy's results. Lévy had started from Cauchy's stress-theorems (see our Arts. 606* and 610*), and arrived at certain general equations. Saint-Venant in his first note solves to a first approximation Lévy's equation (pp. 250—63 of Tome XVIII.) and hopes some mathematician will proceed further. This was done by Boussinesq, who proceeded to a second approximation in a memoir occupying pp. 267—70 of Tome xv. of the *Journal*. Saint-Venant then reconsidered the whole matter in a second memoir, which occupies the following pp. 271—80. In a footnote he recognises Rankine's priority of research. The memoirs of Saint-Venant and Boussinesq appear also in the *Comptes rendus*, T. LXX. 1870, pp. 217—28, 717—24, 751—4 and 894—7.

[243.] *Rapport sur un mémoire de Maurice Lévy: Comptes rendus*, T. LXXIII. 1871, pp. 86—91. This is a report by Saint-Venant and others on Lévy's memoir establishing the general body-stress equations of plasticity in three dimensions: see our Art. 250. The *Rapport* speaks well of Lévy's memoir as advancing the new branch of mechanics, "pour laquelle l'un de nous a hasardé, sans le préconiser comme le meilleur, le terme d'*hydrostéréo-dynamique*." This branch of research has been called later *plastico-dynamics*, a better word, and we shall refer to it simply as *plasticity*.

[244.] *Sur la mécanique des corps ductiles: Comptes rendus*,

- | | | | |
|----------------------|-------------------------------|----------------------------|---------------------------|
| 1. Nut | 10. Fuel gage | 19. Screw | 28. Voltmeter |
| 2. Bracket | 11. Throttle knob | 20. Instruction plate | 29. Ignition switch |
| 3. Bracket | 12. Reservoir drain knob | 21. Windshield wiper knob | 30. Hazard warning switch |
| 4. Nut | 13. Pin | 22. Setscrew | 31. Instruction plate |
| 5. Plate | 14. Air brake knob | 23. Tachometer-hourmeter | 32. Lamp selector switch |
| 6. Screw | 15. Choke knob | 24. Speedometer-odometer | 33. Screw |
| 7. Cab light switch | 16. Screw | 25. Hi-beam lamp | |
| 8. Lamp | 17. Screw | 26. Oil pressure gage | |
| 9. Air pressure gage | 18. Differential lockout knob | 27. Water temperature gage | |

Figure 4-3 — Continued

[246.] The first paper begins with an interesting account of the history of the theory of plasticity. It refers to Tresca's memoirs and to the attempts of Tresca and Saint-Venant himself to obtain solutions by means of pure kinematics. It is pointed out that the problem is essentially mechanical as well as kinematical and involves a consideration of stress as well as of mere continuity.

In the first place the ordinary equations of fluid-motion must be replaced by others involving inequality of pressure in different directions. Thus the well-known type of hydrodynamic equation :

$$\frac{dp}{dx} = \rho \left(X - \frac{du}{dt} - u \frac{du}{dx} - v \frac{du}{dy} - w \frac{du}{dz} \right),$$

becomes the plastico-dynamic type :

$$\frac{dxx}{dx} + \frac{dxy}{dy} + \frac{dxz}{dz} = -\rho \left(X - \frac{du}{dt} - u \frac{du}{dx} - v \frac{du}{dy} - w \frac{du}{dz} \right) \dots\dots\dots(i).$$

The change of sign is due to change from pressure to *traction*.

To this we must add the equation of continuity :

$$\frac{du}{dx} + \frac{dv}{dy} + \frac{dw}{dz} = 0 \dots\dots\dots(ii).$$

The four equations given by (i) and (ii) represent the relation between the flow (velocity-components u, v, w) of the material and the stress-components. The material in the plastic state is treated as incompressible.


[247.] Now Tresca has demonstrated that, if a material is in the plastic stage, the maximum shear across any face must have a constant value K , which he has ascertained experimentally for a variety of materials. This constant resistance to maximum slide we shall term in future the *plastic modulus*. Hence to obtain the plastico-dynamic equations we must express the fact that

$$\text{the maximum shear across any face} = K \dots\dots\dots(iii).$$

Again, Tresca has demonstrated that the direction of the maximum shear is also that of the maximum velocity of slide. This forms then our last condition :

$$\left. \begin{array}{l} \text{maximum shear and maximum slide-} \\ \text{velocity are co-directional} \end{array} \right\} \dots\dots\dots(iv).$$

Equations (i) and (ii), with conditions (iii) and (iv) should give the complete plastico-dynamic equations.



- | | |
|------------------------|----------------------------------|
| 1. EMBLEM PLATE | 7. WHEEL NUT |
| 2. HORN BUTTON | 8. WHEEL |
| 3. CONTACT CUP | 9. TURN SIGNAL HOUSING |
| 4. SPRING | 10. HORN CONTACT ROLLER ASSEMBLY |
| 5. METAL TAPPING SCREW | |
| 6. BASE PLATE ASSEMBLY | |

ME 3810-294-20/4-7

Figure 4-7. Horn button, removal and replacement.

Section IX. MAINTENANCE OF CAB AND ACCESSORY ITEMS

4-27. General

This section contains instructions for removal and replacement of the window glass, operator's seat, body sheet metal, and fenders.

4-28. Window Glass

Refer to paragraph 2-62 for glass removal and installation instructions.

4-29. Operators Seat

a. *Removal.* Refer to figure 4-8 and remove

the capscrews, lockwashers, and nuts and remove the seat.

b. *Installation.* Refer to figure 4-8 and install the seat as shown.

4-30. Cab Sheet Metal and Fenders

a. Refer to figure 4-9 and remove and replace any damaged cab sheet metal.

b. Refer to figure 4-9 and remove or install the fenders.

[249.] Saint-Venant remarks that even these equations will be difficult to solve for any except the simplest cases. He suggests, however, that those for a cylindrical plastic flow would not be difficult to obtain.

In a final paragraph (p. 316) to the first paper Saint-Venant remarks :

Je ferai seulement une dernière remarque : c'est que si, aux six composantes de pressions ci-dessus, $\widehat{xx}, \dots, \widehat{xy}$, l'on ajoute respectivement les termes : $2\epsilon u_x, 2\epsilon v_y, 2\epsilon w_z, \epsilon (v_x + w_y), \epsilon (w_x + u_z), \epsilon (u_y + v_z)$, représentant, comme on sait, ce qui vient du frottement dynamique dû aux vitesses de glissement relatif dans les fluides non visqueux se mouvant avec régularité, les équations des solides plastiques, ainsi complétées, s'étendront au cas où les vitesses avec lesquelles leur déformation s'opère, sans être considérables, ne seraient plus excessivement petites, et pourraient engendrer ces résistances particulières, ordinairement négligeables, dont on a parlé au No. 3. Les mêmes équations, avec tous ces termes, seraient propres, aussi, à exprimer les mouvements réguliers (c'est-à-dire pas assez prompts pour devenir tournoyants et tumultueux) des *fluides visqueux*, où il doit y avoir des composantes tangentielles de deux sortes, les unes variables avec les vitesses u, v, w , et mesurées par les produits de ϵ et de leurs dérivées, les autres indépendantes de ces grandeurs des vitesses, ou les mêmes quelle que soit la lenteur du mouvement, et attribuables à la *viscosité*, dont K représenterait alors le coefficient spécifique.

[250.] In the second paper to which we have referred in our Art. 245, Maurice Lévy establishes two sets of results. In the first place he obtains the general equations of plasticity ; in the next he considers the special case of a cylindrical plastic flow.

We cite the general equations here, but refer to our later discussion of Lévy's memoir for remarks on his method of obtaining them.

The general equations (i) and (ii) hold for this case. The condition (iii) becomes :

$$4(K^2 + q)(4K^2 + q) + 27r^2 = 0 \dots \dots \dots (ix),$$

where

$$q = \Delta_y \Delta_z + \Delta_z \Delta_x + \Delta_x \Delta_y - \widehat{yz}^2 - \widehat{zx}^2 - \widehat{xy}^2,$$

$$r = \Delta_x \widehat{yz}^2 + \Delta_y \widehat{zx}^2 + \Delta_z \widehat{xy}^2 - \Delta_x \Delta_y \Delta_z - 2\widehat{yz} \widehat{zx} \widehat{xy},$$


and

$$\widehat{xx} - \Delta_x = \widehat{yy} - \Delta_y = \widehat{zz} - \Delta_z = \frac{1}{3}(\widehat{xx} + \widehat{yy} + \widehat{zz}).$$

The condition (iv) becomes

$$\frac{\widehat{yz}}{v_z + w_y} = \frac{\widehat{zx}}{w_x + u_z} = \frac{\widehat{xy}}{u_y + v_x} = \frac{\widehat{yz} - \widehat{zx}}{2(v_y - w_z)} = \frac{\widehat{zz} - \widehat{xx}}{2(w_z - u_x)} \dots \dots (x).$$

Thus (i), (ii), (ix) and (x) are the requisite equations.



ME 3810-295-20 '4-9

- | | | |
|---------------------|---------------------------------|---------------------------|
| 1. Window, rear | 13. Ladder bracket | 25. Nut |
| 2. Cab | 14. Park and directional lamp | 26. Capscrew |
| 3. Weatherstripping | 15. Headlight | 27. Capscrew |
| 4. Window | 16. Headlamp door | 28. Battery box |
| 5. Capscrew | 17. Mirror stand | 29. Cover |
| 6. Door assembly | 18. Capscrew | 30. Capscrew |
| 7. Vent door | 19. Running and blackout lights | 31. Lockwasher |
| 8. Weatherstripping | 20. Mirror mounting base | 32. Access cover |
| 9. Window | 21. Capscrew | 33. Seat mounting bracket |
| 10. Vent door | 22. Platform | 34. Capscrew |
| 11. Window | 23. Reflector | 35. Rear fender |
| 12. Capscrew | 24. Platform skirt | 36. Capscrew |

Figure 4-9. Carrier cab assembly, exploded view.

These conditions are of various kinds. A certain portion of the block of matter alone is plastic (called by Tresca the *zone d'activité*), other portions may remain elastic, or after passing through a plastic condition return to elasticity (e.g. a jet of metal after passing an orifice).

The conditions break up into three classes :

1st. Those which relate to the surface of the material at points which have retained or resumed their elasticity. Let such a surface be exposed to a traction T_e and let the elastic stresses be $\widehat{xx}_e, \dots, \widehat{xy}_e$, the suffix e merely referring to their elastic character. The type of surface condition will be

$$\widehat{xx}_e \cos(nx) + \widehat{xy}_e \cos(ny) + \widehat{xz}_e \cos(nz) = T_e \cos(lx) \dots (\text{xvii}),$$

where n is the direction of the surface-normal and l that of the applied traction T_e .

2nd. The material is in a plastic stage at the bounding surface, T_p being the traction: the type of equation, if $\widehat{xx}_p, \dots, \widehat{xy}_p$ denote the plastic stresses, is :

$$\widehat{xx}_p \cos(nx) + \widehat{xy}_p \cos(ny) + \widehat{xz}_p \cos(nz) = T_p \cos(lx) \dots (\text{xviii}).$$

3rd. Equations which must hold at the surface at which the material changes from plasticity to elasticity. These are of the type :

$$(\widehat{xx}_e - \widehat{xx}_p) \cos(nx) + (\widehat{xy}_e - \widehat{xy}_p) \cos(ny) + (\widehat{xz}_e - \widehat{xz}_p) \cos(nz) = 0 \dots (\text{xix}).$$

In the equations (xvii)—(xix) the elastic stresses and plastic stresses must be obtained from the general equations of elasticity and of plasticity respectively.

[255.] On pp. 378—380, Saint-Venant treats the special case of a right circular cylinder of radius r subjected to torsion till plasticity commences in the outer zone from r_0 to r . He easily finds if M be the torsional couple, μ the slide-modulus and τ the torsional angle :

$$M = 2\pi \left[\mu\tau \frac{r_0^4}{4} + K \left(\frac{r^3}{3} - \frac{r_0^3}{3} \right) \right],$$

while at the surface of elasticity and plasticity we must have

$$\mu\tau r_0 = K.$$

There will be no plasticity then so long as

$$\tau < \frac{K}{\mu r}, \text{ or } M < \frac{\pi r^3}{2} K.$$

If τ be greater than this we have :

$$M = \pi K \left(\frac{2}{3} r^3 - \frac{1}{6} \frac{K^3}{\mu^3 \tau^3} \right).$$



*Figure 4-11. Windshield wiper motor, removal and replacement.
(sheet 1 of 2)*

[259.] The general principle, Saint-Venant tells us in his first memoir, of plastic deformation is that the greatest shear at each point shall be equal to a specific constant (denoted by K in Tresca's memoir of 1869). It follows by Hopkins' theorem that at each point the greatest difference between the tractions across different faces ought to equal $2K$: see our Art. 1368*.

Saint-Venant treats two special cases, and a third by approximation. We will devote the following three articles to their discussion.

[260.] The first is that of a right six-face of ductile metal.

If the axes of coordinates be taken parallel to its edges, and its faces be subjected to uniform tractions \widehat{xx} , \widehat{yy} , \widehat{zz} , then these tractions will be the principal tractions at any point of the material, and it will be necessary if $\widehat{xx} \sim \widehat{zz}$ be the greatest difference that:

$$\widehat{xx} \sim \widehat{zz} = 2K \dots \dots \dots (i).$$

This condition is fulfilled if

$$\widehat{xx} = -\widehat{yy} = -\widehat{zz} = K,$$

or if

$$\widehat{xx} = -\widehat{yy} = -\widehat{zz} = -K.$$

Of this Saint-Venant remarks:

C'est dans ce sens qu'il faut entendre, avec M. Tresca, que la résistance, soit à l'allongement, soit à l'accourcissement du solide plastique, est constante, et égale à sa résistance au cisaillement (p. 1010).

An extension of this case is that of a cylinder on any base, for which $\widehat{yy} = \widehat{zz}$ without being equal to K , that is to say the transverse or radial tractions which we will denote by \widehat{rr} are all equal and the longitudinal tractions \widehat{xx} are greater than them. We have then for the condition of plasticity:

$$\widehat{xx} = 2K + \widehat{rr} \dots \dots \dots (ii).$$

If the radial tractions are greater than the longitudinal we have:

$$\widehat{rr} = 2K + \widehat{xx} \dots \dots \dots (iii).$$

Either equation (ii) or (iii) gives us by variation

$$\delta \widehat{xx} = \delta \widehat{rr},$$

or, any increment of longitudinal, is accompanied by an equal increment of transverse traction. This is Tresca's principle that *in plastic solids pressure transmits itself as in fluids*, although he proves it by the principle of work.

[261.] The second case dealt with by Saint-Venant is that of a hollow right circular cylinder placed between two rigid fixed

(5) Refer to figure 4-51 and install the alcohol evaporator.


(6) Refill the cooling system.

4-36. Thermostat and Housing

a. General. There are two thermostats and two housings furnished on this engine, as shown in figure 4-13. The thermostats are of the bypass type, and one is located in each cylinder bank. Removal, test, inspection, and replacement procedures apply equally to each thermostat.

b. Inspection. Inspect the connections to the radiator and thermostat housings for leaks, and the thermostat housing gasket for leaks. Replace faulty hoses or gaskets. When the engine has been run for a period of time long enough to insure that it is warmed up to normal operating temperature, check oil and water temperatures, as shown on the gages on the operator's control panel. If water or oil temperatures show too high or too low, one of the possible causes of the trouble may be the thermostats.

c. Removal. Drain the coolant below the level of the thermostat housings. Refer to figure 4-12 for the location of the drain cock. Then remove the thermostats and housings as follows:



ME 3810-294-20/4-12

Figure 4-12. Radiator removal and replacement.

(4) Refer to figure 4-12, loosen the hose clamps and remove the three radiator hoses.

(5) With the radiator adequately braced, refer to figure 4-12 and remove mounting nuts, lockwashers, plain washers, shock mounts, and stud spacers. Attach a suitable lifting device, take out all slack, and remove the radiator.


d. Radiator Installation.

(1) Refer to figure 4-12 using a suitable lifting device, install the radiator, the two radiator braces, and the lower shock mount material.

(2) Connect the radiator hoses.

(3) Install the windshield washer fluid container and hoses.

(4) Refer to figure 4-10 and install the hood sheet metal.



ME 3810-294-20/4-13

Figure 4-13. Thermostat housings, removal and replacement.

If we make $r = R$, we have $\widehat{rr} = -p$,

or, $p_1 = p + 2K \log (R/R_1) \dots \dots \dots (ix).$

If the pressure applied p_1 has a less value than this, the 'annular fibres' near to the inside face can very well acquire stretches exceeding the limit of elasticity and even that of cohesion for isolated straight fibres; but as the fibres in the neighbourhood of the external face remain elastic, there will not be rupture, nor sensible deformation. Saint-Venant refers to the well-known experiment of Easton and Amos: see our Art. 1474*.

In the last Section 5 of the *Note* Saint-Venant refers to Tresca's somewhat unsatisfactory proof of the formula (ix).

[262.] In a foot-note pp. 1015—1017, Saint-Venant deals approximately with the following case: the outer surface of a right circular hollow cylinder (radii R, R_1) is supposed to rest on a rigid envelope, the internal surface is then subjected to great pressure which diminishes the thickness ($R - R_1$), but increases the height (h), to determine the pressure which will produce this plastic effect. Tresca had obtained a solution of this problem on two hypotheses, which cannot be considered as entirely satisfactory. The general equations of plasticity are indeed too complex to offer much hope of an exact solution for this case. Saint-Venant gives a solution involving only the acceptance of Tresca's second hypothesis namely: that the upper base of the cylinder and all the plane-sections parallel to it remain plane and perpendicular to the axis of the block, and that lines parallel to the axis preserve their parallelism. It is obvious that this hypothesis is only approximately true; but Saint-Venant's investigation is an interesting one, as it deals with one of those cases, in which the maximum difference of the principal tractions is not given by the same pair for all values of the radial distance. This breaks up the solution into two parts corresponding to $3r^2 < \text{or} > R^2$, and the case itself into two sub-cases corresponding to $3R_1^2 < \text{or} > R^2$. Saint-Venant's results are not in accordance with Tresca's.

[263.] *Sur un complément à donner à une des équations présentées par M. Lévy pour les mouvements plastiques qui sont symétriques autour d'un même axe: Comptes rendus, T. LXXIV, 1872, pp. 1083—7.*




Figure 4-15. Engine air cleaner, removal and replacement.

(2) *Replacement.* Refer to figure 4-17 and replace any damaged items.

4-40. Carburetor

a. General. The carburetor is a four-barrel concentric downdraft type unit. It differs from other carburetors in that it has two additional or secondary barrels which operate only during periods of heavy engine loads. Throttle plates in the secondary barrel are vacuum operated. The carburetor is similar to the dual-concentric type carburetor in that it has two primary barrels each of which contain a venturi, main fuel discharge nozzle, throttle plate, idle passages, and choke plate. A throttle operated accelerator pump supplies added fuel for engine acceleration. It also has a power enrichment system which automatically comes into effect whenever an added amount of fuel is needed for full power operation. The governor assembly used is integral with the carburetor and is also vacuum operated.

b. Removal.

(1) Refer to figure 4-18, remove the fuel line to the carburetor and immediately plug the line.

(2) Disconnect the choke, throttle, and governor lines to the carburetor.

(3) Disconnect and remove air intake tubing to the carburetor.

(4) Remove the nuts and lockwashers which secure the carburetor to the intake manifold and remove the carburetor as an assembly.

c. Installation.

(1) Place the carburetor on the intake manifold and secure with nuts and lockwashers, figure 4-18.

(2) Remove fuel line plug installed when carburetor was removed and connect fuel line to carburetor.

(3) Refer to figure 4-18 and connect choke and throttle linkage and the governor air and vacuum lines.

(4) Connect air cleaner tubing to carburetor.

(5) Before returning engine to service, adjust carburetor as described below.

d. Adjustment.

(1) Before adjusting the carburetor, see that ignition timing is correct and that breaker point gap is properly adjusted. See paragraph 4-64. Be sure spark plugs are properly gapped as instructed in paragraph 4-72. See that all carburetor flange bolts are secure and that there are no leaks at gaskets.

(2) Run the engine until it reaches normal operating temperature.

(3) Set engine idle speed at approximately 350-to 400-rpm using throttle stop screw, figure 4-18.

(4) Turn one of the two idle adjusting screws in (clockwise) until engine speed begins to drop.

(5) Turn the same idle adjusting screw in the opposite (counterclockwise) direction, counting the turns, until engine speed again begins to drop.

(6) Return the idle adjusting screw to the midway point.

(7) Repeat the process with the second idle adjusting screw. Each adjusting screw should be turned the same amount. Therefore, it may be necessary to repeat the above procedure to obtain best results. If available, a vacuum gauge may be used to obtain the highest possible steady vacuum reading.

(8) Refer to figure 4-18 and place the accelerating pump link in the hole most distant from the throttle shaft for cold weather operation. Use the hole nearest the throttle shaft for warm weather operation.

[265.] *Sur les diverses manières de présenter la théorie des ondes lumineuses. Annales de Chimie et de Physique*, 4^e série, T. xxv. 1872, pp. 335—381. This memoir was also separately published by Gauthier-Villars in the same year.

The contents belong essentially to the history of the undulatory theory of light. Saint-Venant considers at considerable length the researches of Cauchy, Briot, and Sarrau in this field and points out the defects in the various theories which they have propounded. Finally he deals with Boussinesq's method of obtaining from a general type of equation the special differential equations which fulfil the conditions necessary for explaining the various phenomena of light. Saint-Venant praises highly Boussinesq's hypothesis, and considers that his theory :


qui offre à la fois plus de simplicité, d'unité, de probabilité, et je crois aussi, de rigueur que les autres (quel que soit le remarquable talent avec lequel ont été présentés ces autres essais, qui ont toujours avancé les questions), mérite d'être enseignée de préférence (pp. 380—1).

I must remark, however, that convenient as Boussinesq's hypotheses may be as a grouping together of analytical results under one primitive formula, it cannot be held as sufficient till we understand the reasons why and how the molecular shifts are functions of the ether-shifts and their space and time fluxions, and are able to deduce the *form* of these functions from some more definite physical hypothesis.

§§ 1—2 treat of the early history of elasticity. As in the memoir of 1863 (see our Art. 146—7) Saint-Venant holds that the conditions presented by Green for exact parallelism and those suggested by Lamé for double refraction are only consistent with isotropy.

Aussi Lamé et Green ne sont pas compris dans l'analyse que je fais des recherches de divers auteurs sur la lumière. Il importe que des hommes de talent ne s'égarent plus, en pareille matière, sur les errements des deux illustres auteurs de tant d'autres travaux plus dignes d'eux. (Footnote, p. 341.) See our Arts. 920*, 1108*, 146 and 193.

[266.] *Rapport sur un Mémoire de M. Lefort présenté le 2 août 1875*. This report is by Tresca, Resal and Saint-Venant (*rapporteur*) and will be found in the *Comptes rendus*, T. LXXXI. 1875, pp. 459—464. It speaks favourably of the memoir, which deals with the problem of finding the bending moment at the several



ME 3810-294-20/4-17

Figure 4-17. Fuel lines and fittings, replacement and repair.

turns the plunger to the top of the cylinder at a fixed rate to provide the required fuel pressure. During the upward movement of the plunger, the check valve in the plunger is held closed by pressure above the valve, and fuel is forced into the fuel system. However, the check valve in the bottom of the cylinder bore is open, thus permitting fuel to enter the bore of the cylinder for the next cycle, which starts when the plunger reaches a predetermined point in the tube.

(3) A pulsation dampener in the top of the pump provides steady operation and even pressure in the output line. The pump also incorporates a pressure relief system to assure an immediate return to zero fuel pressure when the ignition is turned off. The filter system is contained in the lower portion of the pump and consists of a filter element and a magnet. The pump mounting bracket serves as the ground connection. The pump must be provided with a good electrical ground. The pump contains a special radio suppression capacitor to prevent radio frequency interference.

b. *Test* If the carburetor floods at engine idling speed or if flooding occurs with the ignition switch turned on and the engine NOT running, examine the engine carburetor float needle valve and seat for wear or foreign matter on the valve or seat. While the ignition is on, the pump continues to operate in order to maintain constant pressure, even after the carburetor float needle valve closes. The following could also adversely affect pump operation:

- (1) Poor ground connection.
- (2) Poor battery-to-ground connection.
- (3) Loose electrical connections anywhere in the circuit.
- (4) Air leaks in lines or at fittings.
- (5) Kinked or clogged lines which restrict fuel flow.

c. *Service.* Service must be limited to the fuel filter element area since the electrical portion is




Figure 4-18. Carburetor adjustment, removal, and replacement.

$$m \frac{d^2 v}{dt^2} = f(r) = f(r_0 + v),$$

$$= v f'(r_0) + \frac{v^2}{2} f''(r_0) + \frac{v^3}{6} f'''(r_0) + \dots$$

If $dv/dt = \dot{v}_0$, for v and $t = 0$, we have as a first approximation

$$v = \frac{\dot{v}_0}{a} \sin at, \text{ where } f'(r_0)/m = -a^2.$$

For a second approximation :

$$v = \frac{\dot{v}_0}{a} \sin at + \frac{b^2 \dot{v}_0^2}{6a^4 r_0} (1 - \cos at)^2, \text{ where } \frac{r_0 f''(r_0)}{m} = b^2.$$

Let us find the mean value v_m of v from $t = 0$ to $2\pi/a$; we have :

$$v_m = \frac{b^2 \dot{v}_0^2}{4a^4 r_0}.$$

Hence the stretch due to the thermal vibration


$$= \frac{v_m}{r_0} = \frac{m \dot{v}_0^2}{2} \frac{1}{2r_0} \frac{f''(r_0)}{\{f'(r_0)\}^2}.$$

Thus we see that the stretch is proportional to the kinetic energy $m\dot{v}_0^2/2$, which is generally regarded as a measure of the absolute temperature, and will be positive if $f''(r_0)$ is positive.

Saint-Venant states that these conclusions will still hold, if the two molecules be replaced by a system. The thermal effect would thus depend on *the derivatives of the second order of the function $f(r)$* .

If there should be a point of inflexion in the curve which represents the law of intermolecular action plotted out to distance, we should have a case in which increase of temperature reduced the volume, as occurs in certain exceptional substances. Saint-Venant suggests the form of the figure below for the curve $y = f(r)$; OD being the distance and Oy the force axis.

Here $Ok = r_0$ marks the point at which the action changes from repulsion to attraction; if the axes Oy , OD are asymptotic in character, we have the infinitely great force and infinitely small force at infinitely small and infinitely great distances respectively well marked. pM marks the maximum attractive force between the molecules, and any force greater than this, if maintained, will produce rupture. It corresponds to a distance Op , which defines that of rupture. Great thermal vibrations which impose such a velocity



ME 3810-294-20/4-20

- | | | |
|------------------------|----------------|--------------------|
| 1. Rod | 10. Crank arm | 19. Spring |
| 2. Nut with lockwasher | 11. Pin | 20. Spring clip |
| 3. Washer | 12. Rod | 21. Trunnion |
| 4. Pedal, accelerator | 13. Rod | 22. Washer |
| 5. Washer | 14. Bracket | 23. Throttle cable |
| 6. Cotter pin | 15. Capscrew | 24. Nut |
| 7. Ball joint | 16. Lockwasher | 25. Nut |
| 8. Nut | 17. Nut | 26. Throttle knob |
| 9. Lockwasher | 18. Clamp | |

Figure 4-20. Accelerator and throttle control, removal, replacement, and repair.

Section XII. MAINTENANCE OF EXHAUST SYSTEM

4-43. General

This section contains maintenance instructions for the exhaust pipes and muffler (fig. 4-21) as allocated by the maintenance allocation chart.

4-44. Muffler and Pipes Replacement

a. *Removal.* Refer to figure 4-21 and remove exhaust pipes and muffler.

b. *Installation.* Refer to figure 4-21 and install exhaust pipes and muffler.

de *Boscovich*, non pas son idée capitale de réduction des atomes à des centres d'action de forces, mais la loi même, la loi physique générale des actions fonctions des distances mutuelles des particules qui les exercent réciproquement les unes sur les autres. Et ils attribuent ainsi au célèbre religieux *l'erreur grave* où sont tombés, suivant eux, Navier, Poisson et nos autres savants, créateurs, il y a un demi-siècle, de la Mécanique moléculaire ou interne. Or cette loi blâmée, cette loi qui a été mise en œuvre aussi par Laplace, etc. et prise par Coriolis et Poncelet pour base de la Mécanique physique, n'est autre que celle de Newton lui-même, comme on le voit non seulement dans son grand et principal ouvrage, mais dans le Scholie général de sa non moins immortelle Optique. L'usage fait de cette grande loi n'est point une erreur; et les formules d'élasticité à coefficients réduits ou, pour mieux dire, *déterminés*, où elle conduit pour les corps réellement solides, tels que le fer et le cuivre, sont conformes aux résultats bien discutés et interprétés d'expériences faites sur ces métaux (Appendice v. des *Leçons de Navier*: see our Art. 195), expériences au nombre desquelles il y en a de fort concluantes, récemment dues à M. Cornu (p. 1225).


That Boscovich deprived an atom of its extension, but that Newton treated intermolecular force as central, is a point which deserves to be recalled to mind: see our Art. 26*.

[270.] *Sur la plus grande des composantes tangentielles de tension intérieure en chaque point d'un solide, et sur la direction des faces de ses ruptures. Comptes rendus*, 1878, T. LXXXVII., pp. 89—92.

Potier had given the following formulæ for the shear \overline{rs} across a face whose normal r makes angles α, β, γ with the directions of the principle tractions T_1, T_2, T_3 :

$$\overline{rs} = (T_1 - T_2) \cos^2 \alpha \cos^2 \beta + (T_2 - T_3) \cos^2 \beta \cos^2 \gamma + (T_3 - T_1) \cos^2 \gamma \cos^2 \alpha,$$
 maximum value of $\overline{rs} = \frac{1}{2}$ (difference of greatest and least principal tractions).

He had then proceeded to apply these formulæ to the conditions of rupture. Saint-Venant notices that these results had been given by Kleitz in 1866, by Lévy in 1870, and by himself in 1864. He might also have added by Hopkins in 1847. The note then points out that rupture in the direction of maximum shear is hardly confirmed by experiments, which point rather to rupture in the direction of maximum stretch. Saint-Venant finally considers the results of some then recent experiments, but remarks on the need for further research in this direction.



ME 3810-294-20/4-22

Figure 4-22. Engine belt and pulley arrangement, removal and replacement.

(5) Install the water pump belts over the fan pulley and water pump idler pulley and adjust belt tension as shown in figure 4-24. Refer to figure 4-24 and install and adjust alternator belts.

(6) Refer to figure 4-22 and install the fan on the water pump hub.

(7) Refer to paragraph 4-35 and install the radiator.

4-47. Fan, Pulley, and Belts

a. General. The belt arrangement for this engine is shown in figure 4-22. The water pump,

water pump idler, and fan pulleys are driven by two belts from the crankshaft pulley. Two additional belts from the fan pulley drive the alternator and air compressor. If it is necessary, for any reason, to remove the water pump pulley on which the fan is mounted, the radiator must be removed as described in paragraph 4-35.

b. Service. All pump, pulley, and idler bearings are lubricated at assembly and require no further lubrication. Therefore, service consists of periodic inspection and replacement of belts and belt tension adjustments as required.

c. Belt Removal and Replacement. If any belts are removed, they must be adjusted as shown in

As the other two molecules are fixed, there is no question here of dilatation. To find the reaction on either molecule we have to substitute this value of v in $f(r_0 + v)$ and we obtain

$$f(r_0 + v) = f(r_0) + \frac{f'(r_0)}{a'} \dot{v}_0 \sin a't + \frac{f''(r_0)}{2a'^2} \frac{\dot{v}_0^2}{2} 2 \sin^2 a't + \dots \dots \dots \text{(iii).}$$

Thus the mean value of p , the pressure upon the envelope of the vibrating elementary mass, would be

$$= f(r_0) - \frac{f''(r_0)}{4f'(r_0)} \frac{\dot{v}_0^2}{2} m \dots \dots \dots \text{(iv).}$$

Saint-Venant remarks that as $f'(r_0)$ is obviously negative ($= -ma'^2/2$), we have only to suppose $f''(r_0)$ negative in order that this may connote an increase of pressure due to the vibration.

Referring to the value of the pressure as given by Eqn. (iv) he suggests in a footnote :

Cette sorte de considération, avec mise en compte, comme il est fait ici, des *dérivées* du second ordre $f''(r)$ des actions, n'est-elle pas propre à remplacer, avec avantage, ces chocs brusques des molécules des gaz contre les parois de leurs récipients, avec réflexions multiples et répétées, que des savants distingués de nos jours ont inventés ou revivifiés, dans la vue de rendre compte mathématiquement des pressions exercées sur ces parois, etc. ? (p. 717.)

[274.] Saint-Venant in his fourth paragraph (p. 717) asks whether we can extend the results here found for two or three molecules to a multitude of molecules. He replies, yes, because it is easy to see that the new terms of the second degree due to the first derivatives $f'(r)$ will *add* to the second derivatives in $f''(r)$. On this point he refers to a footnote on p. 281 of his memoir in the *Journal de Liouville*, 1863 (see our Art. 127), and to one by Boussinesq in the same *Journal*, 1873, pp. 305—61.

Saint-Venant concludes therefore that when on the *rari-constant* hypothesis, we calculate the stresses by means of the linear terms only for the shifts, we destroy all dilatation and all stress due to increase of temperature; *we annul in fact all thermodynamics*. According to his theory then thermal effect is entirely due to the second derivatives of the intermolecular action expressed as a function of intermolecular distance. The point is obviously important in its bearing on the rari-constant hypothesis. Do the constants of $f(r)$, the law of intermolecular reaction, vary with the temperature—as would be the case if the “strength of the intermolecular reaction” were to vary with the energy of pulsa-

Section XIV. MAINTENANCE OF CARRIER ELECTRICAL SYSTEM

4-48. General

The carrier has a 24-volt, negative ground electrical system. Refer to figure 3-4 for the schematic diagram. The system consists of two 12-volt batteries, the starting motor, an alternator with an internal voltage regulator, and other components as shown in the schematic diagram.

WARNING

Always disconnect battery cables before working on electrical components.

4-49. Alternator

a. General. The alternator is the same as is used on the crane. Refer to paragraph 2-88.

b. Belt Adjustment. Refer to figure 4-24 and adjust the alternator belt tension. Note that the alternator belts also drive the air compressor and that the air compressor belt tension is being adjusted at the same time.

c. Alternator Removal and Replacement. Refer to figure 4-25 and loosen alternator drive belts by loosening adjusting lock screw. Remove all electrical leads to the alternator as shown. Tag all leads to show correct location. Support the alternator, remove the adjusting lock screw, and remove the alternator mounting bolts, nuts, and lock washers. Remove alternator. Refer to figure 4-25 and replace the alternator.

d. Alternator Testing. Alternator testing is identical to the procedure for the crane alternator. Refer to paragraph 2-88 and test the alternator.

4-50. Starting Assembly

a. General. The starting motor is designed for high torque, short use applications. It engages the engine flywheel ring gear and is used to crank the engine until it starts. When the engine starts, the starting motor automatically disengages.

CAUTION

Never crank the engine for more than 30 consecutive seconds with the starting motor. If this does not start the engine, wait for at least one minute before trying again.

b. Motor and Solenoid Test. Motor and solenoid testing is identical to the test described in paragraph 2-89.

Figure 4-25. Alternator, removal and replacement.

c. Starting Motor Replacement. Refer to figure 4-26 and remove and replace the starting motor.

d. Starting Motor Solenoid Replacement. Replacement of the carrier starting motor solenoid is the same as replacement of the crane starting motor solenoid. Refer to figure 2-87 and replace the starting motor solenoid.

e. Reverse Polarity Relay. The carrier engine reverse polarity relay is mounted on the cab side panel. The methods of testing and replacing the relay are identical to the crane reverse polarity relay. Refer to paragraph 2-89 and test and replace the carrier reverse polarity relay.

4-51. Distributor

a. General. The distributor is mounted on the engine front cover and secured with a hold-down bolt and washer. The distributor contains a centrifugal advance feature, plus a governor, which consists of a spinner valve positioned by the distributor shaft. The spinner valve governor mechanism supplies air to a diaphragm unit attached to the carburetor throttle body, thus controlling engine speed. The centrifugal advance mechanism consists of two identical weights, which are opposed by spring force. The primary function of the distributor is to open and close the

what results must flow from applying the principles of dynamics to atoms and throwing back the origin of those principles on some still more simple entity. There is much that would induce us to believe (e.g. bright line spectrum of elementary gas at small pressure and not too high temperature) that an atom has an independent motion of its parts, and this suggests that we should try the effect of applying the principles of dynamics not only to the action of one atom upon another, but also to the mutual action of an atom's parts. If multi-constancy be experimentally demonstrated, then we must suppose either (i) the law of intermolecular action is a function of *aspect*, or (ii) the action of the element A upon another B is not independent of the configuration of surrounding elements (*Hypothesis of Modified Action*: see our Vol. I., p. 814). There may be other possibilities, but these, as the most probable, deserve at least early investigation. If the law of intermolecular action is a function of *aspect*, then we should expect to find that intermolecular distance is commensurable with molecular dimensions. According to Ampère and Becquerel the former is immensely greater than the latter; according to Babinet, they are in the ratio of at least 1800 : 1 (see § 13 of Saint-Venant's memoir). It is difficult to understand under these circumstances how *aspect* could be of influence, it would be sufficient to treat each molecule as a mere point or centre of action, which is practically Boscovich's hypothesis. According to the more recent researches of Sir William Thomson, who deals with a molecule as an extended, material body, the mean distance between two contiguous molecules of a solid is less than the $\frac{1}{100000000}$ of a centimetre while the diameter of a *gaseous* molecule is greater than $\frac{1}{800000000}$ of a centimetre (*Natural Philosophy*, Part II., p. 502). Thus intermolecular distance would be less than five times molecular dimensions. In this case it would seem probable that the law of action between parts of two molecules must be the same as the law of action between parts of the same molecule, for it is difficult, although, perhaps, not impossible to understand how one could begin and the other cease to be of importance at such small relative distances as 5 to 1. Resistance alike to positive and negative traction shews that the mean intermolecular distance cannot differ much from that at which intermolecular action changes its sign; further the capacity of the molecule itself to

d. Installation and Timing (Crankshaft Position Unknown).

(1) Remove No. 1 spark plug, then rotate the engine and hold thumb or forefinger over the spark plug hole until you feel pressure. Slowly continue cranking the engine until the timing mark on the crankshaft pulley lines up with the proper mark on the quadrant.

(2) Place a new distributor mounting gasket in the counterbore in the engine.

(3) While holding the distributor cap in approximately the correct position, rotate the distributor rotor so that the rotor tip will point in the direction of the No. 1 terminal on the distributor cap indicated by a dab of paint on the cap. Then turn the rotor 1/8 turn or one cam lobe in the opposite direction of distributor rotation past the No. 1 or No. 8 terminal post.

(4) Slide the distributor in position in the mounting hole on the engine.

NOTE

It may be necessary to move the rotor slightly to start the gear into mesh with the camshaft gear, but the rotor should line up with the no. 1 terminal post when the distributor is down in place.

(5) Install the distributor hold-down clamp, bolt, and lockwasher.

NOTE

Do not tighten at this time.

(6) Connect the primary lead to the coil.

(7) Install the spark plug and high tension wires to the cap if removed; then install the cap to distributor housing, making sure the tang aligns with the slot in the distributor cap.

(8) Start the engine and set the timing as described under *e* below.

e. Ignition Timing.

(1) Make certain that the distributor cap is properly located on the distributor housing and that both spring clips are in place.

(2) The firing order is 1, 8, 7, 3, 6, 5, 4 2, and spark plug cables must be assembled in the distributor cap in this order in a counter clockwise rotation.

(3) Connect a stroboscopic timing light to the No 1 spark plug. Some timing lights are intended to connect one lead to the spark plug terminal and the other to ground (parallel connection). Others require disconnecting the spark plug wire and connecting one of the timing light wires to the spark plug wire and other wire to the spark plug terminal (series connection).

Figure 4-28. Marking rotor position.

turn or one cam lobe in the opposite direction of distributor rotation past the mark previously placed on the distributor housing to locate the rotor.

(3) Slide the distributor in position in the mounting hole on the engine in approximately the same location as when it was removed.

NOTE

It may be necessary to move the rotor slightly to start the gear into mesh with the camshaft gear, but the rotor should line up with the mark when the distributor is down in place

(4) Install the distributor hold-down clamp, bolt and lockwasher.

NOTE

Do not tighten at this time.

(5) Connect the primary lead to the coil.

(6) Install the spark plug and high tension wires to the cap if removed, then install the cap to the distributor housing, making sure the tang aligns with the slot in the distributor cap.

NOTE

If the distributor cap is incorrectly positioned on the distributor housing, it will usually result in a broken rotor when attempting to start the engine.

(7) Start the engine and set the timing as instructed in *e* below.

is presupposed by Saint-Venant throughout the memoir, although, as he remarks, he does not agree with it. It forms indeed the essential difference between this memoir and that of 1844: see his § 7, p. 18.

[277.] Saint-Venant's arguments in favour of the ultimate atom being without extension are of a threefold character:

- (i) arguments from the known physical properties of atoms;
- (ii) metaphysical arguments;
- (iii) theological arguments.

We will briefly refer to some points with regard to these in the following three articles.

[278.] §§ 3—21 deal with more purely scientific arguments based on known properties of atoms. In § 3 we have arguments from the theory of elasticity with special reference to the controversy between Navier and Poisson: see our Arts. 527*—534*. Saint-Venant points out how the continuity of matter is related to the possibility of replacing atomic summations by definite integrals. He proves with great clearness in a footnote pp. 12—15, on the hypothesis of continuity, the following propositions, which are really involved in the result of Poisson's memoirs of 1828 and 1829 and Cauchy's memoir of 1827 (see especially *Journal de l'École polytechnique*, 1831, p. 52, and the *Exercices de mathématiques*, 1828, p. 321, comparing our Arts. 443*, 548* and 616*):

1°. The stress across an elementary plane in a solid body will like that of a liquid at rest have no shearing component.

2°. The traction at any point varies as the square of the density.

3°. If there were no *initial stresses*, no state of strain would produce stress.

Thus on the *rari-constant hypothesis*, we reach impossible physical results or it follows that matter cannot be continuous. This applies also to the ether which could not propagate slide

distances, est celle de la pesanteur universelle, toujours négligeable vis-à-vis des actions à des distances imperceptibles qui produisent l'élasticité, la capillarité, les chocs, les pressions et les vibrations; et ces dernières et énergiques actions se soustrairaient à la règle statique dont nous parlons.


NOTE

Follow the manufacturer's instruction on use of the timing light.

(4) See that timing is 7 degrees before top dead center firing stroke as checked against the ignition timing quadrant and ball, figure 4-29. The engine must be running at low idle speed, which is 400-to-500 rpm.

f. *Point and Condenser Replacement.* Refer to figure 4-30. Note that points and condensers can be replaced before reinstalling distributor.

- (1) Remove distributor cap.
- (2) Remove rotor as shown in figure 4-30 and remove dust cover.
- (3) Refer to figure 4-30 and remove point lock screw and adjusting screw. Remove points.
- (4) Remove condenser by removing attaching screw.
- (5) Install new condenser and points and adjust breaker points as follows:
 - (a) Loosen two screws which hold contact bracket to the upper plate. Screws should be loosened only enough to permit the bracket to move when a small screwdriver is inserted between the plate-bracket notches, as shown in figure 4-30.
 - (b) Rotate the cam (using starter motor) until the rubbing block is on the highest point of the cam lobe.
 - (c) Insert screwdriver as shown in figure 4-30 (between mating notches in upper plate and contact bracket) and turn the screwdriver



ME 3810-294-20/4-29


Figure 4-29. Ignition timing quadrant and ball.

until point gap is 0.017 inch, as measure round feeler gage.

(d) Tighten screws loosened in above and recheck gap. Readjust if nec. Recheck again after first 100 hours of

(6) Install rotor and distributor cap.

Figure 4-30. Distributor point and condenser replacement and adjustment (sheet 1 of 3).



ME 3810-294-20/4-

Figure 4-30. Distributor point and condenser replacement and adjustment (sheet 2 of 3).

journal. Those who are anxious to determine the real source of cohesion will not be hindered from adopting the principle of extended material atoms, if it agrees best with the facts of observation, by the assertion that if they accept and comprehend thoroughly the system of Boscovich it will preserve them from the

deux principales et plus funestes aberrations philosophiques de notre temps et des temps anciens, le panthéisme et le matérialisme (p. 74).

Notwithstanding that many readers will find themselves unable to approve either the method or conclusions of the latter portion of the memoir, the whole should certainly be read for the interesting questions it raises with regard to the physics of elasticity.

[281.] *Des paramètres d'élasticité des solides et de leur détermination expérimentale. Comptes rendus, T. LXXXVI, 1878, pp. 781—5.*

This is a good *résumé* of the relations holding between the various elastic coefficients and moduli in the case of a body possessing three planes of elastic symmetry, and of the experimental methods of finding their values.

[282.] (1) The stress-strain relations will be those of our Art. 117(a). The coefficients are now nine in number; namely, three direct stretch-coefficients, a, b, c the three direct slide-coefficients d, e, f and the three cross-stretch-coefficients d', e', f' . have the following special cases:

(2) Elastic isotropy in planes perpendicular to the axis of x :

$$e = f, \quad e' = f', \quad b = c = 2d + d'.$$

Saint-Venant states the conditions erroneously and says they reduce the *nine* constants to *six*, a, b, d, e, d', e' , but d' is known in terms of b and d , or we reduce them to *five*.

(3) Complete elastic isotropy, or as Saint-Venant puts it, isotropy in two of the axial planes:

$$a = b = c = 2d + d' = 2e + e' = 2f + f', \quad \text{and} \quad d = e = f.$$

This reduces the nine coefficients to *two*, namely $d' = \lambda$ the dilatation coefficient, and $d = \mu$ the slide modulus. Saint-Venant has forgotten to state the relations $d = e = f$.

(4) Que si, sans vouloir (ce qui n'a aucune utilité) étendre l'applicabilité de ces formules aux déformations perceptibles de corps spongieux stratifiés, comme est le liège, ou de mélanges cellulux de solides et de

c. *Test.* Refer to paragraph 2-91 for coil test procedures. No repairs are possible. Replace a faulty coil.

d. *Installation.* Refer to figure 4-31 and install the ignition coil.

4-53. Spark Plugs

a. Removal.

(1) Detach the ignition wires from each spark plug.

(2) Using the proper size deep socket wrench, loosen each spark plug two complete turns only. All spark plugs loosen in a counter-clockwise direction.

(3) The action of loosening each spark plug two turns will also loosen any accumulation of dirt which may be embedded around the base of the spark plug. Use a blast of compressed air to remove this debris and prevent its falling into the cylinder combustion chamber when the spark plug is removed.

(4) Remove all spark plugs, being careful not to lose the metal gaskets beneath each plug.

b. *Test.* Inspect spark plugs for obvious cracks, broken or severely worn points, pitting, discoloration, or accumulations of foreign material. Discard any spark plug not in good apparent condition. If available, install the plugs in a spark plug tester and check for adequate performance.

NOTE

Inspection, cleaning, and adjusting of spark plugs is recommended at 125 hour intervals. The condition of a plug and the color of any deposits found (or type of deposit) can be used to analyze engine performance.

(1) Inspect the spark plug gaskets. If the gaskets are not flattened it is an indication that the spark plugs have not been properly tightened to prevent flow-by between the spark plug and cylinder head. This condition results in excessive burning of the electrodes and overheats the insulator tip which may cause pre-ignition.

(2) If the gaskets are flattened or compressed to the point where they have become distorted (out-of-round) or torn, it is an indication that the spark plugs have been tightened to the extent that damage may have been inflicted on the spark plug itself. Excessive torque often causes strains on the steel shell of the spark plug which results in cracked insulators, distortion of metal shell and gap settings, as well as blow-by between the component parts of the spark plug.

(3) If the gasket is properly compressed (approx. half of original thickness) showing a flat, clean, even surface, it is an indication the spark plugs have been properly installed.

(4) Inspect the condition of the electrodes. The extent of service to which a spark plug has been subjected is generally best indicated by the degree of wear of the electrodes. When the center electrode has become worn away, the ground electrode has become so badly eroded that the sparking area that resetting of the gap is either difficult or impossible, the spark plug is not fit for further efficient engine service and should be replaced if cleaned.

b. Cleaning and Adjusting.

(1) Regardless of the condition of the spark plug gaskets, they should be removed from the plug before cleaning. If new replacement gaskets are available, the old ones should be discarded.

(2) Before abrasive cleaning, any deposits on the firing end of the spark plug should be removed by brushing with a suitable abrasive which will dry quickly by wiping with a clean cloth or by air blast. Failure to do this with fouled spark plugs will result in packing the abrasive inside the firing end of the spark plug.

(3) Place the spark plug in the holder or cleaner adapter of the correct size. Hold the spark plug at the terminal end and while applying the abrasive blast, "wobble" the top of the spark plug in a circle. By this method the abrasive will be able to properly clean the insulator tip and the electrodes. Three seconds should be sufficient to clean most spark plugs. However, the extent of cleaning time should be limited to that which is necessary to clean the deposits on the insulator nose. Prolonged use of the abrasive blast will wear away the insulator, causing irreparable damage to the spark plug. Visual inspection will indicate when the spark plug has been properly cleaned. Loose abrasive remaining inside the firing end should be removed by the "air blast" jet on the cleaner. Do not use picks or screwdriver to remove deposits inside the firing end of the spark plug.

(4) Remove loose abrasive or other foreign material from the spark plug threads with a brass wire brush.

(5) Before setting the gap of a spark plug, pass a thin point file or needle between the sparking areas of the center and ground electrodes.

stresses in three directions, or to a fibrous formation, three relations of the type :

$$\alpha = \frac{(2e + e')(2f + f')}{2d + d'} \dots\dots\dots (i),$$

will sensibly hold, provided E_x , E_y , E_z have not ratios exceeding $\frac{3}{2}$ or at most 2 among themselves. This is the ellipsoidal distribution of elasticity: see our Arts. 138 and 142.

For the case of rari-constant isotropy we have :

$$\alpha = \frac{3ef}{d}, \quad b = \frac{3fd}{e}, \quad c = \frac{3de}{f} \dots\dots\dots (ii),$$

relations admissible in general for the metals.

(9) For wood, where the ratio of E_x to E_y (the axis of x having the sense of the fibres) can amount to 10, 20, 40 and more, we can only take two of the above relations, namely :

$$b = \frac{3fd}{e}, \quad c = \frac{3de}{f} \dots\dots\dots (i),$$

which give :

$$E_x = \alpha - \frac{ef}{2d}, \quad E_y = \frac{fd}{e} \frac{8ad - 4ef}{3ad - ef}, \quad E_z = \frac{e^2}{f^2} E_y \dots\dots\dots (ii),$$

$$\eta_{xy} = \frac{1}{4} \frac{e}{d}, \quad \eta_{xz} = \frac{1}{4} \frac{f}{d}.$$

For a modification of the statements in (8) and (9) with regard to *wood*: see our Arts. 308, 312 and 313.

[283.] Saint-Venant now proceeds to indicate experimental methods of arriving at the values of the following moduli and coefficients.

(1) To find the three direct slide-coefficients, or the slide-moduli d , e , f .

Case (a). If there be isotropy in the plane perpendicular to axis of x ($e=f$). We experiment on the torsion of a right circular cylinder.

Case (b). If e be not equal to f , we use the formula of Art. 29 (modified by Art. 47 and Table I) for the torsion of a prism on rectangular base. Let the base be $2b' \times 2c'$ and let b' be much $> c'$,

$$M_x = -\frac{16\alpha}{l} f \frac{b'c'^3}{3}, \text{ sensibly.}$$




Figure 4-34. Checking and servicing engine oil pan.




Figure 4-35. Draining engine oil pan.

(4) Clean all parts (except the filter element) and dry thoroughly with compressed air.

(5) Check the operation of the pressure relief valve in the filter base. Be sure the ball does not stick or bind.

(6) Place a new body-to-base gasket (14) in the filter base. The gasket must lay flat to form a good seal.

(7) Place a new filter element (5) on the filter base. The larger opening in the element faces the filter base. Set the filter spring (4) on the filter element. Inspect the base edge of the filter body to be sure it is not bent or nicked.

(8) Place the washer (2) on the hold-down bolt (1) and slide it through the body (3), spring (4), and element (5). Tighten the bolt after being sure the filter body is properly centered in the base.

(9) Replace the pipe plug (15) in the filter body and tighten.

(10) Scrape and clean the gasket surface of the filter base and mating surface on the crankcase. Install new gasket and secure the filter as-

sembly to the crankcase with three capscrews. After warming up the engine, check the filter and connections for leaks.

4-60. Oil Cooler and External Lines

a. *General.* The oil cooler is a self-contained unit mounted on the "V" of the engine under the intake manifold. In extremely heavy duty service or very hot climate, the oil cooler is a safety feature to assure safe lubricating oil temperatures, maximum bearing life, and oil economy. In colder climates, the oil cooler works in reverse while the engine is warming up, by heating the crankcase oil quickly for proper engine lubrication and sludge control.

b. *Oil Cooler Removal.* Remove the oil cooler as follows:

(1) Refer to paragraph 4-56 and remove intake manifolds.

rendus, T. LXXXVII. 1878, pp. 849—54 and 893—9. There are additions in the off-print. This memoir was read on the 2nd and 9th of December.

Its object is explained in § 2 (pp. 850—1), after the solutions given in the memoir on *Torsion* (see our Art. 36, Nos. 4 and 5) have been cited :

Clebsch a remarqué, en 1862, qu'on obtient une variété de contours plus grande encore en se servant des coordonnées curvilignes isothermes orthogonales de Lamé (i.e. *conjugate functions*); et MM. Thomson et Tait dans leur beau livre *A Treatise on Natural Philosophy*, 1867, ont indiqué, sans le développer, leur emploi pour étendre les solutions telles que (3) {= (1) of our Art. 36}, relatives aux rectangles rectilignes, à des contours rectangulaires mixtilignes se composant d'un arc de cercle ou de deux arcs concentriques et des deux rayons qui les limitent, "ce qui est" disent-ils, "très-intéressant en théorie et d'une réelle utilité en Mécanique pratique."

Il m'a paru que la solution relative à ces sortes de sections pouvait être obtenue d'une manière simple et directe, sans substituer préalablement une certaine inconnue auxiliaire à l'inconnue géométrique u , et en s'en tenant aux coordonnées polaires ordinaires r, ϕ .

[286.] In § 3, Saint-Venant obtains the required solution in cylindrical coordinates. The fundamental equations (see our Art. 17, Eqn. vi.) become

$$\left. \begin{aligned} u_{rr} + u_r/r + u_{\phi\phi}/r^2 &= 0 \\ r r dr + u_{\phi} dr/r - r u_r d\phi &= 0 \end{aligned} \right\} \dots \dots \dots (i).$$

If γ be the angle of the annular sector, r_0 and $r_1 (> r_0)$ its radii, then the second or surface equation reduces to the following conditions when the median line is taken as initial line :

$$\left\{ \begin{aligned} r r^2 &= -u_{\phi} \text{ for values of } r > r_0 < r_1, \text{ when } \phi = \pm \gamma/2, \\ u_r &= 0 \text{ when } r = r_0 \text{ or } r_1, \text{ for all values of } \phi \text{ between } \pm \gamma/2 \end{aligned} \right\} \dots (ii).$$

These conditions are found to be satisfied by the following value of u ;

$$u = -\frac{\tau r^2 \sin 2\phi}{2 \cos \gamma} - \frac{2\tau}{\pi} \frac{(-1)^n \sum_0^{\infty} (r_1^{m+2} - r_0^{m+2}) r^m - (r_0 r_1)^{m+2} (r_1^{m-2} - r_0^{m-2}) r^{-m}}{r_1^{2m} - r_0^{2m}} \times \frac{\sin m\phi}{1 - m^2/4},$$


where

$$m = \frac{2n+1}{\gamma} \pi.$$

This result is practically obtained by assuming u to be of the form

$$C r^2 \sin 2\phi + \Sigma (A r^m + A' r^{-m}) \sin m\phi,$$

and determining the constants by the surface conditions (ii).



ME 3810-294-20/4-36

- | | |
|------------------------|-------------------------|
| 1. Hold-down bolt | 9. Relief valve ball |
| 2. Shell washer | 10. Filter gasket |
| 3. Filter body | 11. Filter base |
| 4. Filter spring | 12. Washer |
| 5. Filter element | 13. Capscrew |
| 6. Relief valve plug | 14. Body-to-hose gasket |
| 7. Relief valve gasket | 15. Pipe plug |
| 8. Relief valve spring | |

Figure 4-36. Engine full flow oil filter, service and replacement.

(2) Refer to figure 4-37 and remove water crossover pipe (1). Disconnect cooler inlet pipe

(11). Disconnect pipe assembly (21) at (20).

(3) Remove capscrews (18) and lockers (19) which secure covers (8 and 14) engine block. There are five capscrews. Remove the oil cooler from the engine.

NOTE

Cover oil cooler mounting bosses on the crankcase so that foreign material can not enter the engine.

c. Oil Cooler Service. Service as follows

(1) Remove covers (8 and 14, fig.

(2) Immerse oil cooler (7) in a suitable cleaning solution. Drain and blow out air vent and foreign material inside the cooler with clean dry compressed air. Be sure all passages are clean and clear before installation.

(3) Replace covers (8 and 14), using gaskets (6).

d. Oil Cooler Installation.

(1) Install new gaskets (5 and 13) and install oil cooler (7) with capscrews (18) and washers (19).

(2) Reinstall pipes (1 and 11) and connect pipe assembly (21) at fitting (20).

(3) Reinstall manifolds (para 4-56)

e. External Lines.

(1) Removal. Refer to figure 4-37 and move external oil line (21) which connects lubricating oil cooler to the air compressor.

(2) Replacement. Refer to figure 4-37 and replace any damaged external line.

f. Crankcase Breather and Vent Tubing

(1) Removal. Refer to figure 4-38 and remove any defective component of the venting. Annually, replace hose (6, fig. 4-38).

(2) Service. Service of the vent tubing consists of keeping all connections properly cured.

(3) Installation. Refer to figure 4-38 and install vent tubing.

sector on the old Coulomb theory. As is well known (see our Art. 181, (d)) Saint-Venant's theory makes *both torsional moments equal*. It will be seen at once that for bodies of this kind the results of the old theory are most erroneous and very dangerous in practice. The reduction of the torsional resistance for a split section is well brought out by the result $M/\theta = \cdot 5589$ for $\gamma = 360^\circ$.

(2) Annular sectors when $r_1 = 2r_0$:

$\gamma =$	60°	120°	180°
$\frac{M}{\theta}$	$\cdot 0800$	$\cdot 1068$	$\cdot 1160$
$\frac{M}{\theta'}$	$\cdot 6812$	$\cdot 3160$	$\cdot 1909$

We see again that the errors, when the old theory is used, are simply enormous.

[289.] In §§ 9—10 Saint-Venant determines the points of the full sectors, $\gamma = 60^\circ$ and $\gamma = 120^\circ$, where the slide is zero. These points are at distances from the centre differing from those of the centroids by a small amount only. He then gives the values of the shift u for various points of the same two sectors:

Les plus grandes valeurs de u sont aux points de rencontre de l'arc avec les deux côtés rectilignes. La médiane $\phi = 0$ reste immobile, et les éléments de l'arc prennent, sur le plan primitif de la section, des inclinaisons croissantes avec les distances où ils sont du milieu de cet arc.

[290.] In § 11 Saint-Venant states the value and position of the maximum slides for the same two sectors, i.e. he finds the fail-points (*points dangereux*). In both cases the maxima lie upon the contour, but the maximum of the maxima upon the rectilinear sides.

For $\gamma = 60^\circ$ the fail-point is distant $\cdot 5622r_1$ from the centre and $\sigma = \cdot 4900 \tau r_1$,

„ $\gamma = 120^\circ$ the fail-point is distant $\cdot 3671r_1$ from the centre and $\sigma = \cdot 6525 \tau r_1$.

In a footnote Saint-Venant refers to the remark of Thomson and Tait (see their § 710) that for $\gamma > \pi$ the slide becomes infinite at the centre (i.e. when $r = 0$). This does not necessarily connote rupture, but only that the strain is greater than that to

Section XVII. MAINTENANCE OF ACCESSORY DRIVE MECHANISM

4-61. General

Customarily, only the flexible core of the speedometer or tachometer drive is replaced and a method of replacing it is described below. In the event that the entire cable must be replaced, a method of replacing it is also described. The tachometer drive cable is connected to the engine between the banks of cylinders, just forward of the air cleaner.

4-62. Speedometer and Tachometer Drive

a. Flexible Core Replacement. Loosen the

knurled nuts at each end of the flexible drive cable and remove the end. Withdraw the flexible core from within the sheath. Install a new flexible core in the sheath from the gage end and attach the ends of the flexible drive with the knurled nuts.

b. Drive Cable Installation. Install the new drive cable in the same clamps as the old cable and attach the ends of the cable with the knurled nuts.

Section XVIII. MAINTENANCE OF CARRIER ENGINE ASSEMBLY

4-63. General

Engine components and engine connected items which are the responsibility of organizational level maintenance are included in this section. These items include the engine clutch release mechanism, the two transmission shift mechanisms, and the engine valve covers.

4-64. Engine Service and Test

a. Service. Clean, inspect, and lubricate the carrier engine in accordance with instructions in JO 5-3810-294-12/4.

b. Compression Test. A compression check must be made with all spark plugs removed, the throttle wide open and the engine air cleaner removed. Compression should be uniform, not to exceed 10 psi between the highest and lowest reading per cylinders at normal cranking speed. Compression readings will deviate considerably from specifications due to crank speed, altitude, and ambient temperature. Therefore, the specifications listed in paragraph 3-7b(2) are to be used as a basic guide.

NOTE

The best indication of valve or ring leakage is to detect those cylinders not conforming to the allowable 10 psi variation.

4-65. Valve Covers

a. General. Two valve covers are provided, one for each bank of the engine. There will be no need for normal periodic removal and replacement of these covers since valve tappets are replaced on this engine by non-adjustable hydraulic valve lifters.

b. Removal and Replacement. If required due to oil leaks, refer to figure 4-39 and remove and replace valve covers. Always replace the cover gaskets when covers are removed unless replacement gaskets are unavailable and the old gaskets are in good condition.

4-66. Rocker Arms

a. General. This engine is provided with hydraulic valve lifters instead of the more common tappet arrangement. The valve lifters consist primarily of a body, plunger, spring, and check valve. The purpose of the assembly is to keep the rocker arm in tight contact with the end of the valve (zero valve lash), thus eliminating the need for periodic valve tappet adjustments.

b. Adjustment. Because of the use of hydraulic valve lifters, there is no need to adjust valve tappets on this engine.

4-67. Engine Clutch Controls

a. General. The engine clutch can only be adjusted when it is removed and reinstalled. Therefore, this paragraph is restricted to clutch control adjustment and inspection.

b. Inspection. Inspect the clutch pedal free travel by depressing the clutch pedal by hand until resistance is felt. Release the pedal. Measure the distance the pedal travels. It should be between 3/4-and 1-inch. If not, it must be adjusted.

c. Adjustment. Refer to figure 4-40 and adjust the clutch.

The final section of the memoir § 3 (pp. 143—7), is occupied with some general observations on the elasticity of rods whose axes are curves of double curvature. Their only relation to the preceding formula for torsion is the remark that the coefficient of torsional resistance used by some writers, namely $\mu\tau I_0$, must be replaced by $\frac{1}{4}\mu\tau\alpha^4/I_0$. Saint-Venant compares the results of his memoir of 1843 (see our Art. 1584*) with the more recent researches of Bresse and Resal: see our discussion of their memoirs below. There is nothing of importance to note; the footnote p. 145 should be cancelled.


[292.] *Analyse succincte des travaux de M. Boussinesq, professeur à la Faculté des sciences de Lille, faite par M. de Saint-Venant*, 1880. This report consists of 23 lithographed pages.

In April, 1880, Boussinesq had printed and presented to the members of the Academy a notice of his scientific writings. (Danel, Lille, in 4°.) Saint-Venant then drew up the above analysis, strongly recommending Boussinesq for membership of the Academy. Pp. 12—17 (§§ 6—9) treat of his contributions to the theory of elasticity ('*Les travaux de M. Boussinesq sur les solides et leur élasticité ne sont pas moins originaux et importants*'). Pp. 17—20 deal with his various mechanical and physical papers; pp. 20—23 with his contributions to the theory of light. We shall have occasion to return to Saint-Venant's essay when discussing Boussinesq's memoirs.

[293.] A second paper of Saint-Venant's dealing with the elastical researches of a contemporary may be noted here. It is entitled: *Sur le but théorique des principaux travaux de Henri Tresca*. *Comptes rendus*, T. CL, 1885, p. 119—22.

The influence on theory of Tresca's researches and the origin of the science of plasticity are sketched. The writer attributes to Tresca a keen appreciation of theory; he was no mere empiricist, as many have erroneously believed:

Il importe de montrer, dans l'intérêt de sa mémoire comme dans celui de la vérité scientifique, que Tresca fut un esprit plus large, un homme de vraie Science et par conséquent de *théorie* dans la meilleure et la plus saine acceptation de ce mot si souvent mal compris, si fréquemment accusé, par légèreté ou en haine systématique de la Science, de n'exprimer que des chimères (p. 119).



ME 3810-294-20/4-41

1. Lever, main transmission control
2. Lever, transfer case control
3. Lever, front axle control
4. Bracket, control lever
5. Lever
6. Rod, transfer case control
7. Lever, idler

8. Rod, transfer case control, rear
9. Lever, front axle drive
10. Rod, front axle control, rear
11. Idler, shifter rod
12. Pin, yoke
13. Rod, front axle control, rear
14. Rod, main transmission control

Figure 4-41. Axle, transmission, and transfer case controls adjustment.

Section XIX. MAINTENANCE OF STEERING ASSEMBLY

4-69. General

The power steering system (fig. 3-2) consists of a vane type hydraulic steering pump, a fluid reservoir, the steering gear proper (which contains a hydraulic control valve and a power cylinder), and mechanical steering control linkages

4-70. Power Steering Pump and Reservoir

a. Removal. Remove the power steering pump and the pump drive belts as follows:

(1) Refer to figure 4-42, remove the cap nut and drain the fluid from the hydraulic reservoir into a suitable container.

(2) Refer to figure 4-43 and loosen the four adjusting capscrews to relieve power steering pump belt tension. Lift the power steering belts off the pump sheave.

(3) Disconnect pump inlet and discharge lines.

(4) Refer to figure 4-43, remove the adjusting capscrews, nuts, and lockwashers and remove the power steering pump as an assembly.

(5) Refer to figure 4-44 and remove and replace the power steering reservoir. Note that the cover includes a dipstick type level gage. Add oil to FULL mark on dipstick when reinstalling reservoir.

b. Pump Replacement. Install the power steering pump as shown in figure 4-43

c. Belt Tension Adjustment. Refer to figure 4-24 and adjust belt tension which should be 1/2 inch midspan deflection.

d. Reservoir Replacement. Refer to figure 4-44 and replace the reservoir as follows.

(1) Refer to figure 4-42 and drain reservoir by removing cap nut.

(2) Refer to figure 4-44 and remove and replace reservoir.

end of the fixed bar, then the shifts u_2 and u_1 of either bar at any point x during the impact are :

$$u_2 = P_2 V \Sigma \frac{2 \cos \{m\tau_2 (a_1 + a_2 - x)/a_2\} \sin mt}{m \cos m\tau_2 \left(\frac{P_1}{\sin^2 m\tau_1} + \frac{P_2}{\cos^2 m\tau_2} \right)},$$

$$u_1 = P_2 V \Sigma \frac{2 \sin \{m\tau_1 x/a_1\} \sin mt}{m \sin m\tau_1 \left(\frac{P_1}{\sin^2 m\tau_1} + \frac{P_2}{\cos^2 m\tau_2} \right)},$$

where m is a root of the equation :

$$\frac{P_1}{\tau_1} \cot m\tau_1 - \frac{P_2}{\tau_2} \tan m\tau_2 = 0,$$

and $\tau_1 = a_1/k_1$, $\tau_2 = a_2/k_2$; k_1 and k_2 being the velocities of sound in the two bars.

[296.] Saint-Venant then considers the case when τ_2 is very small as compared with τ_1 , and so deduces Navier and Poncelet's expression for the vibrations of a bar struck by a weight on its free terminal: see our Arts. 273*, and 991*. Saint-Venant does not enter into the question of the *time and manner* in which the bars separate. He goes on to remark that in the case of two *free* bars we may express the result in finite terms, as also in the case of one free bar and a weight moving with a definite velocity and striking it longitudinally on one terminal. The case of a bar fixed at one terminal and struck by a moving weight at the other, he does not in this memoir attempt to solve in finite terms. This, however, he proceeded to do in an article in the same volume of the *Comptes rendus*, on pp. 423—427, entitled :

[297.] *Solution, en termes finis et simples, du problème du choc longitudinal, par un corps quelconque, d'une barre élastique fixée à son extrémité non heurtée.*

This solution is very similar to the full treatment of the problem by Boussinesq referred to in our Art. 341. But it fails to determine the instant of separation, and so does not completely solve the problem. After Boussinesq had given his solution Saint-Venant with the aid of Flamant concluded the whole subject with a graphical investigation of the successive states of the bar and the impelling load for the whole duration of the impact: see our Arts. 401—7.




Figure 4-44. Power steering reservoir service and replacement.

Green, Clebsch, Thomson and others: see our Art. 928* and the footnote Vol. I., p. 625.


Généralement et philosophiquement aucune considération purement *mathématique* ne saurait révéler le mode de la dépendance mutuelle des forces agissant sur les éléments des corps, et des changements géométriques qui s'y opèrent, tels que ceux des longueurs et des angles de leurs côtés: la connaissance de ce mode ne peut être dérivée que des faits, ou de quelque loi *physique* exprimant un ensemble de faits constatés (p. 39).

Saint-Venant appeals to experiment and cites Stokes' adduction of the isochronism of sound vibrations with approval: see our Art. 928*. We have remarked elsewhere that the stress-strain relation cannot, however, be treated as linear for the slight elastic strains in many of the materials of practical structures: see Note D of our Vol. I., p. 891.

[300.] But Saint-Venant is not satisfied with appeal to experiment and observation; these give Keplerian laws, without the backbone of Newtonian gravitation:

En général, pour convaincre nos esprits, l'empirisme, qui ne rend compte de rien, ne suffit pas: il nous faut encore une explication, une raison scientifique, où la preuve que les formules qu'on nous propose dépendent de quelque loi assez générale, assez *grandiose*, c'est-à-dire simple, pour que nous puissions en raisonnant, comme faisait Leibnitz, quand ce ne serait que d'une manière instinctive, la regarder comme pouvant être celle à laquelle le souverain Législateur a soumis les phénomènes intimes dont les formules en question représentent et mesurent les manifestations extérieures (pp. 40-1).

Saint-Venant finds this *loi assez générale, assez grandiose* in the law of intermolecular central action, as a function only of the distance, and cites its acceptance by the leading physical mathematicians from Newton to Clausius. He then refers to Green and his followers, who, as we know, appealed to Taylor's Theorem, as a *loi assez grandiose*. Now behind this appeal for 21 independent constants to Taylor's Theorem, although unrecognised by Green, was the important conception that possibly intermolecular action depends not only on the individual molecules, but on the position of each pair of them in the universe relative to other molecules. For example, if intermolecular action arises from molecular pulsations in a fluid ether, we find intermolecular force is a function of molecular surface energy, which surface energy is itself a function of position relative to the totality of other



ME 3810-294-20/4-47

Figure 4-47. Steering column, exploded view.

Is he justified in thus making the translational energy of the molecular centroids a function solely of their position? He seems to think that both the omissions (1) and (2) are legitimate provided that there are no such changes of *temperature* as produce violent atomic vibrations, and that we take the mean of large numbers (see his § 12). But is it not within the bounds of possibility that the mean internal potential energy of the molecules may be changed by an elastic strain, although the mean internal kinetic energy on which the temperature may be supposed to depend remains unchanged? This change in the potential energy of the molecule will be a function of the relative molecular position, but it may be one of *aspect* as well as of centroidal position. If we accept, however, with both Green¹ and Saint-Venant that the former can only depend on the latter, we are thrown back, supposing no sensible thermal changes, on Equation (a).

[303.] Saint-Venant in § 5 proceeds to question whether the Equation (a) can give the form of ψ required by Green. He says that we can replace it by an equation of the form :

$$\Sigma m V^2/2 + \Psi_1(r, r', r'' \dots) = C \dots \dots \dots (b),$$

où Ψ_1 est une nouvelle fonction dont il importe peu que les variables r, r', r'' &c. soient ou ne soient pas, en partie, dépendantes les unes des autres, ... r, r', r'' ... étant les distances des molécules du système tant entre elles qu'avec les centres d'action *fixes* extérieurs (p. 68).

Is this change legitimate? The form (a) retains the possibility of intermolecular action being a function of *aspect*. Is this lost in (b)?—It does not appear to be so if some of the variables r are the distances from *fixed external points*. From this equation we easily deduce for any molecule m , the typical equation :

$$m\ddot{x} = \Sigma \frac{d\Psi_1}{dr} \cos(rx) \dots \dots \dots (c),$$

where Σ denotes a summation with regard to all values of r .

¹ Both Green and Sir William Thomson make the potential energy of the element a function only of the *change in shape*, i.e. of the relative position of molecular centroids. I think this assumes that the internal potential energy of the molecule can only be a function of centroidal position. It may, however, be that the internal potential energy of (either the molecule or) the element is a function of the relative *motion* of (the atoms or) the elements, in which case the velocities would appear in Ψ_1 , and we should obtain by the Hamiltonian process totally different equations to those of Green for elasticity. These *generalised equations of elasticity* leading to the *Dissipative Function* etc., I propose to discuss elsewhere.

variés, et en ajoutant aux parcours d'autres parcours quelconques arbitrairement choisis.


La nullité du travail total produit par un cycle ne peut donc être générale qu'autant qu'elle a lieu *pour chaque action individuelle* ; ce qui oblige à admettre que la force que nous avons appelée R soit fonction de la seule distance que nous avons appelée r (p. 71).

I do not understand the argument which follows the words : *elle cessera de s'observer en ajoutant*. Suppose the molecules represented by electro-magnets then the total action during any motion of one such magnet A on another B would depend not only on the initial and final *relative* positions of A and B , but owing to the induced currents on the paths and positions of A and B with regard to the other bodies in the field. It seems to me that Saint-Venant's argument would compel us to assert that by introducing other magnets into the field or by moving them about in a proper manner, we could obtain perpetual motion.

[305.] Saint-Venant's second argument is of the following kind (see his § 9). If the intermolecular force depends on more than the particular centroidal distance, then the distances between astral molecules will affect the action between terrestrial. Here to start with, we have somewhat of an assumption ; the action of A upon B may depend on the distance of both from C and D but not necessarily on the distance of C from D . For example such might be the case when we treat of *aspect* influence, as given by means of fixed centres having reference only to A and B . Saint-Venant continues : the influence of an astral intermolecular distance on a terrestrial must be absolutely insensible, for even when we are dealing with a small portion of terrestrial matter, the action of its molecules is sensibly independent of the state of other matter even at a visible distance.

Hence the form of Ψ_1 , $(r, r', r'' \dots)$ ought to be such that for any small system $d\Psi_1/dr$ depends sensibly only on the molecules in the immediate neighbourhood of m . This condition of exclusion can be easily fulfilled for molecules at *sensible* distances by making Ψ_1 a function of the inverse powers of $r, r', r'' \dots$. We will now cite Saint-Venant's actual words :

Mais cette ressource d'exclusion sensible est impuissante à l'égard des distances mutuelles de molécules appartenant en particulier à chacun de ces systèmes ou éléments non proches de celui dont on s'occupe.



ME 3810-294-20/4-4

1. Brake valve
2. Treadle valve
3. Air manifold
4. Double-check valve
5. SV-1 valve
6. PP-1 valve
7. Three-way control
8. TW-1 control valve

Figure 4-48. Air brake system piping diagram, valves, hoses, and fittings, removal and replacement (Sheets 1 through 3)

function of $\dot{q}_1, \dot{q}_2, \dot{q}_3 \dots r, r', r'' \dots$. In this case our equation will be of the form :

$$\frac{\Sigma m V^2}{2} + \frac{\Sigma \alpha \dot{q}^2}{2} + \frac{\Sigma \gamma_{sm} \dot{q}_s \dot{q}_m}{2} + \Psi_1(\dot{q}_1, \dot{q}_2, \dot{q}_3, \dots r, r', r'') = \text{const.} \dots (d),$$

where α and γ are certain constants. We should have to apply the general dynamical equations to determine the V 's and \dot{q} 's. Thus the intermolecular force between m_1 and m_2 might be a function of q_s , which in its turn might be found from the dynamical equations as a function of r' and r'' , etc., distances, let us say, between m_3, m_4 etc., while r', r'' would have no *direct* influence on the action between m_1 and m_2 : see Arts. 931*, 1529*.

The point is of very great physical interest, as it really concerns the *direct* application of the Second Law of Motion to the ultimate particles of bodies. Can we or can we not superpose the action of C on A to that of B on A , or does the action of C on A , affect that of B on A ? See the footnotes to our pp. 183 and 185.

[306.] The strong points of the rari-constant argument seem to me to lie in: (i) the *probable* insignificance of the indirect action of C as compared with the direct action of A on B ; (ii) the insufficiency of most of the experiments yet brought to bear against rari-constancy.

Be this as it may, I still feel it impossible to accept the following statements of Saint-Venant as satisfactory :

j'affirme hardiment, et tout le monde, j'en suis convaincu, pensera comme moi, qu'il faudra absolument adopter la forme ou la particularisation indiquée ci-dessus :

$$\Psi_1(r, r', r'') = f(r) + f_1(r') + f_2(r'') + \dots$$

... Elle fait revenir à l'adoption, comme voulue ainsi par l'expérience même, de la loi des actions *fonctions des seules distances où elles s'exercent*, et non des autres distances ; loi que le simple bon sens, aidé d'une observation générale des faits, a fait accepter pendant plus d'un siècle et demi. Et je suis convaincu que Green lui-même y croyait sans s'en rendre compte. Je ne peux, en effet, interpréter d'une autre manière cet instinct de physicien et de géomètre, ce sentiment "que les forces, dans l'univers, sont disposées de manière à faire, du mouvement perpétuel, une naturelle impossibilité." Green, sans aucun doute, refusait ainsi, à chaque action moléculaire mutuelle en particulier, la possibilité contraire... (pp. 72 and 73).

I doubt whether Green had thoroughly seen the important




Figure 4-48. Air brake system piping diagram, valves, hoses, and fittings, removal and replacement (Sheet 2 of 3)

Saint-Venant holds that for a feeble degree of aeolotropy produced by permanent compressions as, for example, in drawn or rolled metal and in some kinds of stone the relations (i) or (ii) suffice. For wood however some other conditions must hold. For let us suppose :

(a) The relations (ii) to hold with equal transverse elasticity (or $a=b$) and rari-constancy then :

$$3f=a, \quad 6e=c+a \quad \text{and} \quad c=6e-3f.$$

We easily find from the formulae of Art. 307, that :

$$\eta_{zw} = \frac{1}{4}e/f, \quad E_z/E_w = \frac{1}{8} \left(18e/f - \frac{e^2}{f^2} - 9 \right),$$

whence

$$\eta_{zw} = 9/4 - \frac{1}{2} \sqrt{18 - 2E_z/E_w}$$

or, in order that the stretch-squeeze ratio be real we must have $E_z/E_w < 9$.

This result is contradicted by Hagen's experiments (see our Art. 1229*). Hagen found :

$$E_z/E_w = \begin{cases} 15 & \text{for oak,} \\ 22.5 & \text{for beech,} \\ 48 & \text{for pine,} \\ 83 & \text{for fir.} \end{cases}$$

(b) The relations (i) to hold together with $a=b$, $d=e=d'=e'$.

It follows that $\eta_{zw} = \frac{1}{4}e/f$, $E_z/E_w = e^2/f^2$,

whence

$$\eta_{zw} = \frac{1}{4} \sqrt{E_z/E_w} \quad E_z/G = \frac{5}{2} \sqrt{E_z/E_w}.$$

These expressions are never imaginary and give reasonable values for η_{zw} up to $E_z/E_w = 4$. After this η_{zw} begins to take unsuitable values till for $E_z/E_w = 80$, we have η_{zw} so large as 2.236.


Clebsch (p. 8, § 2) and at one time Saint-Venant (see our Art. 169 (d)) had held that η must necessarily be $< \frac{1}{2}$. This error the latter had recognised in the *Appendice complémentaire* to the *Leçons de Navier*, and he now adds :

Cette opinion n'est fondée sur aucun fait ; il ne l'exprime même que pour les corps isotropes, et quelques expériences de Wertheim ont montré qu'aux approches de la rupture d'une tige métallique, c'est-à-dire au moment où sa matière est arrivée à un état très fibreux, comparable à celui des bois, une extension de plus diminue le volume ; en sorte que, sans pouvoir aller jusqu'à $\eta = 2.236$, rien n'empêcherait de porter η jusqu'à 1 pour les bois tendres (p. 89).

Saint-Venant now seeks some correction of the amorphic formulae (i) which will give better results than this for η_{zw} when E_z/E_w is large.

[309.] He first proceeds on pp. 89—95 to determine Neumann's stretch-modulus quartic ; he obtains it in the form :

$$\frac{1}{E_r} = \frac{c_x^4}{E_x} + \frac{c_y^4}{E_y} + \frac{c_z^4}{E_z} + 2 \frac{c_y^2 c_z^2}{F_1} + 2 \frac{c_z^2 c_x^2}{F_2} + 2 \frac{c_x^2 c_y^2}{F_3} \dots\dots\dots (iii),$$



- STEP 1. RELEASE ALL AIR BRAKE PRESSURE.
- STEP 2. REMOVE SLACK ADJUSTER COTTER PIN AND PIN.
- STEP 3. UNSCREW AIR LINE CONNECTION TO REAR OF BRAKE CHAMBER AT SWIVEL CONNECTION.
- STEP 4. REMOVE MOUNTING NUTS AND WASHERS.

ME 3810-294-29 4

Figure 4-49. Front wheel brake chamber, removal and replacement.

c. *Brake Shoe Removal* Remove brake shoes as follows:

(1) Jack up the axle of the wheel to be worked on and block the axle so that the wheel is supported off the ground. Be sure the machine is adequately blocked to prevent tipping.

(2) Refer to paragraph 4-85 and remove the wheel. Remove the brake drum nuts shown in the illustration and remove the brake drum.

(3) Refer to figure 4-53, remove the shoe return spring, remove the "C" washers from guide pins and anchor pins, and remove the brake shoes.

d. *Brake Shoe Installation*

(1) Refer to figure 4-53 and install brake shoes.

(2) Refer to paragraph 4-85 and install the wheel.

4-81. Dummy Couplings

a. *General.* Trailer dummy couplings (54) are provided both at the front of the and at the rear. In addition, couplings cated between the rear of the carrier to a "jumper" connection between the carrier the rear of the outrigger box. The dummy plings are used to connect the crane to a vehicle similarly equipped. The crane c another vehicle when the other vehicle tached to the rear pintle hook and wh dummy couplings are connected to the to hicle. The crane can be towed by anot hicle when the front pintle hook is mec ly connected to the other vehicle and the couplings are connected to the towing Figure 4-54 shows a check valve and an o

which shall satisfy those conditions. After some rather complex analysis the necessary and sufficient conditions are found to reduce to

$$\frac{9 + 12 E_z/E_x - \sqrt{81 + 144 E_z/E_x}}{2 + 4 E_z/E_x} > n > \frac{12 + 9 E_z/E_x - \sqrt{144 E_z/E_x + 81 (E_z/E_x)^2}}{4 + 2 E_z/E_x},$$

where we suppose $E_z > E_x > E_y$.

Saint-Venant then gives a table of the limiting values of n and of

$$\eta_{zx} = \frac{1}{4} \frac{d}{f} = \sqrt{\frac{n}{18 - 2n} \cdot \frac{E_z}{E_x}}, \text{ for various values of } E_z/E_x \text{ from 1 to 80}$$

and also for α .

The values of η_{zx} are now found to be possible, provided a suitable value of n be chosen. What shall this be?

[313.] The empirical formula for n


$$1/n = 1 + \frac{1}{\gamma} (E_z/E_x - 1) \dots \dots \dots (\text{v}),$$

is suggested on p. 104. On p. 105 Saint-Venant tabulates the values of n and η_{zx} for the parameter E_z/E_x ($= 1$ to 80) when γ has the numerical values 9 and 22.22 . These values for γ are chosen because, for $E_z/E_x = 80$, they give respectively $\eta_{zx} =$ about $2/3$ and 1 . The Table also contains the corresponding values of E_z/e ($= E/\mu$ with transverse isotropy). These values vary on the first supposition ($\gamma = 9$) from 2.5 to 78.2 , and on the second ($\gamma = 22.22$) from 2.5 to 52.67 . The ratio E/μ can thus be very great, but for E_z/E_x very great, this does not seem at all improbable, at least we have at present no experiments to contradict it. As for the value of γ we need not confine it to 9 or 22.22 , but in general we may take it from 7 or 8 to 30 (p. 108). *Nous pensons qu'on ne courra guère risque de se tromper en faisant $\gamma = 16$* (p. 108).

As Saint-Venant observes there is a great need of new experiments to determine E_z and E_x (by flexure), μ (by torsion) and η ($= -s_x/s_z$, by delicate measurements of the transverse dimensions of bars under traction).

[314.] In default of experiment we may finally adopt as formulae most probably sufficient for elastic problems concerning amorphous aeolotropic solids, such as stone, wood, and the metals employed in the construction of bridges and machines:

$$\left. \begin{aligned} \widehat{xx} &= \frac{3ef}{d} s_x + fs_y + es_z, & \widehat{yz} &= d\sigma_{yz} \\ \widehat{yy} &= fs_x + \frac{3fd}{e} s_y + ds_z, & \widehat{zx} &= e\sigma_{zx} \\ \widehat{zz} &= es_x + ds_y + \frac{3de}{nf} s_z, & \widehat{xy} &= f\sigma_{xy} \end{aligned} \right\} \dots \dots \dots (\text{vi}),$$



ME 3810-294-20 4-54

Figure 4-54. Dummy couplings, removal and replacement.

Section XXI. MAINTENANCE OF CARRIER DRIVE TRAIN

4-82. General

There are two differentials and four propeller shafts in the carrier drive train which require organizational maintenance as described in the following paragraphs

4-83. Propeller Shafts

a General Refer to figure 4-55 for location of the propeller shafts. All four propeller shafts are identical in construction, except for length and termination (flange or lock-strap mounting)

b Removal and Installation. Refer to figure 4-55 and remove capscrews, lockwashers, and nuts to disconnect flange mountings. To disconnect lock strap connections, bend the lock straps away from the capscrews and remove capscrews, lock straps, and bearings. Install flange or lock strap mounted propeller shafts as shown in figure 4-55.

4-56

NOTE

After capscrews and lock straps have been moved, place brass drift to the center of spur and tap with hammer to loosen bearing caps. I move bearings and caps from yoke

4-84. Front Axle Differential

a General The front axle differential (fig. 4-55) is a double-reduction unit which contains a spiral bevel pinion gear and helical spur gear to control drive torque to the front axle

b. Service Refer to the current issue of 3810-294-12 for lubrication instructions

4-85. Rear Axle Differential

a. General. The forward-rear axle assembly (fig. 4-55) is equipped with an interaxle differential which divides drive torque between

[316.] This note is concerned with the applicability of Saint-venant's torsion and flexure solutions to such cases as occur in practice. The first four sections (pp. 174—7) reproduce arguments already given in the memoir on *Torsion* or the *Leçons de Navier* of the approximate elastic equivalence of statically equipollent loads: see our Arts. 8, 9 and 170. The remaining sections (5—17) seek arguments in favour of the legitimacy of the assumptions

$$\widehat{xx} = \widehat{yy} = \widehat{xy} = 0 \dots\dots\dots (a),$$

taken by Saint-Venant as the basis of his solutions. In other words, is it legitimate to assume that for all practical loadings there is little or no mutual action *parallel* to the prismatic cross-section between adjacent longitudinal fibres?

After referring to the labours of Poisson and Cauchy on the subject of rods (see our Arts. 466* and 618*) as involving arbitrary assumptions only true for rods of length great as compared with the linear dimensions of the cross-section, Saint-Venant enquires whether the investigations of Kirchhoff give any better validity to the assumptions (a). He points out that Kirchhoff proves only the possibility, not the necessity of these questionable relations (Art. 181): see my footnote, p. 266.

[317]. Saint-Venant next turns to Boussinesq's memoirs of 1871 and 1879: see later our discussion of that author's researches. Saint-Venant applies the method of those memoirs to the simple case of a bar of homogeneous material with three planes of elastic symmetry.

Instead of setting out from the assumptions (a) our author proposes the following conditions to hold, z being the direction of the prismatic axis:

$$\frac{d^2 s_x}{dz^2} = \frac{d^2 s_y}{dz^2} = \frac{d^2 s_z}{dz^2} = \frac{d^2 \sigma_{xy}}{dz^2} = \frac{d\sigma_{xz}}{dz} = \frac{d\sigma_{yz}}{dz} = 0 \dots\dots\dots (b).$$

These are described as *fort approchées, quand elles ne sont pas rigoureuses*.

From the conditions (b) the conditions (a) are deduced by the principle of elastic work. The proof holds only for *rods*, i.e. prisms the length of which is great as compared with the linear dimensions of the cross-section; the cross-section may, however, be supposed to vary slightly, and the terminal load as well as the

(4) Using a suitable tool, starting at the ring split, force the ring into place around the edge of the wheel rim.

NOTE

It is very important that all rust, corrosion, and accumulated dirt be removed from the ring and its seating surface on the wheel rim.

(5) With the ring installed, turn the tire over so that the ring side is facing the ground. Using an air hose from the side opposite the ring, inflate the tire.

WARNING

Always inflate the tire from the side opposite the ring. If the ring is improperly installed, air pressure may cause it to fly off the wheel and serious injury to personnel may result.

(6) Install the wheel-tire on the vehicle.

4-88. Shock Absorbers

a. Removal. Refer to figure 4-57 and remove the shock absorbers.

b. Installation. Refer to figure 4-57 and install the shock absorbers.



Figure 4-57. Shock absorbers, removal and replacement.

Section XXIII. MAINTENANCE OF PNEUMATIC COMPRESSOR

4-89. General

The air compressor is lubricated by oil from the engine system and cooled by water from the engine system. Therefore, lubrication and cooling depend upon proper lubrication and cooling for the engine. Intake air is taken from the clean air side of the engine air cleaner.

4-90. Compressor Assembly

a. Adjustment. The governor should be adjusted so that it starts compressing air when pressure drops to 105 psi and stops compressing air when pressure reaches 125 psi. To adjust, proceed as follows:

(1) Start the engine and build up air pressure in the air brake system. Check the gage pressure at the cab air pressure gage at the time

the governor cuts off compression. Pressure should be 125 psi.

(2) With the engine still running, make a series of brake applications to reduce reservoir air pressure. Note the pressure at which the governor starts the compressor. This pressure should be 105 psi. Before adjusting, it is recommended that the gage board pressure gage be checked with an accurate independent gage, if one is available.

(3) Remove the governor cover (fig. 4-58).

(4) Refer to figure 4-59 and loosen the adjusting screw locknut. With a screwdriver, turn the adjusting screw counterclockwise (viewed from above) to raise the pressure settings. Turn the screw clockwise to lower the pressure settings. Both the starting and stopping pressure settings will change by an approximately equal amount.

can at best only apply to *rods* and not the prisms of Saint-Venant's problems. It may, however, still be the method

la meilleure et la plus complète qui en ait été théoriquement donnée (p. 190).

Perhaps on the whole the appeal to experiment referred to in our Arts. 8—10 is more satisfactory.

[319.] In a note pp. 195—7 Saint-Venant proves for the case of flexure the results

$$\int \widehat{zx} d\omega = \frac{d}{dz} \int \widehat{zx} x d\omega; \quad \int \widehat{zy} d\omega = \frac{d}{dz} \int \widehat{zx} y d\omega,$$

where z is an axis in direction of the prismatic axis, and x, y are any rectangular axes in the cross-section of which $d\omega$ is an element of area. These formulae express analytically :

ce théorème connu et très utile, que l'effort tranchant, pour une section quelconque, ou la force tangentielle totale dans une direction transversale aussi quelconque, est égale à la dérivée, par rapport à la coordonnée longitudinale, du moment de flexion autour d'une droite tracée sur la section perpendiculairement à cette direction (p. 197).

See pp. 389—9 etc. of the *Leçons de Navier*.

[320.] The following *Note*, pp. 210—20, reproduces only portions of the great or the subsidiary memoirs on *Torsion*: see our Arts. 1, 285 and 291; and the *Note*, pp. 240—2, some results from Chapter XI. of the *Torsion*: see our Art. 49.

The *Note finale du § 37* (pp. 252—82) corrects Clebsch's erroneous assumption of a stress-limit by the proper stretch-conditions. Its contents are extracted from the memoir on *Torsion* and the *Leçons de Navier*: see our Arts. 5, (b)—(f), and 180.

[321.] We may refer to one or two points in this last *Note* :

(a) Saint-Venant takes two simple cases for an isotropic material and compares the stress and stretch-conditions for safe loading. First take the case when only the stresses \widehat{xx} , \widehat{xz} , \widehat{xy} have values differing from zero, we easily find from the equation of our Art. 53, Case (i), that we must have

$$T_0 = \text{or} > (1 - \eta) \widehat{xx}/2 + (1 + \eta) \sqrt{\widehat{xx}^2/4 + \widehat{xy}^2 + \widehat{xz}^2},$$

while Clebsch obtains from the stress condition

$$T_0 = \text{or} > \widehat{xy}/2 + \sqrt{\widehat{xx}^2/4 + \widehat{xy}^2 + \widehat{xz}^2}.$$

Check all water, air, and oil lines to be sure there are no leaks. Refer to paragraph 4-49 and adjust the alternator belt tension since the alternator belt also drives the compressor.

4-91. Alcohol Evaporator Strainer

Refer to paragraph 4-77c for removal and replacement of the alcohol evaporator strainer.

Section XXIV. MAINTENANCE OF FRAME COMPONENTS

4-92. Boom Rest

a. Removal. Refer to figure 4-60 and remove the boom rest.

b. Replacement. Position boom rest as shown in figure 4-60 and install lockwashers and cap-screws.

4-93. Pintle Hook

a. General. The pintle hook (23, fig. 4-61) is mounted on the rear outrigger box.

b. Removal. Remove the cotter pin (11) and nut (12) and remove the pintle hook (23) from the rear outrigger box.

c. Repair. Replace the hinge pin and chain if broken or damaged.

d. Replacement. Install the pintle hook in the rear outrigger and secure with nut (12) and cot-ter pin (11).

4-94. Outriggers

a. Replacement. Refer to figure 4-62 and remove and replace the outriggers.

b. Repair. Refer to figure 4-61 and remove any rust or corrosion from the outrigger beams and boxes and paint in accordance with TM 9-213. Replace any damaged or bound outrigger beam roller or jack screws and damaged outrigger box pins, eye pins, or capscrews. Report any broken or cracked welds to direct support main tenance.




Figure 4-60. Boom rest installed.

the T_1 and T_1' of immediate rupture. A constant ratio between T_1 and T_0 is usually assumed:

rapport qu'on prend généralement d'un dixième en France, d'après l'exemple des colonnes légères d'une ancienne église d'Angers, mais que des ingénieurs anglais portent à un sixième (p. 271).

(c) We may note that Saint-Venant on pp. 274—5 in repeating case 3^o of Art. 122 of the *Torsion*: see our Art. 53, Case (iii), now replaces the s_y/\bar{s}_y and s_z/\bar{s}_z of the notation of that article by *their mean*, so that he appears to have been dissatisfied with the value adopted in the memoir. He does not, however, work out the value of η_2 of our Art. 53, Case (ii) ($=\eta_1$ of his notation).

(d) A very good example of Saint-Venant's fail-point method is given on pp. 279—82 (§ 17). It brings out well the influence which want of isotropy and slide have on the condition for safety.

Let us take the case of a beam of length l , of cross-section ω , and of transverse elastic isotropy denoted by E , μ and η . Suppose it built-in at one end and loaded with P at the other, or of length $2l$ with a load $2P$ in the centre. Then if κ be the swing-radius of the section about the neutral axis and h the distance from that axis of the farthest 'fibre', we see that the fail-point will be at the built-in section which remains plane. Here the maximum stretch and the uniform slide are given by:

$$s = Plh/(E\omega\kappa^2), \quad \sigma = P/(\mu\omega).$$

Whence the condition of our Art. 53, (i), becomes with slightly modified notation:

$$\begin{aligned} T_0 = \text{or} &> \frac{1-\eta}{2} \frac{Plh}{\omega\kappa^2} + \sqrt{\left(\frac{1+\eta}{2}\right)^2 \left(\frac{Plh}{\omega\kappa^2}\right)^2 + \left(\frac{P}{\omega}\right)^2 \left(\frac{T_0}{S_0}\right)^2}, \\ &= \text{or} > \frac{Plh}{\omega\kappa^2} \left\{ \frac{1-\eta}{2} + \frac{1+\eta}{2} \sqrt{1 + \left(\frac{E}{2(1+\eta)\mu}\right)^2 \left(\frac{2\kappa^2}{lh}\right)^2} \right\} \dots (i), \end{aligned}$$

since $S_0/\mu = 2T_0/E$ by our Art. 5, (d).

In the case of the rectangular cross section $b \times c$, with c parallel to the load-plane, we have $\kappa^2 = c^2/12$, $\omega = bc$, $h = c/2$ and the condition becomes:

$$T_0 = \text{or} > \frac{6Pl}{bc^2} \left\{ \frac{1-\eta}{2} + \frac{1+\eta}{2} \sqrt{1 + \left(\frac{E}{2(1+\eta)\mu}\right)^2 \left(\frac{c}{3l}\right)^2} \right\} \dots (ii),$$

or,

$$T_0 = \text{or} > \frac{6Pl}{bc^2} \left\{ 1 + \frac{1}{1+\eta} \left(\frac{E}{12\mu}\right)^2 \left(\frac{c}{l}\right)^2 \right\} \dots \dots \dots (iii),$$

if the second term under the radical is, as usual, small.

Saint-Venant now introduces the following suggestive table determined by the method of our Arts. 312—4, z being the direction of the prismatic axis:

- | | | | |
|------------------------|-----------------------|------------------------|---------------------|
| 1. Capscrew | 13 Rod end | 25. Beam roller | 37. Lockwasher |
| 2. Lockwasher | 14 Lockwasher | 26. Cotter pin | 38. Nut |
| 3. Rod end | 15. Capscrew | 27 Roller pin | 39. Grease fitting |
| 4. Outrigger box pin | 16 Grease fitting | 28. Grease fitting | 40. Outrigger beam |
| 5. Front outrigger box | 17 Outrigger box pin | 29 Outrigger float | 41. Jackscrew cover |
| 6. Capscrew | 18 Rear outrigger box | 30. Pin | 42. Beam roller |
| 7. Lockwasher | 19 Capscrew | 31 Cotter pin | 43. Roller pin |
| 8. Jam nut | 20 Lockwasher | 32. Capscrew | 44. Grease fitting |
| 9. Beam lock pin | 21. Jam nut | 33. Flat washer | 45. Cotter pin |
| 10. Outrigger beam | 22 Outrigger beam | 34 Chain | |
| 11. Cotter pin | 23 Pintle hook | 35 Jackscrew outrigger | |
| 12. Nut | 24 Outrigger beam | 36. Capscrew | |

Figure 4-61 — Continued

We find at once :

$$\left. \begin{aligned} s_x &= -z/\rho, & s_y &= 0, & s_z &= \frac{d'}{c} \frac{z}{\rho}, \\ \sigma_{yz} &= \sigma_{zx} = \sigma_{xy} = 0 \end{aligned} \right\} \dots\dots\dots (ii).$$

Substitute in the formulae of Art. 117, (a) and (b), and we have :

$$\left. \begin{aligned} \widehat{yz} = \widehat{zx} = \widehat{xy} &= 0; & \widehat{zz} &= 0; \\ \widehat{xx} &= \left\{ \frac{d'^2}{c} - (2f + f') \right\} \frac{z}{\rho}; & \widehat{yy} &= \left\{ \frac{d'^2}{c} - f' \right\} \frac{z}{\rho} \end{aligned} \right\} \dots\dots\dots (iii).$$

Here the quantity $2f + f' - d'^2/c$ corresponds for the case of plates to the stretch-modulus in the simple flexure of a bar. We shall denote it by H , where in the case of isotropy, $H = \frac{4\mu(\mu + \lambda)}{2\mu + \lambda}$.

We easily see that (iii) satisfy the body-stress equations.

The load reduces to

$$\widehat{xx} = -\frac{Hz}{\rho}$$

over the sides perpendicular to x , and we can see that this gives a couple round the axis of y for each element $2\epsilon\delta y$ of the side $= M_y\delta y$, where

$$M_y = \int_{-\epsilon}^{+\epsilon} \widehat{xx} \cdot z dz = -2H\epsilon^3/(3\rho).$$

We can cut away a portion of the plate by planes perpendicular to the axis of y if we impose a load at each point of the new sides given by

$$\widehat{yy} = -(H - 2f)z/\rho.$$

Obviously $1/\rho$ must be very small, and the plate then takes a cylindrical curvature of radius ρ .

[324.] *Case of two combined cylindrical flexures.* In § 3 Saint-Venant first combines two solutions such as that of our Art. 323, the value of ρ being the same for both. He transfers to cylindrical coordinates r, ϕ , and thus obtains with the notation of our p. 79 the results :

$$\left. \begin{aligned} u &= -rz/\rho, & v &= 0, & w &= \left(r^2/2 + \frac{d'}{c} z^2 \right) / \rho \\ \widehat{zz} &= 0, & \widehat{rr} &= \widehat{\phi\phi} = -2(H - f)z/\rho \end{aligned} \right\} \dots\dots\dots (iv).$$

This is the case of *spherical* curvature. The proper distribution of side load must be obtained by compounding \widehat{rr} and $\widehat{\phi\phi}$, the shears being all zero. The corresponding total couples are

$$M_r = M_\phi = -\frac{4\epsilon^3}{3} \frac{H - f}{\rho} \dots\dots\dots (v).$$

- STEP 1. TURN JACKSCREWS DOWN TO RELIEVE PRESSURE ON OUTRIGGER BOX PINS. BLOCK OUTRIGGER SO THAT IT WILL NOT TIP WHEN OUTRIGGER PINS ARE REMOVED.
- STEP 2. REMOVE CAPSCREWS, EYE PINS, AND OUTRIGGER BOX PINS. REMOVE OUTRIGGER FROM UNDER CARRIER.
- STEP 3. POSITION OUTRIGGER UNDER CARRIER AND RAISE TO NORMAL POSITION WITH JACKSCREWS. INSTALL OUTRIGGER BOX PINS, EYE PINS, AND CAPSCREWS AS SHOWN




Figure 4-62. Outrigger, removal and replacement (sheet 2 of 2).

Section XXV MAINTENANCE OF FIRE EXTINGUISHER AND TOOL BOX

4-95. Fire Extinguisher

Replace fire extinguishers which have been used, the seals of which have been broken, or which have lost weight of 1/4 pound or more, with a like serviceable item.

4-96. Tool Box

a. Removal Refer to figure 4-63 and remove the tool box.

b. Replacement Replace the tool box as shown in figure 4-63.




Figure 4-63. Tool box installation.

Hence we find for the stresses :

$$\left. \begin{aligned} \widehat{xx} &= \widehat{yy} = \widehat{xy} = 0, \\ \widehat{xz} &= -\frac{3Pz}{2\epsilon^3}(a-x), \quad \widehat{yz} = \frac{3P}{4\epsilon}\left(1 - \frac{z^2}{\epsilon^2}\right), \\ \widehat{yz} &= -\frac{H-2f}{H} \frac{3Pz}{2\epsilon^3}(a-x) \end{aligned} \right\} \dots\dots\dots(\text{vii}).$$

The deflection of the central plane is given by the cubical parabola

$$w_0 = \frac{Pa^3}{2H\epsilon^3} \left(\frac{3}{2} \frac{x^2}{a^2} - \frac{1}{2} \frac{x^3}{a^3} \right) \dots\dots\dots(\text{viii}).$$

This agrees with the case of a rod of length $2a$ and depth 2ϵ , terminally supported and loaded with $2P$ at the centre if the plate-modulus H be replaced by the stretch-modulus E .

[327.] We can cut out a definite portion of the plate by planes perpendicular to y , if we impose the tractive loads given by \widehat{yz} of equations (vii).

Suppose we try to combine two sets of solutions such as (vi) of the previous Article, giving the plate now a flexure parallel to y . Then we find, if Q corresponding to P , and b to a , from (viii) :

$$w_0 = \frac{3}{2H\epsilon^3} \left(\frac{Pax^2 + Qby^2}{2} - \frac{Px^3 + Qy^3}{6} \right).$$

Hence although we combine this with a solution of the form given in Art. 325, we can make only the square not the cubic terms in x and y vanish. In other words for $x = \pm a$, together with $y =$ any value from b to $-b$, and for $y = \pm b$, together with $x =$ any value from a to $-a$, we cannot make $w_0 = 0$. Thus the contour of the mid-plane of the rectangular plate cannot be treated as *fixed*.

Le problème de la flexion de la plaque rectangulaire posée de niveau tout autour ne peut probablement recevoir que des solutions approximatives... (p. 346).

[328.] *Problem of the thick circular plate.* This can be solved accurately for flexure whatever the thickness, if the plate be *symmetrically* loaded in all directions round its axis of figure by forces applied to its cylindrical boundary. Just as in the case of torsion or flexure, these forces will be supposed distributed in a definite manner, but the resultant shearing force and couple about the tangent to the contour of the mid plane will be arbitrary. In practical applications we must appeal to the principle of the elastic equivalence of statically equipollent load-systems: see our Art. 8. We shall suppose that there is no tendency to extension in the plate and that it is bounded by two coaxial cylinders of radii r_1 and r_0 ($r_1 > r_0$).

We shall find that the magnitude of the central shift can be determined for any load whatever, not necessarily symmetrical.



Integrating we find, if A be an arbitrary constant :

$$\frac{1}{r} \frac{d(ru)}{dr} = z \left(\frac{4}{I} \log(r/r_1) - \frac{2}{A} \right) = -\frac{c}{d'} w_z \dots\dots\dots (v).$$

Integrating again we have :

$$\left. \begin{aligned} u &= \frac{z}{I} \left\{ 2r \log(r/r_1) - rz + \frac{Bz}{r} - \frac{rz}{A} + \frac{\phi(z)}{r} \right\} \\ w &= -\frac{d'}{c} \left\{ \frac{2z^2}{I} \log(r/r_1) - \frac{z^3}{A} \right\} + \chi(r) \end{aligned} \right\} \dots\dots\dots (vi).$$

Here B is another arbitrary constant and χ, ϕ arbitrary functions of r and z respectively.

Now we have $\widehat{rz} = e(u_z + w_r) = \frac{3P}{4\epsilon^3} \frac{r_1}{r} (\epsilon^2 - z^2)$; substituting for u and w from (vi) we find the following relation between χ and ϕ :

$$\frac{2r}{I} \log \frac{r}{r_1} - \frac{r}{I} + \frac{B}{r} - \frac{r}{A} + \frac{d\chi}{dr} = \frac{1}{r} \left\{ \frac{2}{I} \frac{d'}{c} z^3 + \frac{2}{I} \frac{H}{e} (\epsilon^2 - z^2) - \frac{d\phi}{dz} \right\}.$$

Saint-Venant remarks that we can satisfy this relation in several ways (p. 350), but the proper method seems to me to equate either side multiplied by r to the same constant. He takes this constant to be zero. If this constant be retained, however, it only alters the value of the constant B in the expressions for the shifts we are about to give, and so may be neglected. We ought to add a constant C' to the value of $\chi(r)$; but this leads to a term in $u = C'/r$, or in $\widehat{rz} = -2fC'/r^2$, which, not containing an odd power of z , would prevent us from fulfilling the condition

$$\int_{-\epsilon}^{+\epsilon} \widehat{rz} dz = 0 \text{ for } r = r_1.$$

Substituting the values obtained by integration for ϕ and χ in (vi), we have :

$$\left. \begin{aligned} u &= -\frac{rz}{A} + \frac{1}{I} \left\{ 2rz \log \frac{r}{r_1} - rz + \frac{2d'}{c} \frac{z^3}{3r} + \frac{2}{r} \frac{H}{e} \left(\epsilon^2 z - \frac{z^3}{3} \right) \right\} + \frac{Bz}{r} \\ w &= \frac{1}{A} \left(\frac{r^2}{2} + \frac{d'z^2}{c} \right) + \frac{1}{I} \left\{ r^3 - \left(r^2 + \frac{2d'z^2}{c} \right) \log \frac{r}{r_1} \right\} - C - B \log \frac{r}{r_1} \end{aligned} \right\} \dots\dots\dots (vii).$$

The values of \widehat{rz} and M_r may then be easily deduced. Saint-Venant gives expressions for them on pp. 351—2. By putting $r = r_1$, we obtain :

$$M_{r_1} = -\frac{4\epsilon^3}{3} \frac{H-f}{A} + \frac{4\epsilon^3}{3} \frac{f-H\gamma^2}{I} - \frac{4\epsilon^3}{3} f \frac{B}{r_1^2} \dots\dots\dots (viii),$$

where γ^2 is given by :

$$\frac{2}{5} \frac{f}{H} \left(\frac{d'}{c} + 4 \frac{H}{e} \right) \frac{\epsilon^2}{r_1^2} = \gamma^2 \dots\dots\dots (ix),$$

and may be neglected when ϵ/r_1 is small.

APPENDIX B

MAINTENANCE ALLOCATION CHART

Section I. INTRODUCTION

B-1. General

a. This section provides a general explanation of all maintenance and repair functions authorized at various maintenance levels.

b. Section II designates overall responsibility for the performance of maintenance functions on the identified end item or component and the work measurement time required to perform the functions by the designated maintenance level. The implementation of the maintenance functions upon the end item or component will be consistent with the assigned maintenance functions.

c. Section III lists the special tools and test equipment required for each maintenance function as referenced from Section II.

d. Section IV contains supplemental instructions or explanatory notes for a particular maintenance function

B-2. Explanation of Columns in Section II

a. *Column (1), Group Number* A number is assigned to each group in a top down breakdown sequence. The applicable groups are listed on the MAC in disassembly sequence beginning with the first group removed.

b. *Column (2), Assembly Group* This column contains a brief description of the components of each numerical group

c. *Column 3 Maintenance Functions* This column lists the various maintenance functions (A through K). The lowest maintenance level authorized to perform these functions is indicated by a symbol in the appropriate column. Work measurement time standards (the active repair time required to perform the maintenance function) are shown directly below the symbol identifying the maintenance level. The symbol designations for the various maintenance levels are as follows:

- C — Operator or crew
- O — Organizational maintenance

- F — Direct support maintenance
- H — General support maintenance
- D — Depot maintenance

The maintenance functions are defined as follows:

A. *Inspect*: To determine serviceability of an item by comparing its physical, mechanical, and electrical characteristics with established standards through examination.

B. *Test*: To verify serviceability and detect incipient failure by measuring the mechanical or electrical characteristics of an item and comparing those characteristics with prescribed standards.

C. *Service*: Operations required periodically to keep an item in proper operating condition, i.e., to clean, to preserve, to drain, to paint, or to replenish fuel, lubricants, hydraulic fluids, or compressed air supplies.

D. *Adjust*: To maintain within prescribed limits, by bringing into proper or exact position, or by setting the operating characteristics to specified parameters.

E. *Align*: To adjust specified variable elements of an item to bring about optimum or desired performance.

F. *Calibrate*: To determine and cause corrections to be made or to be adjusted on instruments or test measuring and diagnostic equipments used in precision measurement. Consists of comparisons of two instruments, one of which is a certified standard of known accuracy, to detect and adjust any discrepancy in the accuracy of the instrument being compared.

G. *Install*: The act of emplacing, seating, or fixing into position an item, part, or module (component or assembly) in a manner to allow the proper function of an equipment or system.

H. *Replace*: The act of substituting a serviceable like type part, subassembly, or module (component or assembly) for an unserviceable counterpart.

I. *Repair*: The application of maintenance

with (§ 14). The plate may now be dealt with as consisting of an 'inner disc' and 'outer annulus.' Then evidently $dw_0/dr=0$ when $r=0$ because the tangent plane to the mid-section at $z=0$, $r=0$, must be horizontal; further round the ring $r=r_0$ the shearing stress must vanish for the inner disc which can thus only be acted upon by couples and will take a spherical curvature ($1/\rho_0$) as in our Art. 324. Thus for the inner disc

$$u = -\frac{rz}{\rho_0}, \quad w = \frac{1}{\rho_0} \left(\frac{r^2 - r_0^2}{2} + \frac{d'}{c} z^2 \right), \quad M_r = -\frac{4\epsilon^3}{3} \frac{H-f}{\rho_0},$$

and for the conditions at $r=r_0$

$$w_0 = 0, \quad \frac{dw_0}{dr} = \frac{r_0}{\rho_0}, \quad M_{r_0} = -\frac{4\epsilon^3}{3} \frac{H-f}{\rho_0}.$$

Three equations to determine the three constants ρ_0 , B and C (ρ is known from M_{r_1}) of the problem are then obtainable by putting $r=r_0$ in the equations (xi) which hold for the outer annulus. Saint-Venant finds:

$$\left. \begin{aligned} B = \frac{r_0 - \gamma^2 r_1^2}{I}, \quad C = \frac{r_0^2}{2\rho} + \frac{1}{I} \left\{ r_0^2 \left(1 - \frac{\gamma^2}{2} \right) + \frac{f}{H-f} \frac{r_0^2}{2} \left(1 - \frac{r_0^2}{r_1^2} \right) \right. \\ \left. - (2r_0^2 - \gamma^2 r_1^2) \log \frac{r_0}{r_1} \right\}, \quad \dots \text{(xiii)}, \\ \frac{1}{\rho_0} = \frac{1}{\rho} + \frac{1}{I} \left\{ \left(\frac{f}{H-f} + \frac{\gamma^2 r_1^2}{r_0^2} \right) \left(1 - \frac{r_0^2}{r_1^2} \right) - 2 \log \frac{r_0}{r_1} \right\} \end{aligned} \right\}$$

whence the values of u , and w for $r > r_0 < r_1$, can be at once found.

The solutions obtained by Saint-Venant in this first case are, as he himself observes, hardly satisfactory except for the case of a very *thin* plate. What he does is to make the vertical shifts of the mid-plane zero for the disc and the annulus when $r=r_0$; then the slopes of the tangent planes for both are equated, and finally the total couples along the same circle $r=r_0$. In the solutions he gives for the shifts the u and w for the annulus are not equal to the u and w for the disc when $r=r_0$, except for the mid-plane. In particular u when $r=r_0$ is a function of z only for the disc, but of z^2 as well for the annulus. In other words we have theoretical separation of the material at $r=r_0$. Thus the solutions are at best only approximate, and cannot be considered to hold at all in the neighbourhood of the rim itself. But shall we assume they hold accurately at points not in the neighbourhood of this rim? If the stresses acting at this rim were really confined to a line, they would certainly produce permanent alterations in the material; are we then justified in assuming that equating the vertical shifts and the tangent plane slopes (w and dw/dr) for

Section II. MAINTENANCE ALLOCATION CHART (PART I)

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
01	U-450 CRANE CRANE, SHOVEL AND EARTH WORKING EQUIPMENT													
0101	Shovel Front Attachment			O	O				O	17.5				
0102	Boom, Shovel	C		0.4	1.5				F	F				
0103	Sprockets	0.1							7.0	7.6				
0104	Chain			O					O	F				
0105	Tightener			0.05	O				1.5	2.6				
0106	Dipper; Pulley Assy				0.5				1.7	4.2				
0107	Stick Assy								O	O				
0108	Braces, Pitch Assy								O	O				
0109	Dipper	C							2.0	3.2				
0110	Teeth, Dipper	0.05							F	F				
0111	Rack	C							8.0	10.3				
0112	Magnetic Switch, Solenoid and Push Button	0.05							D					
0113	Wire Assembly								4.0					
02	BACKHOE ATTACHMENT								O					
0201	Backhoe								2.0					
0202	Boom Assy, Backhoe	C		C					O	O				
0203	Derrick Assy	0.1		0.5					2.5	3.6				
									F	F				
									5.6	12.0				
												H	14.0	

the solutions of (c) are applicable to the case of a plate either fixed or built-in at its contour and loaded with Q uniformly distributed round the ring $r = r_0$. The deflections obtained by Saint-Venant are (p. 362):

(i) Mid-plane contour simply supported or fixed

$$\delta = \frac{3Qr_1^2}{32\pi H\epsilon^3} \left\{ \frac{2H-f}{H-f} \left(1 - \frac{r_0^2}{r_1^2} \right) + \left(\frac{r_0^2}{r_1^2} - \gamma^2 \right) \log \frac{r_0^2}{r_1^2} \right\}.$$

(ii) Cylindrical face built-in

$$\delta' = \frac{3Qr_1^2}{32\pi H\epsilon^3} \left\{ 1 - \frac{r_0^2}{r_1^2} + \left(\frac{r_0^2}{r_1^2} - \gamma^2 \right) \log \frac{r_0^2}{r_1^2} \right\}.$$

For the reasons given in my Art. 331, I am doubtful as to the validity of these results except in the case when we may neglect γ^2 .

[335.] (e) In § 19, p. 362, Saint-Venant explains how we may treat the problem of a thick circular plate subjected to any symmetrical load continuous or discontinuous on a plane face. We have in the case of a continuous load to substitute $\phi(r_0) 2\pi r_0 dr_0$ for Q in the equations of (d) and integrate between the limits 0 and r_0 , to find the total deflection. If we integrate from 0 to r_0 , we shall obtain the deflection of the centre below any ring r_0 and so the form of the surface taken by the mid-plane. Saint-Venant seems to think this process more rigorous than that for thin plates dependent on Lagrange's equation and used by Poisson: see our Arts. 284*, 496*—504*. But I cannot get over the difficulty suggested in my Art. 331. The results are not true for the ring in consideration unless γ^2 may be neglected, but Saint-Venant practically divides his whole plate up into such rings, when thus integrating. It appears to me possible that he may thus be really introducing an important sum of small errors.

In § 21, p. 365, he treats by this method the case of a thick plate uniformly loaded and finds from the results in (d):

$$\delta = \frac{3Qr_1^2}{128\pi H\epsilon^3} \left(\frac{3H-f}{H-f} + 4\gamma^2 \right),$$

$$\delta' = \frac{3Qr_1^2}{128\pi H\epsilon^3} (1 + 4\gamma^2),$$

where Q is the total load.

These results, first given by Boussinesq, agree in the case of uni-constant isotropy and neglect of γ^2 with those of Poisson: see our Art. 502*.

[336.] (f) This case is the most general possible and is thus stated by Saint-Venant:

Mais, lorsqu'on se propose d'avoir seulement la flèche centrale, sans chercher la forme que prend la plaque en ses divers points, une remarque bien simple montre que les expressions en r_1 et r_0 suffisent au calcul de cette flèche pour toutes les distributions possibles, même non symétriques, même discontinues et irrégulières, des charges que supporte la plaque soutenue en haut (p. 363).

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
0411	Cables	C 0.05	---	---	---	---	---	---	O 1.3	---	---	---		
0412	Pulleys	---	---	O 0.3	---	---	---	---	O 1.6	F 2.8	---	---		
0413	Sockets and Pins	C 0.1	---	---	---	---	---	---	O 1.2	---	---	---		
0414	Backstop Assy	---	---	---	---	---	---	---	O 1.3	F 3.2	---	---		
0415	Angle Indicator	C 0.1	---	---	---	---	---	---	O 1.3	---	---	---		
05	HULL WIRING HARNESS													
0501	Conduit	C 0.1	---	---	---	---	---	---	O 2.6	---	---	---		
0502	Wiring	---	---	---	---	---	---	---	F 2.8	O 3.0	---	---		
06	LIGHTS, BATTERIES, AND MISCELLANEOUS ITEMS													
0601	Flood, Clearance, Dome	C 0.1	---	---	---	---	---	---	O 1.3	---	---	---		
0602	Blackout	C 0.1	---	---	---	---	---	---	O 1.3	---	---	---		
0603	Doors, Lens	C 0.05	---	---	---	---	---	---	O 1.0	---	---	---		
0604	Receptacle	C 0.05	---	---	---	---	---	---	O 1.3	---	---	---		
0605	Cables, Slave	C 0.05	---	---	---	---	---	---	O 1.2	F 1.3	---	---		
0606	Battery	C 0.05	O 0.2	C 0.3	---	---	---	---	O 1.1	---	---	---		
0607	Cable	C 0.1	---	---	---	---	---	---	O 1.2	---	---	---		
0608	Box	---	---	---	---	---	---	---	O 1.0	F 2.0	---	---		

Memoir of 1882 on the same subject, will be found on pp. 881—8 (*Complément à la Note finale du § 46*). As these contributions are not due to Saint-Venant we postpone the discussion of their contents until we are dealing with the special researches of Boussinesq and Cerruti.

[339.] The next important addition of Saint-Venant is the *Note finale du § 60*. It is entitled: *Théorie de l'impulsion longitudinale d'une barre élastique par un corps massif qui vient heurter une de ses deux extrémités; et de la résistance de la matière de la barre à un pareil choc*; it occupies pp. 480 a—480 gg. The numerical results of this note together with their graphical representation will be considered in our account of the Memoir of 1883: see our Arts. 401—7.

[340.] The first seven sections (pp. 480 a—480 k) give an account of the various tentative stages in the history of the theory. We have first two theorems of Young, which as first approximations may be cited. Let the bar be of weight P , density ρ , section ω , length l and stretch-modulus E ; let Q be the weight and V the velocity of the body which strikes it at the free end, the other end being fixed.

Then if u be the total shift of the free end, g gravitational acceleration, and we suppose the stretch uniformly distributed, we have from the principle of work:

(i) *Bar horizontal:*

$$\frac{E\omega u^2}{2l} = \frac{Q}{g} \frac{V^2}{2}, \quad \text{or if } u_0 = \frac{Ql}{E\omega} \text{ be the statical shift,}$$

$$u = V \sqrt{u_0/g}.$$

(ii) *Bar vertical:*

$$\frac{E\omega u^2}{2l} = \frac{Q}{g} \frac{V^2}{2} + Qu \quad \therefore u = u_0 + \sqrt{u_0^2 + V^2 \frac{u_0}{g}}.$$

Let $u/l = T_0/E$ the greatest safe stretch within the elastic limit, then in Case (i):

$$\frac{E\omega l}{2} \left(\frac{T_0}{E} \right)^2 = \frac{QV^2}{2g}.$$

Now $\frac{QV^2}{2g}$ is the work necessary to destroy the efficiency of the bar, or its resilience. Hence the resilience of a bar varies as its volume ωl ,

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
14	BOXES, TOOL													
1401	Box	C 0.05							O 1.0	F 2.6				
15	GANTRY ASSY													
1501	Gantry	O 0.05							O 1.3	H 3.0				
16	ACCESSORY ITEMS													
1601	Heater and Switch	C 0.05							O 2.2	F 2.3				
1602	Defroster Hose	C 0.05							O 0.5					
1603	Wiring	C 0.05							O 0.7	F 0.9				
17	HYDRAULIC SYSTEM													
1701	Hose, Fitting, Tubing	C 0.05							O 2.3	F 3.3				
1702	Manifold and/or Control Valves								O 2.2	F 3.7				
1703	Master Cylinder			O 0.05					O 1.3	F 2.0				
1704	Cylinder Hydraulic			O 0.1					O 1.3	F 1.5				
1705	Liquid Reservoir	C 0.05		O 0.05					O 1.1					
18	COOLING SYSTEM													
1801	Radiator	C 0.05	H						O 1.7	H 4.0				
1802	Hoses	C 0.05	C 0.05						O 1.2					
1803	Cowling								O 1.7	F 3.0				
1804	Cap	C 0.05	O 0.1											

[342.] The next insertion of Saint-Venant is the *Note finale* du § 61. It occupies no less than 138 pages (pp. 490—627) and contains the complete theory of the transverse impulse of bars, including results of Saint-Venant's not hitherto published: see our Arts. 104-5, 200-1, and *Notice* II. p. 20, 2°. The *Note* is entitled: *De l'Impulsion transversale des barres élastiques, et de leur vibration avec le corps qui les aura mises en mouvement. Détermination de leur flexion ainsi que des conditions de leur résistance vive ou dynamique.*

[343.] The first 51 sections (pp. 490—597) are devoted to the analytical and numerical solution of various problems of bars vibrating transversely with a load attached:

ces pièces sont supposées *vibrer* non pas *seules* comme le supposent les solutions données par Clebsch, mais *unies avec le corps étranger* dont l'impulsion, ou brusque, ou graduée, les a fait sortir de leur état d'équilibre; car c'est pendant cette union, ne durât-elle que le temps d'une demi-période oscillatoire, que les déplacements relatifs des parties de ces pièces atteignent leur maximum et qu'elles courent le plus grand danger de rupture ou d'énervation dont les calculs de résistance ont pour objet de les sauver (p. 490).

Saint-Venant's method is simply to solve in 'normal' functions or coordinates the equation:

$$\frac{d^2}{dz^2} \left(E\omega\kappa^2 \frac{d^2u}{dz^2} \right) + \frac{p}{g} \left(\frac{d^2u}{dt^2} - g \right) = 0 \dots\dots\dots (i),$$

where u is the transverse shift of the point in the axis at distance z from one end of the bar, p/g is the mass per unit length of the bar and of any permanent load at the same point, g the body acceleration (usually only gravity) on the same length, and $E\omega\kappa^2$ with our usual notation the rigidity, which may vary from point to point. The bar is supposed to be loaded and to receive displacement in a plane which passes through a principal axis of each cross-section. The terminal and initial conditions determine the constants of the normal functions while the conditions at the impelled point select the normal functions required and determine the notes.

[344.] The process of solution and the calculation of the dynamical deflection are generally long, even if we keep only one term of the series, but:

cette expression simple de la flèche dynamique peut, comme je l'ai reconnu dans une multitude d'exemples, être identiquement obtenue

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
22	Guard								O 0.1	F 0.5				
	ELECTRICAL SYSTEM													
	GENERATOR/ ALTERNATOR		O						O 1.5	H 3.2				C-B
2201	Belt	C 0.05	1.0		O 0.5				O 1.0					
23	STARTER ASSEMBLY													
	Solenoid Assy		O 0.5						O 2.2	H 3.1				D-B
2301			O 0.5						O 1.1					E-B
24	IGNITION COMPONENTS													
	Distributor Assy		O	O 0.05					O 0.5	F 1.3				F-B
2401			O	0.05					O 0.5					
2402	Coil		O 0.5						O 0.5					
2403	Spark Plugs		O 0.8						O 1.5					
2404	Wires, Suppression		O 0.8						O 1.5	F 2.6				
25	SENDING UNITS													
	Sender								O 0.2					
2501									O 0.5					
2502	Wires								O 0.3					
2503	Lights	C 0.05												
26	ENGINE ASSEMBLY													
	Engine	C 0.05	O 1.5	O 1.0					F 12.0	H 3.3	H 46.0	D 80.0		G-B
2601		O 0.5							H 23.0	H 26.0				
2602	Crankcase			1.0										

(iv) At the join of two bars :

$$u = u_1, \quad \frac{du}{dz} = \frac{du_1}{dz}, \quad E\omega\kappa^2 \frac{d^2u}{dz^2} = E_1\omega_1\kappa_1^2 \frac{d^2u_1}{dz^2}.$$

(v) At the join of two bars where there is a weight of mass Q/g we must have :

$$\frac{Q}{g} \frac{d^2u}{dt^2} - \frac{d}{dz} \left(E\omega\kappa^2 \frac{d^2u}{dz^2} \right) + \frac{d}{dz} \left(E_1\omega_1\kappa_1^2 \frac{d^2u_1}{dz^2} \right) = 0,$$

together with the relations (iv) : see Saint-Venant's pp. 494-5.

[346.] Let us apply these results to the simple case of a prismatic bar supported terminally and struck by a weight Q with velocity V at its mid-point. Let the length of the bar be $2l$, its weight P , and $\tau^2 = Pl^3/(2gE\omega\kappa^2)$. We shall suppose the bar so placed that the impact is horizontal, or g may be put zero. Equation (i) of Art. 343, thus becomes :

$$\tau^2 \frac{d^2u}{dt^2} + l^4 \frac{d^4u}{dz^4} = 0 \dots\dots\dots(i),$$

together with the conditions :

$$u = 0, \quad \frac{d^2u}{dz^2} = 0, \quad \text{when } z = 0 \dots\dots\dots(ii),$$

$$\tau^2 \frac{d^2u}{dt^2} = \frac{Pl^3}{Q} \frac{d^2u}{dz^2}, \quad \frac{du}{dz} = 0, \quad \text{when } z = l \dots\dots\dots(iii).$$

Take as a particular integral :

$$z = Z_m \left\{ A'_m \frac{\tau}{m^2} \sin \frac{m^2 t}{\tau} + B'_m \cos \frac{m^2 t}{\tau} \right\}.$$

We find

$$m^4 Z_m = l^4 \frac{d^4 Z_m}{dz^4}.$$

The solution of this equation takes the well-known form first given by Euler, (see our Art. 52*) :

$$Z_m = C \sin \frac{mz}{l} + C_1 \cos \frac{mz}{l} + C_2 \sinh \frac{mz}{l} + C_3 \cosh \frac{mz}{l}.$$

To satisfy (ii) and the second of (iii) we must take

$$C_1 = C_3 = 0, \quad C_2 = -C \frac{\cos m}{\cosh m}.$$

Further $u = 0$ when $t = 0$, therefore we have finally u of the form

$$u = \sum \left. \begin{aligned} & \frac{\tau}{m^2} A_m Z_m \sin \frac{m^2 t}{\tau} \\ & Z_m = \frac{\sin (mz/l)}{\cos m} - \frac{\sinh (mz/l)}{\cosh m} \end{aligned} \right\} \dots\dots\dots(iv),$$

where

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild				
29	ACCESSORY DRIVE													
2901	Shaft									F				
2902	Housing									1.7				
									O	F				
									1.8	2.1				
30	CLUTCH ASSY													
3001	Clutch	O		O	O				F	F				I-H
		0.05		0.2	1.0				10.6	6.7				
31	CRANES, SHOVELS AND EARTH WORKING EQUIPMENT													
3101	Engine Clutch Shaft			O					F	F				
3102	Chain and Sprocket			0.5					5.4	4.0				
					O				F					
3103	Horizontal Swing Assy				1.0				2.3	H				
				O	O				F	12.0				
3104	Clutch Bands	C		1.0	1.0				10.0	H				
		0.05		O					F	1.6				
3105	Chain Assy			0.5					2.6					
		O							O					
3106	Boom Hoist Shaft Assy	0.05							1.8	H				
				O	O				H	7.0				
3107	Chain Assy			0.8	0.5				5.8					
		C			O				O					
3108	Brake and Clutch Bands	0.05			0.5				1.9	H				
					O				O	2.2				
3109	Independent Boom Hoist			O	1.0				4.3	H				
					O				12.0	8.7				
3110	Clutch and Brake Bands			0.9	O				O	F				
					O				1.2	2.9				
3111	Chain Assy				O				O					
					O				2.1	H				
3112	Boom Shaft Hoist Assy			O					5.8	6.1				
				0.05										

On evaluating this expression we find

$$A_m = \frac{4V}{m(\sec^2 m - \operatorname{sech}^2 m) + \frac{2P}{Qm}} \dots\dots\dots (\text{vi}).$$

Equations (vi) of this Article with (iv) and (v) of Art. 346 give the complete solution.

Is now this choice of initial velocities a proper one? Saint-Venant has defended it in the *Comptes rendus*, T. LXI. 1865, p. 43, against an objection raised to it. He says that if a small portion of the bar receive an initial velocity, Z_m will be nearly constant for this portion; accordingly equation (v) of the preceding Article gives us for the numerator of A_m , the expression $Z_m(l) \int \psi(z) d\eta$ where $\psi(z)$ is zero except over this small portion, where it has a value slightly less than V . But he remarks that the momentum possessed by this small portion and the weight Q ought to be exactly $\frac{Q}{g} V$, or $\int \psi(z) \frac{d\eta}{g} = \frac{Q}{g} V$.

[349.] We will now indicate the various problems which are dealt with analytically by Saint-Venant.

(a) In §§ 7-14 he treats as a general problem the cases when the bar is not prismatic (i.e. the rigidity $E\omega\kappa^2$ varies), when its ends are fixed in different fashions, when there are various bars or when one bar with a varying load forms the complete system. He shews that supposing the functions Z_m can be found which satisfy the equation :

$$\frac{d^2}{dz^2} \left\{ E\omega\kappa^2 \frac{d^2 Z_m}{dz^2} \right\} = m^4 \frac{p}{g} Z_m,$$

then the integral

$$\int Z_m Z_{m'} d\eta = 0,$$

where η represents the total weight of the system and the integration extends from one end to the other of the system; m and m' are two unequal roots of the characteristic equation in m which arises from the terminal and load conditions (p. 506).

The coefficients of the time function $A_m m^{-2} \sin m^2 t + B_m \cos m^2 t$ will be determined by equations similar to (v) of our Art. 347; A_m depending only on the initial velocities, B_m only on the initial displacements (p. 507).

The value of the denominator of these coefficients, i.e. $\int Z_m^2 d\eta$, can be obtained by the *differentiation* with regard to m of a certain function of Z_m and its fluxions with regard to z (p. 508). Compare Lord Rayleigh's *Theory of Sound*, Vol. I., pp. 209-10.

[350.] (b) The next special example given by Saint-Venant is that of a doubly built-in beam struck at the mid-point. He finds :

(1)	(2)	Assembly group	(3)										(4)	(5)	
			Maintenance functions												
			A	B	C	D	E	F	G	H	I	J			K
32			Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild	Tools and equipment	Remarks
	MISCELLANEOUS ITEMS														
	3201	Data Plates	0	---	---	---	---	---	---	0					
	3202	Caution Plates	0	---	---	---	---	---	---	0					
	3203	Mirrors	0	---	---	---	---	---	---	0					
	3204	Fire Fighting Equipment	0	---	---	---	---	---	---	0					
3205	Cables	0	---	---	---	---	---	---	---	0	F				
			0.05	---	---	---	---	---	---	1.8	1.2				

In both cases

$$A_m = \frac{4}{m} \frac{1}{\frac{dZ_m(a)}{dm} + \frac{2P}{m^2Q}}, \quad (\text{where obviously } Z_m(a) = Z'_m(b)),$$

and the characteristic equation is :

$$mZ_m(a) = \frac{2P}{Q}.$$

See pp. 514—71.

The results given in our Arts. 349—352 correspond with the *introduction of vibratory terms* to the solutions obtained by Cox's method in Art. 1437* and pp. 894—895, c (i), c (ii) and (b) respectively of our first volume. I have gone through Saint-Venant's analysis but not worked out independently his results.

[353.] We have next several cases in which the bar would not be immoveable if it were rigid, *i.e.* the bar is free or pivoted. Here the solution will have an algebraic part as well as a transcendental. This part can sometimes be obtained by retaining the root $m=0$, which has been divided out of the *characteristic* equation; but as a rule it is better to treat it separately as arising from the kinetic conditions of the problem and determine it by general dynamical principles such as the principle of momentum. I will briefly indicate Saint-Venant's treatment in the following example :

(e). A prismatic bar is struck transversely at its two terminals by bodies of weight q and Q moving with velocities v and V respectively. The length of the bar is l and its weight P ; the origin is taken at the end at which q strikes the bar. As before let us take

$$q + P + Q = q, \quad \frac{Pl^3}{gE\omega\kappa^2} = \tau'^2, \text{ as in Case (c) Art. 351.}$$

$$\text{We have then:} \quad \tau'^2 \frac{d^2u}{dt^2} + l^4 \frac{d^4u}{dz^4} = 0 \dots\dots\dots (i).$$

$$\text{For the free ends,} \quad \frac{d^2u}{dz^2} = 0, \text{ when } z = 0 \text{ or } l \dots\dots\dots (ii);$$

$$\left. \begin{aligned} \tau'^2 \frac{d^2u}{dt^2} + \frac{Pl^3}{q} \left(\frac{d^3u}{dz^3} \right) &= 0, \text{ when } z = 0 \\ \tau'^2 \frac{d^2u}{dt^2} - \frac{Pl^3}{Q} \left(\frac{d^3u}{dz^3} \right) &= 0, \text{ when } z = l \end{aligned} \right\} \dots\dots\dots (iii);$$

$u = 0$, for $t = 0$; $du/dt = v$ when $z = 0$, $= V$ when $z = l$, and equal zero for all other values of z at the epoch $t = 0$.

¹ Saint-Venant has a for our l , b for our a and b_1 for our b , EI for our $E\omega\kappa^2$, with other slight differences. I have altered his notation to agree with that of our first volume.

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
06	BATTERIES													
0601	Battery	C	O	C					O					A-B
		0.05	0.1	0.1					1.1					
0602	Cables	C							O	O				
									1.2	1.2				
07	BODY, CAB, HOOD ASSY													
0701	Cab								F	F				
									12.0	11.0				
0702	Door	C							O	F				
		0.05							1.5	3.0				
0703	Glass	C							O					
		0.05							4.0					
0704	Hood								O	F				
									1.1	2.2				
0705	Fender								O	F				
									1.3	3.4				
08	ACCESSORY ITEMS													
0801	Windshield Wiper	C							O	F				
		0.05							1.3	1.3				
0802	Windshield Washer	C							O					
		0.05							1.0					
0803	Wiper Blades	C							O	O				
		0.05							1.0					
0804	Data Plates	C							O					
		0.05							1.1					
09	GAGES													
0901	Instruments, Speed and Distance	C							O					
		0.05							2.5					
10	COOLING SYSTEM													
1001	Radiator			C					O	H				
				0.05					2.0	2.9				
1002	Hoses	C							O					
		0.05							2.1					

By straightforward integration we can shew that both these expressions $= \frac{2P}{m} \times \{\text{the function of } m \text{ to the left of equation (viii)}\}$, and therefore both $= 0$.

We have thus $\int (C + C' \frac{z}{l}) Z_m dq = 0$, or, *the algebraic part* has no influence on the determination of the value of A_m , which accordingly equals :

$$\frac{qvZ_m(0) + QVZ_m(l)}{qZ_m^2(0) + QZ_m^2(l) + \frac{P}{l} \int_0^l Z_m^2 dz},$$

as before. Saint-Venant gives on p. 525 the lengthy expressions for the numerator and denominator of this quantity. Equation (vii) gives us easily the numerator and all but the expression $\int_0^l Z_m^2 dz$ in the value of the denominator. The value of this integral I find to be :

$$\frac{1}{P} \left[P^2 \left\{ \frac{3}{m} (\sin m \cosh m - \cos m \sinh m) (1 - \cos m \cosh m) + (\sinh m - \sin m)^2 \right\} \right. \\ \left. + 2Pq \{ 6 \sin m \sinh m (1 - \cos m \cosh m) + m (\cosh m - \cos m) (\sinh m - \sin m) \} \right. \\ \left. + q^2 \{ 2m^2 (\sinh^2 m - \sin^2 m) + 6m \sin m \sinh m (\sin m \cosh m - \sinh m \cos m) \} \right].$$

There is one point, however, which we must notice, namely, that equations (iv) and (v) have only been proved for the *algebraic portions* of the solution, but they must hold generally. Substituting the full value of u , we find that these equations will still be satisfied, if :

$$q \Sigma A Z_m(0) + Q \Sigma A Z_m(l) + \Sigma \int_0^l A Z_m \frac{P}{l} dz = 0,$$

$$Ql \Sigma A Z_m(l) + \Sigma \int_0^l A Z_m \frac{Pz}{l} dz = 0.$$

But these equations are satisfied for each Z_m of the sum by reason of equations (ix).

I do not think this point is explicitly brought out by Saint-Venant, although in a long footnote pp. 521—4, he proves a more general proposition, namely :

On peut donc, dans les problèmes de mouvement des barres ou tiges élastiques libres ou pivotantes autour de points ou d'axes fixes, établir *séparément* la partie algébrique ou de solidification, et la partie transcendante ou vibratoire, de leur mouvement. Et même on peut généralement, ce qui est encore mieux, ne s'occuper que de celle-ci, qui seule intéresse le problème de la résistance de la matière, sans craindre que la non-prise en considération de celle-là soit une cause d'erreur (p. 524).

That is, the principles of kinetics will hold for the algebraic and transcendental parts of the solution separately as we have seen in the above example.

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
14	AIR LINES, COUPLINGS													
1401	Couplings	C							O					
1402	Lines	0.05							2.1					
		C							O					
		0.05							1.5					
15	FAN AND WATER PUMP													
1501	Pump, Water								O	F				
									2.5	2.3				
16	FAN ASSEMBLY													
1601	Bearing, Shaft, Pulley			O					O					
1602	Fan	C		0.05					1.1					
1603	Belt	0.05							O					
		C			O				0.6					
		0.05			0.5				O					
17	ELECTRICAL SYSTEM								1.5					
1701	Alternator		O						O	F				C-B
1702	Belt	C	0.5		O				1.5	3.2				
		0.05			0.2				O					
18	STARTER MOTOR								1.0					
1801	Solenoid		O						O	F				D-B
			0.5						2.2	3.2				E-B
			O						O					
			0.5						1.1					
19	IGNITION COMPONENTS													
1901	Distributor		O						O	F				F-B
1902	Coil	O	0.9						1.0	1.7				
		0.5							O					
1903	Spark Plugs	O			O				0.8					
		1.8			1.2				O					
1904	Wiring, Suppression	O							1.9					
		1.5							O	F				
									2.9	2.5				

We have to solve the equation

$$\tau^2 \left(\frac{d^3 u}{dz^3} - g \right) + l^4 \frac{d^4 u}{dz^4} = 0 \dots\dots\dots (i),$$

subject to the terminal conditions :

$$u = 0, \quad \frac{d^2 u}{dz^2} = 0 \text{ when } z = 0; \quad \frac{du}{dz} = 0 \text{ when } z = l \dots\dots\dots (ii),$$

$$Q + Q' - \frac{Q + Q'}{g} \frac{d^2 u}{dz^2} = -2E\omega\kappa^2 \frac{d^3 u}{dz^3} \left\{ \begin{array}{l} \text{when } z = l \dots\dots\dots (iii). \\ \tau^2 \left(\frac{d^3 u}{dz^3} - g \right) = \frac{Pl^3}{Q + Q'} \frac{d^3 u}{dz^3} \end{array} \right.$$

or,

Saint-Venant takes $u = u_1 + U$ where u_1 is independent of the time and chosen so that the gravitational terms disappear from equations (i) and (iii) i.e. :

$$-g\tau^2 + l^4 \frac{d^4 u_1}{dz^4} = 0; \quad -g\tau^2 (Q + Q') = Pl^3 \frac{d^3 u_1}{dz^3}, \text{ when } z = l.$$

$$\text{Thus we have} \quad \frac{d^3 u_1}{dz^3} = \frac{g\tau^2}{l^4} (z - l) - g\tau^2 \frac{Q + Q'}{Pl^3},$$

and integrating having regard to equations (ii), we find

$$u_1 = \frac{Pl^3}{48E\omega\kappa^2} \left\{ 8 \frac{z}{l} - 4 \left(\frac{z}{l} \right)^3 + \left(\frac{z}{l} \right)^4 \right\} + \frac{(Q + Q') l^3}{6E\omega\kappa^2} \left\{ \frac{3}{2} \frac{z}{l} - \frac{1}{2} \left(\frac{z}{l} \right)^3 \right\} \dots\dots\dots (iv).$$

The equations for U can now be easily solved, we deduce :

$$U = \sum Z_m \left(\frac{\tau}{m^2} A_m \sin \frac{m^2 t}{\tau} + B_m \cos \frac{m^2 t}{\tau} \right) \text{ where } Z_m = \frac{\sin \frac{mz}{l}}{\cos m} - \frac{\sinh \frac{mz}{l}}{\cosh m},$$

and the characteristic equation is :

$$m (\tan m - \tanh m) = 2P/(Q + Q') \dots\dots\dots (v).$$

In order to determine B_m and A_m we have, if $\phi(z)$ and $\psi(z)$ be respectively the initial shift and velocity corresponding to U ,

$$B_m = \frac{\int \phi(z) Z_m d\mathbf{q}}{\int Z_m^2 d\mathbf{q}}, \quad A_m = \frac{\int \psi(z) Z_m d\mathbf{q}}{\int Z_m^2 d\mathbf{q}}.$$

Now, $U_{t=0}$ = the initial value of $u - u_1$,

$\dot{U}_{t=0}$ = the initial value of $\dot{u} - \dot{u}_1$.

Further the initial value of u is the deflection due to the bar's own weight P and the load Q' attached.

$$\text{Hence we have:} \quad U_{t=0} = -\frac{Ql^3}{6E\omega\kappa^2} \left\{ \frac{3}{2} \frac{z}{l} - \frac{1}{2} \left(\frac{z}{l} \right)^3 \right\}.$$

Further $\dot{u}_1 = 0$, or $\dot{U}_{t=0} = V$ for the weight Q , whose abscissa is l , but for all other points $\dot{U}_{t=0} = 0$.

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
24	PISTON, CONNECTING RODS													
2408	Pistons, Rings, Pins	H 1.9							H 12.0					
2409	Rods, Connecting, Bearings	H 1.8				H 4.3			H 19.0	H 8.0				
25	VALVES, CAMSHAFT AND TIMING SYSTEM													
2501	Valves and Inserts								F 12.0	F 6.0				
2502	Arms, Rocker and Shaft								F 2.3	F 3.7				
2503	Tappets	F 0.9							F 6.0					
2504	Camshaft, Bearings and Timing Gear	F 0.9							F 16.0					
2505	Cover	O 1.0							H 2.5					
26	CLUTCH													
2606	Clutch Assy				O 1.1				F 7.3	F 3.9				I
2607	Clutch Release Mechanism Linkage, Pedal, Yoke Bearing				O 1.3				F 2.9					
27	TRANSMISSION													
2701	Transmission Assy	C 0.05		O 0.5					F 2.4	H 3.9				
2702	Transmission Control Assy	O 0.05							F 2.1	F 3.2				
	Transmission Cover	O 0.5							O 1.7					

I will indicate the method adopted by Saint-Venant. He supposes the arms of the beam each equal l , and that the forces applied to each extremity may be represented by a periodic term of the form $2Q \cos \Omega t$ which practically acts perpendicular to the beam. He justifies this assumption in the following manner :

Quant à la forme à assigner aux expressions des efforts verticaux q et q_1 exercés par les bielles, observons que si, du côté gauche, l'on appelle $-Q_1$ l'effort opérateur qu'exerce, tangentiellement à sa circonférence, une roue montée sur l'arbre du volant, et d'un rayon égal à la longueur r_1 de la manivelle, effort qui est rendu sensiblement constant lorsque le volant a un moment d'inertie de grandeur suffisante, et si Ω est la vitesse angulaire de la manivelle, on doit prendre, le temps t étant supposé compté à partir de l'instant où celle-ci est horizontale,

$$q_1 = -2Q_1 \cos \Omega t.$$

En effet q_1 devra avoir son maximum négatif pour l'angle $\Omega t = 0$, son maximum positif pour $\Omega t = \pi$: il devra être nul aux *points morts*, où $\Omega t = \pi/2$ et $3\pi/2$; enfin comme l'espace parcouru *verticalement* par le bouton de la manivelle pendant le temps dt est $\Omega r_1 dt \cos \Omega t$, le travail de la force q_1 pendant le parcours d'une demi-circonférence est $r_1 \int_{-\pi/2}^{+\pi/2} q_1 \cos \Omega t d(\Omega t)$; intégrale qui, si l'on y fait $q_1 = -2Q_1 \cos \Omega t$ est justement égale à $-Q_1 \pi r_1$, c'est-à-dire au travail de la force tangentielle constante $-Q_1$; en sorte que l'expression posée pour q_1 est bien ce qu'il faut pour que cette force verticale entretienne le mouvement du mécanisme en fournissant, à la fin de chaque période, le travail opérateur qui a été dépensé pendant sa durée (p. 549).

If we accept these values for the forces acting on the beam we can easily state the analytical conditions of the problem.

For the right arm: $\tau^2 \frac{d^2 u}{dz^2} + l^4 \frac{d^4 u}{dz^4} = 0,$
with $\frac{d^2 u}{dz^2} = 0$ and $E\omega\kappa^2 \frac{d^3 u}{dz^3} + q = 0$, when $z = l$ } (i).

For the left arm: $\tau^2 \frac{d^2 u_1}{dz_1^2} + l^4 \frac{d^4 u_1}{dz_1^4} = 0,$
with $\frac{d^2 u_1}{dz_1^2} = 0$ and $E\omega\kappa^2 \frac{d^3 u_1}{dz_1^3} + q_1 = 0$, when $z_1 = l$ } (ii).

When $z = z_1 = 0$, we must have $u = u_1 = 0$
 $\frac{du}{dz} = -\frac{du_1}{dz_1}$ and $\frac{d^2 u}{dz^2} = \frac{d^2 u_1}{dz_1^2}$ } (iii).

The initial conditions will be of the following kind:

When $t = 0$, $u = \phi(z)$, $\frac{du}{dt} = \psi(z)$, $u_1 = \phi_1(z_1)$, $\frac{du_1}{dt} = \psi_1(z_1)$... (iv).

We put also: $q = 2Q \cos \Omega t$, $q_1 = 2Q_1 \cos \Omega t$,

$$\Omega = n^2/\tau \text{ where } \tau^2 = Pl^3/(2gE\omega\kappa^2).$$

Now Saint-Venant takes $u = v + U$; $u_1 = v_1 + U_1$, and chooses v and v_1 so that q and q_1 shall disappear from the equations (i) and (ii), and shall separately satisfy all the conditions but (iv). Substituting u and u_1 in the equations (i) to (iii) we find they remain the same with the suppression of q and q_1 , that is: $\frac{d^3 U}{dz^3}$ and $\frac{d^3 U_1}{dz_1^3}$ vanish for $z = l$ and $z_1 = l$ respectively.

(1) Group No.	(2) Assembly group	(3) Maintenance functions											(4) Tools and equipment	(5) Remarks
		A	B	C	D	E	F	G	H	I	J	K		
		Inspect	Test	Service	Adjust	Align	Calibrate	Install	Replace	Repair	Overhaul	Rebuild		
32	BRAKES													
3201	Brake Service								F 8.7	F 6.3				
3202	Shoes								F 6.3	F 6.3				
33	PROPELLER SHAFTS													
3301	Shafts			O 0.1					O 2.3	F 3.6				
34	WHEELS, TRACK AND SUSPENSION													
3401	Torque Rod								H 7.3	H 6.2				
3402	Wheel Assembly	C 0.05							O 1.3					
3403	Tires and Tubes	C 0.05		C 0.1					O 3.3					
35	SPRINGS, SHOCK ABSORBERS													
3501	Torque Rods								H 12.6	H 13.2				
3502	Springs								F 16.0	F 8.2				
3503	Shock Absorbers	C 0.05							O 8.2					
36	FRONT AXLE													
3601	Axle Assembly								F 3.2	F 13.6				
3602	Differential Assy			O 0.1					F 8.3	H 12.2				
37	REAR AXLE													
3701	Axle Assy								F 3.2	H 4.6				

whether it has been previously noticed, or how far the dimensions of the beams of ordinary beam-engines ensure its fulfilment. We can throw it into a simpler form. Let f = the deflection of either extremity of the beam subject only to its own weight, then

$$f = \frac{Pl^3}{8E\omega k^3},$$

or
$$p < \frac{3.557}{4\pi} \sqrt{\frac{g}{f}} < .272 \sqrt{\frac{g}{f}}.$$

[360.] Saint-Venant does not draw any numerical conclusions from his results, which seem to me to suggest several points of importance, but only remarks finally :

Nous n'insisterons pas sur la solution, dont nous croyons avoir posé les bases, de ce problème complexe et délicat, solution qui, une fois développée, fournira la connaissance des plus grandes dilatations à contenir dans de justes limites, en réglant les dimensions de cet organe de mécanisme, soumis à des forces toujours variables, le faisant fléchir et vibrer alternativement dans deux sens opposés (p. 553).

[361.] We now pass to that portion of Saint-Venant's work which is peculiarly characteristic of the man, namely to the practically important numerical calculation of the results given in the previous articles. This occupies pp. 553—576 (§§ 32—42). The appalling amount of work that lies behind the numbers given can only be appreciated by those who have attempted similar calculations. The graphical representation of the results, although the plates have been long engraved, has not yet been published (see footnote p. 557)¹. The plaster model referred to in our Art. 105 will be found, however, of considerable service as offering a concise picture of the whole motion in a particular and most important case.

[362.] Saint-Venant treats in §§ 32—5 the problem of the doubly supported bar centrally struck: see our Arts. 104 and

¹ I much regret that it has been settled that these plates shall *not* be published, Saint-Venant at a date later than the footnote of 1883 having expressed an opinion that the curves ought to be plotted out for more frequent values of t/τ and z/l , as well as for a wider range of the ratio P/Q . It is to be hoped, having regard to the practical importance of the problem, that some one will be found willing to undertake the labour of the requisite numerical calculations.

Section III. SPECIAL TOOL AND SPECIAL TEST EQUIPMENT REQUIREMENTS

Reference code	Maintenance category	Nomenclature	Tool number
1-H 2-D	F,H O	Clutch Alinement Tool (Stub Shaft) Adjust Governor	SE20272-1 (81007)

Section IV. REMARKS

Reference code	Remarks
	CARRIER
A-B	On vehicle test
B-B	On vehicle test
C-B	On vehicle test
D-B	On vehicle test
E-B	On vehicle test
F-B	On vehicle test
G-B	Compression
H-I	Metalize and resize
I-I	Install ring gear only
J-B	On vehicle test
	CRANE
A-B	On vehicle test
B-B	On vehicle test
C-B	On vehicle test
D-B	On vehicle test
E-B	On vehicle test
F-B	On vehicle test
G-B	Compression
H-I	Metalize and resize
I-I	Install ring gear
J-D	On vehicle adjust

[363.] In § 33 Saint-Venant describes how he has traced the form taken by the rod at different intervals of time from $t = .1\tau$ up to $t = 2.25\tau$. From these curves he has deduced by graphical measurement the maximum curvatures and the times at which they occur. I reproduce some of his results in the accompanying table.

Resilience of a simple-supported beam, struck transversely.

When $P/Q =$	1/4	1/2	1	2	4
Maximum deflection	$1.091 V\tau$	$.739 V\tau$	$.477 V\tau$	$.297 V\tau$	$.167 V\tau$
at about $t =$	1.92τ	1.34τ	1.18τ	$.82\tau$	$.78\tau$
Maximum curvature	—	$2.60 V\tau/l^2$	$1.75 V\tau/l^2$	$1.30 V\tau/l^2$	—
at about $t =$	—	$\left\{ \begin{smallmatrix} 1.25\tau \\ 1.65\tau \end{smallmatrix} \right\}$	1.20τ	$\left\{ \begin{smallmatrix} .75\tau \\ 1.1\tau \end{smallmatrix} \right\}$	—

It will be noted that the instant of maximum deflection and that of maximum curvature do not coincide. Saint-Venant remarks that at each instant of time the maximum curvature is not central, although the maximum of the maxima for the various times as above tabulated is central.

The maximum stretch at any instant $= h/R$, where h is the distance of the 'outer fibre' from the neutral axis and $1/R$ is the curvature; this must be less than T_0/E , where T_0 gives the fail-limit: see our Art. 173. Hence our condition for non-failure is

$$T_0/E > h\beta V\tau/l^2,$$

or
$$V < \frac{1}{\beta} \frac{l^2 T_0}{E h \tau},$$

where $\tau^2 = \frac{Pl^3}{2gE\omega\kappa^2}$, and β must be put equal to 2.60, 1.75 or 1.30 according as P/Q equal $\frac{1}{2}$, 1 or 2.

Saint-Venant throws this into a slightly different form. By substituting τ and squaring we find:

$$\frac{QV^2}{2g} < \epsilon \cdot \frac{T_0^2}{E} 2l\omega \frac{\kappa^2}{h^2}.$$

Here T_0^2/E is the modulus of resilience, $2l\omega$ is the volume of the beam, κ^2/h^2 is in general a number independent of the linear

PART ONE

CRANE INDEX

	Paragraph	Page
A		
Accessory Drive Shaft and Housing Replacement	2-100	2-106
Administrative Storage	1-4	1-1
Air Cleaner Assembly Service and Replacement	2-78	2-84
Alternator	2-88	2-84
Belt adjustment	2-88b	2-94
Belt replacement	2-88c	2-94
Test	2-88d	2-94
Replacement	2-88e	2-95
Angle Indicator Replacement	2-48	2-47
B		
Backhoe Conversion	2-8	2-11
Backhoe Dipper Assembly	2-38	2-41
Backhoe Front Attachment	2-32	2-40
Service	2-32a	2-40
Dipper assembly pitch adjustment	2-32b	2-41
Repair and replacement	2-32c	2-41
Backstop Assembly Replacement	2-47	2-47
Batteries	2-53	2-51
Test	2-53b	2-51
Replacement	2-53c	2-51
Boom Hoist Brake and Clutch	2-108	2-111
Brake band removal	2-108b	2-111
Brake adjustment	2-108c	2-111
Clutch removal and replacement	2-108d	2-111
Clutch adjustment	2-108e	2-111
Boom Jib Mast Service and Replacement ..	2-44	2-45
Boom Maintenance	2-37	2-42
Bridle Assembly Service, Replacement and Repair	2-41	2-48
C		
Cables.		
Inspection and Repair	2-118	2-138
Replacement	2-45	2-45
Carburetor	2-83	2-88
Adjustment	2-83b	2-88
Removal and replacement	2-83c	2-88
Chain and Sprocket Adjustment	2-104	2-110
Clamshell and Dragline Bucket Service, Replacement and Repair	2-42	2-43
Clamshell Conversion	2-5	2-7
Conversion, Equipment	2-3	2-1
Backhoe	2-8	2-11
Clamshell	2-5	2-7
Crane	2-4	2-3
Dragline	2-6	2-9
Piledriver	2-7	2-10
Shovel	2-9	2-14
Counterweight Removal and Installation	2-116	2-137
Crane Boom Maintenance	2-37	2-42
Crane Conversion	2-4	2-3

calorifiques ou une sorte de *fusion*, à revenir de l'état fibreux ou à particules entrelacées, à l'état cristallin ou grenu ?

Des expériences, dont il est difficile de tracer le programme, mais où pourra jouer un rôle essentiel le mesurage de ces déformations persistantes regardées comme annonçant des commencements d'énervation et de désagrégation, seront nécessaires pour renseigner là-dessus la théorie qui devra, quels qu'en soient les résultats, se bien garder d'abdiquer son rôle et de renoncer aux considérations et patients calculs dont nous avons, à l'instar de nos maîtres, tâché de donner quelques spécimens.

The experiments on repeated load to which we shall refer later in this volume have thrown light on some at least of Saint-Venant's problems.

[365.] Saint-Venant passes in § 35 to the problem of our Art. 355 with $Q' = 0$. He remarks that the maximum value of the second part of u (Equation vi) treated as *consisting only of the first term* will be reached when

$$\tan \frac{m^2 t}{\tau} = - \frac{m^2 V \tau}{g \tau^2}.$$

He thus deduces for the time-terms' bracket the value

$$\frac{1}{m^2} \sqrt{(g \tau^2)^2 + (m^2 V \tau)^2}.$$

Hence the total deflection f produced by the blow is given by:

$$\begin{aligned} f &= \text{maximum of } u - \text{initial deflection due to weight of beam,} \\ &= \frac{Q l^3}{6 E \omega \kappa^2} + \frac{4}{m_0^4 + \frac{Q m_0^6}{2 P} (\sec^2 m_0 - \operatorname{sech}^2 m_0)} \sqrt{\left(\frac{P l^3}{2 E \omega \kappa^2} \right)^2 + (m_0^2 V \tau)^2}. \end{aligned}$$

Here m_0 is the first root of the characteristic Equation (v) of Art. 356, or since $Q' = 0$, of the Equation of Art. 362. Saint-Venant calculates on p. 562 the value of the coefficient of the radical and finds it has almost exactly for values of $P/Q = \frac{1}{4}, \frac{1}{2}, 1, 2, 4$ the same value, namely $Q/(3P)$, as when P/Q is extremely small.

$$\text{Hence} \quad f = f_s + \sqrt{f_s^2 + f_d^2},$$

where f_s is the statical deflection and

$$f_d = \frac{Q m_0^2}{3 P} V \tau \dots\dots\dots (i)$$

is the dynamical deflection of Art. 363 to a first approximation.

If $V = 0$, we have non-impulsive resilience, and $f = 2f_s$, a theorem of Young's.

[366.] In the next sections (§§ 36—7), Saint-Venant shews that the solution obtained on the hypothesis of Cox, that the form

	Paragraph	Page
G		
Gantry Inspection and Replacement	2-65	2-51
Glass Replacement	2-21	2-31
General Methods Used to Attain Proper Suppression	2-62	2-51

H**Heater and Switch:**

General	2-66a	2-61
Heater replacement	2-66b	2-61
Hook Block Service and Replacement	2-39	2-41
Hook Rollers:		
Adjustment	2-111c	2-111
General	2-111a	2-111
Removal and replacement	2-111b	2-111
Horn Replacement	2-56	2-51
Horn Wiring Replacement and Repair	2-57	2-51
Hose, Fittings and Tubing:		
Bleeding	2-70c	2-61
General	2-70a	2-61
Replacement	2-70b	2-61
Hull Wiring Harness Repair	2-50	2-41
Hydraulic Fluid Reservoir:		
General	2-72a	2-61
Replacement	2-72c	2-61
Service	2-72b	2-61

I

Identification and Tabulated Data	1-7	1-1
Idler Sprocket Replacement	2-27	2-3
Ignition Coil and Spark Plugs:		
Coil testing	2-91b	2-91
Coil replacement	2-91c	2-91
General	2-91a	2-91
Spark plug removal	2-91d	2-91
Spark plug test and adjust	2-91e	2-10
Spark plug installation	2-91f	2-10
Ignition Components		
Distributor assembly	2-90a	2-9
Distributor replacement and adjustment	2-90c	2-9
Distributor timing	2-90d	2-9
Points and condenser replacement	2-90b	2-9
Inspecting and Servicing the Equipment	2-1	2-
Installation	2-2	2-
Interference Suppression Components		

L

Lights:		
General	2-51a	2-1
Headlights	2-51b	2-1
Marker lights, dome lights, flood lights, and trouble lights	2-51c	2-1
Repair	2-51d	2-1

M

Machinery Mechanism Controls:		
Control levers and pedals	2-114a	2-1
Toggle lever linkage	2-114b	2-1
Maintenance Forms and Records	1-2	1
Maintenance Repair Parts	2-14	2-
Manifold and/or Control Valves:		
Hydraulic cylinder replacement	2-71b	2-
Master cylinder replacement	2-71a	2-

O

Operator's Seat Replacement	2-63	2-
-----------------------------------	------	----

The case given in our Vol. I., p. 896, (iii), Saint-Venant does not appear to have considered.

In a footnote he remarks that the second approximation will be far from exact in cases like those of Arts. 353 and 354 where the bar is free or pivoted at one point only.

[368.] Saint-Venant next proceeds to obtain Cox's formula by an elementary method. In a long footnote he gives the history and a proof of the principle of virtual shifts as applied to impulsive forces (pp. 577—82). His method is more general and simpler than Cox's, and as it gives a general expression for the value of the mass-coefficient γ , we indicate it here: see his pp. 578—87:

Let V be the initial impact-velocity of the weight Q ; let V_1 be the final impact velocity, or the velocity attained by Q when the beam begins to bend, let v_1 be the velocity of any point of the beam immediately after the impact, so that $v_1 = V_1$ at the mid-point. Take the shifts at the instant when the bending effect begins as the virtual shifts, then:

$$\left(\frac{Q}{g} V - \frac{Q}{g} V_1\right) V_1 dt - \int \frac{dP}{g} v_1 \cdot v_1 dt = 0,$$

the integral extending along the length of the beam. Dividing by $Q V_1^2 \frac{dt}{g}$, we have

$$V/V_1 = 1 + \frac{P}{Q} \int \left(\frac{v_1}{V_1}\right)^2 \frac{dP}{P},$$

or

$$V_1 = 1 + \frac{V}{\gamma} P/Q \left\{ \dots \dots \dots (i). \right.$$

where

$$\gamma = \int \left(\frac{v_1}{V_1}\right)^2 \frac{dP}{P}$$

The determination of γ thus depends entirely on the relation we choose between v_1 and V_1 . Cox's assumption is that: the relation between the statical shifts at the centre and any other point holds continuously during the motion. Thus if $u = U_1 \phi(z)$ be the relation,

$$\dot{u} = \dot{U}_1 \phi(z), \text{ or } v_1 = V_1 \phi(z).$$

This gives

$$\gamma = \int \{\phi(z)\}^2 \frac{dP}{P} \dots \dots \dots (ii).$$

Now the total kinetic energy of the system after impact must be

$$= \frac{Q}{g} \frac{V_1^2}{2} + \int \frac{v_1^2}{2} \frac{dP}{g} = \frac{Q V_1^2}{2g} \left(1 + \gamma \frac{P}{Q}\right) = \frac{Q V^2}{2g} / \left(1 + \gamma \frac{P}{Q}\right).$$

	Paragraph	Page
Suppression Leads:		
Removal -----	2-92a	2-100
Test -----	2-92b	2-100
Swing Brake:		
Adjust -----	2-109d	2-111
General -----	2-109a	2-111
Replacement of brake shoes -----	2-109b	2-111
Service -----	2-109c	2-111
Swing Lock Assembly -----	2-112	2-111
Switches and Wiring Replacement and Repair -----	2-55	2-58

T

Tabulated Data -----	1-7	1-1
Tachometer Drive -----	2-100	2-106
Tachometer Gage -----	2-58	2-58
Tagline Service, Adjustment and Repair -----	2-40	2-42
Testing of Radio Interference Suppression Components -----	2-24	2-30
Thermostat, Housing and Gasket:		
General -----	2-85a	2-92
Installation -----	2-85e	2-92
Removal -----	2-85c	2-92
Service -----	2-85b	2-92
Test -----	2-85d	2-92
Tools and Equipment -----	2-12	2-25
Transmission Service -----	2-75	2-82
Troubleshooting -----	2-20	2-27

W

Water Pump Replacement -----	2-86	2-92
Wiring Replacement -----	2-68	2-68

height, must be calculated by the methods of the memoir on flexure: see our Art. 69. But the addition of this material only introduces into γ a term of the order $\left(\frac{\text{height of end-section}}{\text{height of mid-section}}\right)^7$ which is negligible.

(d) On pp. 595—597 Saint-Venant deduces the result of our Art. 365 by Cox's method.

[371.] Leaving on one side for a moment Saint-Venant's §§ 52—55 we observe the following points in the concluding pages of this long *Note*:

(i) pp. 620—623. An examination of the results of the *Iron Commissioners' Report* and Hodgkinson's experiments: see our Arts. 943* and 1409—10*. This amounts to little more than the remark that Hodgkinson's $\frac{1}{2}$ is almost equal to the theoretical value $\frac{17}{35}$ of γ , and the statement that the values of the modulus obtained by applying the resilience formulæ to 67 experiments agree sufficiently well among themselves.

(ii) Saint-Venant remarks that $f_d = V \sqrt{\frac{f_s}{g} \frac{1}{1 + \gamma P/Q}}$ can be applied to a variety of cases of impact, as those of carriage springs, etc.; the value of γ being known $\left\{ \text{i.e. } \int \left(\frac{v_1}{V_1} \right)^2 \frac{dP}{P} \right\}$, so soon as we have assumed v_1/V_1 to have the ratio of the corresponding statical deflections (p. 624). At the same time the method of vibrations involving the transcendental series ought to be used to control this result wherever it is possible (p. 625).

(iii) *The values obtained by Cox's method for the maximum curvature and so for the maximum stretch are not sufficiently exact, and we must have recourse to the transcendental series or the numbers given in our Art. 363. Thus in the case of a simply supported beam centrally struck we should have by Cox's method $1/\rho = 3f_d/l^2$, but the values deduced from the Table in our Art. 363 give*

$$3f_d/l^2 \times \left\{ \begin{array}{l} 1.183 \\ 1.252 \\ 1.486 \end{array} \right\} \text{ according as } P/Q = \left\{ \begin{array}{l} \frac{1}{2} \\ 1 \\ 2 \end{array} \right\}.$$

Saint-Venant gives an empirical formula for these *three* cases

PART TWO

CARRIER INDEX

	A	Paragraph	
Accelerator and Throttle Controls:			
General	4-42a		
Removal, replacement, and repair	4-42b		
Administrative Storage	3-4		
Air Cleaner Assembly:			
General	4-38a	4-1f	
Removal	4-38c	4-1f	
Installation	4-38b	4-1f	
Air Reservoirs:			
General	4-78a	4-4f	
Installation	4-78c	4-4f	
Removal	4-78b	4-4f	
Alcohol Evaporator			
General	4-77a	4-4f	
Installation	4-77d	4-4f	
Removal	4-77b	4-4f	
Repair	4-77c	4-4f	
Alcohol Evaporator Strainer Removal and Replacement	4-91	4-61	
Alternator:			
Belt adjustment	4-49b	4-	
General	4-49a	4-	
Removal and replacement	4-49c	4-a	
Testing	4-49d	4-2f	
Axle, Transmission, and Transfer Case Controls	4-68	4-40	
B			
Batteries and Cables	4-26	4-7	
Boom Rest Removal and Replacement	4-92	4-61	
Brake Chambers			
Installation	4-76b	4-4f	
Removal	4-76a	4-4f	
C			
Cab Sheet Metal and Fenders	4-30	4-11	
Carburetor	4-40	4-1f	
Adjustment	4-40d	4-1f	
General	4-40a	4-1f	
Installation	4-40c	4-1f	
Removal	4-40b	4-1f	
Carrier Engine Service and Test	4-64	4-3f	
Compressor Assembly:			
Adjustment	4-90a	4-5f	
Installation	4-90c	4-6f	
Removal	4-90b	4-6f	
D			
Data Plates	4-33	4-1	
Description	3-6	3-	
Destruction of Army Material to Prevent Enemy Use	3-3	3-	
Detailed Lubrication Instructions			

Hence if we find that value for P/Q (say, n) for which the numerical coefficient of $\frac{h}{\kappa} \frac{V}{\Omega}$ is sensibly unity, we may say that the maximum stretch for that and all other larger values of P/Q is given by the expression $\frac{h}{\kappa} \frac{V}{\Omega}$, and takes place in the first instant of the impact.

See the Note in the *Comptes rendus* 1882, p. 1044, or Boussinesq, *Application des Potentiels à l'étude... du mouvement des solides élastiques*, p. 486.

From some slight calculations I have made I believe this result will be reached when P/Q lies between 2.5 and 3. If this be true, it very much limits the range within which there is any necessity to apply the transcendental series to ascertain the curvature and so the condition of failure. We may then, I think, say that after $P/Q = 2.5$, the maximum-stretch is always given by the formula $\frac{V}{\Omega} \frac{h}{\kappa}$ or is independent of the mass of Q .

[372.] We must now return to pp. 597—619 of Saint-Venant's note which we have omitted above. They deal with *Willis' Problem* or the resilience of a horizontal beam subjected to a travelling load: see our Arts. 1417*—1422*. We shall include under our discussion the memoirs of Phillips¹ and Renaudot², because these writers have made mistakes in their analysis, which have been rectified by Saint-Venant. With Saint-Venant's additions and rectifications we shall thus be able to give the reader a more complete view of the advance made by the problem since the memoir of Stokes: see our Arts. 1276*—1291*.

[373.] We will first give the equations for the complete problem as propounded by Phillips. Let P be the weight, $2l$ the length, $E\omega\kappa^2$ the rigidity of the beam, u the shift to the right and u_1 to the left of the travelling load Q (distant $x = Vt$ from the right-hand terminal) of points distant z and z_1 from right and left-hand ends of the beam. We shall suppose the beam simply supported.

¹ *Calcul de la résistance des poutres droites telles que les ponts, etc. sous l'action d'une charge en mouvement. Annales des mines*, t. vii., pp. 467—506, 1855.

² *Étude de l'influence des charges en mouvement sur la résistance des ponts métalliques à poutres droites. Annales des ponts et chaussées*, t. i. 4^e série, pp. 145—204, 1861.

	Paragraph	Page
Ignition Coil:		
General	4-52a	4-31
Installation	4-52d	4-32
Removal	4-52b	4-31
Test	4-52c	4-32
Inspecting and Servicing the Equipment	4-1	4-1
Installation and Equipment Conversion	4-2	4-1
Intake and Exhaust Manifolds:		
Installation	4-56c	4-33
Inspection and repair	4-56b	4-33
Removal	4-56a	4-33
Interference Suppression Components	4-15	4-5
L		
Lights:		
Repair of Wiring	4-23b	4-7
Replacement	4-23a	4-7
M		
Maintenance Forms and Records	3-2	3-1
Maintenance Repair Parts	4-7	4-1
Muffler and Pipes Replacement	4-44	4-23
O		
Oil Cooler and External Lines:		
Crankcase breather and vent tubing	4-60f	4-36
External lines	4-60e	4-36
General	4-60a	4-35
Oil cooler installation	4-60d	4-36
Oil cooler removal	4-60b	4-35
Oil cooler service	4-60c	4-36
Operator's Seat Replacement	4-29	4-11
Outriggers Repair and Replacement	4-94	4-61
P		
Pintle Hook Repair and Replacement	4-98	4-61
Power Steering Pump and Reservoir:		
Belt tension adjustment	4-70c	4-41
Pump replacement	4-70b	4-41
Removal	4-70a	4-41
Reservoir replacement	4-70d	4-41
Preventive Maintenance Checks and Services	4-11	4-1
Propeller Shafts		
General	4-83a	4-56
Removal and installation	4-83b	4-56
R		
Radiator and Cap		
General	4-35a	4-16
Radiator cap test and replacement	4-35b	4-16
Radiator installation	4-35d	4-17
Radiator removal	4-35c	4-16
Rear Axle Differential:		
General	4-85a	4-58
Service	4-85b	4-58
Reinstallation after Movement		4-5
Replacement of Suppression Components	4-16	3-1
Reporting of Errors	3-5	
Rocker Arms:		
Adjustment	4-66b	4-39
General	4-66a	4-39
S		
Scope	3-1	3-1

Let us assume

$$u = u' + \frac{1}{\beta} U, \quad u_1 = u'_1 + \frac{1}{\beta} U_1,$$

substitute and neglect $\left(\frac{1}{\beta}\right)^2$. We find from Equations (i) by dividing out by $1/\beta$:

$$\left. \begin{aligned} \frac{d^4 U}{dz^4} &= \frac{3P}{8l^3 E \omega \kappa^2} (2l - x) z = \frac{3P}{8l^3 E \omega \kappa^2} x_1 z, \text{ if } x_1 = 2l - x, \\ \frac{d^4 U_1}{dz_1^4} &= \frac{3P}{8l^3 E \omega \kappa^2} x x_1 \end{aligned} \right\} \dots \text{(vi).}$$

Equations (ii) now become:

$$\left. \begin{aligned} U &= 0, \text{ and } \frac{d^2 U}{dz^2} = 0 \text{ when } z = 0, \\ U_1 &= 0, \text{ and } \frac{d^2 U_1}{dz_1^2} = 0 \text{ when } z_1 = 0 \end{aligned} \right\} \dots \text{(vii).}$$

Integrating (vi) we have

$$\left. \begin{aligned} U &= \frac{3Px_1}{8l^3 E \omega \kappa^2} \left\{ \frac{z^5}{5!} + \frac{Cz^3}{3!} + Dz \right\} \\ U_1 &= \frac{3Px}{8l^3 E \omega \kappa^2} \left\{ \frac{z_1^5}{5!} + C_1 \frac{z_1^3}{3!} + D_1 z_1 \right\} \end{aligned} \right\} \dots \text{(viii).}$$

These satisfy equations (vii).

It remains to determine C, D, C_1, D_1 , by Equations (iii) and (iv). But they become:

$$\left. \begin{aligned} (U)_{z=0} &= (U_1)_{z_1=x_1}, \quad \left(\frac{dU}{dz} \right)_{z=0} + \left(\frac{dU_1}{dz_1} \right)_{z_1=x_1} = 0, \\ \left(\frac{d^2 U}{dz^2} \right)_{z=0} &= \left(\frac{d^2 U_1}{dz_1^2} \right)_{z_1=x_1} \end{aligned} \right\} \dots \text{(ix).}$$

Further, (iv) may be written

$$\left(\frac{d^3 U}{dz^3} \right)_{z=0} + \left(\frac{d^3 U_1}{dz_1^3} \right)_{z_1=x_1} = \frac{Q\beta}{E \omega \kappa^2 g} \frac{d^2 y}{dt^2} = \frac{3}{2l} \frac{d^2 y}{dx^2}.$$

Now $y = u_1$ when $z = x_1$, or after a short reduction

$$y = \frac{Qx^2 x_1^2}{6l E \omega \kappa^2} + \frac{Pxx_1(4l^2 + xx_1)}{48l E \omega \kappa^2}.$$

Since $x_1 = 2l - x$, we have: $\frac{d(xx_1)}{dx} = 2(l - x) = x_1 - x$, and thus find

$$\frac{3}{2l} \frac{d^2 y}{dx^2} = \frac{1}{E \omega \kappa^2} \left\{ 2Q - \frac{3xx_1}{l^2} \left(Q + \frac{P}{8} \right) \right\}.$$

	Paragraph	Page
Tire and tube removal -----	4-87c	4-58
Wheel installation -----	4-87b	4-58
Wheel removal -----	4-87a	4-58
Window Glass -----	4-28	4-11
Windshield Wipers:		
Blade replacement -----	4-32b	4-12
Low air pressure valve -----	4-32c	4-12
Motor replacement -----	4-32a	4-12
Wiring Harness Repair -----	4-19	4-6

Adding $\frac{1}{\beta} U$ to u' of (v) we obtain the complete solution to this degree of approximation. We may write down the complete value thus obtained, u_1 being obviously given by interchanging x_1 with x and z_1 with z :

$$u = \frac{Qx_1}{12lE\omega\kappa^2} \{x(2x_1 + x)z - z^3\} + \frac{P}{48lE\omega\kappa^2} (8l^2z - 4lz^3 + z^4) \\ + \frac{1}{\beta} \frac{3Px_1}{8l^3E\omega\kappa^2} \left[\frac{z^5}{120} + \frac{z^3}{6} \left\{ -\frac{x}{6}(x + 5x_1) + \frac{4Q}{3P}(2l^2 - 3xx_1) \right\} \right. \\ \left. + \frac{z}{360} \{x_1x(58x^2 + 8x_1^2 + 92xx_1) + 7x^4\} + \frac{2z}{9} \frac{Q}{P} (3xx_1 - 2l^2)x(x + 2x_1) \right] \dots (\text{xiv}^a).$$

This embraces both Saint-Venant's forms (ω) and (ω'), p. 615 *g*, and I have tested them, and find they agree with this result.

If $x = x_1 = z = l$ we find:

$$u_l = \frac{Ql^3}{6E\omega\kappa^2} + \frac{5Pl^3}{48E\omega\kappa^2} + \frac{1}{\beta} \left\{ \frac{Ql^3}{6E\omega\kappa^2} + \frac{9}{80} \frac{Pl^3}{E\omega\kappa^2} \right\} \\ = \frac{Ql^3}{6E\omega\kappa^2} \left(1 + \frac{1}{\beta} \right) + \frac{5Pl^3}{48E\omega\kappa^2} \left(1 + \frac{27}{25} \frac{1}{\beta} \right) \dots (\text{xiv}^b).$$

If we put $P = 0$, we obtain Stokes' result: see our Art. 1287*. It will be observed that these expressions for the bending-moment and the deflection have been reached *without any assumption as to the value of the ratio Q/P* .

[377.] We may make some remarks on the above results. Phillips first gave the complete equations for the problem and included the effect of the inertia of the beam (i.e. the terms in P). He obtained erroneous coefficients, however, for the terms in $1/\beta$. The correct values were first obtained by Saint-Venant, and his process is much shorter than Phillips'. In § 54 (pp. 609—612) Saint-Venant gives an elementary proof of the value of the bending moment in our equation (xiii^a). He does not make use of the general differential equations, but calculates and sums the parts of the bending moment due to statical loading, to the 'centrifugal force' of the travelling load $\left(\frac{Q}{g} \frac{V^2}{\rho} \right)$, and to the mass accelerations $\left(\frac{P}{2lg} \frac{dz}{dt} \frac{d^2u}{dt^2} \right)$ of each element dz of the beam. The parts due to the last two influences are of the first order in $1/\beta$ and so we use in them the statical values for $1/\rho$, the curvature, and u . We may ask whether the expressions in Equations (xiii^b) and (xiv^b) give the maxima values of M and u .

By Order of the Secretary of the Army:

CREIGHTON W. ABRAMS
General, United States Army
Chief of Staff

Official:

VERNE L. BOWERS,
Major General, United States Army,
The Adjutant General.

Distribution:

To be distributed in accordance with DA Form 12-25B (qty rqr block no. 334) Organization Maintenance requirements for Cranes, Truck Mounted.

☆ U. S. GOVERNMENT PRINTING OFFICE - 1968 O - 201-421 (80254)

where
$$\frac{X}{Z} \Big\} = 5 \frac{8l^3 \left\{ \frac{x}{z} \right\} - 4l \left\{ \frac{x^3}{z^3} \right\} + \left\{ \frac{x^4}{z^4} \right\}}{16l^4},$$

and the deflection at z is given by

$$u = Z \left(\nu + \frac{Pl^3}{15E\omega\kappa^2} \right) \dots\dots\dots(ii),$$

thus determining what is represented by ν .

The equation (i) shews that ν is of the same order as Q/P , and Stokes solves it on the supposition that Q/P is so small that quantities of the order $(Q/P) \times \nu$ may be neglected, i.e. he omits the last term of the bracket on the right-hand side. Saint-Venant, however, seeks a value of ν by approximations in which powers of $1/\beta$ are neglected, in other words, *he makes no assumptions as to the value of the ratio Q/P except that P/Q is not to be extremely large.* In most practical cases Q and P will not be very far from equality, and the exception is accordingly legitimate. If we take

$$r^2/l^2 = \frac{31}{252} \frac{P}{Q} \frac{1}{\beta}, \text{ where } \frac{1}{\beta} = \frac{2QlV^2}{3gE\omega\kappa^2},$$

we have the small quantities in terms of which Saint-Venant solves the equation (i).

It will be found that $r/2l = 1/q$, where q is the constant of Stokes' investigation: see our Art. 1290*.

$$\left\{ \text{We may note that } S_1 \text{ of Stokes} = \frac{Pl^3}{6E\omega\kappa^2}, \right.$$

$$\left. \text{and } f'_s \text{ of Saint-Venant} = \frac{5Pl^3}{48E\omega\kappa^2} \right\}.$$

[380.] The solution found by Saint-Venant is given by:

$$\begin{aligned} \nu = & \frac{Ql^3}{15E\omega\kappa^2} \left(X - r^2 \frac{d^2X}{dx^2} + \frac{1}{\beta} X \frac{6lx - 3x^2 - 2l^2}{l^2} \right) \\ & - \frac{Ql^3}{6E\omega\kappa^2} \left\{ 1 - \frac{2}{\beta} + 3 \left(\frac{r}{l} \right)^2 \right\} \frac{r}{l} \sin \frac{x}{r} \dots\dots\dots(iii). \end{aligned}$$

See his p. 615 e.

Substituting for ν in equation (ii) of Art. 379 we have u . For the central-deflection as the load passes we find

$$\begin{aligned} u_l = & \left. \begin{aligned} & \frac{125}{128} \frac{Ql^3}{6E\omega\kappa^2} \left(1 + \frac{1}{\beta} \right) + \frac{5Pl^3}{48E\omega\kappa^2} \left(1 + \frac{155}{336} \frac{1}{\beta} \right) \\ & - \frac{25l^3}{96E\omega\kappa^2} \left[Q \left(1 - \frac{2}{\beta} \right) + \frac{31}{84} \frac{P}{\beta} \right] \frac{r}{l} \sin \frac{l}{r} \end{aligned} \right\} \dots(iv). \end{aligned}$$

The algebraic terms as might be supposed owing to the method of approximation, are not exactly the same as in (xiv^b). The factor $\frac{125}{336}$ instead of 1 is not, however, important, while the factor $\frac{155}{336}$ instead of

$\frac{27}{25}$ occurs only in terms involving $1/\beta$. Saint-Venant concludes that the algebraic terms given by the first method are the correct ones, and that we may add to them the expression

$$-\frac{25l^3}{96E\omega\kappa^2} \left[Q \left(1 - \frac{2}{\beta} \right) + \frac{31}{84} \frac{P}{\beta} \right] \frac{r}{l} \sin \frac{l}{r},$$

in order to approximately account for the periodic terms. This result and (iv) differ from those of Saint Venant (α') p. 615 h and (δ') p. 615 i but seem to me to give the correct value of u_i .

The corresponding part to be subtracted from the bending moment at the centre as the load passes it is

$$-\frac{5}{8} l \left[Q \left(1 - \frac{2}{\beta} \right) + \frac{31}{84} \frac{P}{\beta} \right] \frac{r}{l} \sin \frac{l}{r}$$

This again differs from Saint Venant's results (β') p. 615 h and (ϵ') p. 615 j. By a misprint which has escaped correction he has the fraction $\frac{27}{24}$ where I have $\frac{27}{24}$.

[381] The last extension of the problem which we shall consider here is that of Renaudot, who does not deal with the case of an isolated load (as a locomotive) but with that of a continuous load (as a train of trucks or carriages) crossing the bridge. Let p be the weight per foot run of the girder, p' that of the travelling load the head of which is distant $x = Vt$ from the right hand terminal. In this case equations (i) of our Art. 373, are replaced, on the supposition that the train is longer than bridge, by

$$E\omega\kappa^2 \frac{d^4 u}{dz^4} - (p + p') = -\frac{p}{g} \frac{d^2 u}{dt^2} - \frac{p'}{g} \frac{d^2 w}{dt^2} \quad (1)$$

$$E\omega\kappa^2 \frac{d^4 u_1}{dz_1^4} - p = -\frac{p}{g} \frac{d^2 u_1}{dt^2} = -\frac{pV}{g} \frac{d^2 u_1}{dx^2} \quad (11)$$

Here w is the shift of the element $(p'/g) dz$ of the train on the bridge, and z is to be put in w equal to Vt less the constant distance between the given element and the head of the train. Thus while the z in du/dt is not a function of t , that in dw/dt is to be treated as a function of t , or since $x = Vt$ we may write

$$\frac{dw}{dt^2} = V \left\{ \frac{d^2 u}{dx^2} + 2 \frac{du}{dx dz} + \frac{d^2 u}{dz^2} \right\}$$

Thus the first equation becomes

$$E\omega\kappa^2 \frac{d^4 u}{dz^4} - (p + p') = -\frac{pV}{g} \frac{d^2 u}{dx^2} - \frac{p'V}{g} \left\{ \frac{d^2 u}{dx^2} + 2 \frac{du}{dx dz} + \frac{d^2 u}{dz^2} \right\} \quad (111)$$

Starting from equations (11) and (111) with the necessary terminal conditions for each portion of the girder, we may proceed as in our Arts. 373—376 to determine first the statical and then the first dynamical

approximation. The maximum bending-moment will be greatest when the load just covers the whole girder. It is then given by

$$M_t = \frac{p+p'}{2} l^2 \left(1 + \frac{5}{8} \frac{1}{\beta'}\right), \text{ where } \frac{1}{\beta'} = \frac{p' l^2 V^2}{g E \omega \kappa^2}.$$

Similarly we may deduce the bending-moment when the train is headed by a locomotive of weight Q followed by a train of weight p' per foot-run. In order to obtain the position of the maximum bending-moment, it will, as in Art. 377, be sufficient to find the values of z and x which give the maximum moment for the statical approximation. These are

$$x = 2l - Q/p', \quad z = l \left\{1 + \frac{Q}{2pl} \cdot \frac{Q}{2(p+p')l}\right\},$$

and they must be substituted in the second approximation involving the terms in $1/\beta$ and $1/\beta'$ (see pp. 616—618).

Renaudot neglects the term $2 \frac{d^2 u}{dx dz}$ in equation (iii) as of small importance. He arrives at a wrong value, i.e. $\left(1 + \frac{2}{3\beta'}\right)$, for the bracket in the value of the bending-moment.

[382.] Saint-Venant remarks that Phillips has also treated the case of a travelling load crossing a beam *doubly built-in*. His solution is, however, erroneous, as has been pointed out both by Bresse and Saint-Venant, nor would it be of much value to correct his results, for built-in ends (*encastrements*) never produce their full effect, and such alternating motions as occur with travelling loads in bridges soon deprive such ends of nearly all their effect (see p. 619 and our Arts. 733* and 188).

There is also a reference on p. 619 to Bresse's exact solution for the case of a bridge across which a very long train is continuously moving with velocity V , so that the bridge takes up a permanent form. In this case equation (iii) of Art. 381 becomes

$$E \omega \kappa^2 \frac{d^4 u}{dz^4} - (p+p') = - \frac{p V^2}{g} \frac{d^2 u}{dz^2},$$

and we can find an exact solution. It gives for the maximum bending-moment

$$M_t = \frac{p+p'}{2} l^2 \cdot 2\beta'' \{\sec \sqrt{1/\beta''} - 1\}, \text{ where } \frac{1}{\beta''} = \frac{p l^2 V^2}{g E \omega \kappa^2},$$

or, $M_t = \frac{p+p'}{2} l^2 \left(1 + \frac{5}{12} \frac{1}{\beta''}\right)$ approximately.

This result is less than that of our Art. 381, or we see that the dangerous instant is that in which the train just covers the whole

bridge It is then producing impulsive changes in the elastic line of the bridge, and not a steady form of the elastic line as in the case of a very long train imagined to be continuously crossing

[383] We now reach Saint-Venant's last contribution to the annotated Clebsch namely, the *Note finale du § 73*, pp 689—752 It is entitled *Theorie de la flexion et des autres petites déformations des plaques élastiques planes minces, tirée directement des équations différentielles générales de l'équilibre d'élasticité des solides*

The *Note* consists of four essentially distinct parts (i) a deduction of the general elastic body-shift equations for thin plates, (ii) a full discussion of the contour conditions, and the controversy with regard to them, (iii) the solutions for statical equilibrium of thin circular plates, and (iv) a reproduction with extensions of Navier's results obtained in the memoir of 1820, and hitherto only published in extract see our Arts 258*—64* I propose to deal somewhat at length with this *Note* as it forms distinctly the best treatment hitherto given for thin plates Saint-Venant adopts Boussinesq's method (see the memoirs of 1871 and 1879 in the Chapter devoted to that elastician) but with certain important modifications He describes Clebsch's investigation, notwithstanding that it starts with unnecessary simplifications, as "obscure, indirect and very complex" I think the terms are fully warranted

[384] Let the mid plane of the plate be taken as that of $z = 0$ and let its faces be $z = \pm \epsilon$ We shall endeavour to deduce from the three body stress equations, a single equation involving only the stresses \widehat{xx} , \widehat{yy} , \widehat{xy} and given quantities Let the body stress equations be

$$\left. \begin{aligned} \frac{d\widehat{xx}}{dx} + \frac{d\widehat{yx}}{dy} + \frac{d\widehat{zx}}{dz} + X &= 0 \\ \frac{d\widehat{xy}}{dx} + \frac{d\widehat{yy}}{dy} + \frac{d\widehat{zy}}{dz} + Y &= 0 \\ \frac{d\widehat{xz}}{dx} + \frac{d\widehat{yz}}{dy} + \frac{d\widehat{zz}}{dz} + Z &= 0 \end{aligned} \right\} \quad (1)$$

Adding the third of these equations to the differentials of the first two with regard respectively to x and y , such differentials before addition being multiplied by z , we find

$$z \left\{ \frac{d\widehat{xx}}{dx} + 2 \frac{d\widehat{xy}}{dx dy} + \frac{d\widehat{yy}}{dy} \right\} + \frac{d}{dz} \left\{ \frac{d}{dx} (z \widehat{yz}) + \frac{d}{dy} (z \widehat{yz}) + \widehat{zz} \right\} + z \left(\frac{dX}{dx} + \frac{dY}{dy} \right) + Z = 0$$

Integrating this from $z = +\epsilon$ to $z = -\epsilon$,

$$\int_{-\epsilon}^{+\epsilon} \frac{d^2 \widehat{xx}}{dx^2} z dz + 2 \int_{-\epsilon}^{+\epsilon} \frac{d^2 \widehat{xy}}{dx dy} z dz + \int_{-\epsilon}^{+\epsilon} \frac{d^2 \widehat{yy}}{dy^2} z dz + \phi(xy) = 0 \dots (ii),$$

where

$$\begin{aligned} \phi(xy) = Z' + (\widehat{zz})_{+\epsilon} - (\widehat{zz})_{-\epsilon} + \frac{dX''}{dx} + \frac{dY''}{dy} + \frac{d}{dx} [\epsilon \{(\widehat{xz})_{+\epsilon} + (\widehat{xz})_{-\epsilon}\}] \\ + \frac{d}{dy} [\epsilon \{(\widehat{yz})_{+\epsilon} + (\widehat{yz})_{-\epsilon}\}] \dots (iii), \end{aligned}$$

$$\text{and} \quad Z' = \int_{-\epsilon}^{+\epsilon} Z dz, \quad X'' = \int_{-\epsilon}^{+\epsilon} z X dz, \quad Y'' = \int_{-\epsilon}^{+\epsilon} z Y dz;$$

the subscripts denote as usual that the stresses are to be given their values at the surfaces $z = \pm \epsilon$.

All the terms in the expression $\phi(xy)$ are thus known quantities.

[385.] The question of what further assumptions we shall make now arises. Those usually made are the following:

1°. $\widehat{zz} = 0$. (This is made even by Boussinesq and Lévy, the most recent writers on the subject.)

2°. $s_x = z/\rho$, $s_y = z/\rho'$, where ρ and ρ' are the two curvatures of the plate at its mid-plane for the point x, y . It follows that:

$$\left. \begin{aligned} s_x &= -z \frac{d^2 w_0}{dx^2} \\ s_y &= -z \frac{d^2 w_0}{dy^2} \end{aligned} \right\} \dots \dots \dots (iv),$$

where w_0 is the normal shift of the point x, y of the mid-plane.

Using the stress-strain relations for three planes of elastic symmetry (see our Art. 117 (a)), we easily find from 1° and 2°:

$$\left. \begin{aligned} \widehat{xx} &= (a - e'^2/c) s_x + (f' - d'e'/c) s_y \\ \widehat{yy} &= (f' - d'e'/c) s_x + (b - d'^2/c) s_y \end{aligned} \right\}, \text{ and } \frac{d^2 \widehat{xy}}{dx dy} = -2zf \frac{d^4 w_0}{dx^2 dy^2} \dots (iv^h).$$

Substituting in (ii) and integrating we have the equation:

$$(a - e'^2/c) \frac{d^4 w_0}{dx^4} + 2(2f + f' - d'e'/c) \frac{d^4 w_0}{dx^2 dy^2} + (b - d'^2/c) \frac{d^4 w_0}{dy^4} = \frac{3}{2\epsilon^3} \phi(xy) \dots (v).$$

This becomes in the case of elastic isotropy parallel to the mid-plane:

$$\left(\frac{d^2}{dx^2} + \frac{d^2}{dy^2} \right)^2 w_0 = \frac{3}{2H\epsilon^3} \phi(xy) \dots \dots \dots (vi),$$

where $H = a - e'^2/c$, the plate-modulus of our Art. 323.

This is the equation obtained by Lagrange, Poisson and Cauchy: see our Arts. 284*, 484* and 640*.

[386] On pp 696—700 (§§ 4—5) Saint Venant considers what are the arguments in favour of the assumptions 1^o and 2^o of the previous Article. He remarks that owing to the thinness of the plate, the normal or z variations of both the stresses and the strains must be large as compared with the longitudinal variations. Hence as a first approximation, we have the fluxions with regard to x and y of both stress and strain components more and more nearly zero as the plate is taken thinner and thinner. It is sufficient however to assume that those of \widehat{xx} , \widehat{xy} and \widehat{yy} are zero or small. The body stress equations then give

$$\frac{d\widehat{xx}}{dz} + X = 0, \quad \frac{d\widehat{zy}}{dz} + Y = 0$$

Thus the stresses \widehat{xx} , \widehat{zy} on integration will be of the order ϵ , or as Saint Venant puts it

Si on les intègre par rapport à la petite coordonnée z on voit que les composantes \widehat{xx} , \widehat{zy} n'ont de valeurs, à l'intérieur d'un tronçon ou élément de plaque, que celles qu'elles peuvent avoir sur une des deux bases, plus ce qui vient des forces A , B , agissant sur sa masse. Ces forces locales n'ont qu'une influence insignifiante qui n'est presque rien en comparaison de ce qui vient à la fois de toutes les forces agissant sur le reste de la plaque ainsi que sur ses bords par les réactions des appuis ou autrement, et dont les effets accumulés se transmettent au tronçon à travers ses quatre faces latérales, ce qui s'applique surtout aux composantes agissant horizontalement (pp 697—8)

The third body stress equation, however shows that \widehat{zz} is very small as compared with \widehat{xx} , \widehat{zy} because these quantities occur with *lateral variation*, hence \widehat{zz} is doubly small as compared with \widehat{xx} , \widehat{xy} and \widehat{yy} . Thus we may take $\widehat{zz} = 0$ as all writers have hitherto done.

[387] This argument is not, perhaps, quite convincing. It would seem at first sight better to assume \widehat{zz} to be *very approximately a function of x , y only*. The expressions then for \widehat{xx} , \widehat{xy} , \widehat{yy} would contain together with the terms linear in z , terms not involving z , but functions of x , y only. These terms disappear when we substitute them in equation (11) and integrate between $z = +\epsilon$ and $-\epsilon$. But here a new difficulty arises, suppose the surface of the plate $z = +\epsilon$ subjected to a load $\widehat{z} = \chi(x, y)$. This will make no change in the first three terms of equation (11) of Art 384 although we cannot suppose $\widehat{z} = 0$, but it will lead to a difficulty with regard to the expression $\phi(xy)$.

This expression contains terms of the form $(-)\epsilon$ and $(-)\epsilon$, the former $= \chi(x, y)$ and the latter is zero. Hence it follows that \widehat{z} must vary with z from $+\epsilon$ to $-\epsilon$. Saint Venant (p 699) says we must take $(-)\epsilon = \chi(x, y)$ and put $(-)\epsilon = 0$, but this seems to me to destroy the basis of his approximation. Possibly, following the hint he gives on p 700, the true method is to consider that, when the dimensions of a body are very small in any sense, then a *surface load* in the same sense will give the same strains perpendicular to that sense as the *integral of a body force* also in that sense. Thus the flexure equations for a beam are

deduced on the assumption that there is *no* lateral stress, yet we do not hesitate to use them for beams subject to continuous lateral load¹. I conclude then that it is best to put $\bar{z}z$ always *zero* (and not a definite value as Saint-Venant does on p. 699) and assume, when plates have a surface distribution of load, that the result of such load so far as the shifts of the points of the mid-plane are concerned can be represented by a body force, whose integral between the faces is equivalent per unit area to the surface load.

[388.] In § 5 Saint-Venant shews that from the assumptions, or approximate values :

$$\frac{d(\sigma_{xz}, \sigma_{xy})}{dx, dy} = 0, \quad \frac{d^2 s_z}{dx^2, dxdy, dy^2} = 0 \dots\dots\dots(a),$$

(which are less restrictive than $\sigma_{xz} = \sigma_{xy} = 0$, and $\bar{z}z = 0$) we can deduce results embracing those of our Art. 385, 1^o and 2^o.

Writing the first set of expressions at length we easily find that :

$$\frac{ds_x}{dz} = -\frac{d^2 w}{dx^2}, \quad \frac{ds_y}{dz} = -\frac{d^2 w}{dy^2}, \quad \frac{d\sigma_{xy}}{dz} = -2\frac{d^2 w}{dxdy} \dots\dots(\beta).$$

Whence we see by differentiating with regard to z that :

$$\frac{d^2 s_x}{dz^2} = -\frac{d^2 s_z}{dx^2} = 0, \quad \frac{d^2 s_y}{dz^2} = -\frac{d^2 s_z}{dy^2} = 0, \quad \frac{d^2 \sigma_{xy}}{dz^2} = -2\frac{d^2 s_z}{dxdy} = 0.$$

Thus the second z fluxions of s_x, s_y, σ_{xy} are zero, or we may write w_0 for w in (β) ; it follows that we must have :

$$s_x = s_x^0 - z\frac{d^2 w_0}{dx^2}, \quad s_y = s_y^0 - z\frac{d^2 w_0}{dy^2}, \quad \sigma_{xy} = \sigma_{xy}^0 - 2z\frac{d^2 w_0}{dxdy} \dots\dots(\gamma),$$

where the zero affixed refers the quantity to the mid-plane.

Saint-Venant remarks of the equations (γ) :

Elles montrent, comme conséquence cinématique des égalités posées (a) , que les dilatations de petites droites matérielles horizontales de direction donnée varient *linéairement* le long de toutes les lignes primitivement verticales, des divers points desquelles ces petites horizontales auraient été tirées.

Il convient de remarquer en passant que cela n'entraîne nullement, comme conséquence, que ces verticales resteront exactement droites et normales au feuillet moyen devenu courbe, car leurs petits intervalles horizontaux peuvent très bien croître linéairement avec z quoiqu'elles soient devenues courbes, si celles qui sont voisines affectent des inflexions pareilles, ainsi qu'il arrive pour les *sections* voisines, dans les tiges éprouvant la *flexion* dite *inégaie* (p. 699 : see our Art. 325).

It will be noted that this treatment brings out the real difficulties and assumptions of the problem, better than those which start by

¹ Since writing the above I have obtained the *full* solution for a simply supported beam continuously loaded on its upper surface, I find $\bar{z}z$ is of the *same* order as xy , where x is the direction of the axis of the beam, and z the direction of the load.

assuming the strain energy to be a function of the curvatures and so deduce by Lagrange's, or other, method the fundamental equation of the plate see Thomson and Tait, § 639, or Lord Rayleigh's *Sound*, Vol I, § 214

I may remark that the equations (ii) and (iii) obtained in Art. 384 still hold if 2ϵ the thickness of the plate changes gradually with x and y

[389] Returning to the body stress equations of Art 384, let us integrate the first two between the limits $\pm\epsilon$ of z We note first, however, since

$$\begin{aligned}\widehat{xx} &= \left(a - \frac{e'^2}{c}\right) s_x + \left(f' - \frac{d e'}{c}\right) s_y \\ &= \left(a - \frac{e'^2}{c}\right) \left(s_x^0 - z \frac{d^2 w_0}{dx^2}\right) + \left(f' - \frac{d e'}{c}\right) \left(s_y^0 - z \frac{d^2 w_0}{dy^2}\right)\end{aligned}$$

by equations (γ) of Art 388, that

$$\left. \begin{aligned} \int_{-\epsilon}^{+\epsilon} \widehat{xx} dz &= 2\epsilon \left\{ \left(a - \frac{e'^2}{c}\right) s_x^0 + \left(f' - \frac{d e'}{c}\right) s_y^0 \right\} = 2\epsilon \widehat{xx}_0, \\ \text{similarly } \int_{-\epsilon}^{+\epsilon} \widehat{xy} dz &= 2\epsilon \widehat{xy}_0, \text{ and } \int_{-\epsilon}^{+\epsilon} \widehat{yy} dz = 2\epsilon \widehat{yy}_0 \end{aligned} \right\} \quad (1),$$

where the affixed $_0$ denotes a mid plane value

Hence from the integration of the body stress equations we obtain

$$\left. \begin{aligned} 2\epsilon \left(\frac{d\widehat{xx}_0}{dx} + \frac{d\widehat{xy}_0}{dy} \right) + (\widehat{zx})_{+\epsilon} - (\widehat{zx})_{-\epsilon} + X' &= 0, \\ 2\epsilon \left(\frac{d\widehat{xy}_0}{dx} + \frac{d\widehat{yy}_0}{dy} \right) + (\widehat{zy})_{+\epsilon} - (\widehat{zy})_{-\epsilon} + Y' &= 0, \end{aligned} \right\} \quad \begin{array}{l} \text{where } X' \text{ and } Y' \text{ are the} \\ \text{integrals of } X \text{ and } Y \\ \text{across the plate} \end{array}$$

Substitute the values of the mid plane stresses in terms of the mid plane shifts u_0, v_0 and we have

$$\left. \begin{aligned} 2\epsilon \left\{ \left(a - e' / c\right) \frac{d^2 u_0}{dx^2} + (f + f' - d e' / c) \frac{d^2 v_0}{dx dy} + f \frac{d^2 u_0}{dy^2} \right\} + (\widehat{zx})_{+\epsilon} - (\widehat{zx})_{-\epsilon} + X' &= 0 \\ 2\epsilon \left\{ (b - d' / c) \frac{d^2 v_0}{dy^2} + (f + f' - d e' / c) \frac{d^2 u_0}{dx dy} + f \frac{d^2 v_0}{dx^2} \right\} + (\widehat{zy})_{+\epsilon} - (\widehat{zy})_{-\epsilon} + Y' &= 0 \end{aligned} \right\} \quad (11)$$

These equations reduce in the case of isotropy parallel to the plate to the simpler forms (p 702)

$$\left. \begin{aligned} 2\epsilon \left\{ H \frac{d}{dx} \left(\frac{du_0}{dx} + \frac{dv_0}{dy} \right) + f \frac{d}{dy} \left(\frac{du_0}{dy} - \frac{dv_0}{dx} \right) \right\} + (\widehat{zx})_{+\epsilon} - (\widehat{zx})_{-\epsilon} + X &= 0 \\ 2\epsilon \left\{ H \frac{d}{dy} \left(\frac{du_0}{dx} + \frac{dv_0}{dy} \right) - f \frac{d}{dx} \left(\frac{du_0}{dy} - \frac{dv_0}{dx} \right) \right\} + (\widehat{zy})_{+\epsilon} - (\widehat{zy})_{-\epsilon} + Y &= 0 \end{aligned} \right\} \quad (111),$$

where H is the plate modulus of Art 323

It will be noticed that these equations for the shifts u_0, v_0 are independent of that for w_0 , or the transverse and longitudinal strains exercise no influence on each other This has already been remarked by Cauchy and Poisson see our Arts 483* and 640*

[390.] In §§ 8—10 Saint-Venant considers the effect of great stresses parallel to the mid-plane on the normal shift w_0 . Thus he obtains what may be called the terms due to the action of the plate as a transverse membrane. He finds that in the function $\phi(xy)$ of equations (v) and (vi) of Art. 385 we must include the expression :

$$2\epsilon \left(\frac{d^2 w_0}{dx^2} \widehat{xx}_0 + 2 \frac{d^2 w_0}{dxdy} \widehat{xy}_0 + \frac{d^2 w_0}{dy^2} \widehat{yy}_0 \right) - \frac{dw_0}{dx} \{ (\widehat{xx})_{+\epsilon} - (\widehat{xx})_{-\epsilon} + X' \} \\ - \frac{dw_0}{dy} \{ (\widehat{xy})_{+\epsilon} - (\widehat{xy})_{-\epsilon} + Y' \}.$$

From the sum of this expression and $Z' + (\widehat{xx})_{+\epsilon} - (\widehat{xx})_{-\epsilon}$ equated to zero we deduce the equation for the transverse equilibrium of a membrane. In its present form it has been obtained on the supposition that 2ϵ is constant; the alterations for 2ϵ variable are indicated by Saint-Venant in a footnote, p. 704.

[391.] In § 13 Saint-Venant commences his treatment of the contour conditions. Let α be the angle between the normal to the mid-plane contour at any point and the axis of x , let P, Q, R be the components of the applied load parallel to the axes, and ds, dn elements of the arc and normal of the mid-plane contour.

We find at once :

$$P = \widehat{xx} \cos \alpha + \widehat{yx} \sin \alpha, \quad Q = \widehat{xy} \cos \alpha + \widehat{yy} \sin \alpha, \quad R = \widehat{xz} \cos \alpha + \widehat{yz} \sin \alpha.$$

Hence by equations (i) of Art. 389, we have :

$$2\epsilon (\widehat{xx}_0 \cos \alpha + \widehat{yx}_0 \sin \alpha) = \int_{-\epsilon}^{+\epsilon} P dz = P',$$

$$2\epsilon (\widehat{xy}_0 \cos \alpha + \widehat{yy}_0 \sin \alpha) = \int_{-\epsilon}^{+\epsilon} Q dz = Q'.$$

Substitute for the mid-plane stresses in terms of the shifts and we have :

$$2\epsilon \left\{ \left[(a - e'^2/c) \frac{du_0}{dx} + (f' - d'e'/c) \frac{dv_0}{dy} \right] \cos \alpha + f' \left(\frac{du_0}{dy} + \frac{dv_0}{dx} \right) \sin \alpha \right\} = P',$$

$$2\epsilon \left\{ \left[(f' - d'e'/c) \frac{du_0}{dx} + (b - d'^2/c) \frac{dv_0}{dy} \right] \sin \alpha + f' \left(\frac{du_0}{dy} + \frac{dv_0}{dx} \right) \cos \alpha \right\} = Q'.$$

These are the sufficient and necessary contour conditions for longitudinal strain. When there is elastic isotropy parallel to the mid-plane they reduce to

$$2\epsilon \left\{ \left[H \left(\frac{du_0}{dx} + \frac{dv_0}{dy} \right) - 2f \frac{dv_0}{du_0 dx} \right] \cos \alpha + f' \left(\frac{du_0}{dy} + \frac{dv_0}{dx} \right) \sin \alpha \right\} = P'.$$

[392.] Saint-Venant next turns to the more controverted conditions involving the normal shift w_0 . He proceeds to calculate M_s, M_n and R' , the first two symbols representing the moments round tangent

and normal respectively to the mid-plane contour for the load applied to the strip $2\epsilon \times ds$, and R' being the total shearing load on the same strip.

$$\begin{aligned}\text{Now } M_s &= \int_{-\epsilon}^{+\epsilon} (P \cos \alpha + Q \sin \alpha) z dz = P' \cos \alpha + Q' \sin \alpha \\ &= -\frac{2\epsilon^3}{3} \{ \widehat{xx}'' \cos^2 \alpha + 2\widehat{xy}'' \sin \alpha \cos \alpha + \widehat{yy}'' \sin^2 \alpha \},\end{aligned}$$

where, r and p being any two directions,

$$\widehat{rp}'' \times \frac{2\epsilon^3}{3} = - \int_{-\epsilon}^{+\epsilon} \widehat{rp} z dz,$$

and as before, a single dash on the loads denotes an integration with regard to z from $+\epsilon$ to $-\epsilon$, and a double dash an integration after multiplication by z , between the same limits. Substituting from equations (1) of Art 389 for the stresses we find

$$\begin{aligned}M_s &= -\frac{2\epsilon^3}{3} \left\{ \left[(a - e'^2/c) \frac{d^2 w_0}{dx^2} + (f' - d'e'/c) \frac{d^2 w_0}{dy^2} \right] \cos^2 \alpha + 4f \frac{d^2 w_0}{dx dy} \sin \alpha \cos \alpha \right. \\ &\quad \left. + \left[(b - d'^2/c) \frac{d^2 w_0}{dy^2} + (f' - d'e'/c) \frac{d^2 w_0}{dx^2} \right] \sin^2 \alpha \right\}\end{aligned}$$

Or, for elastic isotropy parallel to the mid plane

$$M_s = -\frac{2\epsilon^3}{3} \left[(H - 2f) \left(\frac{d^2 w_0}{dx^2} + \frac{d^2 w_0}{dy^2} \right) + 2f \frac{d^2 w_0}{dn^2} \right] \quad (1)$$

This first condition is not the subject of discussion but has been generally accepted

[393] In a similar manner we find

$$\begin{aligned}M_n &= Q' \cos \alpha - P' \sin \alpha, \\ &= \frac{2\epsilon^3}{3} \{ \sin \alpha \cos \alpha (\widehat{xx}'' - \widehat{yy}'') - (\cos^2 \alpha - \sin^2 \alpha) \widehat{xy}'' \},\end{aligned}$$

where

$$\widehat{xx}'' - \widehat{yy}'' = \left(a - f' + \frac{d' - e'}{c} e' \right) \frac{d^2 w_0}{dx^2} - \left(b - f' - \frac{d' - e'}{c} d' \right) \frac{d^2 w_0}{dy^2},$$

or, $\quad = (a - f') \left(\frac{d^2 w_0}{dx^2} - \frac{d^2 w_0}{dy^2} \right)$ with elastic isotropy parallel to the mid plane

$$\text{And again,} \quad \widehat{xy}'' = 2f \frac{d^2 w_0}{dx dy}$$

$$\begin{aligned}\text{Further } R' &= \int_{-\epsilon}^{+\epsilon} R dz = \cos \alpha \int_{-\epsilon}^{+\epsilon} \widehat{zx} dz + \sin \alpha \int_{-\epsilon}^{+\epsilon} \widehat{zy} dz \\ &= \cos \alpha \left[\epsilon \{ (\widehat{zx})_+ + (\widehat{zx})_- \} + \Lambda'' - \frac{2\epsilon^3}{3} \left(\frac{d\widehat{xx}''}{dx} + \frac{d\widehat{yy}''}{dy} \right) \right] \\ &\quad + \sin \alpha \left[\epsilon \{ (\widehat{zy})_+ + (\widehat{zy})_- \} + Y' - \frac{2\epsilon^3}{3} \left(\frac{d\widehat{xy}''}{dx} + \frac{d\widehat{xy}''}{dy} \right) \right],\end{aligned}$$

where

$$\frac{\widehat{dxx}''}{dx} + \frac{\widehat{dxy}''}{dy} = (a - e'^2/c) \frac{d^3w_0}{dx^3} + (2f + f' - d'e'/c) \frac{d^3w_0}{dx dy^2},$$

$$\frac{\widehat{dxy}''}{dx} + \frac{\widehat{dyy}''}{dy} = (b - d'^2/c) \frac{d^3w_0}{dy^3} + (2f + f' - d'e'/c) \frac{d^3w_0}{dx^2 dy},$$

reducing respectively to the differentials with regard to x and y of $H \left(\frac{d^2w_0}{dx^2} + \frac{d^2w_0}{dy^2} \right)$, when there is elastic isotropy parallel to the mid-plane.

These results can be easily deduced by integrating \widehat{zx} and \widehat{yz} from expressions of the form :

$$\begin{aligned} \widehat{zx} &= \frac{d(z \cdot \widehat{zx})}{dz} - z \frac{d\widehat{zx}}{dz} \\ &= \frac{d(z \cdot \widehat{zx})}{dz} + z \left(\frac{d\widehat{zx}}{dx} + \frac{d\widehat{xy}}{dy} + X \right). \end{aligned}$$

I have reproduced the values of M_s , M_n and R' , because they are the most complete hitherto given and will be useful for reference hereafter.

[394.] Saint-Venant adopts Thomson and Tait's 'reconciliation' (see our Art. 488*) and replaces the couples M_n by an additional shear $\frac{dM_n}{ds}$ added to R' . In other words he equates the contour load to the couple M_s and the shear $R' + \frac{dM_n}{ds}$.

He attributes this method of reconciling Kirchhoff and Poisson to Boussinesq (p. 715). There are two points which arise in this reconciliation which deserve to be noted. The first objection to the replacement of the couples M_n by a distributed shear is that referred to in our Art. 488*, namely that the Kirchhoff contour conditions could not be used for the case of a *discontinuous* distribution of shearing force and normal couple. Saint-Venant replies to this :

S'il y avait des forces extérieures isolées, appliquées en certains points de ce cylindre et faisant couples autour de ses normales, elles seraient capables d'y imprimer à la plaque, entre ces points, des torsions finies. Aucun auteur n'a supposé l'existence de pareilles forces, qui sont capables de produire des altérations permanentes de la contexture de la matière de la plaque si elles agissent avec une certaine intensité sur des portions excessivement petites de sa surface. Tous supposent que les forces se répartissent sur des surfaces d'étendue finie ; et nous ne considérerons même, ainsi qu'ils l'ont tous fait, que des forces agissant sur le cylindre contournant d'une manière continue et graduelle (p. 714).

The second objection is that due to M Lévy (see our Art 397), he holds that when the couple M_n is due to vertical forces we can replace it by a shear distribution perpendicular to the plate, but that when it is due to horizontal forces this is not allowable. This point has been discussed at length by Boussinesq (see the Chapter we have devoted to that elastician), and Saint-Venant sums up his arguments in the following words

Si ces couples sont formés par des forces horizontales tangentes au cylindre, agissant en sens opposés, les unes au dessus, les autres au dessous de la périphérie moyenne, et si la plaque est supposée avoir une épaisseur comparable aux deux autres dimensions, ces couples pourront conspirer pour produire certains effets d'ensemble dont nous ne nous occupons pas, tels qu'une *inflexion* imprimée à toutes les arêtes, et accompagnée de cette torsion générale autour d'un axe vertical dont il a été traité dans les chapitres relatifs aux tiges. Mais si la plaque est extrêmement mince, ces sortes de déformations sont négligeables. Les couples de forces horizontales dont il s'agit s'exerçant d'une manière continue sur les arêtes successives, ne produiront que ces torsions *locales* dont nous nous occupons ici, et leurs effets seront sensiblement les mêmes que ceux de couples de forces verticales *de même moment*, qu'on leur substituerait en faisant tourner ceux là de 90 degrés, substitutions qui se font, comme on sait, dans la statique élémentaire des corps solides (p 714)

We may I think conclude that

1° The shift-equation ((vi) of Art 385) for thin plates is only an approximation and depends upon the assumptions that $\widehat{zz} = 0$ and that s_x, s_y, σ_{xy} contain *only the first power* of z , as in Eqns (γ) of our Art 388. These assumptions are, however, probable and the approximation is close when the thickness of the plate is extremely small.

2° To the same degree of approximation the *two* boundary conditions of Kirchhoff are true for very thin plates.

3° When the plate has a thickness small but not indefinitely small compared with its other dimensions, the equation of Lagrange can under certain conditions still hold, but it is not then legitimate to replace the normal couple by a distribution of shearing-load.

This latter conclusion is *opposed* to Saint-Venant's opinion on p 720. He shews that if the following conditions hold

$$\frac{d^2 \widehat{z}}{dx^2, dxdy, dy^2} = \frac{d'(\sigma_{xx} \sigma_{yy})}{dx^2, dxdy, dy^2} = \frac{d^3 s_z}{dx^3, d^2 xdy, d^2 ydx, dy^3} = 0,$$

we can still deduce Lagrange's equation, but these conditions allow of a definite but small thickness for the plate. He then states that Kirchhoff's contour conditions remain true. Now it seems to me that we can no longer replace normal couples by vertical shearing-loads, for this will cause a difference in the strain of the plate to a distance into its material of the same order as its thickness, and this distance is no longer vanishingly small as compared with the other dimensions of the plate.

[395.] Saint-Venant now proceeds to an interesting summary of other writers' treatment of the problem of thin plates. He notes that Poisson and Cauchy assume that the stresses can be expanded in powers of z giving convergent series. From this assumption Saint-Venant deduces equations (γ) of our Art. 388. He remarks of this assumption that it has never found supporters—*elle n'est pas suffisamment fondée, et peut se trouver souvent en défaut*. I must notice, however, that Saint-Venant's own assumptions of our Art. 385 really lead to the expression of the stresses \widehat{xx} , \widehat{xy} and \widehat{yy} as *linear functions* of z , (see equations (iv^b) of Art. 385 and (γ) of Art. 388,) while from the first two body stress-equations we obtain by integration for \widehat{xx} and \widehat{yy} *quadratic functions* of z together with terms $-\int_0^z X dz$ and $-\int_0^z Y dz$ which cases be linear in z . Thus Poisson's is only a too general statement of the
 SAINT-VENANT himself.

[396.] Saint-Venant appears to think that the terms $Z' + \frac{dX''}{dx} + \frac{dY''}{dy}$ which occur in the function $\phi(xy)$ of his result (see equation (iii) of our Art. 384) do not agree with the similar terms obtained by Poisson (see equation (9) of our Art. 484*) and Cauchy (see Equation (70) of our Art. 640*). With proper transformation of symbols these are:

$$2\epsilon \left\{ \left[Z + \frac{\epsilon^2}{6} \frac{d^2 Z}{dz^2} \right]_{z=0} + \frac{\epsilon^2}{3} \left[\frac{d}{dz} \left(\frac{dX}{dx} + \frac{dY}{dy} \right) \right]_{z=0} \right\}.$$

Now Poisson and Cauchy assume forms such as:

$$X = X_0 + z \left(\frac{dX}{dz} \right)_0 + \frac{z^2}{2} \left(\frac{d^2 X}{dz^2} \right)_0 + \text{etc.},$$

$$\therefore X'' = \int_{-\epsilon}^{+\epsilon} X dz = \frac{2\epsilon^3}{3} \left(\frac{dX}{dz} \right)_0 + \text{terms involving fifth and higher powers of } \epsilon.$$

Similarly

$$Z' = \int_{-\epsilon}^{+\epsilon} Z dz = 2\epsilon Z_0 + \frac{2\epsilon^3}{6} \left(\frac{d^3 Z}{dz^3} \right)_0 + \text{terms involving fifth and higher powers of } \epsilon,$$

$$\text{or } Z' + \frac{dX''}{dx} + \frac{dY''}{dy} = 2\epsilon \left\{ \left[Z + \frac{\epsilon^2}{6} \frac{d^3 Z}{dz^3} \right]_{z=0} + \frac{\epsilon^2}{3} \left[\frac{d}{dz} \left(\frac{dX}{dx} + \frac{dY}{dy} \right) \right]_{z=0} \right\}$$

+ terms involving fifth and higher powers of ϵ , which may be neglected

Thus their assumption does not lead to an error in this point as Saint-Venant suggests. It seems to me also that Poisson and Cauchy's hypothesis is more valid than that of Clebsch and other writers who simply put $\widehat{zx} = \widehat{zx} = \widehat{zy} = 0$

[397] At this point Saint-Venant notices Maurice Lévy's memoir of 1877 (see *Journal de Liouville*, 1877, pp 219—306, or our discussion of the memoir later). Lévy investigates what are the possible solutions for a prism with two free faces, when the shifts u, v, w are supposed capable of being expressed in a series of ascending powers of z and the forces acting on the lateral sides of the prism have a given resultant load. It follows that the stresses will now be given in ascending powers of z , and that there is no limitation as to the thickness of the plate (or height of the prism). Lévy finds (1) that the powers of z in u, v, w and in $\widehat{xx}, \widehat{xy}$ and \widehat{yy} cannot surpass the third, (2) that the stress $\widehat{zz} = 0$ throughout the prism, and (3) that the stresses $\widehat{xz}, \widehat{yz}$ contain only second powers of z , which appear through the factor $(\epsilon^2 - z^2)$.

It will be seen that these results of Lévy give the proper limitation to Cauchy and Poisson's hypothesis, and shew clearly its relation to Saint-Venant's assumptions. Saint-Venant on pp 726—733 deals with another part of Lévy's memoir, namely, the term he has introduced into the values of the shifts u and v in order that the *three* surface conditions of Poisson may be satisfied for thin plates. This term is periodic in z , but Saint-Venant following Boussinesq rejects it as producing effects only of the same order as those we are neglecting in our approximation. We shall return to this point later when treating of Lévy's memoir and his controversy with Boussinesq.

[398] Saint-Venant now turns to the concrete application of the thin plate formulae. He first deals with circular plates and obtains the following results

Let there be a uniform surface load p per unit of area.

(i) *When the contour simply rests on a ring of its own radius a .*

Shift of mid-plane at radius r :

$$w_0 = \frac{3pa^4}{128H\epsilon^3} \left[\left(\frac{r}{a} \right)^4 - 1 - \frac{4H-2f}{H-f} \left\{ \left(\frac{r}{a} \right)^2 - 1 \right\} \right].$$

Central Shift $f_0 = \frac{3H-f}{H-f} \frac{3pa^4}{128H\epsilon^3}.$

(ii) *When the contour is built-in.*

$$w'_0 = \frac{3pa^4}{128H\epsilon^3} \left\{ 1 - 2 \left(\frac{r}{a} \right)^2 + \left(\frac{r}{a} \right)^4 \right\},$$

$$f'_0 = \frac{3pa^4}{128H\epsilon^3}.$$

Further we find that:

When the plate is simply supported: the line of inflexion, given by $\frac{d^2w_0}{dr^2} = 0$, is determined by $r = a \sqrt{\frac{2H-f}{3(H-f)}}$, or $= .931 a$ if $H/f = 8/3$, as in the case of uniconstant isotropy.

When it is built-in: the line of inflexion is determined by $r = .5773 a$, and the line of zero-moment (i.e. where $M_s = 0$) by $r = a \sqrt{\frac{H-f}{2H-f}}$, or $= .6202 a$ in the case of uniconstant isotropy.

The maximum stretches in the two cases, given by the greatest values of $s_r = -z \frac{d^3w_0}{dr^3}$, are respectively:

$$s_0 = \frac{2H-f}{H-f} \cdot \frac{3pa^2}{32H\epsilon^2} \left(= \frac{117pa^2}{1280\mu\epsilon^2}, \text{ for uniconstant isotropy} \right),$$

$$s'_0 = \frac{3pa^2}{16H\epsilon^2} \left(= \frac{9pa^2}{128\mu\epsilon^2}, \text{ for uniconstant isotropy} \right).$$

The conditions for the fail-limit are thus easily written down. Compare with these results those of Poisson in our Arts. 497*—504*.

[399.] The last pages of Saint-Venant's *Note* are occupied with a reproduction and extension of Navier's memoir on rectangular plates (pp. 740—52).

Let us take the origin at one of the angles of the plate (sides a , b , and $a < b$) the sides being the axes.

We have here to solve the equation (vi) of our Art. 385, namely:

$$\left(\frac{d^2}{dx^2} + \frac{d^2}{dy^2} \right)^2 w_0 = \frac{3}{2H\epsilon^3} \phi(xy),$$

subject in the case of a simply supported edge to the conditions

$$\left. \begin{aligned} H \frac{d^2 w_0}{dy^2} + (H - 2f) \frac{d^2 w_0}{dx^2} &= 0, \text{ when } x=0 \text{ or } a, \text{ for values of } y \text{ from } 0 \text{ to } b, \\ H \frac{d^2 w_0}{dx^2} + (H - 2f) \frac{d^2 w_0}{dy^2} &= 0, \text{ when } y=0 \text{ or } b, \text{ for values of } x \text{ from } 0 \text{ to } a, \\ w_0 &= 0 \text{ for all points of the contour} \end{aligned} \right\}$$

The solution is easily found to be (p. 743)

$$w_0 = \frac{3}{2\pi^4 H \epsilon^3} \sum_{m=1}^{\infty} \sum_{n=1}^{\infty} A_{mn} \frac{\sin \frac{m\pi x}{a} \sin \frac{n\pi y}{b}}{\left(\frac{m}{a} + \frac{n}{b}\right)^3},$$

where
$$A_{mn} = \frac{4}{ab} \int_0^a d\alpha \int_0^b d\beta \sin \frac{m\pi\alpha}{a} \sin \frac{n\pi\beta}{b} \phi(\alpha, \beta)$$

This result is applied to the calculation of the following special examples

Case (a) A uniformly distributed load p per unit of surface area
Here

$$w_0 = \frac{24p}{\pi^6 H \epsilon^3} \sum_{m'=1}^{\infty} \sum_{n'=1}^{\infty} \frac{1}{m'n'} \frac{\sin \frac{m'\pi x}{a} \sin \frac{n'\pi y}{b}}{\left(\frac{m'}{a} + \frac{n'}{b}\right)^2},$$

the summations being for odd numbers m', n' only

The maximum or central deflection f_0 is very nearly given by the first term of this series with $x=a/2, y=b/2$, or we find

$$f_0 = \frac{24(pab) a^3 b^3}{\pi^6 H \epsilon^3 (a+b)}$$

The second term will, for $a=b$, be only 1/75 of this

The maximum stretch s_0 is very nearly given by

$$s_0 = \frac{24ab^3}{\pi^4 H \epsilon (a+b)} pab$$

Case (b) An isolated central load = P Here

$$w'_0 = \frac{6P}{\pi^4 H ab \epsilon} \sum_{m'=1}^{\infty} \sum_{n'=1}^{\infty} \frac{(-1)^{\frac{m'-1}{2}} (-1)^{\frac{n'-1}{2}}}{\left(\frac{m'}{a} + \frac{n'}{b}\right)} \sin \frac{m'\pi x}{a} \sin \frac{n'\pi y}{b},$$

where m' and n' are odd numbers only

Here
$$f = \frac{6Pa b}{\pi^4 H \epsilon (a+b)}$$

nearly, but not so approximately as in the like result for f_0 in *Case (a)*, and

$$s'_0 = \frac{6ab^3}{\pi^2 H \epsilon^2 (a^2 + b^2)^2} P.$$

Hence f'_0/f_0 and s'_0/s_0 for the same total loads $= \pi^2/4 = 2.5$ nearly: see our Art. 263*.

[400.] We have given a large amount of space to this monumental work because it contains much that is of value to both physicist and technologist, and we would gladly bring home to both the important services which Saint-Venant has rendered to the science of elasticity. His annotated *Clebsch* will long form the standard book of reference on our subject, but it is possible that the results we have here collected will reach some to whom it may not be accessible.

[401.] *Détermination et Représentation graphique des lois du choc longitudinal.* This memoir was presented to the Academy on July 16, 23, 30, and August 6, 1883. It appeared in the *Comptes rendus*, T. xcvi., 1883, pp. 127, 214, 281 and 353. An off-print of it with a note by Boussinesq (*Comptes rendus*, T. xcvi., 1883, p. 154) was afterwards put together and repaged. This off-print was distributed also as an appendix to the annotated *Clebsch*.

references will be to the *sections* which are the same in the *Comptes rendus* and in the off-print.

The memoir is due to Saint-Venant in conjunction with M. Flamant the co-translator of the *Clebsch* and professor at the École des Ponts et Chaussées, Paris.



[402.] After a short account as in the *Clebsch* (see our Art. 341) of the evolution of the problem the authors refer to the analytical solution given by Boussinesq (see the same article and Boussinesq's *Application des potentiels à l'étude de l'équilibre... des solides élastiques*, p. 508 *et seq.*) and reproduced by them on pp. 480 k—480 gg of the *Clebsch*.

D'après cette Note (du § 60 de *Clebsch*), le choc longitudinal s'accomplit suivant des lois ayant des expressions analytiques différentes, se succédant l'une l'autre à des intervalles déterminés. Par exemple, les dérivées des déplacements des divers points de la barre varient, d'un instant à l'autre, tantôt avec gradation continue, tantôt par bonds considérables donnant aux mouvements une empreinte périodique de l'acquisition brusque de vitesse qui a été faite au premier instant du choc par l'élément heurté.

1

2

Line $x=l$, or fixed terminal



Il nous a donc paru utile de présenter ici aux regards, par une suite d'épures ou de diagrammes, une peinture de ces singulières et remarquables lois, afin de les éclairer et d'en faire bien comprendre la nature et les intéressantes conséquences (§ 1)

What then our authors accomplish is the *graphical* representation of the results of Boussinesq's analytical solution which was obtained in terms of discontinuous functions. It is one of the many instances in which Saint-Venant has helped to make of practical value the results of most intricate analysis. He was ever conscious that till theoretical formulae are reduced to simple numbers, the task of the mathematician is very far indeed from completion. Only the final diagram or numerical table can fitly crown the analytical labours of the mathematical physicist.

By means of such graphical representation we see at a glance the chief laws of the phenomena investigated, and are able to determine which approximate formulae we may fairly accept, and which we must replace by others better adapted to represent the exact facts of the case.

[403] I reproduce the more important diagrams of the memoir as their practical value for engineers and technologists seems to me very considerable.

The following notation is adopted¹

l = length, ω = cross section, ρ = density, P = weight, E = stretch modulus, u = shift (at distance x from impelled end) of the bar, $a = \sqrt{E/\rho}$, or the velocity of sound. One end of the bar is fixed, and we may suppose it placed horizontally and struck horizontally by a mass of weight Q with velocity V . If the bar be vertical the effect produced by its weight must also be taken into account.

At the instant at which the blow ends, $du/dx = s_x = 0$ for $x = 0$ (see our Art. 204) and the following numerical values are obtained

$Q/P < 1.7283$	the blow ends between the times $t = 2l/a$ and $4l/a$,
$Q/P > 1.7283 < 4.1511$	$= 4l/a$ and $6l/a$,
$Q/P > 4.1511 < 7.35$	$= 6l/a$ and $8l/a$

[404] The first diagram which I reproduce gives the shifts u for zero, quarter, half and three-quarter span for times $at/l = 0$ to $at/l = 7.5$. Along the horizontal axis at/l is measured, along the

¹ In the memoir the authors use a for our l , σ for our ω , and ω for our a .

vertical axis $u = au/(Vl)$. Three curves are drawn for $r \equiv P/Q = 1$, $\frac{1}{2}$ and $\frac{1}{4}$ respectively, and having for scale 20 mm. for the unit of both at/l and u .

The shifts for the duration of the impulse are denoted by a heavy line ending in a small circle which marks the end of the impulse; the shifts after the impulse are marked by dotted lines, till they begin to repeat themselves when the lines become again heavy.

Whenever $at - x$ or $at + x - 2l$ is a multiple of $2l$ we note sudden changes in the slope (or the *shift-velocity*) of these curves; the points where these changes occur are termed by the authors *points de brisures*.

Les pieds des ordonnées de ces points de brisures sur les lignes horizontales d'abscisses marquées $x = l/4$, $x = l/2$, $x = 3l/4$ se trouvent, ainsi, aux rencontres de ces trois horizontales avec les obliques joignant en deux sens opposés les points $at/l = 0, 2, 4 \dots$ de l'horizontale $x = 0$ du bas, avec ceux $at/l = 1, 3, 5 \dots$ d'une horizontale $x = l$ tracée au haut. Celles de ces obliques qui montent de gauche à droite ont, en effet, pour équations $at - x = 0, 2l, 4l \dots$ et celles qui descendent ont $at + x - 2l = 0, 2l, 4l \dots$. Ces lignes obliques *figurent, en x et t , la marche de l'onde d'ébranlement*, tant directe que réfléchie aux extrémités de la barre, ou ce que parcourrait la tête de cette onde, si la barre vibrante était emportée perpendiculairement à sa longueur avec une vitesse a/l . Cela montre bien que les *bonds* et les *brisures* sont déterminés *par le passage de cette onde*; et cela donne une raison sensible du binôme et du trinôme $at - x$ et $at + x - 2l$ que M. Boussinesq a fait figurer dans ses formules de déplacements, etc. (§ 8).

We see that in all cases the maximum shift is at the end which receives the impulse.

[405.] The second diagram (Fig. 4 of the memoir) gives graphically the law of squeeze at the terminals and at $\frac{1}{4}$, $\frac{1}{2}$ and $\frac{3}{4}$ span for the same values of P/Q . Here the abscissae are at/l , and the ordinates $d = (-s_x) \alpha/V$, or the squeezes reduced in the ratio of α to V . The scale of the abscissae is 20 mm. for $at/l = 1$ and of the ordinates 10 mm. for $d = 1$.

We note that in all cases the maximum squeeze is at the fixed end.

[406.] The third and fourth diagrams (figures 5 and 6 of the memoir) give:

0,637

20 47



end of



20 46

0,488

0,552



0,841



20 6

7 1

end of



(1) *The maximum shifts at the end struck (u_m)*

Here the abscissa gives Q/P from 0 to 6, and the ordinate $u_m a/(Vl)$, the scale of the unit of both being equal to 20 mm. The heavy line is given by the true theory, the broken line is the parabola given by the first approximation $\frac{a}{V} \frac{u_m}{l} = \sqrt{\frac{Q}{P}}$, the pointed line is the curve given by the second approximation $\frac{a}{V} \frac{u_m}{l} = \sqrt{\frac{Q}{P} \frac{1}{1 + \frac{1}{3} \frac{P}{Q}}}$ compare our Arts 943*,

368, and the *Historique Abîégé, Leçons de Navier*, footnote p cccxiii

We see at once that the *Hodgkinson-Saint-Venant approximation gives the terminal shifts with very considerable accuracy, and may be adopted with safety for all values of $Q/P > \frac{1}{2}$*

In the course of the calculations the following numerical results not indicated on the diagram are obtained

The maximum shift u_m is reached if

$$Q/P < 5.686 \quad \text{between } t = 2l/a \text{ and } 4l/a,$$

$$Q/P > 5.686 < 13.816 \quad ,, \quad t = 4l/a \text{ and } 6l/a,$$

$$Q/P > 13.816 < 25.16 \quad ,, \quad t = 6l/a \text{ and } 8l/a$$

(2) *The maximum squeezes ($-s_x$) at the fixed end*

The three curves have for abscissae the values of Q/P from 0 to 25.10, the upper heavy curve has for ordinates the exact values of $(-s_x) a/V$ where s_x is given its maximum value, i.e. at the fixed end. The lower heavy curve is the parabola obtained by taking for ordinates

$$d = \frac{a}{V} (-s_x) = \sqrt{\frac{Q}{P}},$$

and the dotted curve by taking for ordinates

$$d = \frac{a}{V} (-s_x) = \sqrt{\frac{Q}{P}} + 1$$

For the abscissa scale 5 mm is taken for $Q/P = 1$, and for the ordinate scale 20 mm for $d = 1$

It will be seen that the true values differ immensely from the values given by the old formula $d = \sqrt{Q/P}$. Thus that formula never suffices for finding the maximum squeeze¹

¹ It may be obtained as follows. Suppose the shift uniformly distributed and its maximum mean value = u_m . Then work done = $\frac{1}{2} F \omega l \left(\frac{u_m}{l} \right) = \frac{1}{2} Q \frac{V}{2}$ when the maximum is reached. Hence

$$(-s_x)_m = \frac{u_m}{l} = \frac{V}{a} \sqrt{\frac{Q}{P}} \quad \text{or} \quad \frac{a}{V} \left(\frac{u_m}{l} \right) = \sqrt{\frac{Q}{P}}$$

observes that the discovery of its absolute form indeed is unnecessary for the establishment of the formulae of elasticity, hydraulics and electricity.

[409.] *Sur la flexion des prismes. Comptes rendus*, T. CII., 1886, pp. 658—664 and pp. 719—722. This memoir by Resal professes to point out an error in Saint-Venant's memoir on the flexion of prisms of 1856: see our Art. 69. The writer notes that Saint-Venant fixes the direction of a rectilinear element of the first face and not the direction of the first element of the prismatic axis. He then proceeds to assert that Saint-Venant has not taken account of the relation $\int xz d\omega + P = 0$: see our Art. 81. He endeavours to shew that this has led Saint-Venant to erroneous results in the case of the elliptic cross-section, but he himself falls into an error in his algebra, and so gives the colour of an error to Saint-Venant's work.

Boussinesq in a note in the same volume of the *Comptes rendus*, pp. 797—8, entitled: *Observations relatives à une Note récente de M. Resal sur la flexion des prismes*, points out Resal's algebraic error, and remarks that the difference between the terminal conditions of Saint-Venant and those proposed by Resal only produces a small rotation of the coordinate axes, and introduces no change into the expressions for the strains or stresses.

Resal in a few words (p. 799) acknowledges his error.

[410.] *Courbes représentatives des lois du choc longitudinal et du choc transversal d'une barre prismatique, dressées par feu de Saint-Venant, publiées par M. Flamant. Journal de l'École Polytechnique*, LIX^e Cahier, pp. 97—128, 1889.

In the case of transverse impulse these curves are those referred to in our Arts. 105 and 361, while results drawn from those for longitudinal impact are mentioned in our Arts. 107 and 341: see also the passages in the *Notices* referred to in our Art. 108. The footnote on p. 244 of the present volume stating that it had been decided that the plates should not be published was printed nearly two years ago, and was made on the authority of M. Flamant. I can only hope that this footnote, however confusing to the reader, may, perhaps, have helped

to bring about a reconsideration of the question of publication¹
The plates were engraved as far back as 1873

[411] In the case of longitudinal impact the exact results—calculated from Boussinesq's solution in finite terms—are known and have been discussed by Saint-Venant and Flamant see our Arts 401—7 These enable us to compare for this case the approximate graphical and the actual results While the accordance is fairly good for the maximum shifts, it is not very close for the stretches In the case of transverse impact we are not yet able to test the accuracy of the graphical values of the curvature, which have been obtained from the shift-curves based on the first few terms of the transcendental series, but the fact that the shift-curves shew *no abrupt changes of slope*, as in the case of longitudinal impact, leads me to believe that far greater accuracy is obtainable by graphical processes for the case of transverse than for that of longitudinal impact Compare Plates IV—VI of the memoir or Diagram I of our p 277 with Plates X and XI of the memoir

Flamant himself writes

Quoi qu'il en soit, le travail de Saint Venant a un intérêt suffisant pour justifier sa publication il peut servir d'exemple en montrant comment, grâce a un labeur considerable par l'étendue duquel cet infatigable travailleur ne s'est pas laisse rebuter, les valeurs de ces series à termes periodiques de périodes décroissantes peuvent être représentées graphiquement, et il donne, tout au moins, sui les grandeurs de ces quantites, une première indication permettant de deduire des conséquences pratiques qui, si elles ne sont pas absolument exactes, n'en sont pas moins précieuses, puisqu'elles constituent tout ce que l'on sait sui ce sujet si important au point de vue de la stabilité des constructions (pp 98—9)

The text which accompanies the plates is principally extracted from the *Annotated Clebsch* (§§ 60 and 61, see our Arts 339, 342 *et seq*), so that the whole may be looked upon as really a work of Saint-Venant which has been carefully edited by Flamant

[412] Pages 99—110 deal with longitudinal impact The Plates I—III shew the graphical stages preparatory to drawing the shift curves for five points of the bar in the case of $P/Q = \frac{1}{4}$ (the notation

¹ The footnote appeared in *The Plactical Researches of Barre de Saint Venant*, Cambridge, 1889 an off print of our Chapter x

being that of our Art. 403). Plate IV. gives these curves, while Plates V. and VI. contain like curves for the cases $P/Q = \frac{1}{2}, 1, 2$, and 4. These curves serve in general the same purposes as those of Diagram I. of our p. 277, but they do not give the same abrupt changes of slope. The slope of these curves measures the stretch (or squeeze) and it is easy to see that its maximum occurs at the fixed end; unfortunately the slope of a tangent to an approximate curve is unlikely to give very good results. Thus for $P/Q = \frac{1}{2}$, Saint-Venant finds the maximum slope to be $2.825 V/a$ and to occur at a time $at/l = 3.25$. The accurate values are $3.213 V/a$ and $at/l = 3$ (see our Diagram II. p. 278). The errors are even larger than this in the ratios of the maximum to the mean squeezes (pp. 109—110). But Saint-Venant's graphical values shew at least that one errs greatly in taking, as is usually done in the text-books, the mean for the maximum squeeze.

[413.] The curves for transverse impact we have already discussed in our Arts. 362—3 and 371. It is unfortunate that we have so little means of testing their accuracy. For the reasons given above, however, I am inclined to think the results more accurate than in the previous case. Saint-Venant assumes the form of a small arc at the lowest point of one of the instantaneous positions of the central axis to be a parabola with its axis vertical and so takes the curvature 8 times the subtense divided by the square of the chord (p. 119). I wish it had been possible to reproduce Plates X. and XI., but their scale precluding this, I must content myself by referring the reader to the original memoir.

Flamant makes (pp. 122—4) some interesting comparisons between longitudinal and transverse impact, and shews that if the same body falls with the same velocity first longitudinally and then transversely on a bar, the strain is considerably greater in the latter than in the former case, although the ratio of the strains diminishes as P/Q increases.

[414.] In conclusion Flamant remarks that in both cases the cross-sections are supposed to remain plane and that this is far removed from reality in the case of transverse impact, for the strain will really propagate itself in spherical or ellipsoidal surfaces from the point of impact, and these are not approximately coincident with the plane transverse cross-sections except at distances which are a considerable number of times greater than the depth of the bar. Flamant also refers to Boussinesq's solution (see the Chapter we have devoted to that scientist) but remarks that it leads to formulæ so complicated that it does not seem possible to deduce any practical results from them (p. 124). Thus Saint-Venant's graphical calculation of the strain for these special cases

is all the theory we can at present use in practical structures subjected to transverse impact

[415] Saint-Venant died on January 6, 1886. The President of the Academy on announcing his death at the meeting held on January 11, used the following words

La vieillesse de notre éminent confrère a été une vieillesse benie. Il est mort plein de jours, sans infirmités, occupé jusqu'à sa dernière heure des problèmes qui lui étaient chers, appuyé pour le grand passage sur les espérances qui avaient soutenu Pascal et Newton (*Comptes rendus*, T. CII, 1886, p. 73)

Short notices of his life appeared in the *Comptes rendus*, T. CII, pp. 141—7, 1886 by Phillips, and in *Nature*, February 4, 1886 by the Editor of the present volume. A full and excellent account by Boussinesq and Flamant of his life and work, together with a complete bibliography of his contributions to science, was published in the *Annales des Ponts et Chaussées* for November, 1886. In presenting this paper to the Academy, Boussinesq said

Nous avons tâché d'y rappeler, avec tous les détails que comportait l'étendue matérielle de texte dont nous pouvions disposer, l'existence si bien remplie et les travaux les plus marquants du profond ingénieur géomètre, notre maître à tous deux, qui a été une des gloires de l'Académie à notre époque et un modèle pour les travailleurs de tous les temps (*Comptes rendus*, T. CIV, 1887, p. 215)

A more popular account of Saint-Venant's life based chiefly on the notices in the *Annales* and *Nature* will be found in the *Tablettes biographiques*, *Deuxième Année* 1888

[416] *Saint-Venant*. In estimating the value of Saint-Venant's contributions to our subject, we have first of all to note that he is essentially the originator on the theoretical side of modern technical elasticity. In his whole treatment of the flexure, torsion and impact of beams he kept steadily in view the needs of practical engineers, and by means of numerical calculations and graphical representations he presented his results in a form, wherein they could be grasped by minds less accustomed to mathematical analysis. At the same time he was no small master of analytical methods himself, and he undertook in addition purely numerical calculations before which the majority would stand aghast. His memoirs on the distributions of elasticity round a point and of

homogeneity in a body opened up new directions for physical investigation, while his numerous discussions on the nature of molecular action have greatly assisted towards clearer conceptions of the points at issue. The hypotheses of modified molecular action and of polar molecular action may either or both be true, or false; but we see now clearly that it is to the investigation of these hypotheses and not to the experiments of Oersted, Regnault etc. nor to the viscous fluid and ether jelly arguments of the first supporters of multi-constancy to which we must turn if we want to investigate the question of rari-constancy¹. Saint-Venant's foundation, on the basis of Tresca's investigations, of the new branch of theoretical science, which he has termed *plastico-dynamics*, has not only direct value, but shews clearly the fallacy of those who would identify plastic solids and viscous fluids. The fundamental equations in the two cases differ in character; a difference which may be expressed in the words—the plastic solid requires a certain magnitude of stress (shear), the viscous fluid a certain magnitude of time for any stress whatever, to permanently displace their parts.

Not the least merit of Saint-Venant's work is the able band of disciples he collected around him. His influence we shall find strongly felt when investigating the work of Boussinesq, Lévy, Mathieu, Sarrau, Resal and Flamant. He formed the connecting link between the founders of elasticity and its modern school in France.

The vigorous spirit, the striking mental freshness, the perfect fairness of his thought enabled him to penetrate to the basis of things; the depth of his affection, his kindly foresight and consideration, his rare personal devotion attached to him all who came in his way and stimulated them to renewed investigation (Flamant and Boussinesq: *Notice sur la vie et les travaux de B. de St. V.*, p. 27).

¹ This is well brought out by the comparison of Voigt's recent memoir (*Göttinger Abhandlungen*, 1887) with those of the early supporters of multi-constancy.

CHAPTER XI

MISCELLANEOUS RESEARCHES 1850-60

SECTION I

*Mathematical Memoirs*¹, including those of W J M Rankine

[417] W J M Rankine *On the Centrifugal Theory of Elasticity, and its connection with the Theory of Heat* *Edinburgh Royal Society Proceedings*, Vol III pp 86—91, 1851 This paper deals only with the elasticity of fluids and gases

[418] W J M Rankine *Laws of the Elasticity of Solid Bodies* This paper was read before the British Association at Edinburgh, 1850 It is briefly noticed in the *Report* for that year see our Art 1452* It is published at length in the *Cambridge and Dublin Mathematical Journal*, Vol VI 1851, pp 47—80, with additions, pp 178—181 and pp 185—6 It is reprinted on pp 67—101 of Rankine's *Miscellaneous Scientific Papers* edited by W J Millar The pages of the latter will be briefly referred to as *S P* while we are dealing with Rankine's memoirs

¹ The titles of the separate sections of this chapter refer rather to the method than to the substance of the memoirs Thus this section discusses researches of Bresse Phillips Winkler etc , which are of the first importance to engineers while the physical and technical sections will be found to contain many papers of great interest to mathematicians The overwhelming number of memoirs demanded some classification and the grouping of them broadly into mathematical physical and technical sections seemed the least objectionable arrangement In certain cases memoirs have been taken out of their proper section or their chronological order with a view to grouping kindred researches or bringing together the complete work of an individual scientist

[419.] Section I. of the memoir (pp. 48—54, *S. P.* pp. 68—73) contains reproductions of formulae already given by Cauchy, Lamé and others for expressing the stresses or strains in any three rectangular directions in terms of those in any three other rectangular directions. I may note that Rankine uses *pressures* where I use positive tractions and that he uses symbols T_1, T_2, T_3 for the *halves* of what I have termed the slides, a notation which I am inclined to think would be of value if it had been generally adopted: see our Vol. I. p. 881.

On p. 49 (*S. P.* p. 68) he writes :

It is desirable that some single word should be assigned to denote the state of the particles of a body when displaced from their natural relative positions. Although the word *strain* is used in ordinary language indiscriminately to denote relative molecular displacement, and the force by which it is produced, yet it appears to me that it is well calculated to supply this want. I shall therefore use it, throughout this paper, in the restricted sense of *relative displacement of particles* whether consisting in dilatation, condensation or distortion.

to Rankine that we owe the scientific appropriation
strain.

[420.] In Section II. (pp. 54—63, *S. P.* pp. 73—81) of the paper Rankine restricts his enquiries to

homogenous bodies possessing a certain degree of symmetry in their molecular actions, which consists in this: that the actions upon any given particle of the body of any two equal particles situated at equal distances from it within the sphere of molecular action, in opposite directions, shall be equal and opposite (p. 54, *S. P.* p. 73).

He is thus dealing with a case of what might be termed *central elastic symmetry*.

By a process of rather general reasoning in what is entitled: *Theorem I.* (p. 55) and by the assumption of the linearity of the stress-strain relations Rankine reaches expressions for the stresses which with our system of notation may be given as :

$$\begin{aligned}\widehat{xx} &= a s_x + f' s_y + e' s_z, & \widehat{yz} &= d \sigma_{yz}, \\ \widehat{yy} &= f'' s_x + b s_y + d' s_z, & \widehat{zx} &= e \sigma_{zx}, \\ \widehat{zz} &= e' s_x + d'' s_y + c s_z, & \widehat{xy} &= f \sigma_{xy}.\end{aligned}$$

There are thus twelve apparently independent constants. Rankine does not note that the principle of energy requires us to suppose that $d'' = d'$, $e'' = e'$, $f'' = f'$, which reduces these formulae to those of our Art. 117 formulae (α).

[421] Rankine now proceeds to *Theorem II* (p 61, *S P* I 79) which he states as follows *The coefficient of rigidity is the same for all directions of distortion in a given plane*, or in analytical language he would say that $\widehat{yz} = \widehat{y'z'}$ if $\sigma_{yz} = \sigma_{y'z'}$ whatever rectangular directions lying in the same plane y, z and y', z' may be. This *Theorem II* does not appear to be correct and Rankine's error seems to have arisen from his supposing that a pure shearing force alone can change the angles of a rhombic prism. He has neglected to take into account the tractions which would have to be distributed over the faces to produce the sort of distortion he is considering, and although the work required to produce the distortion might be the same, however it was produced, yet the equality does not involve the equality of the shears, except when the rhombic angles are right. In the latter case his theorem reduces to the well-known results $\widehat{yz} = \widehat{zy}$ and $\sigma_{yz} = \sigma_{zy}$.

[422] By means of the erroneous *Theorem II*, Rankine in *Theorem III* (p 61, *S P* p 80) deduces relations of the type

$$4d = b + c - d' - d'' \quad (i),$$

or remembering the real equality of d' and d'' ,

$$2d + d' = \frac{1}{2}(b + c) \quad (ii)$$

But this is the well-known *second* type of relation for bodies with an ellipsoidal distribution of elasticity, or for what Saint Venant has termed *amorphous bodies* see our Arts 230—1, 308. Rankine's results, if true, ought to hold for crystals with three rectangular planes of elastic symmetry, but such bodies do not satisfy the above conditions. Hence *all the further conclusions of Rankine's paper which depend upon the truth of (i) or (ii) can be considered to hold only for the limited range of amorphous or other bodies for which the ellipsoidal relations of the second type hold*.

[423] Section III (pp 63—66, *S P* pp 81—4) is entitled *Results of the Hypothesis of Atomic Centres*. In this by rather vague reasoning Rankine deduces that when molecular force is central and a function only of the distance

$$d = d' = d'', \quad e = e' = e'', \quad f = f' = f'',$$

which are the usual conditions of rational constancy. He bases his result on what he terms the hypothesis of Boscovich, which he considers not to be true for all solid bodies, he holds, however, that it may be corrected by combining it with an hypothesis of his own, to which we shall return later. We have several times had occasion to point out that the hypothesis of Boscovich does not really involve the condition

[419.] Section I. of the memoir (pp. 48—54, *S. P.* pp. 68—73) contains reproductions of formulae already given by Cauchy, Lamé and others for expressing the stresses or strains in any three rectangular directions in terms of those in any three other rectangular directions. I may note that Rankine uses *pressures* where I use positive tractions and that he uses symbols T_1, T_2, T_3 for the *halves* of what I have termed the slides, a notation which I am inclined to think would be of value if it had been generally adopted: see our Vol. I. p. 881.

On p. 49 (*S. P.* p. 68) he writes:

It is desirable that some single word should be assigned to denote the state of the particles of a body when displaced from their natural relative positions. Although the word *strain* is used in ordinary language indiscriminately to denote relative molecular displacement, and the force by which it is produced, yet it appears to me that it is well calculated to supply this want. I shall therefore use it, throughout this paper, in the restricted sense of *relative displacement of particles*, whether consisting in dilatation, condensation or distortion.

It is thus to Rankine that we owe the scientific appropriation of the word *strain*.

[420.] In Section II. (pp. 54—63, *S. P.* pp. 73—81) of the paper Rankine restricts his enquiries to

...ous bodies possessing a certain degree of symmetry in their ...ar actions, which consists in this: that the actions upon any ...particle of the body of any two equal particles situated at equal ...ances from it within the sphere of molecular action, in opposite directions, shall be equal and opposite (p. 54, *S. P.* p. 73).

He is thus dealing with a case of what might be termed *central elastic symmetry*.

By a process of rather general reasoning in what is entitled: *Theorem I.* (p. 55) and by the assumption of the linearity of the stress-strain relations Rankine reaches expressions for the stresses which with our system of notation may be given as:

$$\begin{aligned} \widehat{xx} &= as_x + f's_y + e''s_z, & \widehat{yz} &= d\sigma_{yz}, \\ \widehat{yy} &= f''s_x + bs_y + d's_z, & \widehat{zx} &= e\sigma_{zx}, \\ \widehat{zz} &= e's_x + d''s_y + cs_z, & \widehat{xy} &= f\sigma_{xy}. \end{aligned}$$

There are thus twelve apparently independent constants. Rankine does not note that the principle of energy requires us to suppose that $d'' = d'$, $e'' = e'$, $f'' = f'$, which reduces these formulae to those of our Art. 117 formulae (a).

[421] Rankine now proceeds to *Theorem II* (p 61, *S P* p 79) which he states as follows *The coefficient of rigidity is the same for all directions of distortion in a given plane*, or in analytical language he would say that $\widehat{yz} = \widehat{y'z'}$ if $\sigma_{yz} = \sigma_{y'z'}$ whatever rectangular directions lying in the same plane y, z and y', z' may be. This *Theorem II* does not appear to be correct and Rankine's error seems to have arisen from his supposing that a pure shearing force alone can change the angles of a rhombic prism. He has neglected to take into account the tractions which would have to be distributed over the faces to produce the sort of distortion he is considering, and although the work required to produce the distortion might be the same, however it was produced, yet this equality does not involve the equality of the shears, except when the rhombic angles are right. In the latter case his theorem reduces to the well-known results $\widehat{yz} = \widehat{zy}$ and $\sigma_{yz} = \sigma_{zy}$.

[422] By means of the erroneous *Theorem II*, Rankine in *Theorem III* (p 61, *S P* p 80) deduces relations of the type

$$4d = b + c - d' - d'' \quad (1),$$

or remembering the real equality of d' and d'' ,

$$2d + d' = \frac{1}{2}(b + c) \quad (11)$$

But this is the well known *second* type of relation for bodies with an ellipsoidal distribution of elasticity, or for what Saint Venant has termed *amorphous bodies* see our Arts 230—1, 308. Rankine's results, if true, ought to hold for crystals with three rectangular planes of elastic symmetry, but such bodies do not satisfy the above conditions. Hence *all the further conclusions of Rankine's paper which depend upon the truth of (1) or (11) can be considered to hold only for the limited range of amorphous or other bodies for which the ellipsoidal relations of the second type hold*.

[423] Section III (pp 63—66, *S P* pp 81—4) is entitled *Results of the Hypothesis of Atomic Centres*. In this by rather vague reasoning Rankine deduces that when molecular force is central and a function only of the distance

$$d = d' = d'', \quad e = e' = e'', \quad f = f' = f'',$$

which are the usual conditions of *ran* constancy. He bases his results on what he terms the hypothesis of Boscovich, which he considers not to be true for all solid bodies, he holds, however, that it may be corrected by combining it with an hypothesis of his own, to which we shall return later. We have several times had occasion to point out that the hypothesis of Boscovich does not really involve the conditions

of rari-constancy (see our Art. 276), and that Boscovichian systems may be chosen which do not lead to rari-constancy has been recently demonstrated by Sir William Thomson: see *Proceedings of the Royal Society of Edinburgh*, July, 1889, or *Mathematical Papers*, Vol. III. pp. 395—427. Further Rankine's reasoning has been questioned by Sir William Thomson in a note attached to the memoir: see p. 80 (*S. P.* p. 98). The reply of Rankine to this criticism is given on pp. 178—81 (*S. P.* pp. 98—100).

Of course equations (7) and (8) of this section will be erroneous unless the body possesses ellipsoidal elasticity of the second type, and thus we are obliged to reject Rankine's fascinating statement on p. 66 (*S. P.* p. 84) that:

in a body whose elasticity arises wholly from the mutual actions of atomic centres, all the coefficients of elasticity are functions of the three coefficients of rigidity [i.e. the three slide-coefficients, d , e , f]. Rigidity being the distinctive property of solids, a body so constituted is properly termed a *perfect solid*.

[424.] In Section IV. of the memoir (pp. 66—9, *S. P.* pp. 84—6) Rankine applies his *Hypothesis of Molecular Vortices* to the elasticity of solids. He had previously written several papers on this hypothesis dealing with the elasticity of gases and vapours and generally with the mechanical theory of heat. For our present purposes it is sufficient to cite the description Rankine gives of his hypothesis in this memoir (pp. 66—7):

Supposing a body to consist of a continuous fluid, diffused through space with perfect uniformity as to density and all other properties, such a body must be totally destitute of rigidity or elasticity of figure, its parts having no tendency to assume one position as to *direction* rather than another. It may, indeed, possess elasticity of volume to any extent, and display the phenomena of cohesion at its surface and between its parts. Its longitudinal and lateral elasticities will be equal in every direction; and they must be equal to each other by equation (5).

[Here Rankine gives conditions which amount to putting $d = e = f = 0$, $a = b = c = d' = e' = f' = d'' = e'' = f''$ in the stress-strain relations of our Art. 420. He afterwards writes the latter series of quantities = J , which he terms the coefficient of *fluid elasticity*.]

If we now suppose this fluid to be partially condensed round a system of centres, there will be forces acting between those centres greater than those between other points of the body. The body will now possess a certain amount of rigidity; but less, in proportion to its longitudinal and lateral elasticities, than the amount proper to the condition of perfect solidity. Its elasticity will, in fact, consist of two parts, one of which, arising from the mutual actions of the centres of

condensation, will follow the laws of perfect solidity, while the other will be a mere elasticity of volume, resisting change of bulk equally in all directions

There is indeed much that is suggestive in Rankine's hypothesis of molecular vortices, as well as in his attempt to separate elasticity into the two factors of perfect solidity and of perfect fluidity, which involve the conceptions of rigidity and bulk elasticity. But from what we have seen above these factors of elasticity do not correspond exactly to fluid and Boscovichian methods of action, and Rankine's *imperfect solid* cannot in general be obtained by superposing on a fluid elasticity the rigidity of a *perfect solid*, i.e. the elasticity of a rari-constant substance

The expressions given in Rankine's Equation (9) for the direct-stretch and cross-stretch coefficients in terms of the slide modulus and J would only be true for a particular type of amorphic body

In the case of isotropy relations such as (11) of our Art 422 certainly do hold and then we have

$$a = b = c = 3d + J = 3e + J = 3f + J,$$

$$d' = e' = f' = d + J = e + J = f + J$$

Thus in the ordinary isotropic notation of our *History* the coefficient of fluidity, or J , $= \lambda - \mu$ and it vanishes on the Boscovichian or rather uni-constant hypothesis

Rankine's special error would thus seem to lie in the extension of his results from isotropy to aeolotropy other than that of certain amorphic bodies

To this Section a *Note* is added (pp 69—71, *S P* pp 87—9) containing a reference to the researches of Green, MacCullagh, Stokes, Poisson, Navier, Cauchy, Lamé and Wertheim, with a comparison of their notations for the elastic constants with that of Rankine himself. The latter remarks of Wertheim's hypothesis ($\lambda = 2\mu$) that it must be regarded as doubtful. "If the effect of heat is to diminish μ and increase J , there may be some temperature for each substance at which M. Wertheim's equation is verified."

[425] Section V (pp 71—80, *S P* pp 89—98) is entitled *Coefficients of Pliability, and of Extensibility and Compressibility, Longitudinal, Lateral, and Cubic. Examples of their Experimental Determination*. These are the coefficients which Rankine afterwards termed *Thlipsinomic* (see our Art 448), or those which express strain in terms of stress. For the stress strain relations

of our Art. 420, the coefficients of pliability are the reciprocals of the coefficients of rigidity, i.e. of the slide-coefficients d, e, f .

For the stretches Rankine has in our notation :

$$s_x = a_1 \widehat{xx} - b_3 \widehat{yy} - b_2 \widehat{zz},$$

$$s_y = -b_3 \widehat{xx} + a_2 \widehat{yy} - b_1 \widehat{zz},$$

$$s_z = -b_2 \widehat{xx} - b_1 \widehat{yy} + a_3 \widehat{zz},$$

and he classifies the coefficients as follows :

a_1, a_2, a_3 are coefficients of *longitudinal extensibility and compressibility*. We may perhaps better term them *direct traction coefficients*, they are coefficients of 'stretchability.' b_1, b_2, b_3 are coefficients of *lateral extensibility and compressibility*. We may perhaps better term them *cross traction coefficients*. Our terminology would thus be in accordance with that which we have adopted for the usual elastic or tasinomic coefficients: see the footnote on our page 77.

Rankine then proceeds to express these six thlipsinomic coefficients in terms of the four constants, d, e, f and J , of which he imagines in the case of central elastic symmetry all the other elastic constants to be functions. His results are rather lengthy and appear to have no application except to the case of a certain type of amorphous body (see our Art. 422). For the special case of isotropy we have

$$a = \frac{2\mu + J}{5\mu^2 + 3\mu J}, \quad b = \frac{\mu + J}{10\mu^2 + 6\mu J},$$

$$d = \frac{3}{5\mu + 3J} \quad \text{or} \quad \frac{1}{d} = J + \frac{5}{3}\mu.$$

Here d is what Rankine terms the coefficient of cubic compressibility, or $1/d$ what we have termed the *dilatation-modulus* and represented by F : see Vol. I. p. 885. Further $1/a$ is obviously E , the stretch-modulus, and $b = \eta/E$, where η is the stretch-squeeze ratio. There is thus little of importance here beyond the terminology.

Rankine then proceeds to show how the rigidity (μ), fluid elasticity (J), longitudinal elasticity ($\lambda + 2\mu$), lateral elasticity (λ), as well as the thlipsinomic coefficients a, b and d may be experimentally ascertained. He determines them for brass and crystal glass from Wertheim's experiments, and indicates how they might be found for aeolotropic bodies (pp. 75—80).

[426.] We have already referred to Sir W. Thomson's criticism with which the memoir concludes and to Rankine's rejoinder (pp. 178—81, *S. P.* pp. 97—100). An additional *Note* (pp. 185—6, *S. P.* p. 100—1) merely gives the relations between the symbols of the present memoir and those of Clerk-Maxwell's memoir of 1850: see our Art. 1536*.

[427] W J M Rankine *On the Laws of Elasticity Cambridge and Dublin Mathematical Journal*, Vol VII 1852, pp 217—34 (*S P* pp 101—118) This is a sequel to the memoir referred to in our Arts 418—26, the sections being numbered in continuation The object of this portion of the memoir is to compare the results and symbols of Haughton and Green with those adopted by the author Rankine here follows Lagrange's method of investigation and sums up his assumptions in the following postulates

(1) That the variations of molecular force concerned in producing elasticity are sufficiently small to be represented by functions of the first order of the quantities on which they depend and,

(11) That the integral calculus and the calculus of variations are applicable to the theory of molecular action It is thus apparent that the science of elasticity is, to a great extent, one of deduction *à priori* (p 230, *S P* p 114)

These do *not* seem to me the only assumptions of the paper, for Rankine again reduces in the case of rari-constancy the stress-strain relations of our Art 420 to relations having only three independent constants He obtains the relations of the second ellipsoidal type (see our Art 422, (11)) but by a hypothesis very different from that of the earlier part of his paper

[428] Section VI entitled *On the Application of the Method of Virtual Velocities to the Theory of Elasticity* (pp 217—24) follows closely the methods of Haughton's memoirs of 1846—9, and contains nothing of special note¹ We may remark that Rankine endorses Haughton's view of the relation $\widehat{xy} = \widehat{yx}$ cited in our Art 1517*

Mr Haughton correctly remarks that this often quoted Theorem of Cauchy is not true for all conceivable media It is not true, for instance, for a medium such as that which Mr MacCullagh assumed to be the means of transmitting light It is true, nevertheless, for all molecular pressures which properly fall under the definition of elasticity, if that term be confined to the forces which preserve the figure and volume of bodies (p 221, *S P* p 105)

Here as in the earlier part of the memoir Rankine insists upon the distinction between the resistances to change of bulk and to change of form, and in the following section he again builds up

¹ See our Arts 1503*—1517*

an elastic solid of the ordinary type by superposing a fluid elasticity upon a homogeneous body consisting of centres of force only and so having *rari-constant* equations.

[429.] Section VII. is entitled: *On the Proof of the Laws of Elasticity by the Method of Virtual Velocities* (pp. 224—30, *S. P.* pp. 108—114). The following words exactly reproduce Rankine's position:

The fluid elasticity considered in the last article cannot arise from the mutual actions of centres of force; for such actions would necessarily tend to preserve a certain arrangement amongst those centres, and would therefore resist a change of figure. Fluid elasticity must arise either from the mutual actions of the parts of continuous matter, or from the centrifugal force of molecular motions, or from both those causes combined.

On the other hand it is only by the mutual action of centres of force that resistance to change of figure and molecular arrangement can be explained, that property being inconceivable of a continuous body. The elasticity *peculiar* to solid bodies is, therefore, due to the mutual action of centres of force. Solid bodies may nevertheless possess, in addition, a portion of that species of elasticity which belongs to fluids.

The investigation is simplified by considering in the first place the elasticity of a solid body as arising from the mutual action of centres of force only, and afterwards adding the proper portion of fluid elasticity (p. 224, *S. P.* p. 108).

Rankine deduces by a process, some steps of which I do not grasp¹, usual *rari-constant* equations of elasticity. These it will be remembered have 15 independent constants (see our Art. 116 and footnote). To get the most general system of coefficients he adds a constant J to the *rari-constant* direct-stretch and cross-stretch coefficients, i.e. takes

$$[xxxx] + J, \quad [xyxy] + J, \text{ etc.}$$

but he does not add this constant to the coefficients like $[xyxy]$ which in the *rari-constant* theory are equal to those of type $[xyxy]$. Thus he really supposes the *multi-constant* coefficients to satisfy relations of the type

$$[xyxy] - [xyxy] = [yyzz] - [yzyz] = [zzxx] - [xxzz] \{ = \text{Rankine's } J \} \dots (i),$$

together with the three purely *rari-constant* conditions:

$$\left. \begin{aligned} [xyyz] &= [xyxz] \\ [yyzx] &= [yzyx] \\ [zxyx] &= [xxzy] \end{aligned} \right\} \dots \dots \dots (ii).$$

¹ For example, how the expression on p. 226 (*S. P.* p. 110) for the total action of an indefinitely slender pyramid is obtained, supposing $\phi(r)$ to be the law of intermolecular force.

Hence he puts the six rari constant relations on different footings, the latter three always hold, the former three (obtained by putting $J=0$) do not generally hold and are replaced by the two of type (i) above

The most general aeolotropy has thus for Rankine only *sixteen* constants. It would be interesting to know how far experimentally Rankine's views are justified. Are any of the inter constant relations of rari-constancy more generally satisfied than others? Rankine's defective theory can hardly in itself be considered an argument in favour of the reduction of the constants to sixteen. Unfortunately the results (ii) are identically satisfied for all bodies possessing three rectangular planes of elastic symmetry, and thus experiments would have to be made on very complex aeolotropic systems.

[430] Rankine now proceeds to reduce his sixteen elastic coefficients to *four*, three rari-constant coefficients supplemented by the coefficient of fluidity J . He first reduces the sixteen to seven by putting the coefficients of asymmetrical elasticity (see our footnote p 77) zero. The exact reasoning by which he reaches this result (p 228, *S P* 112) is far from clear to me, but I presume it does not amount to more than his previous supposition of the central symmetry of the elastic distribution. He apparently supposes that his reasoning is perfectly general.

The next stage is to reduce the six remaining rari constant coefficients to three by means of the ellipsoidal conditions of the second type see our *Ait* 422, (ii). Rankine deduces these conditions by a method totally different from that of the first part of his memoir, and he asserts that they hold for "all known homogeneous substances" (p 229, *S P* p 112). He proceeds as follows.

Let $\phi(r)$ be the law of central intermolecular force and Σ denote a molecular summation over a cone of elementary solid angle, then he assumes that $R = \Sigma r \phi'(r)$ is a function $F(\iota)$ of ι "the mean interval between centres of force in a given direction". If the direction-cosines of this direction be l, m, n , and f, g, h, k , be constants, he assumes that referred to the axes of elasticity ι will be of the form

$$\iota = \text{exponential } (f + gl + hm + kn)$$

He then continues

Let us assume as a *Fifth Postulate*, what experience shows to be sensibly true of all known homogeneous substances—viz that their elasticity varies very little in different directions. Those substances, such as timber whose elasticity in different directions varies much, are not homogeneous, but composed of fibres, layers, and tubes of different substances (p 229, *S P* p 112)

Thus he deduces that $gl^2 + hm^2 + kn^2$ must be very small as compared with f , or that we may take:

$$R = \psi(f) + \psi'(f)(gl^2 + hm^2 + kn^2),$$

substituting this value of R in the summation expressions¹ for the elastic constants he easily deduces relations of the type

$$\frac{1}{2} \{ |yyyy| + |zzzz| \} = 3 |xyzy|$$

or those of the second ellipsoidal type.

[431.] Rankine concludes this section of his memoir by the two postulates I have cited at the beginning of my criticism in Art. 427. Those postulates do not seem to me to involve the reduction of the twenty-one elastic constants to three. The memoir suggestive in parts, seems full of very doubtful reasoning. The results of this memoir are indeed rejected in the one *On Axes of Elasticity...*, discussed in our Arts. 443—52 where Rankine states that “there is now no doubt that the elastic forces in solid bodies are not such as can be analysed into fluid elasticity and mutual attractions between centres simply.” But my present point is that, even if they could be, there would be no *necessary* reduction of the constants below sixteen, so that Rankine’s reason—as his hypotheses are at fault.

[2.] In a *Note to Sections VI. and VII.* appended to the memoir and entitled: *On the Transformation of the Coefficients of Elasticity by the aid of a Surface of the Fourth Order* (pp. 231—4, *S. P.* pp. 114—8), Rankine gives expressions for the transformation of the coefficients of elasticity from one set of rectangular axes to a second. I believe this to be the first occasion (1852) on which expressions were given for the transformation of the elastic coefficients. The same results, however, were obtained by Saint-Venant in a much simpler symbolic form some years later (1863) and have already been cited in this work: see our Art. 133. Hence I do not propose to reproduce the earlier discussion, merely noting Rankine’s undoubted priority, which was fully admitted by Saint-Venant: see our footnote p. 89, and Art. 135, etc.

¹ I am not certain of the accuracy of these summation expressions if $\phi(r)$ be the law of intermolecular force. But I think Rankine’s results would follow if $F(r)$ of our equation (xxx.) Art. 143 were made a function of i .

[433] W J M Rankine *On the Velocity of Sound in Liquid and Solid Bodies of limited Dimensions, especially along Prismatic Masses of Liquid* Cambridge and Dublin Mathematical Journal, Vol VI 1851, pp 238—67 (*S P* pp 168—199)

Rankine remarks that if we could ascertain the velocities of transmission of vibratory movements along the axes of elasticity of an *indefinitely extended* mass of any substance we should at once be able to calculate its coefficients of elasticity. As we cannot experiment on such a mass of solid elastic material, the best results, which can be obtained in practice are those based on the transmission of nearly longitudinal vibrations along prismatic or cylindrical bodies. If the vibrations were *solely* longitudinal, we should be able to find the “true longitudinal elasticity,” i.e. the direct stretch-coefficient. It is however “impossible to prevent a certain amount of lateral vibration of the particles, the effect of which is to diminish the velocity of transmission in a ratio depending on circumstances in the molecular condition of the superficial particles, which are yet almost entirely unknown.” Rankine holds that the supposition that the stretch-modulus is obtained from experiments upon the longitudinal vibrations of a rod or bar is

inconsistent with the mechanics of vibratory movement, and accordingly, experiment has shown that the elasticity corresponding to the velocity of sound in a rod agrees neither with the modulus of elasticity, nor with the true longitudinal elasticity, although it is in some cases nearly equal to the former of those quantities, and in others to the latter (p 239, *S P* p 169)

We will briefly indicate the course of Rankine’s investigations in the following six articles

[434] Pp 240—6 (*S P* pp 170—6) are entitled *General Equations of Vibratory Motion in Homogeneous Bodies*. In this paper Rankine integrates the general equations of vibratory motion for a solid having central elastic symmetry, i.e. with nine independent elastic coefficients see our Art 117, (a)

Rankine adopts as types of solution shifts with factors of the form

$$e^{\frac{2\pi}{\lambda} \{ax + by + cz \pm \sqrt{-1}(\sqrt{\epsilon} \, t - av - by - cz)\}}$$

where ϵ has three different values given by the roots of a particular cubic equation. Certain rather complex relations must hold among

the constants. Taking a series of such terms Rankine finds for the shifts :

$$\left. \begin{aligned} u &= \Sigma \left[e^{\frac{2\pi}{\lambda}(ax+by+cz)} \left\{ l \cos \frac{2\pi}{\lambda} (\sqrt{\epsilon}.t - ax - by - cz) \right. \right. \\ &\quad \left. \left. + l' \sin \frac{2\pi}{\lambda} (\sqrt{\epsilon}.t - ax - by - cz) \right\} \right] \dots\dots(i). \\ v &= \Sigma (\text{terms in } m, m' \text{ instead of } l, l') \\ w &= \Sigma (\text{terms in } n, n' \text{ instead of } l, l') \end{aligned} \right\}$$

Thus there are fourteen constants $\lambda, \sqrt{\epsilon}, a, b, c, a', b', c', l, l', m, m', n, n'$ for each set of terms, and these are connected by the equation $a^2 + b^2 + c^2 = 1$ and six other equations of condition, or we have seven independent constants.

Such expressions Rankine says "contain the complete representation of the laws of small molecular oscillations in a homogeneous body of any dimensions and figure" (p. 245, *S. P.* p. 175).

The special case of an indefinitely extended medium has been treated by Poisson, Cauchy, Green, MacCullagh, Haughton, Blanchet, and Stokes; see our Arts. 523*, 1166*—78*, 917*—21*, 1519*—22*, and 1268*—75*. Rankine gives the principal results which depend upon the fact that in this case for small oscillations we must have

$$a' = b' = c' = 0.$$

See his pp. 246—8 (*S. P.* pp. 176—8).

[435.] Pp. 248—50 (*S. P.* pp. 178—80) deal with the *General Case of a Body of limited Dimensions*. Here the velocity is no longer a function only of the direction-cosines a, b, c of the wave front, but also of a', b', c' . Rankine in these pages gives the shift-speeds, the stretches, the slides and the six stresses as deduced from equations (i). Taking the special case of an isotropic medium (pp. 250—6, *S. P.* pp. 180—184) and the axis of x as direction of propagation, Rankine puts

$$a = 1, b = 0, c = 0, a' = 0,$$

and finds for the velocities of propagation in our notation,

$$\begin{aligned} \sqrt{\epsilon} &= \sqrt{\frac{(\lambda + 2\mu)}{\rho}} \sqrt{1 - b'^2 - c'^2}, \\ \sqrt{\epsilon} &= \sqrt{\frac{\mu}{\rho}} \sqrt{1 - b'^2 - c'^2} \quad (\text{pp. 250—1, } S. P. \text{ p. 181}). \end{aligned}$$

Hence these velocities of propagation are less than in an *unlimited* mass in the ratio $\sqrt{1 - b'^2 - c'^2} : 1$.

[436.] Rankine now remarks that :

It may be shown that the vibrations corresponding to the velocity

$\sqrt{\frac{\mu}{\rho} \sqrt{1 - b'^2 - c'^2}}$ cannot take place in a body of which the surface is free unless $b' = 0$, $c' = 0$, in which case they are reduced to ordinary transverse vibrations (p 251, *S P* p 182)

This is shown in an *Appendix II* (pp 265—7, *S P* pp 197—9) entitled *General Equations of nearly-transverse Vibrations*. Herein Rankine calculates out the surface traction in his prism and shows that if it is to be zero we must have $b' = c' = 0$, and the nearly transverse vibrations become accurately transverse

[437] The vibrations which have the velocity

$$\sqrt{\frac{\lambda + 2\mu}{\rho} \sqrt{1 - b'^2 - c'^2}}$$

are termed by Rankine *nearly longitudinal*, for the longitudinal component predominates, and are dealt with by him on pp 251—4 (*S P* pp 182—4). He finds expressions for the surface stresses and remarks that if we knew “the laws which determine the superficial pressures in vibrating bodies” these expressions would enable us to find b' and c' and so determine the velocity of propagation. “Those laws, however, are as yet a matter of conjecture only.” It seems to me that a reasonable hypothesis is that the surface stress or load vanishes, but even then except in very special cases Rankine’s expressions would probably be too complex to afford any manageable solution of the problem (see two memoirs by Chree, *Quarterly Journal of Mathematics*, Vol xxiii pp 317—42 and Vol xxiv pp 340—58).

For a musical note “the velocity of propagation must be the same for all the elementary vibrations into which the motion may be resolved,” that is to say $b'^2 + c'^2$ must have the same value in all the terms of the expressions for the shifts. This leads Rankine to considerably simplify his equations for the stresses, strains and surface loads in this particular case see his pp 254—6 (*S P* pp 184—7). Rankine does not, however, draw any special conclusions from these simplified results.

[438] Rankine next turns (pp 256—60) to the relation between the velocities of sound in a rectangular horizontal prism of liquid and in an infinite mass of the same liquid, and he shows that on a certain hypothesis as to the surface conditions, based upon his own theory of molecular vortices, these velocities would be in the ratio of $\sqrt{2} / \sqrt{3}$, as indeed Wertheim found them by experiment see our Arts 1349*—51*. Returning to the vibrations of solid rods Rankine, *adopting a hypothesis like that for liquids*, gives results for the cases of rectangular and circular prismatic

rods. Not only are the hypotheses here rather vague but the results do not seem very satisfactory. In the case of the rectangular prism Rankine supposes the lateral vibrations of the particles to take place parallel to one pair of faces of the prism only, and he finds that the same relation holds between the velocities of sound in a solid prism and in an infinite mass as for a liquid. The case of the rod of circular cross-section is investigated in an Appendix I. (pp. 262—5, *S. P.* pp. 193—6), and Rankine concludes that the ratio of $\sqrt{1-b'^2-c'^2}:1$ lies between $\sqrt{1}:\sqrt{2}$ and $\sqrt{2}:\sqrt{3}$, approaching the less value as the diameter of the rod diminishes. Comparison with some experiments of Wertheim and Savart does not give very satisfactory results, and Rankine supposes that the freedom of the lateral vibrations is really limited by the means used to fix the rods so that the ratio of the two velocities generally exceeds $\sqrt{2}:\sqrt{3}$ and sometimes approaches equality. See Chree, *Quarterly Journal of Mathematics*, Vol. XXI. p. 295, and Vol. XXIII. pp. 335, 341.

[439.] Rankine concludes generally that:

(i) In liquid and solid bodies of limited dimensions, the freedom of lateral motion possessed by the particles causes vibrations to be propagated less rapidly than in an unlimited mass.

(ii) The symbolical expressions for vibrations in limited bodies are distinguished by containing exponential functions of the coordinates as factors; and the retardation referred to depends on the coefficients of the coordinates in the exponents of those functions, which coefficients depend on the molecular condition of the body's surface—a condition yet imperfectly understood (p. 261, *S. P.* p. 192).

It seems to me that the proper condition at the body's surface is the vanishing of the stress, but that in most cases of longitudinal vibrations this leads to very complex conditions for the determination of the coefficients of the coordinates in the exponentials. Otherwise I think we may safely agree with these conclusions of Rankine's, and he certainly put the matter in a clearer light than it was left by Wertheim: see our Arts. 1349*—51* and the last memoir of Chree's cited, pp. 324—5.

[440.] W. J. M. Rankine: *On the Vibrations of Plane Polarised Light*. *Philosophical Magazine*, Vol. I. 1851, pp. 441—6 (*S. P.* pp. 150—5). This is an attempt to explain by some rather general reasoning based on Rankine's theory of 'molecular vortices' (or

atomic *nuclei* surrounded by elastic atmospheres see our Art 424) the phenomena of polarised light We only refer to it here to cite the following remarks

For if there is any proposition more certain than others respecting the laws of elasticity, it is this —that the transverse elasticity of a medium, or the elasticity which resists *distortion* of the particles, depends upon the position of the *plane of distortion*, being the same for all directions of distortion in a given plane This law is implicitly involved in the researches of Poisson, of M Cauchy, of Mr Green and others on elasticity (p 441, *S P* p 150)

This can only refer to Theorem II of the memoir of 1850 see our Arts 421—2 As Rankine is here talking of crystalline bodies his statement is erroneous

The keynote to Rankine's researches is to be found in the hypothesis

That the medium which transmits light and radiant heat consists of the *nuclei* of the atoms vibrating independently, or almost independently, of their atmospheres, *absorption* being the transference of motion from the nuclei to the atmospheres, and *emission* its transference from the atmospheres to the nuclei (p 443, *S P* p 152)

The difficulty is then to understand how the ether of space, which must consist of atomic *nuclei* in order to transmit, is still incapable of absorbing

[441] W J M Rankine *General View of an Oscillatory Theory of Light Philosophical Magazine*, Vol VI 1853, pp 403—14 (*S P* pp 156—67) This paper contains no reference to the theory of elasticity, and is rather difficult to follow owing to the suppression of the "strict mathematical analysis" by which its conclusions were deduced

[442] W J M Rankine *On the General Integrals of the Equations of the Internal Equilibrium of an Elastic Solid* This is published in the *Proceedings of the Royal Society*, Vol VII 1856, pages 196—202 It is an abstract of a memoir which was received December 7, 1854 Judging from the abstract the memoir must have been of a very elaborate character but it does not seem to have been ever published see our Arts 454 and 455

After some definitions and general statements apparently

reproducing results of the ordinary theory of elasticity, we are told that the "*Second Section* of the paper relates to the problem of the general integration of the equations of the internal equilibrium of an Elastic Solid, especially when it is *not isotropic*." The solution seems to have been in Cartesian coordinates and obtained in some way by expanding the stresses in trigonometrical series of the three coordinates, but it is extremely difficult to follow the account given.

The *Third Section* appears to have dealt with Lamé's problem of the rectangular prismatic solid (see our Arts. 1079*—80*). Apparently the method consisted only in a long series of what, I should imagine, would be very troublesome approximations (p. 201).

The *Fourth Section* dealt with the general integrals of the equations of elasticity for an isotropic solid.

Finally Rankine insists upon the importance for practical purposes of the distinction between the *cone of shear* and the *cone of slide*. By this I judge that he had in the memoir drawn attention to the facts that the directions of maximum stress and strain do not necessarily coincide, and that rupture does not always take place across the direction of maximum stress: see our Arts. 1367*—8*.

[443.] W. J. M. Rankine: *On Axes of Elasticity and Crystal-line Forms*: *Phil. Trans.* 1856, pp. 261—285 (*S. P.* pp. 119—149). This paper was read on June 21, 1855. It is remarkable for the number of new, and not improbably physically important results relating to the twenty-one elastic constants which it states, as well as for the novel nomenclature which it proposes to introduce.

Unfortunately the writer obtains his results by the application of "that branch of the Calculus of Forms which relates to linear transformations, and which has recently been so greatly advanced by the researches of Mr Sylvester, Mr Cayley, and Mr Boole." I say, unfortunately, as it will rarely happen that the elastician will have made a sufficiently wide study of *invariants*, *covariants*, *contragredients et hoc genus* to understand the processes of this memoir, while terms such as *umbral matrices* and *contra-ordinates* tend at the best to obscure the simple physical principles which

often lie behind the equations. The biquadratics which give the distributions of stretch-modulus and direct-stretch coefficient are no doubt *tasymmetric covariants*, but it may well be questioned whether this is the clearest method of approaching their discussion. Luckily Saint-Venant in his memoir of 1863 has given short and direct proofs of most of Rankine's results bringing out in each case their physical bearing—see our Arts 132—7 which should be compared with Arts 445—7.

[444] Rankine commences with the statement that

As originally understood, the term “axes of elasticity” was applied to the intersections of three orthogonal planes at a given point of an elastic medium, with respect to each of which planes the molecular actions causing elasticity were conceived to be symmetrical.

The next two paragraphs (p 261, *S P* p 119) refer to the peculiar hypothesis of the earlier memoirs—see our Arts 424, 429, etc. The writer states that if the elasticity of solids arose from the action of centres obeying the rari-constant hypothesis or partly from such action and ‘partly from an elasticity like that of a fluid, resisting change of volume only,’ then it is easy to prove that three such planes of symmetry exist in every homogeneous solid. It is not obvious that three such planes would exist in a homogeneous aeolotropic solid with 15 constants, unless we could reduce those fifteen constants in the method of the earlier memoirs, a method which we have seen to be erroneous. Rankine further remarks that there is now no doubt that elastic stress is not such as can be accounted for by fluid elasticity and central intermolecular action as a function of the distance. This of course is merely a declaration of his own multi-constant views, which is somewhat obscured by the reference to “fluid-elasticity.”

Assuming multi-constancy Rankine conveniently defines an axis of elasticity as any direction with respect to which certain kinds of elastic stresses are symmetrical, or

speaking algebraically, *directions for which certain functions of the coefficients of elasticity are null or infinite* (p 261, *S P* p 119).

The former seems a clearer statement than the latter.

[445] We now give a Table of Rankine's nomenclature premising that he adopts $\theta\lambda\psi\mu\varsigma$ to denote strain and $\tau\alpha\sigma\iota\varsigma$ to denote stress.

Table of Tasinomic Coefficients or Constants.

Our notation for constant.	Our name for constant.	Rankine's name for	
		Constant.	Elasticity.
$ xxxx $	Direct stretch	Orthotatic	Direct or Longitudinal
$ xyyy $	Cross stretch		Lateral
$ xyxy $	Direct slide		Rigidities
All other types	—	Plagiotatic	Unsymmetrical

It will be noted that Rankine's nomenclature does not distinguish by special names between a cross slide and a cross stretch-slide coefficient ($|xyyz|$ and $|xxyy|$).

We have further the following surfaces :

Thlipsimetric Surface = stretch-quadric : see our Art. 612*.

Tasimetric Surface = stress-quadric : see our Art. 610*.

Rankine forgets the double sign in writing down these equations: see his p. 264 (*S. P.* p. 122), (3) and (4).

Orthotatic Ellipsoid. If $\iota_{xx}\iota_{yy}\iota_{zz}$ symbolically denote $|xxxx|$ its equation

$$\begin{aligned} & \cdot \iota_{yy} + \iota_{zz}) \{ \iota_{yy} (\iota_{yy} + \iota_{zz} + \iota_{xx}) \} y^2 + \{ \iota_{zz} (\iota_{zz} + \iota_{yy} + \iota_{xx}) \} z^2 \\ & (\iota_{xx} + \iota_{yy} + \iota_{zz}) \{ yz + 2 \{ \iota_{xx} (\iota_{xx} + \iota_{yy} + \iota_{zz}) \} zx + 2 \{ \iota_{xy} (\iota_{xx} + \iota_{yy} + \iota_{zz}) \} xy \\ & - (\iota_{xx} + \iota_{yy} + \iota_{zz}) (\iota_{xx}^2 + \iota_{yy}^2 + \iota_{zz}^2) = 1. \end{aligned}$$

Heterotatic Ellipsoid. This has for equation :

$$\begin{aligned} & \{ |yyzz| - |yzzy| \} x^2 + \{ |zzxx| - |zxzx| \} y^2 + \{ |xxyy| - |xyxy| \} z^2 + 2 \{ |xxxy| - |xxyx| \} yz \\ & + 2 \{ |xyyz| - |yyzx| \} zx + 2 \{ |yyzz| - |zzxy| \} xy = 1. \end{aligned}$$

The three *orthotatic axes* are the principal axes of the orthotatic ellipsoid, the three *heterotatic axes* those of the heterotatic ellipsoid. For the former three axes equations of the type

$$|yzxx| + |yzyy| + |yzzz| = 0$$

hold, and they possess the physical property which we may state in the following words :

At each point of an elastic solid, there is one position in which a cubical element may be cut out, such, that a uniform dilatation of that element by equal stretches of its three dimensions, shall produce no shear on the faces of the element (p. 266, *S. P.* p. 126).

This physical property is not very obviously conveyed in Rankine's method of looking at the orthotatic ellipsoid. It follows at once from Saint-Venant's treatment of the subject : see our Art. 137, (ii).

For the heterotatic axes we have three relations of the type

$$|xxxy| - |xyxz| = 0,$$

and the physical property which we may thus state

*At each point of an elastic solid, there is one position in which a cubical element may be cut out, such that if there be a distortion of that element round (i.e. a slide perpendicular to) x , and an equal distortion round y , the traction on the faces normal to x arising from the distortion round x shall be equal to the shear round z arising from the distortion round y (p 267, *S P* p 126)*

The coefficients of the heterotatic ellipsoid are termed *heterotatic differences*, they vanish on the *isotropic hypothesis* Rankine terms *fluid elasticity* that elasticity for which the heterotatic ellipsoid becomes a sphere, the body is then *heterotatically isotropic*

A body is *orthotatically isotropic* when the orthotatic ellipsoid becomes a sphere

A body which is both heterotatically and orthotatically isotropic is *not completely isotropic* as it has still 11 independent constants

[446] The next surface dealt with by Rankine is what he terms the *biquadratic tasmomic surface*, or

$$\{(\epsilon_x x + \epsilon_y y + \epsilon_z z)^2\}^2 = 1$$

It is the biquadratic which gives the distribution of the direct-stretch coefficient

He terms its coefficients the *homotatic coefficients* Diameters of this surface which are normal to the tangent planes at their extremities are termed *euthytatic axes* (p 268, *S P* p 127) Rankine returns later to the consideration of these axes in *Sections 22—29*

He now proceeds to the dissection of this surface by rectangular linear transformation By this means it is always possible to make three of the terms with odd exponents or three functions of such terms vanish Thus Rankine shows we may find three mutually rectangular axes for which three equations of the type

$$|yyy| = |zzz|$$

hold These axes he terms the *principal metatatic axes* They possess the following property (supposing them to be the axes of x, y, z)

If there be a stretch along y and an equal squeeze along z (or vice versa), no shear will result round x on planes normal to y and z (p 268, *S P* p 128)

Suppose the axes of coordinates to be any whatever, and let y', z' be any other pair of rectangular axes in the plane of y, z , then it is easy to show (by the method of our Art 133) that

$$|yyy| - |zzz| = \{2|yyy| + 4|yyy| - |yyy| - |yyy|\} \frac{\sin 4\omega}{4} + \{|yyy| - |yyy|\} \cos 4\omega$$

where $\omega = \angle yOy'$

Hence, in each plane in an elastic solid, there is a system of two pairs of axes metatatic for that plane and forming with each other eight equal angles of 45° .

If x, y, z be the principal metatatic axes, then $|yyyz| = |zzyz|$ and we see that $|y'y'y'z| = |z'z'y'z|$ when $\omega =$ any multiple of 45° .

Or, in each of the three metatatic planes, there is a pair of diagonal metatatic axes, bisecting the right angles formed by the principal metatatic axes (p. 269, *S. P.* p. 128). These six metatatic axes and their productions are perpendicular to the faces of a rhombic dodecahedron.

A solid is *metatatically isotropic* when for a cubical element cut out in any position, a stretch in the direction of one axis and an equal squeeze along another produce no shear on the faces.

Metatatical isotropy involves three relations of the type

$$2|yyzz| + 4|yzyz| - |yyyy| - |zzzz| = 0$$

for all sets of axes. These expressions are termed *metatatic differences*.

[447.] *Orthotatic Symmetry.* When one and the same set of orthogonal axes are at once orthotatic, heterotatic, metatatic and eutythatic, or the twelve plagiotatic coefficients vanish, the solid is said to possess *orthotatic symmetry*. This reduces the elastic constants to the *nine orthotatic coefficients*.

Cybotatic Symmetry. In addition to orthotatic symmetry let the three direct-stretch coefficients be equal to each other, the three direct-slide coefficients and the three cross-stretch coefficients. In this case the coefficients reduce to three and the symmetry is *cybotatic* (p. 270, *S. P.* p. 130).

The metatatic difference will in this case be equal to

$$2|yyzz| + 4|yzyz| - 2|xxxx|$$

and unless this vanishes the body will not be metatatically isotropic. Green's proposed structure for the ether endowed it with cybotatic symmetry: see our Art. 146.

If the metatatic difference vanishes then cybotatic symmetry reduces to bi-constant isotropy, or what Rankine terms *pantatic isotropy* (p. 271, *S. P.* p. 131).

[448.] Rankine next passes to *Thlipsinomic Coefficients* or those which express strain as a linear function of stress. We may express these coefficients as follows, a, b, c denoting the directions of the axes x, y, z :

$$s_x = (aaaa) \widehat{xx} + (aabb) \widehat{yy} + (aacc) \widehat{zz} + (abbc) \widehat{yz} + (acac) \widehat{zx} + (aabc) \widehat{xy}.$$

If symbolically we put $(aaaa) = \nu_a \nu_a \nu_a \nu_a$ and $\widehat{xx} = \xi_a \xi_a$, $\widehat{yz} = 2\xi_y \xi_z$, we may throw the strain into the form useful for symbolic operations:

$$s_x = \nu_a \nu_a (\nu_a \xi_a + \nu_y \xi_y + \nu_z \xi_z)^2.$$

Rankine gives the following nomenclature

Our notation for constant.	Our name for constant.	Rankine's name for	
		Constant.	Strain property
(aaaa)	Direct traction	Orthothlyptic { Euthythlyptic Platythlyptic Goniorthlyptic Plagiorthlyptic	Longitudinal Extensibility
(aabb)	Cross traction		Lateral Extensibility
(bcbc)	Direct shear		Pliability
All other types	—		Unsymmetrical Pliability

It is easy to see that all the Thlipsinomic axes coincide with the corresponding systems of Tasinomic axes. As a rule platythlyptic (or cross traction) coefficients are negative (p 273, *S P* p 134)

[449] Rankine next proceeds to consider strains and stresses when referred to oblique axes, with a view of dealing more at length with the biquadratic tasinomic surface and the euthytatic axes, see our Art 446. By transformation to oblique (or rectangular) axes he reduces the equation of this surface to its canonical form, in which it has only nine terms, those in y^2z , yz^2 , z^2x , zx^2 , x^2y and xy^2 being removed. This involves the vanishing of six plagiomatic coefficients for that system of axes, namely

$$|yyyz| = |xyyz| = |zzxz| = |xxzx| = |xxyy| = |yyxy| = 0$$

or, as we should say, all the direct stretch slide coefficients are zero. These three axes which always exist but may be oblique or rectangular are termed the *principal euthytatic axes*.

[450] We have next the following classification with regard to forms of euthytatic distribution

(1) If a solid has three oblique principal euthytatic axes making equal angles with each other round an axis of symmetry, and if each of these axes has equal systems of homotatic coefficients, i.e. if the biquadratic tasinomic surface reduce to the form

$$|xxxx| (x^4 + y^4 + z^4) + 2 \{ |yyyz| + 2 |yzyz| \} (y^2z^2 + z^2x^2 + x^2y^2) \\ + 4 \{ 2 |xxxy| + |xxyx| \} xyz (x + y + z) = 1,$$

then the solid is said to possess *rhombic symmetry*, for the three oblique axes are normals to the faces of one rhombohedron. The axis of symmetry must be a fourth euthytatic axis.

(ii) In the limiting case when the three oblique axes make angles of 120° with each other, they lie in the same plane and are normal to the axis of symmetry and to the faces of a hexagonal prism. This is *hexagonal symmetry*.

Rankine (pp 278—9, *S P* pp 140—1) proves various properties

of this kind of symmetry having regard to the existence of other euthytatic axes.

(iii) If a solid has one euthytatic axis (z) normal to the other two (xy) still oblique, these two having equal sets of homotatic coefficients, it is said to possess *orthorhombic symmetry*, its principal euthytatic axes being normals to the faces of a right rhombic prism. A sub-case of orthorhombic symmetry is the existence of further pairs of euthytatic axes in the planes zx , zy . When such exist they are normals to the faces of an *octohedron with a rhombic base*.

(iv) The three principal euthytatic axes being orthogonal, we have *orthogonal symmetry*. This subdivides itself according to the existence of other euthytatic axes in none, all or two of the principal euthytatic planes into a distribution of euthytatic symmetry marked by a rectangular prism, by an irregular rhombic dodecahedron, or by an octohedron with rectangular base.

(v) Orthogonal symmetry with equal sets of homotatic coefficients for each axis is called *cyboïd symmetry*. The three cases corresponding to those of (iv) are marked by a cube, a regular rhombic dodecahedron and a regular octohedron.

(vi) *Monaxal symmetry*. The homotatic coefficients are completely isotropic round one axis. The principal euthytatic axes are the axis of symmetry and all lines perpendicular to it. If other euthytatic axes exist they are normal to the surface of a cone (p. 280, *S. P.* p. 143).

(vii) *Complete isotropy* of the homotatic coefficients is the case in which every direction is an euthytatic axis.

[451.] On pp. 280—1 (*S. P.* pp. 143—4) Rankine classifies the several *primitive forms known in crystallography* on the basis of these various distributions of the euthytatic axes. He makes the following statement:

It is probable that the normals to *Planes of Cleavage* are euthytatic axes of minimum elasticity.

He brings no evidence on this point, and it seems to me somewhat doubtful for the following reasons:

(i) Any biquadratic surface would give a similar system of symmetrical forms, which might be classified in the same manner. Why should the biquadratic which determines the distribution of the direct-stretch coefficient be chosen? Rankine's euthytatic axes correspond to directions in which this coefficient has a maximum or minimum value, and therefore the planes of cleavage would be perpendicular to directions in which the direct-stretch coefficient has a maximum or minimum value.

(ii) It would seem quite as reasonable, if not more reasonable, to choose as our fundamental biquadratic that which gives the distribution of the stretch-modulus (see our Art. 309). For the directions of the

maximum or minimum rays of this figure are those for which a given traction produces a minimum or maximum stretch. But even then it is not yet proven that in an *aeolothropic* body rupture will first occur across the directions of greatest stretch.

(iii) If we put all the stresses zero except \widehat{xx} , we have

$$\begin{aligned} s_x &= (aaaa) \widehat{xx}, & s_y &= (bbaa) \widehat{xx}, & s_z &= (ccaa) \widehat{xx}, \\ \sigma_{yz} &= (bcaa) \widehat{xx}, & \sigma_{zx} &= (caaa) \widehat{xx}, & \sigma_{xy} &= (abaa) \widehat{xx} \end{aligned}$$

The maximum stretch s_x for a given traction \widehat{xx} will thus occur for that direction in which $(aaaa)$ (really $1/E$) is a maximum, but how far will rupture (supposing elasticity to last up to rupture!) be affected by the existence and magnitude of the other components of strain? The magnitude of these depends in each case on the value round the given direction of the plathythptic and plagiorthptic coefficients.

(iv) Thus it would seem to me that if we assume the direction of the greatest stretch for a given traction to determine that of ultimate rupture, then it would be better to form the biquadratic giving the euthythptic coefficient $(aaaa)$ in any direction, and deduce euthythptic instead of euthytatic axes as giving the planes of cleavage. The ultimate planes of cleavage thus obtained may coincide with Rankine's, but the conditions would appear in a different form, and the whole process have a more direct physical meaning.

(v) It must be remarked that some geological writers hold that the planes of cleavage are perpendicular to the directions of maximum or minimum traction. These are not necessarily those in which either the stretch modulus or the direct-stretch coefficient is a maximum or a minimum. Their view would lead to a third method of treating the problem: see our Art. 1367*.

[452] On pp. 282—3 (*S P* pp. 145—7) of the memoir are some general remarks. Thus Rankine notes that the 15 homotatic coefficients on which the euthytatic axes depend, may be considered as independent of the six heterotatic differences on which the heterotatic axes depend. In other words, granting an euthytatic classification of crystals, bodies may have the same crystalline form and yet differ materially in the laws of their elasticity. This would not be possible in the case of *laminar* constant elasticity.

It may be noted that Rankine rejects the hypothesis of the luminiferous ether being a simple elastic medium, as no such medium could give a rotation of the plane of polarisation. He notes also that the refractive action of a crystal on light requires fewer constants than are supplied by the crystal's elasticity.

The memoir concludes with a note on *Sylvestrian Umbrae* (pp. 284—5, *S P* pp. 147—9).

[453] W. J. M. Rankine. *On the Stability of Loose Earth*. This is published in the *Philosophical Transactions* for 1857, pp.

9—27; it was received June 10 and read June 19, 1856: an abstract of it is given in the *Proceedings of the Royal Society*, Vol. VIII., 1857, pp. 185—7.

The memoir employs some of the elementary formulæ of stress in the problem of earthwork. Suppose that the axes of coordinates at a certain point coincide with the principal axes of stress. Let T_1 , T_2 , T_3 be in descending order of magnitude, and let them denote the *principal tractions*. Take the plane which contains the directions of T_1 and T_3 ; and in that plane suppose a straight line making an angle ψ with the direction of T_1 : consider the stress on the plane at the point which is normal to the straight line. Denote this stress by R ; let P be the tractive, Q the shearing component of R ; and let θ denote the angle between the directions of P and R . Then put

$$S = \frac{1}{2}(T_1 + T_3), \quad D = \frac{1}{2}(T_1 - T_3);$$

and it will be found that the following results are easily deduced from the elementary formulæ of stress:

$$P = S + D \cos 2\psi, \quad Q = D \sin 2\psi,$$

$$\tan \theta = \frac{D \sin 2\psi}{S + D \cos 2\psi};$$

the maximum value of θ is $\sin^{-1} D/S$, and it occurs when

$$\psi = \frac{\pi}{4} + \frac{1}{2} \sin^{-1} \frac{D}{S}.$$

[454.] In the *Comptes rendus*, Vol. L., 1860, p. 235, there is a note of the *Grand Prix de mathématiques*. This had been offered for the second time in 1857, for a solution of the following problem:

Trouver les intégrales des équations de l'équilibre intérieur d'un corps solide élastique et homogène dont toutes les dimensions sont finies, par exemple d'un parallélépipède ou d'un cylindre droit, en supposant connues les pressions ou tractions inégales exercées aux différents points de sa surface.

The commissioners were Liouville, Lamé, Duhamel and Bertrand. The problem for the right six-face was first proposed by Lamé: see our Arts. 1079*—80*.

Two memoirs were sent in, but as neither of them contained the solution of the question proposed, the prize was not awarded

but proposed again for 1861. One of these memoirs was, I believe, due to Rankine. "In 1857 he also sent to the French Academy of Sciences a memoir,—*De l'Équilibre intérieur d'un corps solide, élastique, et homogène*" See the *Memoir* of Rankine by P. G. Tait prefixed to the *Miscellaneous Scientific Papers*, p. xxiii.

This is probably closely connected with the paper of which an abstract is given in the *Proceedings of the Royal Society* see our Art 442. Its non-publication and the failure at Paris suggest that the analysis was probably defective as well as lengthy. A portion only of the Paris paper was afterwards in 1872 communicated to the Royal Society of Edinburgh and is published in the *Transactions* Vol. xxvi see our Arts 455—62.

[455] W. J. M. Rankine *On the Decomposition of Forces externally applied to an Elastic Solid* *Transactions of the Royal Society of Edinburgh*, Vol. xxvi, 1872, pp. 715—27.

The author writes

The principles set forth in this paper, though now (with the exception of the first theorem) published for the first time, were communicated to the French Academy of Sciences fifteen years ago, in a memoir entitled *De l'Équilibre intérieur d'un corps solide, élastique, et homogène*, and marked with the motto, "Obvia conspicimus, nubem pellente Mathesi," the receipt of which is acknowledged in the *Comptes rendus* of the 6th April, 1857.

See our Arts 442 and 454.

The memoir is like nearly all Rankine's papers, extremely suggestive, and rich in terminology, amounting in this case to very unnecessary verbosity.

[456] The memoir opens with the statement of the following theorem (which had been given in the *Philosophical Magazine*, Vol. x, p. 400, 1855)

Every self balanced system of forces applied to a connected system of points is capable of resolution into three rectangular systems of parallel self balanced forces applied to the same points (p. 715).

The three rectangular axes to which the three systems of self balanced forces are parallel are termed *isorrhopic axes*. Rankine proves the proposition by appeal to the theory of covariants. But it is easily proved *ab initio*. Let X, Y, Z be the components of force acting on the point x, y, z . Then for equilibrium we must have

$$\Sigma X - \Sigma Y = \Sigma Z = 0,$$

$$\Sigma (Yz - Zy) = \Sigma (Zx - xZ) - \Sigma (Xy - Yx) = 0$$

Consider the line drawn through the origin with direction-cosines l, m, n , then the force at x, y, z parallel to this line is $lX + mY + nZ = P$ say. Let r be the distance between the origin and x, y, z ; let ϕ be the angle between r and (l, m, n) . Then the quantity $rP \cos \phi$ is independent of the directions of the coordinate axes and consequently

$$\Sigma rP \cos \phi$$

is (a covariant or) the same in form for all systems of rectangular axes through the origin. But it equals

$$\Sigma (lx + my + nz) (lX + mY + nZ) = l^2 \Sigma Xx + m^2 \Sigma Yy + n^2 \Sigma Zz \\ + mn \Sigma (Yz + Zy) + nl \Sigma (Zx + Xz) + lm \Sigma (Xy + Yx).$$

Putting with Rankine :

$$\Sigma Xx = A, \quad \Sigma Yy = B, \quad \Sigma Zz = C, \\ \Sigma Yz = \Sigma Zy = D, \quad \Sigma Zx = \Sigma Xz = E, \quad \Sigma Xy = \Sigma Yx = F,$$

we have this equal to

$$Al^2 + Bm^2 + Cn^2 + 2Dmn + 2Enl + 2Flm.$$

But there are three rectangular directions, namely those of the principal axes of the quadratic surface :

$$Ax^2 + By^2 + Cz^2 + 2Dyz + 2Ezx + 2Fxy = 1 \dots \dots \dots (i),$$

for which $D = E = F = 0$, in this expression.

Hence there are three directions for which :

$$\Sigma X = 0, \quad \Sigma Xy = 0, \quad \Sigma Xz = 0, \\ \Sigma Y = 0, \quad \Sigma Yz = 0, \quad \Sigma Yx = 0, \\ \Sigma Z = 0, \quad \Sigma Zx = 0, \quad \Sigma Zy = 0,$$

which proves the theorem.

Rankine terms (i) the *Rhopimetric Surface*; its coefficients the *Rhopimetric Coefficients*; its principal axes are the *Isorrhopic Axes* and the corresponding values of A, B, C the *Principal Rhopimetric Coefficients*. An *Arrhopic System* of forces is defined as one for which *all* the rhopimetric coefficients are zero. Rankine adds that in this case every axis is an isorrhopic axis, but the proper and sufficient conditions for this are that $A = B = C$, while $D = E = F = 0$.

[457.] Rankine next applies his theory of isorrhopic axes to reduce any load system applied to an elastic solid to three separate self-balanced systems of parallel loads and thus the problem of elastic equilibrium to the solution of three separate cases of parallel loading. He justifies this reduction by remarking that although we may not in the treatment of an elastic solid transfer the point of application of a force to *any* point in the line

of action of the force, we may still resolve each force at its point of action into components in different directions, or

When the straining forces to which an elastic solid is subjected are restricted within certain limits, the straining effect of any number of self balanced systems of forces combined is sensibly equal to the sum of the effects which those systems respectively produce when acting separately (p 716)

If X, Y, Z be the body-forces at x, y, z , X', Y', Z' the components of load at x', y', z' on the element dS of surface, then the rhopimetric coefficients for an elastic solid will be given by formulae of the type

$$\left. \begin{aligned} A &= \iiint x X \rho dx dy dz + \iint x' X' dS \\ D &= \iiint z Y \rho dx dy dz + \iint z' Y' dS \\ &= \iiint y Z \rho dx dy dz + \iint y' Z' dS \end{aligned} \right\} \quad (u),$$

whence the isorrhopic axes can be found (p 717)

[458] After reproducing the body- and surface-stress equations in Lamé's notation, Rankine proceeds to remove the terms involving terrestrial gravitation from the body stress equations. Such gravitation is usually the only body force which occurs in elastic problems. Take the plane of yz horizontal through the centroid of the body and the axis of x vertically downwards, then by assuming

$$\widehat{xx} = \widehat{xx}' - g\rho x,$$

we cause the body forces to disappear from the differential equations

The first surface-stress equation now becomes

$$X' = l(\widehat{xx}' - g\rho x') + m\widehat{xy} + n\widehat{xz}$$

Hence a system of surface tractions given by

$$X' = -g\rho l x', \quad Y' = 0, \quad Z' = 0,$$

would just balance the weight of the body. We may thus withdraw the weight of the body from our consideration of the problem, if we take away from the internal stress \widehat{xx} found after removal of the gravitation terms the quantity $g\rho x'$, and further suppose the surface load increased by the component $g\rho l x'$ parallel to the axis of x .

This system of surface and body load is according to Rankine anihopic, for from (u)

$$B = C = D = E = F = 0$$

Further

$$\begin{aligned} A &= \iiint x g \rho dx dy dz + \iint x' (-g\rho x' l) dS \\ &= g\rho \{ \iiint x dx dy dz - \iint x' l dS \} \end{aligned}$$

Now the first integral vanishes since the plane of yz passes through the centroid and the second term also, Rankine says, if we remember the changes in sign of l . But this seems to me only true if the surface is symmetrical about the plane of yz .

The system of surface-loads which forms with the gravitation of a body an arrhopic system, Rankine terms an *antibarytic* load-system ('antibarytic pressures') and the corresponding body-stresses are *antibarytic stresses*.

The system of stresses left after taking away the antibarytic stresses from the actual stresses at the several elements of a body's surface are termed *abarytic stresses* ('abarytic pressures') (p. 719).

The internal stresses corresponding to an abarytic system of surface loading satisfy equations of the type :

$$\frac{d\widehat{xx}}{dx} + \frac{d\widehat{xy}}{dy} + \frac{d\widehat{xz}}{dz} = 0.$$

[459.] The memoir next proceeds to an analysis of abarytic load-systems. Rankine gives the following definition: An abarytic surface-load which produces uniform stress throughout an elastic solid is termed *homalotatic*. An abarytic system may be broken up into a homalotatic system and an arrhopic system in the following manner. Calculate the six rhopimetric coefficients and assume the internal stresses to be equal to these coefficients divided by the volume of the solid, i.e. take

$$\begin{aligned}\widehat{xx} &= A/V, & \widehat{yy} &= B/V, & \widehat{zz} &= C/V, \\ \widehat{yz} &= D/V, & \widehat{zx} &= E/V, & \widehat{xy} &= F/V.\end{aligned}$$

These satisfy the body-stress equations and give for the surface load

$$X' = \frac{1}{V} (lA + mF + nE),$$

$$Y' = \frac{1}{V} (lF + mB + nD),$$

$$Z' = \frac{1}{V} (lE + mD + nC),$$

or, a homalotatic system of surface-load.

The rhopimetric coefficients for this surface-load are of the type :

$$\begin{aligned}A_0 &= \iint x X' dS \\ &= \frac{1}{V} \{ A \iint x l dS + F \iint x m dS + E \iint x n dS \} \\ &= \frac{1}{V} A V = A,\end{aligned}$$

for,

$$\iint x m dS = \iint x n dS = 0.$$

Thus the rhopimetric coefficients of the homalotatic system are equal to those for the complete abarytic system, or if the homalotatic system be subtracted from the abarytic system we must be left with a pure arrhopic system. (pp. 720—1).

Rankine remarks that the above homalotatic system of six uniform stresses really denotes the *mean state of stress* of the whole body. It

may be remarked that the axes of principal traction of the homalotatic system are the isorrhopic axes of the complete abarytic system

[460] By following out the operations indicated in the above articles we reduce any system of load applied to an elastic body to the solution of a problem in airhopic loading. Thus the reduction of the load system into three rectangular systems of parallel load can be made for any three rectangular axes, for example, for axes parallel to the axes of figure of a body, which will as a rule considerably simplify the problem (p 722)

[461] The next section of the memoir investigates those cases in which internal stress is independent of the coefficients of elasticity of the solid. Rankine concludes that when the shifts can be expressed by algebraic functions of the coordinates not exceeding the second degree, and consequently the stresses by constants and linear functions of the coordinates, this result will follow. The stresses will then be of the type

$$\widehat{xx} = c_1 + e_1x + f_1y + g_1z,$$

$$\widehat{yz} = c_4 + e_4x + f_4y + g_4z$$

Rankine gives no general name to stresses of this type¹, but classifies them as follows

The constant terms c_1, c_4 etc correspond to a *homalotatic* load-system

The coefficients e_1, f_2, g_3 are equivalent to an *antibarytic* load-system

The coefficients $f_1, g_1, e_2, g_2, e_3, f_3$ correspond to a *homalocamptic* load system, or to stresses due to uniform bending

The coefficients e_4, f_5, g_6 correspond to a *homalostrephic* load system or to stresses due to uniform twisting (pp 723—4)

Rankine shows that both homalocamptic and homalostrephic load-systems are airhopic (pp 724—5). He does not discuss or give a name to the stresses arising from f_4, g_4, e_5, g_5, e_6 and f_6

[462] In conclusion Rankine takes (pp 725—7) two simple examples of homalocamptic and homalostrephic stresses. The first embraces practically the Euler Bernoulli theory of flexure, and the second the torsion of an elliptic cylinder allowing for the distortion of the cross sections

The latter investigation starts from the assumption that

$$\widehat{xz} = by, \quad \widehat{xy} = cz,$$

where b and c are undetermined constants. Rankine determines them erroneously, for in line 19 of p 727 he puts $y/p + z/q = 1$, which

¹ Catching for a moment Rankine's mania for nomenclature we might term all the cases in which the stresses are linear functions of the coordinates cases of *cathygrammic* stress

does not hold as his point y , z is not on the perimeter of the elliptic cross-section. Had he noted this he would have found just *double* the values he gives for \widehat{xz} and \widehat{xy} in equation (22), and these would then have been in agreement with the results of Saint-Venant as cited in our Art. 18. I do not understand the remark as to Cauchy with which the memoir closes. These two examples are, however, of little importance.

[463.] W. J. M. Rankine: *On the Stability of Factory Chimneys. Proceedings of the Philosophical Society of Glasgow*, Vol. IV, pp. 14—18, Glasgow, 1860. This paper treats only of the effects of the wind and of the weight of the chimney, and does not discuss its elastic strength even in the matter of crushing due to the weight of the chimney itself. It is a simple problem in statics which is here dealt with, and can be easily solved by an appeal to the theory of the core: see our Art. 815* and Vol. I., p. 879.

[464.] W. J. M. Rankine: *A Manual of Applied Mechanics*. London, 8vo. 1858—1888. The first edition of this work was published in 1858 and the twelfth in 1888 edited by W. J. Millar. The first edition contains xvi + 640 pages and the twelfth xiv + 667 pages. The chief additions made by the Editor are contained in the Appendix. My references will be to the pages of the more readily accessible twelfth edition. The work itself is important in the history of elasticity, for it was among the first to bring the theory of elasticity in a scientific form before engineering students. Rankine himself writes in his preface:

A branch of Mechanics not usually found in elementary treatises is explained in this work, viz., that which relates to the equilibrium of stress, or internal pressure, at a point in a solid mass, and to the general theory of the elasticity of solids. It is the basis of a sound knowledge of the principles of the stability of earth, and of the strength and stiffness of materials; but so far as I know, the only elementary treatise on it that has hitherto been published is that of M. Lamé (p. iii).

We will briefly note the several parts of this work which treat of our subject, commenting on anything which seems to have been novel at the date of its publication.

[465.] Pp. 68—127 deal with stresses in solids and deduce those in liquids as a special case.

(a) Rankine, as in his memoir of 1855, reserves the term *stress* for the dynamic aspect of elasticity, strain for its geometrical aspect. A further progress in differentiation of terms is made by defining *shear* as tangential stress, i.e. ceasing to treat it as a name for strain. see our Vol. I, p. 882

(b) Rankine deals with such problems as 'centres of stress' (load points), 'neutral axis,' 'conjugate stresses' and the relation of these quantities to moments of inertia (pp. 71—85). He gives general expressions for the traction and shear across any plane (pp. 92—3) and for the discovery of the principal tractions. He deals with the special case so important in practice of uniplanar stress (pp. 95—112) and with the 'ellipse of stress'. His treatment of this subject is the fullest which, I think, had been given at the time of publication of his work, and his discussion of stress centres although a little later than that of Bresse (see our Arts. 815* and 516) was probably worked out quite independently. Thus, if the system of stress in a plane be given by \widehat{xx} , \widehat{yy} , \widehat{xy} referred to rectangular axes in the plane, and n denote the normal to any plane perpendicular to this plane and t the trace of these two planes, Rankine shows that

$$\widehat{nn} = \widehat{xx} \cos^2 (xn) + \widehat{yy} \sin^2 (xn) + 2\widehat{xy} \cos (xn) \sin (xn),$$

$$\widehat{nt} = \frac{1}{2}(\widehat{xx} - \widehat{yy}) \sin 2 (xn) - \widehat{xy} \cos 2 (xn),$$

whence he easily deduces the properties of the principal uniplanar tractions and of the ellipse of stress, and applies them to a variety of special problems. Most of his results have found their way into other text-books and papers sometimes with scanty acknowledgement, I may cite in this matter a dissertation by Kopytowski *Ueber die inneren Spannungen in einem freiaufliegenden Balken*, pp. 1—17

(c) I may draw special attention to the Problem on pp. 110—12 entitled *Combined stresses in one plane. Given the normal intensities and directions of any number of simple stresses whose directions are in the same plane, required the directions and intensities of the pair of principal stresses [tractions] resulting from their combination*

Let the principal tractions be T_1 and T_2 , and let the first make an angle ϕ with the axis of x , x and y being two arbitrary rectangular axes taken in the plane of the stresses

Let p , p' denote the normal intensities of any two of the given stresses, then Rankine shows that

$$T_1 + T_2 = \Sigma (p),$$

$$T_1 - T_2 = \sqrt{\Sigma (p) + 2\Sigma \{pp' \cos 2 (pp')\}},$$

$$\tan 2\phi = \frac{\Sigma \{p \sin 2 (xp)\}}{\Sigma \{p \cos 2 (xp)\}}$$

Thus the intensities of the principal tractions can be found without assuming planes of reduction, but to find their directions requires us to do this

(d) On pp. 112—127 we have the body-stress equations deduced and a few special applications to fluids etc.

(e) The theory of uniplanar stresses developed in the previous sections is applied on pp. 129—269 to framework, arches, buttresses, earth-pressure, domes, masonry and brick-work of all kinds. This involves a considerable discussion of the properties of the core (see our Art. 815*) which is not however referred to directly by name. The topics discussed fall outside the limits of our present subject.

[466.] Chapter III. entitled: *Strength and Stiffness*, occupies pp. 270—377 and forms for its date an excellent practical treatise on the technical side of elasticity. We can only note a few

As usual Rankine strives to give scientific definiteness terms which are in wide but rather vague use. Thus for he proposes the following nomenclature for the fracture with characteristic kinds of strain (p. 272):

	<i>Strain.</i>	<i>Fracture.</i>
Longitudinal	{ Extension [Stretch]	Tearing
	{ Compression [Squeeze]...	Crushing and Cleaving.
Transverse	{ Distortion [Slide].....	Shearing
	{ Torsion	Wrenching [Twisting]
	{ Bending	Breaking across [Snapping].

This analysis of the more usual forms of strains is convenient, but objection might well be taken to some of the words for fracture; thus a *wrenching* fracture is associated in our minds rather with a combination of torsion and pull than with pure torsion¹. Perhaps the term 'twisting fracture' would be less liable to misinterpretation. 'Breaking across fracture' is also rather cumbersome and might be more briefly termed *snapping*.

(b) Rankine's discussion and definitions of perfect and imperfect elasticity and of set (pp. 272—3) are perhaps not wholly satisfactory in the light of more recent knowledge, but his further definitions require notice:

(i) The *Ultimate Strength* of a solid is the stress required to produce fracture in some specified way. [This is now usually termed *absolute strength*.]

¹ I should prefer to retain the name *wrench* for the stress side of the strain combined of a stretch and a torsion (which might perhaps be called a *wring*). We might then scientifically appropriate *sprain* for the set-strain produced by a wrench.

(ii) The *Proof Strength* is the stress required to produce the greatest strain of a specific kind consistent with safety, that is with the retention of the strength of the material unimpaired. A stress exceeding the proof strength of the material, although it may not produce instant fracture, produces fracture eventually by long continued application and frequent repetition (p 273)

This definition of proof strength is not scientifically very accurate, for it neither suggests the method nor shows the possibility of its determination. In many cases we may have set without any reduction of absolute strength, and thus proof strength is not by any means measured by the elastic limit. Rankine notes this and remarks (p 274)

(iii) The determination of proof strength by experiment is now, therefore, a matter of some obscurity, but it may be considered that the best test known is the *not producing an increasing set by repeated application*

Obviously this is merely a negative test and could only be successful in ascertaining the proof strength of a given piece of material, after the material had been rendered unfit for further use. Rankine defines strength whether ultimate or proof, as the product of two quantities, *Toughness* and *Stiffness*

(iv) *Toughness*, ultimate or proof, is here used to denote the greatest strain which the body will bear without fracture or without injury as the case may be

(v) *Stiffness*, which might also be called *hardness*, is used to denote the ratio borne to that strain [toughness] by the stress required to produce it

Thus while toughness is measured as a strain, stiffness is measured by a tasinomic (or elastic) coefficient of some particular kind. It does not seem correct, however, to identify hardness with this conception of stiffness

(vi) *Malleable* and *ductile* solids have ultimate toughness greatly exceeding their proof toughness

(vii) *Brittle* solids have their ultimate and proof toughness nearly equal

(viii) *Resilience* or *Spring* is the quantity of mechanical work required to produce the proof strain, and is equal to the product of that strain by the *mean stress* in its own direction which takes place during the production of that strain,—such stress being either exactly or nearly equal to one half of the stress corresponding to the proof strain p 273

It would be better to distinguish between absolute, proof and elastic resilience, and then perhaps to reserve the word *spring* for the latter only: see our Vol. I., p. 875, and Art. 340.

(ix) *Pliability* (Extensibility, Compressibility, Flexibility, to which we might add Shearability and Twistability) is a general term used to denote the inverse of *stiffness*. It is accurately measured by a *thlipsinomic coefficient* (p. 273).

(x) *Working Stress* on the material of a structure is made less than the proof strength in a certain ratio to be determined by practical experience, in order to provide for unforeseen contingencies (p. 274).

Such a ratio is termed a *factor of safety*. The ratios of the ultimate strength to the proof strength and to the working stress are also termed *factors of safety*. There is a table of such factors on p. 274.

[467.] Rankine now turns to the mathematical theory of elasticity, especially to the discussion of strains, strain-energy, and the usual problems of technical elasticity. He considers that the generalised Hooke's Law is "fulfilled in nearly all the cases in which the stresses are within the limits of proof strength—the exceptions being a few substances very pliable, and at the same time very tough, such as caoutchouc" (p. 275). This statement seems practically to identify the proof strength with the limit of linear elasticity—an identity which itself seems to be the exception rather than the rule: see our Arts. 850*—5*, 857*, 1217*, 1296*, and Vol. I., p. 891, Note D.

We may remark that the *Manual* uses *isotropic* and *amorphous* as synonymous terms (p. 278). This is not in accordance with the terminology of the present work: see our Arts. 4 (η), 115, and 142, 230.

[468.] Rankine (pp. 280—3) discusses at some length uniplanar strain and the ellipse of strain. He works out problems of hollow, cylindrical and spherical shells and obtains results corresponding to those of Lamé but he uses only elementary processes. He adopts, however, (pp. 293 and 296) stress limits of strength: see our Arts. 1013*, 1016*, and footnotes. He gives the variation of the cross-section for a doubly built-in heavy beam of 'uniform strength': see his p. 336 and our Art. 5(e), and then passes to shearing-stress and strength (as in rivetted joints of all kinds), to compression and crushing (splitting, shearing, bulging, buckling, cross-breaking), to flexure (bending moment, shear and transverse strength, i.e. snapping), to beams of equal and greatest strength (solids of *equal resistance*, etc.) and to *Lines of Principal Stress in Beams*. These are treated on the supposition that the stress-system of a beam under flexure is uniplanar, but the researches of Saint-Venant have shown this to be incorrect: see our Arts. 99—100. Such lines of stress as are figured by Rankine on p. 342 and are to be found in many practical

text-books, are therefore even in the most favourable cases, e.g. the thin web of a girder, only rough approximations. Similarly Rankine's treatment of the influence of slide when combined with flexure in producing deflection is erroneous see our Art 556 and our discussion below of Winkler's memoir of 1860. Then follow a number of problems on the elastic line for various beams which do not call for special notice. This section of the chapter concludes with a reference to the 'Hydrostatic Arch' first fully discussed by Yvon-Villarceaux. Its equation may be written

$$Py = E\omega\kappa^2/\rho,$$

where ρ is the radius of curvature at any point of the elastic line, $E\omega\kappa^2$ is the flexural rigidity, P a constant and y the depth of a point on the elastic line below a fixed horizontal. Its full investigation obviously requires elliptic functions see Rankine's p. 353 and compare his pp. 190—5 for the treatment by elliptic functions.

[469] Rankine next passes to *Torsion* and *Combined Torsion and Bending* with little to be noted, then to *Crushing by Bending*. Here a formula of the type

$$P = \frac{T_0\omega}{1 + c \frac{l^2}{h^2}}$$

is given for the strength P of a pillar or column of length l and least diameter h , cross section ω and tensile strength T_0 , c being an empirical constant depending on the material. Rankine apparently gives T_0 absolute, proof, or working stress values and considers that corresponding values will thus be obtained for P . He states that this formula was first proposed by Tredgold and afterwards revived by Gordon, who determined the values of c from Hodgkinson's experiments. For pillars with both ends *rounded* instead of built in we must take $4c$ for c (pp. 361—3).

This part of Rankine's book concludes with a discussion of various kinds of girders and some miscellaneous remarks on strength and stiffness. A considerable number of useful practical tables of elasticity and of strength of various materials will be found in the pages of the work as well as in the *Appendix*¹.

[470] The last portion of the *Applied Mechanics* which refers to our subject is the fourth chapter of Part V entitled *Motions of Phable Bodies*, pp. 552—65. It treats briefly of bodies attached to light springs the inertia of which is neglected and to a few cases of elastic vibrations. There appears to be no novelty in it.

On the whole Rankine's *Applied Mechanics* may be taken as a book which was a very distinct advance on any work previously

¹ The latter contains also in the later editions a sufficient discussion of the analytical treatment of continuous beams and of Clapeyron's theorem.

published professing to deal with the problems of technical elasticity. Such works as these of Rankine and Weisbach separate very distinctly the first decade of our half-century from the previous thirty years. The step to them from books of the type of Tredgold's is very great and marks the beginning of the era of 'technical education.'

[471.] In Vol. I. of the *Abhandlungen der math.-phys. Classe der Königlich sächsischen Gesellschaft der Wissenschaften*, Leipzig, 1852, pp. 133—168, is a memoir by Seebeck entitled: *Ueber die Querschwingungen gespannter und nicht gespannter elastischer Stäbe*. The memoir itself is due to the year 1849, and belongs essentially to the theory of sound. Let m be the mass per unit length of the bar, $E\omega\kappa^2$ its rigidity and P the longitudinal stress, then the equation for the transverse displacement y at distance x from a terminal is :

$$m \frac{d^2 y}{dt^2} = -E\omega\kappa^2 \frac{d^2 y}{dx^2} + P \frac{d^2 y}{dx^2} \dots\dots\dots (i).$$

Seebeck thus omits the effect of the angular rotation of the sections of the rod. His equation may be compared with the fuller equation given by Donkin: *Acoustics*, p. 168. Seebeck first sets $P = 0$, and finds in this case from the resulting equation loops, the nodes etc., for the six possible variations among fixed, free and supported terminals. His numerical results are of very considerable value, and have been largely used by later writers on sound.

[472.] The second part of the memoir deals with the vibrations of stretched rods, and the particular point of interest is the modification in tone produced by the stiffness of musical strings. There are two cases which Seebeck deals with, and which have formed the subject of experiments: (i) both ends pivoted, (ii) both ends clamped. (The third case, one end pivoted and one clamped, can of course be deduced from the latter of these by doubling the length of the rod.) In the former case Seebeck shows that

$$n^2 = \frac{i^2 \pi^2}{l^2} \left(\frac{P}{m} + \frac{E\omega\kappa^2}{l^2} \right) = n_1^2 \left(1 + i^2 \pi^2 \frac{E\omega\kappa^2}{Pl^2} \right) \dots\dots\dots (ii)$$

$$= n_1^2 + n_0^2 \dots\dots\dots (iii),$$

where $n/2\pi$ is the frequency of vibrations of the stretched rod, $n_0/2\pi$ the frequency without the stretch, $n_1/2\pi$ the frequency for the rod treated as a flexible string under tension P , l the length of the rod and i any integer. This result is the law stated by N. Savart and deduced

theoretically by Duhamel, but which *only* holds for pivoted terminals Savart's experiments were, however, made with rods with *clamped* terminals see our Art 1228*

Obviously the stiffness of a doubly-fixed string destroys the harmonic character of its tones

Passing to the case of a doubly clamped rod Seebeck shows that (11) does not hold and that the determination of the notes is much more complex For the case, however, of the not too high sub tone 2 of a stiff string or flexible rod, he finds

$$n^2 = n_1^2 \left\{ 1 + 4 \left(\frac{E\omega\kappa^2}{Pl^2} \right)^{\frac{1}{2}} + (12 + 2\pi^2) \frac{E\omega\kappa^2}{Pl^2} \right\} \quad (1v),$$

where the notation is the same as in the previous case (p 162) Thus in this case we have two different effects, the purity of the harmonics is destroyed by the stiffness and all the notes are raised in pitch

Both Donkin and Lord Rayleigh refer to Seebeck's memoir, but it is somewhat singular that Donkin misstates the result (1v), and Lord Rayleigh while questioning Donkin's conclusion does not note that Seebeck has really settled the point Lord Rayleigh possibly had not been able to see Seebeck's memoir and perhaps Donkin, whom he follows, had read it somewhat carelessly The following are the passages in question

Donkin gives (1v) without the last term of the curled bracket and after comparing it thus mutilated with (11) remarks

We see that they differ essentially, especially in this respect, that, in the case (1v) of *fixed faces* the pitch of all the component tones is raised, by the rigidity, through the same interval, so that they do not cease to form a harmonic series, whereas in the other case (11) each tone is raised through a greater interval than the next lower one, and the series is therefore no longer strictly harmonic (*Acoustics*, p 182)

Lord Rayleigh on the other hand, after giving equation (1v) in Donkin's form, remarks

According to this equation the component tones are all raised in pitch by the same small interval, and therefore the harmonic relation is not disturbed by the rigidity It would probably be otherwise if terms involving $\kappa^2 l^2$ were retained, it does not therefore follow that the harmonic relation is better preserved in spite of rigidity when the ends are clamped than when they are free, but only that there is no additional disturbance in the former case though the absolute alteration of pitch is much greater (*Theory of Sound*, Vol I p 245)

It is to be hoped that this oversight will not lead any one to repeat needlessly Seebeck's investigation

[473] Seebeck shows that the correction for stiffness is extremely small in most practical cases (p 163) For example, on his own lecture room mono-chord, the 27th tone was the first that differed from harmonic purity by as much as a comma ($\frac{1}{10}$)

There is an appendix to the memoir giving an account of some

experiments of Seebeck's on the tones of doubly-clamped stiff cords He considers that experiment and theory (as represented by (iv)) are in close agreement (pp. 164—168).

[474.] A passage in Seebeck's memoir (p. 136 ftn.) refers to the changes in amplitude of vibration produced by causes which are neglected in Equation (i) of our Art. 471. He remarks that one of these causes is elastic after-strain, and refers for a further discussion on this point to the *Programm der technischen Bildungsanstalt zu Dresden*, 1846. This latter contains an excellent little paper by Seebeck on the various methods which have been used for determining the stretch-modulus and the character of the errors to which they are liable. It is entitled: *Ueber Schwingungen, mit besonderer Anwendung auf die Untersuchung der Elasticität fester Körper* (pp. 1—40). Therein will be found lists very complete at that date of the stretch-moduli of various materials obtained by both statical and vibrational methods, as well as a fairly comprehensive list of experimental investigations on this point. One or two statements deserve special notice: see my foot-note Vol. I. p. 756.

(a) Seebeck discusses (pp. 9—13) the effect of a constant frictional force and of an air-resistance proportional to the velocity in reducing the amplitude of oscillation of an elastic body.

(b) He carefully distinguishes between the 'imperfect elasticity' which arises from set and that which arises from elastic after-strain. He points out that Wertheim's statement that all bodies, even under the feeblest stress, receive set (see our Arts. 1296* and 1301*, 7° and 8°) does not prove anything more than the fact that Wertheim's material had not been reduced to a state of ease (p. 29); and he remarks how absurdly confusing is the term 'perfectly elastic' as used in the text-book theory of the impact of spherical and other bodies (pp. 28 and 31).

(c) He attributes the reduction in amplitude of vibration, even in metals, in a great extent to elastic after-strain, at the same time expanding and developing Weber's arguments: see our Art. 712*.

(d) He considers that the effect of elastic after-strain must be to render the value of the stretch-modulus as determined by statical measurement smaller than the value obtained from vibrations:

Denn während der kurzen Dauer einer Schwingung kann nur der kleinste Theil der Nachwirkung in Thätigkeit treten, dagegen sie bei der längeren Dauer des statischen Versuchs die gemessene Dehnung merklich vergrößern und daher einen kleineren Modulus geben muss (p. 34).

(e) He holds that the effect of after strain was mingled with the temperature effect in the experiments of Weber and Wertheim referred to in our Arts 705* and 1297*. Hence those results must give too great a difference between the specific heats at constant pressure and constant volume. The objection applies perhaps more strongly to Wertheim's than to Weber's mode of experimenting. See the remarks of Clausius referred to in our Art 1398*—1405*.

(f) Finally I may note a little scrap of historical information bearing on the problem of impact which Seebeck gives on p. 32. He points out that Daniel Bernoulli had attempted to calculate the loss of kinetic energy in the form of elastic vibrations which occurs when a body strikes centrally and transversely a free rod. Bernoulli came to the conclusion that $\frac{5}{9}$ of the total energy before impact would be taken up as elastic vibrations in the rod. His investigation is based upon the assumption that the rod will be bent into the form corresponding to its deepest tone. Bernoulli's memoir is published in the *Novi Commentarii Acad. Petropol.* Tom xv p. 361, 1770. It may be taken as the first attempt to treat impact elastically, and the primary step in investigations which have been so ably followed up by Poisson, Cauchy, Saint-Venant, F. Neumann, Boussinesq and Hertz: see our Arts 203—20, 401—7, 410—14 and subsequent articles in this History.

[475] Seebeck also contributed papers treating of the theory of the vibrations of elastic bodies to Dove's *Repertorium der Physik*, Bd vi pp. 3—100, Berlin, 1842, and Bd viii pp. 1—108 (*Akustik*, separate pagination), Berlin, 1849. These papers deal principally with the theory of sound, and may even yet be read with interest. I would call attention especially to pp. 52—4 of the latter paper wherein Seebeck draws attention to Savart's *etwas kunstlichen und nicht einwurffreien Vorstellung* of the mode in which combined longitudinal and transverse vibrations displace the sand on a vibrating rod: see our Art 327*. These pages are entitled *Ueber die Sandanhäufungen auf longitudinal-schwingenden Körpern*. Seebeck's theory causes the sand to accumulate at the nodes and not like Savart's at the loops. Although only descriptive, Seebeck's statements are much clearer than Savart's, and they have been reproduced with considerable experimental detail by Terquem: see Section II of this Chapter.

Seebeck died in 1849.

[476] Clausen *Ueber die Form architektonischer Säulen*, *Bulletin physico-mathématique de l'Académie*, T. ix pp. 368—79, St. Petersburg 1851. Also *Mélanges Mathématiques et Astronomiques*,

Tome I. (1849—53) pp. 279—94, St Petersburg, 1853. Clausen seeks to find the form of a column which for a given buckling load shall have the least volume. This problem as we have remarked is of no very great practical importance, for in the comparatively short columns of architecture, the longitudinal stress produces set long before the buckling load is reached: see our Arts. 1258—9*. Lagrange as we have seen (Art. 113*) obtained the differential equation required for the solution of the problem and showed that the right circular cylinder is *one*, and under certain conditions, the only solution. Clausen has succeeded in solving the general differential equation, and comes to a different result. In the following lines he somewhat misstates Lagrange's conclusions as to the best form of column:

Als Eigenschaft der zweckmässigsten Form wurde angenommen, dass sie bei gleicher Höhe und Tragkraft das kleinste Volumen enthalte. Lagrange wandte zur Auflösung dieser viel schwierigeren Aufgabe den von ihm erfundenen Variationscalcul an, und gelangte zuletzt zu dem sehr auffallenden Resultate, dass die Säule von gleicher Dicke die stärkste bei gleichem Volumen sei. Seit dieser Zeit ist diese Aufgabe meines Wissens nicht berührt worden.—Indem ich die Auflösung auf eine andere Art versuchte, gelang es wider Erwarten, die Differentialgleichung, deren allgemeine Integration Lagrange nicht versucht hatte, auf elliptische Transcendenten zu reduciren, wodurch es sich zeigt, dass die zweckmässigste Form vom Cylinder abweicht, und dass das Volumen dieses bei gleicher Höhe und Tragkraft sich zum Volumen jener Form verhält wie $1 : \sqrt{3/4}$ (p. 368).

[477.] Let ω be the area of the cross-section. Then we have if ds be an element of the axis of the column, volume $= V = \int_0^l \omega ds$, and this is to be a minimum. Further if P be the load and y the deflection, we have upon the Eulerian theory

$$E\omega\kappa^2 \frac{d^2y}{ds^2} = -Py.$$

Now κ^2 varies as ω , if all the cross-sections are similar figures with their centroids in the axis, or $\kappa^2 = \beta\omega$, say. Hence

$$\frac{d^2y}{ds^2} = -\frac{P}{E\beta} \frac{y}{\omega}.$$

We have thus to make $\int_0^l \left(y \left| \frac{d^2y}{ds^2} \right| \right)^{\frac{1}{2}} ds$ a minimum.

By direct application of the Calculus of Variations I deduce the equation

$$\frac{d^2}{ds^2} \sqrt{y / \left(\frac{d^2 y}{ds^2} \right)^3} = \sqrt{1 / y \frac{d^2 y}{ds^2}}$$

This agrees with Clausen's result stated as Equation (3) p 372 if we introduce a minus sign under both roots. He seems to me to employ an unnecessarily complex process to reach this simple conclusion. Let us write $z = \omega \sqrt{E\beta/P}$, then we have to solve

$$\frac{d^2 y}{ds^2} = -\frac{y}{z^2} = -y^{\frac{1}{2}} u^{-\frac{2}{3}} \quad (1),$$

$$\frac{d^2 u}{ds^2} = -y^{-\frac{2}{3}} u^{\frac{1}{3}} \quad (2),$$

where

$$u = \sqrt{-y / \left(\frac{d^2 y}{ds^2} \right)^3}$$

Multiply these equations by $\frac{du}{ds}$ and $\frac{dy}{ds}$ respectively, add and integrate, and we find

$$\begin{aligned} \frac{dy}{ds} \frac{du}{ds} &= C - 3 (uy)^{\frac{1}{2}} = C - 3z \\ &= 3 (z_0 - z) \end{aligned} \quad (3),$$

if $z = z_0$ for the point at which

$$\frac{dy}{ds} = 0$$

Multiply (1) by u , (2) by y , and add their sum to the double of (3) then we have

$$\frac{d^2 (yu)}{ds^2} = \frac{d^2 (z^3)}{ds^2} = 6z_0 - 8z,$$

or integrating $\left(\frac{d(z^3)}{ds} \right)^2 = c^4 + 12z_0 z^3 - 12z^4 \quad (4),$

c^4 being an arbitrary constant

Whence we deduce

$$ds = \frac{3z^2 dz}{\sqrt{c^4 + 12z_0 z^3 - 12z^4}} \quad (5)$$

Thus z , and so the section, is given in terms of the arc s of the axis by means of elliptic functions

[478] We have now to determine the value of the constant c^4 . According to Lagrange (Art 112*) we may measure the efficiency of a column of given height by the ratio P/V , and P varies as V/l^4 . Hence if two columns carry the same load we must have $V/l^4 = V_0/l_0^4$, or the

volume of a column which is of unit length and carries the same load is given by

$$V_0 = V/l^2.$$

Clausen takes as his condition for determining c^4 that V_0 must be a minimum. After some rather troublesome analysis he finds $c^4 = 0$. Equation (5) now becomes :

$$ds = \frac{\sqrt{\frac{3}{4}} \sqrt{z} dz}{\sqrt{z_0 - z}} \dots\dots\dots (6).$$

Further,

$$dV = \omega ds = \sqrt{\frac{P}{E\beta}} z ds = \sqrt{\frac{P}{E\beta}} \sqrt{\frac{3}{4}} \frac{z^{\frac{3}{2}} dz}{\sqrt{z_0 - z}} \dots\dots\dots (7).$$

Let us put $z = z_0 \cos^2 \theta$,

$$s = z_0 \int \sqrt{\frac{3}{4}} \cos^2 \theta d\theta = \frac{\sqrt{3}}{4} z_0 [2\theta + \sin 2\theta],$$

$$V = z_0^2 \sqrt{\frac{P}{E\beta}} \int \sqrt{\frac{3}{4}} \cos^4 \theta d\theta = \frac{\sqrt{3}}{32} z_0^2 \sqrt{\frac{P}{E\beta}} [12\theta + 8 \sin 2\theta + \sin 4\theta].$$

To obtain the total length and volume we must take these expressions between the limits $\pm \frac{1}{2}\pi$ of θ supposing the strut doubly pivoted.

$$\text{Hence} \quad l = \frac{\sqrt{3}\pi z_0}{2}, \quad V = \frac{3\pi\sqrt{3}}{8} z_0^2 \sqrt{\frac{P}{E\beta}} \dots\dots\dots (8),$$

$$V_0 = V/l^2 = \frac{\sqrt{3}}{2\pi} \sqrt{\frac{P}{E\beta}} \dots\dots\dots (9).$$

[479.] Now suppose we take a column the cross-section of which is uniform ($\omega = \omega_0$) but of the same shape as before, then we have

$$\frac{d^2 y}{ds^2} = -\frac{P}{E\beta} \frac{y}{\omega_0^2},$$

$$\text{and} \quad y = C_1 \sin \left(\sqrt{\frac{P}{E\beta}} \frac{s}{\omega_0} + C_2 \right),$$

C_1 and C_2 being constants.

$$\text{We readily find } \sqrt{\frac{P}{E\beta}} \frac{l}{\omega_0} = \pi, \text{ or } l = \pi \omega_0 \sqrt{\frac{E\beta}{P}}.$$

Further since the columns are to be of the same height we must have this equal to the l of Equation (8), and it follows that,

$$\omega_0 = \frac{\sqrt{3}}{2} \sqrt{\frac{P}{E\beta}} z_0.$$

We deduce for V' , the volume of this uniform column,

$$V' = l\omega_0 = \frac{3}{4} \pi \sqrt{\frac{P}{E\beta}} z_0^2,$$

whence from (8)

$$V : V' :: \sqrt{3} : 2,$$

that is, for the same buckling load and height the volume of the column of variable section is less than that of the column of uniform section in the ratio of $\sqrt{3} : 2$

[480] Clausen devotes pp 770—80 to the consideration of the problem of the column built-in at one end and loaded at the other, instead of the doubly pivoted strut of the previous investigation. He arrives at the conclusion, which he might have foreseen, that the former agrees in shape with either half of the latter. He figures this column and remarks 'dass die Form, wie mir scheint, eine dem Augen nicht ungefällige ist'—an opinion, I think, which will not be accepted by many.

In the present memoir the form of the cross-sections is left undetermined, they are merely assumed to be similar and similarly placed. Clausen remarks, however, that the circle is not the form which offers the greatest resistance to buckling, he gives no analysis of the point. Since, however, the load carried by the best column is always the same as that of a column of uniform section of $2/\sqrt{3}$ times its volume, we have only to compare the loads carried by the latter for various forms of cross-section to arrive at a variety of comparative results. These loads, if the length and the area of the cross-section of the column remain the same, vary as κ^2 . Thus take a rectangular section $2a \times 2b$ and $b < a$ and compare it with a circular section of radius c , the relative efficiencies are as $c^4/4b^3$ where $\pi c^2 = 4ab$, or they are as $a/\pi b^3$, therefore the rectangular section will be better than the circular if $b > 3a/\pi$ i.e. if the side b lies between $(3/\pi)a$ and a .

Thus certain rectangular sections, almost square, are better than circular sections in the matter of buckling. The practical value of the whole of this investigation must, however, be questioned see our Arts 146*, 911*, 958* and 1258*.

[481] E Segnitz *Ueber Torsionswiderstand und Torsionsfestigkeit Journal für die reine und angewandte Mathematik*, Bd 43, 1852, pp 340—364.

The author seems quite ignorant of the existence of the slide-modulus and of the shearing resistance of a material, he endeavours to explain torsion by the longitudinal extension of the rod or prism treated as a bundle of fibres. Young (*Natural Philosophy*, Vol I p 139) had already pointed out the insufficiency of this hypothesis. It had also been considered as a corrective factor by Maxwell, Wertheim and Saint-Venant see our Arts 1549*, 51, and Wertheim's memoir on *Torsion* in Section II of this Chapter.

The memoir ought scarcely to have been printed in Crelle's *Journal* in 1852.

[482.] E. Phillips: *Rapport sur un Mémoire de M. Phillips, concernant les ressorts en acier employés dans la construction des véhicules qui circulent sur les chemins de fer. Comptes rendus, T. 34, 1852, pp. 226—35.* This report by Poncelet, Seguiet and Combes speaks very fully and favourably of Phillips' results. It will be found useful to those to whom the original memoir in the *Annales des Mines* is not accessible: see our Art. 483. The commissioners remark that:

Le travail de M. Phillips sera fort utile aux ingénieurs et aux constructeurs, qui y trouveront des règles rationnelles et d'une application facile, pour l'établissement des ressorts capables de satisfaire, avec la moindre dépense de matière, à des conditions données de flexibilité et de résistance (p. 235).

They recommend the publication of the memoir in the collection of the *Savants étrangers*.

A portion of the report is printed as a foot-note on the first page of the memoir in the *Annales*, where there is an additional remark by M. Combes that the formulæ for springs given somewhat earlier by Blacher (see Section III. of this Chapter) were really due to Clapeyron.


[483.] E. Phillips: *Mémoire sur les ressorts en acier employés dans le matériel des chemins de fer. Annales des Mines, Tome I. 1852, pp. 195—336.* We have already referred to previous notes and memoirs by Phillips on this subject (see our Art. 1504*), but this memoir is the principal one, indeed it is one of the most important that has ever been published on the theory of laminated springs. It consists of three chapters and a long *Note*. We shall consider these at some length.

[484.] The first chapter is entitled: *Théorie mathématique des ressorts*. It occupies pp. 195—227, and should be taken in conjunction with the *Note* entitled: *Démonstration des formules de la flèche et de la flexion d'un ressort quelconque sous charge*, which is appended to the memoir (pp. 319—36). The theory here developed is very complete and has been carefully verified experimentally by Phillips, the details of his experiments being given in other parts of the memoir.

Les résultats qu'elle donne ont été vérifiés dans les cas les plus divers, par des expériences directes, avec un degré de précision extrême,

auquel j'étais loin de m'attendre moi même, et qui parait indiquer, de la part de l'acier, un état d'élasticité bien plus parfait que dans le fer ou dans la fonte (p 196)

[485] Let a spring be supposed built up of a number of separate laminae eL , e_1L_1 , e_2L , etc projecting one beyond the other as in Fig (1) and let eL be the 'matrix lamina.' Let the distances of the terminals of these laminae from the mid plane VV of the spring,—where



symmetry enables us to treat the spring as *built-in*,—be given respectively by L , L_1 , L , etc, let the curvatures of the different laminae at their respective central axes after manufacture be given at a section distant z from VV by $1/r$, $1/r_1$, $1/r$, etc, let a load Q be applied to the terminal L , and $1/\rho$ then be the curvature at z of the matrix lamina, let e , e_1 , e , etc be the distances between the central axis of the matrix lamina and the central axes of the laminae e_1L_1 , eL , etc, let M , M_1 , M , etc be the flexural rigidities of the successive laminae

Phillips supposes that the laminae are throughout in contact with each other, and afterwards investigates the conditions for this. Let then p , p_1 , p , etc be the pressures per unit length between the first and second, the second and third, laminae etc at the section distant l from VV . Now Phillips practically *assumes* that the distance between any cross section and VV is the same whether measured perpendicular to VV or along the central axis of the lamina. This is probably almost true in practice, but such an equation as that at the middle of his p 201 requires some comment of this kind see however p 282 of the memoir and our Art 488

Applying the Bernoulli-Eulerian theory of flexure and neglecting weight of the spring, we easily deduce:

$$M \left(\frac{1}{r} - \frac{1}{\rho} \right) = Q (L - z), \quad \text{or} \quad 1/\rho = \frac{B + Qz}{M},$$

$$B = \frac{M}{r} - QL.$$

L_2 as part of the matrix-lamina,

$$M_1 \left(\frac{1}{r} - \frac{1}{\rho} \right) = Q (L - z) - \int_z^{L_1} p (l - z) dl \quad \dots\dots\dots(i),$$

that of the second lamina,

$$M \left(\frac{1}{r_1} - \frac{1}{\rho + \epsilon} \right) = \int_z^{L_1} p (l - z) dl,$$

so:

$$M \left(\frac{1}{r} - \frac{1}{\rho} \right) + M_1 \left(\frac{1}{r_1} - \frac{1}{\rho + \epsilon} \right) = Q (L - z).$$

When ϵ is so small compared with ρ that it may be neglected, as is usually the case, we have:

$$\frac{1}{\rho} = \frac{B_1 + Qz}{M + M_1}, \quad \text{where} \quad B_1 = \frac{M}{r} + \frac{M_1}{r_1} - QL.$$

Continuing this process we easily find for the curvature at a point on the matrix-lamina lying between L_i and L_{i+1} ,

$$\left. \begin{aligned} \frac{1}{\rho} &= \frac{B_i + Qz}{M + M_1 + M_2 + \dots + M_i} \\ \text{where} \quad B_i &= \frac{M}{r} + \frac{M_1}{r_1} + \frac{M_2}{r_2} + \dots + \frac{M_i}{r_i} - QL \end{aligned} \right\} \dots\dots\dots(ii).$$

Calling this $1/\rho_i$, let us find the difference of $1/\rho_{i+1}$ and $1/\rho_i$ where $z = L_{i+1}$, we have

$$\frac{1}{\rho_{i+1}} - \frac{1}{\rho_i} = \frac{M_{i+1}}{\sum_0^i M_q \times \sum_0^{i+1} M_q} \left\{ Q (L - L_{i+1}) + \sum_0^i M_q \left(\frac{1}{r_{i+1}} - \frac{1}{r_q} \right) \right\} \dots\dots(iii),$$

where $\sum_0^i F(M_q, r_q)$ denotes, if F be any function of the M 's and r 's,

$$F(M, r) + F(M_1, r_1) + F(M_2, r_2) + \dots + F(M_i, r_i).$$

Now L is $> L_{i+1}$, and as a rule $r_{i+1}, r_i, r_{i-1} \dots r_1, r$ must either be equal or in ascending order of magnitude from r_{i+1} to r , if the laminae are to touch, hence $1/\rho_{i+1} - 1/\rho_i$ is a finite quantity and there is an abrupt change of curvature at the point where the $(i+1)$ th sheet laps the i th. This abrupt change could be got rid of by making $M_{i+1} = 0$ at that point, or by trimming and pointing off the end of the lamina as suggested either in our Fig. (ii) or in our Fig. (iii).

Le même raisonnement se continue pour toute l'étendue de la maîtresse feuille, et on vérifie ainsi l'utilité de ce fait pratique que tous les bons ressorts ont les extrémités de leurs feuilles aiguës et amincies (p 204)

[486] The stretch s_z at distance v from the central axis of the matrix lamina, or at distances v_1, v_2 , etc from the central axes of the second, third laminae, etc will be given by formulae of the type

$$s_z = v \left(\frac{1}{r} - \frac{1}{\rho} \right),$$

$$s_z = v_1 \left(\frac{1}{r_1} - \frac{1}{\rho + \epsilon} \right), \quad s_z = v_2 \left(\frac{1}{r_2} - \frac{1}{\rho + \epsilon_{i-1}} \right) \quad (\text{iv})$$

Whence if e, e_1, e_2 , etc be the successive thicknesses of the laminae we have formulae for the maximum stretches of which the type for the matrix lamina between L_i and L_{i+1} is

$$s_z = \frac{e}{2} \left[\frac{\sum_1^2 M_q \left(\frac{1}{r} - \frac{1}{r_q} \right) + Q (L - z)}{\sum_0^2 M_q} \right] \quad (\text{v})$$

Suppose all the laminae to be of the same curvature before being built up into the spring, or the r 's to be all equal at the same cross section of the spring, then

$$s_z = \frac{e}{2} \frac{Q (L - z)}{\sum_0^2 M_q} \quad (\text{vi}),$$

or, when there is no original difference of curvature in the laminae, the nature of the curve in which the laminae are shaped and then initial curvature have no influence on the stretches in the spring or upon its resistance (pp 207—8)

[487] Phillips remarks that the formula (ii) of the previous article enables us to calculate out the value of ρ for a succession of positions on the matrix-lamina for any given spring, and thus to draw a curve of its form under a given load. He gives (p 206) details of five experiments in which the deflections thus obtained were compared with their experimental values. There is an extremely close accordance between the experimental and theoretical results.

[488] We next pass to the analytical determination of the deflection, the investigation of which occupies pp 319 *et seq* of the *Vote*. We have generally from (ii)

$$\frac{1}{\rho} = a + bz \quad (\text{vii}),$$

where

$$a = \frac{\sum_0^i (M/r) - QL}{\sum_0^i M}, \quad b = \frac{Q}{\sum_0^i M}.$$

Phillips has λ where we have z , λ being the distance from VV of a given section measured along the central axis of the matrix-lamina, but as we have already pointed out equation (ii) is accurately true only when we use z and not λ . Phillips by neglecting the difference between $d\lambda/dz$ and unity writes (vii) in the form :

$$\frac{dp}{d\lambda} (1 + p^2)^{-\frac{3}{2}} = a + b\lambda \dots\dots\dots (\text{viii}),$$

where $p = dy/dz$, or is the slope of the tangent at the central axis to the horizontal, i.e. to the direction perpendicular to that of the load Q . This equation (viii) he integrates on the assumption that a and b are constants along the central axis between the laps, and finds :

$$\frac{p}{\sqrt{1 + p^2}} = C + a\lambda + \frac{b}{2} \lambda^2,$$

but the left-hand side $= dy/d\lambda$, hence integrating again

$$y = C' + C\lambda + \frac{1}{2}a\lambda^2 + \frac{b}{6} \lambda^3 \dots\dots\dots (\text{ix}).$$

to me that (ix) is only true so far as we may legitimately get λ and z . Phillips does not seem to have remarked that λ already supposed this interchange allowable when he puts λ instead of z on the right-hand side of (vii). Thus the true limitation to Phillips' investigations appears to be that any curvatures, however considerable, may be given to the laminae in manufacture, but that when the spring is made up and in the unloaded state it ought to be very approximately flat. This condition is probably satisfied in most springs in practical use.

In our investigations we shall replace Phillips' λ by z , since we use λ in a special technical sense in this work, but we shall suppose z measured indifferently either along the horizontal or along the central axis of the matrix-lamina.

[489.] C and C' , a and b will have different values for each separate lap of the spring. Let the spring have $n + 1$ laminae and let A_n, B_n be the values of a and b for the portion of the matrix-lamina which covers all the other n laminae, A_{n-1}, B_{n-1} the values of a and b for that portion which covers only $n - 1$ laminae, and so on, and let $C_n, C'_n, C_{n-1}, C'_{n-1}$ be the corresponding values of C and C' . As before L_n, L_{n-1} , etc., L will be the semi-lengths of the successive laminae from the lowest upwards. The conditions to be satisfied at the lap of two laminae are that the deflection and slope shall be continuous;

while if deflections be measured from the lowest point of the central axis of the matrix-lamina we must obviously have $\bar{C}_n = C'_n = 0$

An easy application of an ordinary method of solving finite difference equations leads to the results

$$\left. \begin{aligned} C_{n-l} &= \sum_1^k (A_{n-l+1} - A_{n-l}) L_{n-l+1} \\ &\quad + \frac{1}{2} \sum_1^k (B_{n-l+1} - B_{n-l}) L_{n-l+1}^2 \\ C'_{n-l} &= -\frac{1}{2} \sum_1^k (A_{n-l+1} - A_{n-l}) L_{n-l+1}^2 \\ &\quad - \frac{1}{3} \sum_1^k (B_{n-l+1} - B_{n-l}) L_{n-l+1}^3 \end{aligned} \right\} \quad (\text{x}),$$

the summation being for k , while between L_{n-l+1} and L_{n-l}

$$y = C'_{n-l} + C_{n-l} z + A_{n-l} \frac{z^2}{2} + B_{n-l} \frac{z^3}{6} \quad (\text{x1})$$

We have thus the deflection at any point of the matrix-lamina. To find the deflection due to the load Q , we must find the value of y when $Q = 0$. Let y_0 be its value and let ${}_0A_{n-l+1}$, ${}_0B_{n-l+1}$, etc be the corresponding values of A_{n-l+1} and B_{n-l+1} then we easily see from formulae for a and b that ${}_0B_{n-k+1}$ etc are all zero, and further that

$$A_{n-l+1} - {}_0A_{n-l+1} = -\frac{QL}{\sum_0^{n-l+1} M}$$

Thus for $f = y_0 - y$ we have the expression

$$\begin{aligned} f &= \frac{QL}{2} \sum_1^k \frac{M_{n-l+1}}{\sum_0^{n-k+1} M} \frac{L_{n-l+1}}{\sum_0^{n-k} M} - \frac{Q}{3} \sum_1^k \frac{M_{n-l+1}}{\sum_0^{n-k+1} M} \frac{L_{n-l+1}^2}{\sum_0^{n-k} M} \\ &\quad - \left\{ QL \sum_1^k \frac{M_{n-l+1}}{\sum_0^{n-k+1} M} \frac{L_{n-l+1}}{\sum_0^{n-l} M} - \frac{Q}{2} \sum_1^k \frac{M_{n-l+1}}{\sum_0^{n-k+1} M} \frac{L_{n-l+1}}{\sum_0^{n-l} M} \right\} z \\ &\quad + \frac{QL}{2} \frac{z}{\sum_0^{n-l} M} - \frac{Q}{6} \frac{z^2}{\sum_0^{n-k} M} \quad (\text{x11}) \end{aligned}$$

[490] Phillips considers various special cases of the formula (x11) of the preceding article. Thus the total deflection f of the spring due to the load Q will be obtained by putting $z = L$ and $k = n$, we then find

$$f = \frac{QL}{3M} + Q \sum_{k=1}^{n-k} \left\{ \frac{M_{n-l+1}}{\sum_0^{n-l+1} M} \frac{L_{n-l+1}}{\sum_0^{n-l} M} \left(LL_{n-l+1} - \frac{L_{n-l+1}^2}{2} - L \right) \right\} \quad (\text{x111})$$

A special case of this is when all the flexural rigidities are equal ; we then have :

$$f = \frac{QL^3}{3M} + \frac{QL_1}{1.2M} \left(LL_1 - \frac{L_1^2}{3} - L^2 \right) + \frac{QL_2}{2.3.M} \left(LL_2 - \frac{L_2^2}{3} - L^2 \right) \\ + \dots + \frac{QL_n}{n(n+1)M} \left(LL_n - \frac{L_n^2}{3} - L^2 \right) \dots \dots \dots (\text{xiv}).$$

Phillips still further simplifies this by taking

$$L - L_1 = L_1 - L_2 = L_2 - L_3 = \dots = l,$$

or supposing the laminae equally spaced out ; he then proves that after certain reductions we have :

$$f = \frac{QL^3}{3(n+1)M} + \frac{QL^3}{3M} \left(\frac{n(n-1)}{2} + \frac{1}{2} + \frac{1}{3} + \frac{1}{4} + \dots + \frac{1}{n+1} \right) \dots \dots (\text{xiv})'.$$

These results show us that when the flexural rigidity and curvature of each lamina are constant throughout its length and the rigidities the same for all laminae, then the deflection (i) is proportional to the charge, (ii) is independent of the primitive curvature and form of the laminae (pp. 319—329).

[491.] Phillips now proceeds to extend the results just stated by an ingenious process of general analysis to the case in which the primitive curvatures vary in any arbitrary manner. He shows that the deflection is still proportional to the charge and independent of the original form and curvatures of the laminae (pp. 329—33). This independence of the deflection on the primitive form of the laminae seems a result likely to be important in the practical construction of springs.

It is further shown that the change in the sine of the angle which the tangent at any point to the central axis of the matrix-lamina makes with the horizontal is also proportional to the load and independent of the primitive form and curvature of the laminae.

[492.] On pp. 215—19 Phillips calculates the pressures between the various laminae at any section given by z . Suppose the section taken between L_k and L_{k+1} (see fig. (i) in our Art. 485) ; let ϖ = the pressure per unit length between the matrix-lamina and the first sub-lamina, ϖ_1 between the first and second sub-laminae, $\dots \varpi_{k-1}$ between the $k-1$ th and k th laminae, then Phillips easily deduces after the manner of our Art. 485, that :

$$\left. \begin{aligned} w &= \frac{d'}{dz^3} \left\{ \sum_1^k M_q \left(\frac{1}{r_q} - \frac{1}{\rho + \epsilon_{q-1}} \right) \right\} \\ w_1 &= \frac{d^2}{dz^3} \left\{ \sum_2^k M_q \left(\frac{1}{r_q} - \frac{1}{\rho + \epsilon_{q-1}} \right) \right\} \\ w_{k-1} &= \frac{d^n}{dz^3} \left\{ M_k \left(\frac{1}{r_k} - \frac{1}{\rho + \epsilon_{k-1}} \right) \right\} \end{aligned} \right\} \quad (\text{xv})$$

Thus since ρ is given by (11) we can find these pressures, they must all be positive if the laminae are to have no tendency to separate

[493] The memoir then passes to the effect of vibrations on springs and to their resilience

(a) The case of a weight Q placed upon the centre of a spring is very easily dealt with, if we assume with Phillips that the inertia of the spring may be neglected. The motion is then simple-harmonic and of period $2\pi\sqrt{f/g}$, where f is the statical deflection which Q would produce in the spring

(b) If β be the ratio of load to deflection, so that $Q = \beta f$, the resilience is well known to be $\beta f^2/2$ or $Q^2/(2\beta)$. Now let w be the amount of work due to a blow which will just flatten the spring, and let the statical force required to flatten it be P , then we have

$$w = P^2/(2\beta),$$

$$\text{or} \quad P = \sqrt{2\beta w} = \sqrt{\frac{2w \times Q}{f}}$$

Phillips gives the result in the form

$$P = \sqrt{\frac{2w}{f}} \times Q$$

on p 223, which is obviously a misprint

(c) The resilience may also be given another form suggestive of Young's theorem (see our Vol 1 p 875)

The work required to bend an element dz of a lamina from curvature $1/\rho'$ to $1/\rho$, the sheet having an initial curvature $1/r$ is well known to be

$$\frac{1}{2} M \left\{ \left(\frac{1}{r} - \frac{1}{\rho} \right) - \left(\frac{1}{r} - \frac{1}{\rho'} \right) \right\} dz$$

Thus the work required to flatten the element from its curvature of manufacture on $1/r$

$$- \frac{1}{2} \frac{M}{r} dz$$

Hence if the length of the lamina be l and its cross section w

be rectangular and of height e , the work required to flatten the whole lamina, supposing its stretch-modulus E ,

$$= E \frac{\omega l}{24} \frac{e^2}{r^2}.$$

Now the stretch in the lamina has for maximum value $s = \frac{1}{2}e/r$, and if U be the volume of the lamina, the work done

$$= \frac{EU s^2}{6}.$$

Hence the work done in flattening the spring

$$= \Sigma \left(\frac{EU s^2}{6} \right).$$

Supposing all the laminae to have the same final stretch on flattening, then we have, if V be the total volume of the spring :

$$\text{Total resilience} = \frac{EV s^2}{6} \dots\dots\dots (\text{xvi}).$$

Cases may arise in which the blow begins to act upon the spring when it is already in a state of strain, i.e. its primitive condition is one of strain. In this case ρ_0 , the initial radius of curvature, is not equal to r , but $\frac{1}{r} - \frac{1}{\rho_0} = \frac{2s_0}{e}$, where s_0 is the initial stretch. Hence the work required to flatten the element dz of a lamina is equal to

$$\begin{aligned} & \frac{1}{2} M \left(\frac{1}{r^2} - \frac{4s_0^2}{e^2} \right) dz \\ &= E \omega \left(\frac{e^2}{24r^2} - \frac{s_0^2}{6} \right) dz, \end{aligned}$$

or, for the total work on a lamina we have the expression

$$\frac{E}{6} \left(U s^2 - \int_0^U s_0^2 dU \right).$$

Hence the total resilience of the spring

$$= \frac{E}{6} \left(V s^2 - \Sigma \int_0^U s_0^2 dU \right) \dots\dots\dots (\text{xvii}).$$

Of this result Phillips writes :

Le travail se trouve donc diminué toutes les fois que le ressort ne part pas de sa position de fabrication. Or c'est ce qui arrive pour tous les ressorts de choc et de traction qui sont posés avec une certaine bande ; mais on voit que la différence sera toujours assez faible quand s_0 ne sera pas très grand, parce que s_0 n'entre que par son carré. Ainsi, dans les ressorts ordinaires, où s_0 est environ $1/3$ de s , on perd environ $1/9$ de la puissance du ressort pour résister au choc. On voit, en même temps, qu'il y a avantage à faire en sorte que la bande de pose du ressort qui répond à un effort d'environ 1000

kilogrammes, produise un allongement s_0 le plus faible possible, par conséquent, sous ce point de vue, il y a avantage, toutes choses égales d'ailleurs, à employer des ressorts un peu roides plutôt que très flexibles (p 226)

[494] *Chapitre Deuxième* entitled *Des formes les plus convenables à donner aux ressorts et des règles pour les calculer*, occupies pp 227—301 and contains many points of great interest

Phillips first draws attention to the fact, referred to in our Art 491, that the primitive form of the laminae is practically of little importance

Il y a donc avantage, sous le rapport de la simplicité, à choisir des arcs de cercle, et c'est cette forme que je suppose adoptée (p 227)

In the second place it is evident that the best sort of spring will be built-up in such a manner that all its parts are equally strained under any load or at least the maximum load (or maximum strain due to any oscillations) which it is designed to bear. As a rule this maximum strain will occur when the spring is completely flattened, and in such state the maximum stretches in all the laminae ought to be equal. The maximum stretch of the matrix-lamina on flattening = $e/(2r)$ and this will be the same for every section of it. If the laminae have initially the same curvature then they will have the same maximum stretch in every cross-section when flattened out. But supposing the laminae have before being formed into the spring initially different curvatures, we have then to ask how they can be spaced out so that the spring can be reduced to approximate flatness, and what conditions must be satisfied in order that the maximum stretches shall be the same for all the laminae

Let $2P$ be the load which applied to the middle of the spring reduces it to approximate flatness. Then Phillips takes as his condition of flatness that the curvature of the matrix lamina shall be zero at each lap of a sub lamina. This gives us from equation (ii) of our Art 485

$$B_{i-1} + PL_i = 0, \quad B_i + PL_{i+1} = 0, \text{ etc },$$

or generally,
$$P(L_i - L_{i+1}) = M_i/\rho_i,$$

which leads us to
$$L_i - L_{i+1} = M_i/(Pr_i) \quad (\text{xviii})$$

(xviii) is the formula which determines the spacing of the laps. If the laminae are all of equal rigidity and initially of equal curvature we have

$$L - L_1 = L_1 - L_2 = \dots = L_i - L_{i+1} = \dots = \frac{M}{Pr_i} \quad (\text{xix}),$$

which determines the spacing for this special case

If any lamina say the k th has a considerable initial strain, then we have $r_k < r$, and therefore if the stretch on flattening is to be the same for the k th lamina and for the matrix-lamina we must have

$s_0 = \frac{e_k}{2r_k} = \frac{e}{2r}$, or we must have $e_k < e$. If $l_k = L_k - L_{k+1}$, we have

$l_k = M_k / (Pr_k) = Ebe_k^3 / (12Pr_k)$, similarly $l = Ebe^3 / (12Pr)$, where b is the breadth of the laminae; hence it follows that $e_k / l_k > e / l$, and therefore

$l_k < \frac{e_k}{e} l$ and $l_k e_k < \frac{e_k^2}{e^2} le$, but $e_k < e$ so that *a fortiori* we have

$$l_k < l \text{ and } l_k e_k < le.$$

If we flatten the spring out so as easily to calculate its volume, we see that if there is no initial strain and therefore all the depths of the laminae and the spacings equal, the volume, omitting that of the matrix-lamina, will be measured by an isosceles triangle of area $L^2 e / l$ less the sum of the little triangles of bases l and height e , or eL . Now if there be initial strain since $e_k / l_k > e / l$, we see that the perimeter of the figure formed by joining the corners of successive laminae falls outside the above isosceles triangle and has therefore a greater area, call it F ; we have to subtract from this figure the sum of the little triangles of bases l_k and heights e_k , or the volume of the spring will be measured by $F - \sum l_k e_k$, but by what precedes $F > L^2 e / l$ and $l_k e_k < le$. Hence the volume of the spring having a considerable initial strain and the same flexibility and absolute resistance which requires a given load to flatten it, is greater than that of a spring with equal heights and spacings for its laminae, and having the same matrix-lamina (pp. 231—

the other hand if the thicknesses of the laminae increase from

rix downwards it may be shewn that the volume of the spring is

man in the case when all the thicknesses are equal (pp. 238—9).

Phillips then proceeds to shew that as a general rule the non-equality of the heights and curvatures of the sub-laminae with those of the matrix-lamina has very little influence upon the deflection of the matrix-lamina. For if $e_k / r_k = e / r$ and $e_k < e$, it follows that $e_k^3 / r_k < e^3 / r$ or $M_k / r_k < M / r$, or the resistance to initial strain is greater in the matrix-lamina than in any sub-lamina (pp. 233—4).

In the case of a spring with laminae equally curved initially it is easy to prove that the maximum stretches at all the cross-sections in all the laminae will be equal, even if the load be not the maximum or flattening load.

[495.] Hitherto Phillips has only made the curvature for the maximum load P zero at the laps. He now proposes to deduce the proper shaping off of the ends of the laminae in order that the curvature may be zero at all points.

For the matrix lamina itself from L to L_1 we must have

$$\frac{M}{r} - P(L - z) = 0,$$

or, if y be the variable thickness of the lap and $L - z = x$, since M varies as y^3 we have

$$y^3/x = \text{constant} = e^3/(L - L_1),$$

which determines the value of y for each x

For the first sub lamina we have

$$\frac{M}{r} + \frac{M_1}{r_1} - P(L - z) = 0,$$

or
$$\frac{M}{r} + \frac{M_1}{r_1} - P(L - L_1) - P(L_1 - z) = 0,$$

whence, since the matrix lamina has uniformly $M/r = P(L - L_1)$ after $z = L_1$,

$$\frac{M_1}{r_1} = P(L_1 - z) \quad (\text{xx}),$$

or, if $L_1 - z = x_1$, $y_1^3/x_1 = \text{constant} = e_1^3/(L_1 - L)$

Thus the thickness at the ends of the first sub lamina follows the same law as in the case of the matrix lamina, and the like may be shown of the other successive laminae. Instead of tapering off the thickness we might have reduced the breadth, or terminated our laminae in poignard or triangle form (see fig (iii) of our Art 485). Phillips states that this latter method is the more wasteful (pp 237—8).

[496] A formula is obtained by Phillips on pp 332—6, which seems of considerable interest and practical value. He finds namely the deflection of a 'complete' or 'incomplete' spring when all the laminae are of the same section except at the laps, where account is taken of their proper shaping. He supposes also equal curvatures of manufacture.

Calling m the flexural rigidity of the k th lamina at the shaped lap, we have by equations of the type (xx),

$$\frac{m}{r} = P(L_{k-1} - z),$$

and by the law of spacings (xix), since the spaces are equal,

$$\frac{M}{r} = Pl$$

Further $(k-1)l + L_{k-1} = L$

Whence since

$$\{(k-1)M + m\} \left(\frac{1}{r} - \frac{1}{\rho} \right) = Q(L - z),$$

we easily find

$$\frac{1}{\rho} = \frac{P-Q}{P} \frac{1}{r} \quad (\text{xxxi})$$

Thus the curvature for the complete portion of the spring or the

part which is staged is constant, and thus the matrix lamina takes the form of a circular arc whatever be the load.

Suppose the staging to cease with the n th lamina so that the length $2L_n$ of the spring is neither tapered nor covered by any sub-laminae, then we have

$$nM \left(\frac{1}{r} - \frac{1}{\rho} \right) = Q (L - z).$$

$$\text{But} \quad \frac{1}{r} = Pl/M = P(L - L_n)/(nM).$$

Thus we have

$$\frac{1}{\rho} = a + bz \dots\dots\dots(\text{xxii}),$$

$$\text{where} \quad a = \{P(L - L_n) - QL\}/(nM), \quad b = Q/(nM),$$

$2L_n$ being the portion of the n th lamina not thinned down.

For the portion of the spring which is complete we have

$$\frac{1}{\rho} = a' \dots\dots\dots(\text{xxiii}),$$

$$\text{where} \quad a' = \frac{P - Q}{P} \frac{1}{r} \text{ by (xxi).}$$

If (xxii) and (xxiii) be twice integrated and the four constants of integration determined by the vanishing of the deflection and slope when $z = 0$, and by the equality of the deflections and slopes when $z = L_n$ as obtained from the two expressions for the curvature of the complete and incomplete portions, then the following expression for f , the droop due to the load Q , is reached after some algebraical reductions :

$$f = \frac{Q}{6nM} \{2L^3 + (nl)^3\} \dots\dots\dots(\text{xxiv}).$$

If the spring is complete, $nl = L$ and

$$f = \frac{QL^3}{2nM} \dots\dots\dots(\text{xxv}),$$

or $3/2$ of the value of the droop of a spring of n equal flat laminae of the same rigidity M and of the same length $2L$.

Phillips gives details (on pp. 214—5 of the memoir) of experiments on the deflection of springs actually in use on various railway wagons and locomotives, and compares the experimental values with those calculated from the formula (xxiv). There is a very remarkable accordance between theory and experiment.

[497.] To calculate the depths and spacings of the laminac of the most general type of spring we must use the formulae :

$$\frac{e}{2r} = \frac{e_1}{2r_1} = \frac{e_2}{2r_2} - \dots = s_0,$$

where s_0 is the maximum stretch in each lamina when the spring is flattened, and

$$L - L_1 = \frac{M}{Pr}, \quad L_1 - L_2 = \frac{M_1}{Pr_1}, \quad L_2 - L_3 = \frac{M_2}{2r_2}, \quad \text{etc.},$$

P being half the central load required to flatten the spring

Of these results Phillips writes

S'il arrive que les épaisseurs augmentent de quantités trop petites pour qu'on puisse donner à toutes les feuilles les épaisseurs calculées d'après leurs rayons, on donnera à plusieurs feuilles, en partant du haut, une épaisseur commune égale à la moyenne entre leurs épaisseurs, et un étagement commun égal à la moyenne de leurs étagements, on fera de même pour plusieurs des feuilles suivantes, et ainsi de suite jusqu'à ce que le ressort soit terminé. Quant aux amincissements, ils se calculeront par la règle générale (pp 240—1)

[498] There are two special methods of easily designing a laminated spring to which Phillips refers on pp 238—9

(a) We may suppose all the laminae cut as it were from one and the same hoop of metal, so that all have the same primitive curvature and thickness. When the spring is manufactured there will then be a very slight initial strain in the laminae before the spring is loaded. Such a spring possesses the advantages referred to in our Art 494

(b) We may suppose the laminae to have no initial strain by describing the laminae from the same centre and with bounding radii increasing by the mean of the thicknesses of adjacent laminae, while the thicknesses themselves increase proportionately to the radii of the central axes, or obey the relation

$$\frac{e}{2r} = \frac{e_1}{2r_1} = \frac{e_2}{2r_2} = \dots = \frac{e_n}{2r_n} = s_0$$

This sort of spring besides having no initial strain has also the advantage of a slightly but sensibly less volume than that described in

(a). This is really the converse of the proposition in our Art 494, p 340, because by Art 497 the ratios of the successive thicknesses to the corresponding spacings vary inversely as the thicknesses and so now decrease

[499] On pp 240—2 of the memoir are given a number of interesting properties of springs, the laminae of which have the same or sensibly the same thickness (Case (a) of the previous Article)

If H be the total thickness at the mid section of such a spring supposed complete, l the equal spacing of the laps, L the half length and b the breadth of the matrix lamina, $2P$ the flattening load and V the volume, then we have in the notation of the previous articles

$$H = \frac{e}{l} L, \text{ nearly, } l = \frac{M}{Pr} = \frac{Ebe^3}{12Pr}, \quad V = H L b, \text{ nearly}$$

Further if f be the drop of the spring when unloaded, then since

there is little or no initial strain: $r = L^2/2f = \frac{e}{2s_0}$ by the first equation of our Art. 498, (b). Whence we deduce

$$H = \frac{6Pf}{Es_0^2 b L}.$$

Now let ν equal the *flexibility* of the spring, or, the droop produced when a unit load is put at each extremity, then we must have, supposing stress and strain proportional:

$$f = \nu P,$$

and hence:
$$H = \frac{6P^2\nu}{Es_0^2 b L}, \quad \text{and} \quad V = \frac{6P^2\nu}{Es_0^2}.$$

Thus we find for a given material that:

(a) The total thickness of a spring is proportional directly to:

- (i) the square of the flattening load,
- (ii) the flexibility,

inversely to:

- (i) the breadth of the spring,
- (ii) its length.

(b) The volume of a spring is proportional to:

- (i) the square of the flattening load,
- (ii) its flexibility,

and further:

(c) Springs having the same flexibility and ultimate resistance, $2P$, have also sensibly the same volume.

Since $l/L = e/H = \frac{Es_0^3 L^3 b}{6Pf^2}$, and we must have $l < L$, it follows that the length L of the spring ought to be such that:

$$L < \left\{ \frac{6Pf^2}{Es_0^3 b} \right\}^{\frac{1}{3}},$$

a condition generally satisfied in practice.

[500.] Phillips next proceeds to apply his theoretical results to the practical calculation of the dimensions of springs, chiefly those of railway wagons. He determines numerically the lengths of the various laminae suitable for springs of various classes. The springs thus calculated were constructed and the experimental deflections agreed very closely with those obtained by theory (pp. 242—52). The data assumed are (i) the flexibility of the spring (ν); (ii) its absolute resistance ($2P$); (iii) the chord of manufacture ($2c$) of the spring; (iv) the normal load ($2Q$); (v) the breadth of the laminae (b). Phillips supposes in addition

that the limit of resistance of the spring is reached under the load $2P$ corresponding to flattening. He shows, however, how the details may be calculated when the flattening load corresponds to neither $2P$ nor to $2Q$, and also when the data are otherwise varied. Since the flexibility is known, the droop produced by $2P$ the flattening load, that is the subtense f of manufacture, is known. Phillips then puts without further comment $L = \sqrt{c^2 + f^2}$, or he equates the length of the spring to the chord of half its arc thus tacitly neglecting quantities of the order $\{(L-c)/L\}^2$. This is, however, in accordance with his previous approximations see our Arts 484 and 488. He further supposes the laminae to be of equal initial curvature and thickness and neglects any initial strain. Thus he easily deduces that the values e , l of the thickness and the spacing are given respectively by

$$e = \frac{c^2 + f^2}{f} s_0, \quad l = \frac{Ebe^3f}{6P(c' + f)},$$

while the number of laminae will be the whole number in the quotient L/l .

For steel Phillips takes $E = 20,000$ kilogrammes per sq mm and $s_0 = 0.025$, as a thoroughly safe stretch below the fail-limit for good steel.

On pp 247—8 he shows that, when the laminae are described about the same centre, the thickness of the k th lamina, its radius of curvature and the corresponding spacing will be found from those of the $(k-1)$ th lamina by the formulae

$$e_k = \frac{e_{l-1}(2r_{k-1} + e_{l-1})}{2r_{l-1} - e_{k-1}}, \quad r_l = \frac{e_k}{2s_0}, \quad l_k = \frac{M_k}{Pr_k}$$

The first formula might for practical purposes be replaced by

$$e_l = e_{l-1} \left(1 + \frac{e_{k-1}}{r_{k-1}} \right)$$

[501] On pp 252—5 after discussing the effect of bolting the matrix lamina and under certain conditions several of the sub laminae of the spring to a rigid frame on which the load is placed, Phillips next turns to the very important practical point of whether adjacent laminae do or do not tend to gape. His consideration of this matter occupies pp 255—68, and is of great interest. There are three fundamental types of laminated springs to be considered (a) the first type when the curvature of manufacture and the thickness of the laminae are equal for all, (b) the second type when the thicknesses decrease from the matrix to the sub lumen, and (c) the third type when they increase. In both (b) and (c) it is supposed that the thicknesses, radii of curvature and the spacings are calculated by the formulae of our Art 497, i.e. that they are determined so that the stretch on flattening is the same for all the laminae.

Phillips shows that for the first type of spring each lamina experiences only pressure at its terminals and that each such pressure is half the load the laminae remain exactly fitted to one another.

without sensible pressure, but without gaping—‘ce qui est conforme à l’expérience’ (p. 256). When a spring is of the second type the laminae tend before, but not after flattening to separate. Finally if a spring is of the third type its laminae tend to separate after but not before flattening. In both cases (b) and (c) there is complete contact right along all the laminae for the load corresponding to flattening. These effects may be somewhat, but only slightly modified at the sections of the spring corresponding to the ends of the laminae. This modification will be very small if the spring under its normal load does its work in a flat condition.

On voit ainsi, en outre, qu’il convient de faire en sorte qu’un ressort travaille habituellement aplati sous la charge qu’il supporte; indépendamment de ce qu’alors les glissements des feuilles, et par suite le travail dû au frottement sont moindres (p. 268).

Phillips deduces the important conclusions we have referred to above from the expressions for the pressure between successive laminae which we have reproduced in our Art. 492.

[502.] Pages 268—93 of the memoir are devoted to what the author terms a *ressort à auxiliaire* or a *reserve spring*. He describes it in the following words:

En principe, on a fait remplir par des appareils différents deux conditions essentiellement distinctes: la flexibilité et la résistance qui n’ont nullement besoin d’être remplies par le même instrument. Le ressort se compose alors des deux parties: l’une, formée de feuilles toutes de même épaisseur, constitue le ressort proprement dit: elle travaille seule ordinairement sous la charge normale; l’autre, placée au-dessous, est plus épaisse et divergente, et ne vient en contact avec elle que sous un excès de charge et successivement. Cette dernière partie qui sert d’auxiliaire est calculée d’après l’excès de résistance propre qu’on désire attribuer au ressort, quelle que soit d’ailleurs cette résistance (p. 269).

The part of a reserve spring which is called into play by the normal load may be termed the *main spring*, the part which is only called into play when the normal load is surpassed the *secondary spring*. In order that a reserve spring may offer a progressive resistance to oscillations beyond the normal load, the secondary spring must be constructed in such a manner as to establish only a gradual contact with the main spring.

If the extreme resistance $2P$ of the spring be reached when both its parts are flattened and $2Q$ be the normal load, then the contact of main spring and secondary spring ought to begin when the load is $2Q$ and go on up to complete coincidence under $2P$. The main spring will generally be formed of a number of laminae of equal thickness spaced in the usual manner and calculated so as to have a given droop i under the normal load $2Q$. The calculation of the main spring under these conditions, especially when the form sought is to involve the least expenditure of material, is a matter of rather troublesome approximation but is discussed very fully by Phillips (pp. 270—5 etc.).

The secondary spring may be made in one of several forms, for example it may be (1) circular,—in this case its radius of manufacture r' ought to be equal to the radius at the centre of the last lamina of the main spring when under load $2Q$, i.e. if there be n laminae of equal rigidity and curvature of manufacture in that part of the spring we must have

$$1/r' = \frac{\frac{nM}{r} - QL}{nM},$$

or (11), the shape of the secondary spring may be the elastic line of the last lamina when under the normal load, or better a form a little more curved than this so that the oscillations of the main spring may be carried gradually and not abruptly to the secondary. This case is discussed by Phillips on pp 286—92

[503] He remarks that in most cases it is sufficient to make the secondary spring consist of a single lamina. Its semi length L' will be that of the last lamina of the main spring diminished by the spacing $M/(Pr)$, and we should then have in case (1) to determine its rigidity M' from the equation

$$M' = Pr' L'$$

A more complex condition comes in, however, if we take a single lamina for the secondary spring in case (11), for in this case its rigidity m' (and so the thickness of the lamina) must vary throughout and the maximum stretch must not exceed s_0 when the lamina is flattened. We have then in the notation of our previous articles

$$m'/r' = P(L' - z),$$

while $m' = \frac{1}{1-z} Ebe'^3$, and if there be n laminae in the main spring we have

$$1/r' = \frac{\frac{nM}{r} - Q(L - z)}{nM}$$

Further, s_0 must be $> e'/(2r')$

Whence we easily deduce

$$(L' - z) \left\{ \frac{nM}{r} - Q(L - z) \right\} < \frac{2s_0^3 Ebn M}{3P}$$

The left-hand side will be found to be a true maximum for

$$z = \frac{1}{2} \left(L + 2L' - \frac{nM}{rQ} \right),$$

and since $L - L' = nM/(Pr)$,

the inequality may be easily reduced to

$$\frac{2}{3} Q \frac{nM}{r} \left(\frac{1}{r} - \frac{1}{p} \right)^2 < \frac{s_0^3 E b}{P} < \frac{3}{9} \frac{M}{P r^2},$$

if we remember the value of M and that $e = 2rs_0$ for the main spring. Hence finally we must have :

$$n < \frac{27}{4} \frac{QP^2}{(P-Q)^3}.$$

For example if $P = 2Q$ we must have $n < 27$. This sets a limit to the number of laminae in the main spring when the secondary spring consists of a single lamina shaped like the form of the main spring under the load $2Q$ (pp. 289—90).

[504.] Phillips on p. 282 draws attention for the first time to the source of error—which may rise to importance, especially in the case of reserve springs,—from the chord and arc of the matrix lamina having been treated as interchangeable in the equations: see our Arts. 485, 488, and 500. He measures the amount of error thus introduced and shows how it may be allowed for. He remarks that the flexure due to a given load is obtained as the difference of two formulae, one of which gives the subtense without load and the other with load. The latter formula he holds to be sufficiently exact in practice when the chord and arc are interchanged, since the normal load approximately flattens the spring; the former must be modified if the difference between the arc and chord gives a sensible difference in the value of the subtense when the two are interchanged. If L and S be semi-chord and semi-arc the quantities $L^2/(2r)$ and $S^2/(2r)$ must be practically equal (pp. 282—4).

[505.] A remark of Phillips on p. 295 is worth citing. It refers to the springs we have classed in our Art. 501 as of the *third* type :

Je ferai remarquer, en passant, que le type déjà décrit des ressorts à feuilles d'épaisseurs croissantes, qui travaillent aplatis sous la charge normale, et dont toutes les feuilles éprouvent dans l'aplatissement un même allongement, rentre réellement dans la classe des ressorts à auxiliaire, car les rayons étant croissants, les feuilles ne viennent en contact que successivement. Ce fait est d'autant plus saillant, que souvent ces ressorts se terminent par une ou deux grosses feuilles. Seulement le propre de ces ressorts est que toutes les feuilles sont jointives sous la charge normale, et qu'alors toutes éprouvent les mêmes allongements.

[506.] The few remaining points in the second chapter of the memoir may be very briefly indicated

On pp. 295—8 Phillips deals more particularly with the calculation of springs intended to resist impact, and gives details of various springs actually constructed for the *Chemin de Fer de l'Ouest*. Phillips describes a novel kind suitable for resisting both impact and steady pressure and offering special advantages for passenger coaches on railways. These springs have secondary springs attached to them consisting of one or more large laminae so arranged that the flexibility is much less after the load has passed a certain limit (e.g. 3000 kilogs.), and thus specially

heavy loads or impacts do not tend to vary very greatly the relative heights of the buffers of the carriages

On pp 299—301 we have a short resumé of the results of the chapter and an indication of how the theory therein developed may be used for the investigation of new forms of springs It is followed by a table of numerical details of all the springs which had been constructed according to Phillips' theory before 1851

[507] *Chapitre troisième* is entitled *Expériences sur l'élasticité de l'acier* and occupies pp 302—18 A description of the apparatus employed is given and long details of experiments on various kinds of steel, tempered, annealed, hammered etc Phillips concludes that for practical purposes we may take the stretch modulus at 20,000 kilogs per sq mm and the fail limit, or that limit which it is not advisable to exceed even for an occasional and exceptional load, as a stretch of from 004 to 005 according to the quality of the steel, while for the normal load the stretch should not exceed 002 to 003

Dans les meilleurs ressorts faits jusqu'à présent, l'acier travaille habituellement à environ 0022 sous la charge normale (p 317)

In the course of his investigations Phillips notes that to stretch steel for once up to 005 or 006 saves it from any sensible set when again subjected to the same strain (p 316), and further he briefly refers (p 318) to a result associated with the 'paradox in the theory of beams' as a subject for future study Thus he states that a stretch of 0095 (instead of 005) corresponding to a load of 190 kilogs per sq mm can be reached in *flexure* experiments without danger

The appended *Note* then follows, the details of which have been given in the course of our analysis of the memoir

[508] The memoir just considered is a striking example of how a very simple elastic theory—sufficiently accurate for the range of facts to which it is applied—can be made to yield most valuable results Phillips' theory of springs such as are employed in the ordinary rolling stock of railways is one of those excellent bits of work which can only be produced by the practical man with a strong theoretical grasp I have devoted considerable space to its discussion as the *Journal* in which it appears is not among the most accessible, and so far as I know the only text-book in which extracts have yet found a place is M Flamant's *Stabilité des constructions Résistance des matériaux*, Paris, 1886 pp 574—88

[509] Giuseppe Fagnoli *Riflessioni intorno la teoria delle pressioni che un corpo o sistema di forma invariabile esercita contro appoggi rigidi ed immovibili da quali è sostenuto in equilibrio Mem dell' Accad delle Scienze di Bologna T VI, 1852 pp 109—38*

This memoir, as long-winded as its title, was probably the last attempt to solve without the aid of the theory of elasticity the problem of the reactions upon a body of more than three points of support. It seems to me utterly obscure and involves the strange metaphysical conception of internal reactions in 'perfectly rigid bodies.'

[510.] A. Popoff: *Sur l'intégration des équations relatives aux petites vibrations d'un milieu élastique. Bulletin de la société impériale des naturalistes de Moscou. T. XXVI., Première Partie, pp. 342—56, Moscow, 1853.*

This paper deduces by a slightly different method the solutions of the uniconstant elastic equations for small vibrations first obtained by Ostrogradsky and Poisson: see our Arts. 739*—41* and 564*.

There does not seem any particular advantage in the method of Popoff and he draws no new conclusions from his solutions.

[511.] A. Popoff: *Intégration des équations qui se rapportent à l'équilibre des corps élastiques et au mouvement des liquides: Bulletin physico-mathématique de l'Académie...de St Pétersbourg, T. XIII, 1855, pp. 145—9.* This is reprinted (with the title only in Russian) in the *Mélanges mathématiques et astronomiques, T. II., pp. 284—9.*

The paper was received in October 1852.

Adopting the notation of our footnote p. 79, and supposing the elastic body to be under the influence of no body-forces and in equilibrium then we can easily show that the equations of elasticity in cylindrical coordinates are:

$$\left. \begin{aligned} \nabla^2 \theta &= 0, \\ \nabla^2 u - \frac{u}{r^2} - \frac{2}{r^2} \frac{dv}{d\phi} + \frac{\lambda + \mu}{\mu} \frac{d\theta}{dr} &= 0, \\ \nabla^2 v - \frac{v}{r^2} + \frac{2}{r^2} \frac{du}{d\phi} + \frac{\lambda + \mu}{\mu} \frac{d\theta}{r d\phi} &= 0, \\ \nabla^2 w + \frac{\lambda + \mu}{\mu} \frac{d\theta}{dz} &= 0, \end{aligned} \right\} \dots\dots\dots(i),$$

where

$$\nabla^2 = \frac{d^2}{dr^2} + \frac{1}{r} \frac{d}{dr} + \frac{1}{r^2} \frac{d^2}{d\phi^2} + \frac{d^2}{dz^2},$$

or is the Laplacian in cylindrical coordinates.

Further,
$$\theta = \frac{du}{dr} + \frac{u}{r} + \frac{1}{r} \frac{dv}{d\phi} + \frac{dw}{dz} \quad (11)$$

We can obtain by our Art 884* the thermo elastic equations of equilibrium, if we write for θ in (1) θ' and instead of (11) write

$$\theta' = \frac{du}{dr} + \frac{u}{r} + \frac{1}{r} \frac{dv}{d\phi} + \frac{dw}{dz} - \frac{\beta}{\lambda + \mu} q \quad (111),$$

where for thermal equilibrium, $\nabla q = 0 \quad (117),$

q being the temperature at r, ϕ, z

It is these thermo elastic body shift equations, which Popoff has solved. He has not considered the surface conditions nor the stresses, and he limits his investigation to cases in which q, θ', u, v and w do not become infinite for $r=0$ ¹

[512] The solution is really in terms of Bessel's functions, although he expresses them by integrals of the form given in equation (4), Art 371, of Todhunter's *Functions of Laplace, Lamé and Bessel*. The solution is fairly straight-forward although only the outline of the integrations is given. The results are somewhat too lengthy to be reproduced here, but should be consulted by any one endeavouring to solve the general problem of the strain in a right-circular elastic cylinder subjected to any system of surface stress. To show the type of solution I cite the value of w

$$w = \Sigma \left\{ [(Ae^{ar} - A'e^{-ar}) \cos n\phi + (Be^{ar} - B'e^{-ar}) \sin n\phi] \right. \\ \left. \times (ar)^n \left\{ \epsilon + \frac{\lambda + \mu}{2\mu} (2n\epsilon - ar\zeta) \right\} \right\},$$

where
$$\epsilon = \int_0^\pi \cos(ar \cos \chi) \sin^n \chi d\chi,$$

$$\zeta = \int_0^\pi \sin(ar \cos \chi) \sin^n \chi \cos \chi d\chi,$$

and n is an integer to be given all values from 0 to ∞ . A, A', B, B', a are constants to be determined by the surface conditions.

The constant a is in practice the most difficult to determine, it appears in each Bessel's function and in each exponential, and even for the simple cases of axial symmetry, we obtain an appalling equation to ascertain its relation to n . The analogy of stunts leads us to see that there are many cases in which it must be imaginary.

The values of u and v are still more complex, and it seems to me that really practical progress will hardly be made by attempting to carry this solution in Bessel's functions further. Possibly more might be achieved by solving Laplace's equation in cylindrical coordinates by a definite integral and then attempting to deduce definite integral solutions for the shifts.

¹ In his notation $\theta = \omega$ $(\lambda + \mu)/\mu = 1$ $\beta q/\mu = \Delta\theta$ $u = \delta u$ $v = \delta v$ $w = 0$

[513.] J. B. Phear: *Note on the Internal Pressure at any point within a body at rest.* *Cambridge and Dublin Mathematical Journal*, Vol. ix., 1854, pp. 1—6. A proof of the existence of Lamé's stress-ellipsoid of no peculiar interest: see our Art. 1059*. The author remarks that this representation of stress is "so elegant that it seems to deserve a place in our University mathematics."

[514.] M. Bresse: *Recherches analytiques sur la flexion et la résistance des pièces courbes*, Paris, 1854, 269 pp. and three plates. This treatise consists of five chapters and treats analytically on the Bernoulli-Eulerian hypothesis the flexure of curved ribs, in particular, circular arches. It contains a very complete discussion of the problem, and Bresse's tables are of considerable value in testing any proposed circular arch. At the same time the graphical methods of Eddy are of more general application and would probably be now-a-days adopted, at least as a method of verification and comparison. I proceed to give some account of the contents of this treatise.

[515.] Chapter I., is entitled: *Étude hypothétique de la répartition d'une force sur la section droite d'un prisme.* Pp. 1—43 are occupied with a very full, clear and interesting discussion of the neutral axis and the load-point (stress-centre) relations to the ellipse of inertia, and applications to the core, the centre of percussion and centre of pressure of a given area or cross-section. After comparing this chapter with the *Cours lithographié* referred to in our Art. 813*, I have no doubt that the *Cours* was due to Bresse, or that we owe to him the important conception of the core and all that flows from it. I regret that I was not able to associate his name with this conception in Vol. I.

It is to be noticed that Bresse proves these properties on the assumption that the stretch-modulus varies over the cross-section. He treats it as if it were a variable distribution of surface density over that section.

[516.] Pp. 44—56 of this chapter are entitled: *Répartition d'une charge totale sur la base d'un prisme n'ayant pas d'adhérence avec son appui.*

Suppose a loaded prism to rest on a horizontal base. This base can give pressure but not tension. Suppose farther the resultant vertical

load P on the prism to meet this base in the point H . If H lies within the core, the base will be required to give pressure only and the distribution of that pressure will follow the law laid down in our Art 815*. On the other hand, if H falls outside the core, we cannot make use of the formula in our Art 815* as it gives in part tensions. The problem considered by Bresse is then *How must the pressures be distributed over the portion of the prism's base remaining in contact with the plane in order that the resultant of these pressures may be equal and opposite to P ?*

Obviously the boundary between the parts of the section remaining and not remaining in contact must be the neutral axis for the part remaining in contact. Otherwise a portion of the section on both sides would give pressure or be in contact. The problem then reduces to the following: To cut a portion off a given area by a straight line, such that the load point or stress centre of the area cut off when it has the straight-line as neutral axis may be a given point.

For the general case Bresse only suggests a method of tentative solution. Namely to take (i) a series of parallel neutral axes and find the load points of the portions they cut off, the series of points so obtained gives a curve, which we may term the 'load point curve', and, (ii) to draw such load point curves for a variety of directions of the series of parallel neutral axes. Obviously the load-point curve which goes through the given load point H solves the problem.

On pp 46—48 Bresse proves an interesting property of the load point curve, namely that the tangent to this curve at any load point passes through the centroid of the area cut off by the corresponding neutral axis.

In the particular case when the given load point lies upon an axis of symmetry of the section of the prism, we have only to draw neutral axes perpendicular to this symmetrical axis and the required one can often be fairly easily found. Bresse works out the required dividing line in the case of the rectangle, circle, ellipse, etc., in which cases the analysis is not difficult. In particular in the case of a rectangle $2a \times 2b$, when the load point is at a distance na from the centre ($n > \frac{1}{3}$) on the axis of symmetry parallel to the sides $2a$, the neutral axis lies on the opposite side to the load point at a distance from the centre equal to $a(2 - 3n)$, and the maximum stress is in the side of the rectangle parallel to the neutral axis and

$$= \frac{P}{4ab} \frac{4}{3(1-n)}$$

It is shown on p 52 that the maximum stress in the case of a circular cross section increases much more rapidly as the load point is removed further from the centre than in the case of a rectangular one the side of which is equal to the diameter of the circle.

[517] Bresse's second chapter is entitled *Generalites sur la flexion et la resistance des pieces courbes* (pp 60—67). This chapter gives a very clear account of what the author understands by an

arched rib (*pièce courbe*) and the limits he has set to his discussion of the general problem. Thus he neglects slide, he supposes torsion to produce no effect so great that the rib-axis cannot still be dealt with as a plane curve, and he calculates the stress across any section on the assumption that the section is in the unstrained position; he allows, however, for a gradual change of cross-section and for a variation of the stretch-modulus in the cross-section. The 'mean-fibre' of the rib is defined as the locus of the centroids of the cross-sections, when those cross-sections are supposed to have a superficial density at each point equal to the stretch-modulus. He sums up the problems he proposes to deal with as follows:

(i) To find the stress over each cross-section of the rib supposing the loads and reactions given.

(ii) To find the effects of a change of temperature in producing stress and shift.

(iii) To calculate the reactions when the unstrained form and the load are given.

[518.] Chapter III. is entitled: *Flexion et résistance des pièces courbes, lorsque la pièce, dans l'état primitif et dans l'état de flexion, se trouve dans un plan contenant aussi les forces extérieures* (pp. 68—156).

The first section (pp. 68—76) of this chapter deals with problem (i) of the previous article. It shows how to find the stress-centre (load-point) of each cross-section when the reactions and the external forces on the rib are known. Suppose the rib divided up into elements and the corresponding distributed or concentrated loads represented by a single resultant for each element. Now form a vector-polygon of these elementary loads and the two terminal reactions. Choose the meet of the two reactions as ray-pole of this vector-polygon, and draw a corresponding link-polygon¹ for the rib, its first link being the reaction at one of the terminals of the arch. This is the 'line of pressure' of the arch, and it meets each cross-section of the rib in the corresponding stress-centre. The total stress at this stress-centre is measured by the corresponding ray of the vector-polygon. This stress may be resolved in and perpendicular to the cross-section. The component in the plane of the cross-section gives the *total* shearing stress across the section; the component *P* perpendicular to the plane, if substituted in the formula of our Art. 815* or of p. 879 of Vol. I. gives the distri-

¹ Vector- and link-polygons are the convenient terms by which Clifford generalised the names force- and funicular-polygons.

bution of traction over the cross section Bresse is dealing with cases where the plane of flexure is the plane of loading, i.e. the load plane passes through a principal axis of each cross section (note our Art 14), so that the formula takes the simple form

$$T = \frac{P}{\omega} \left(1 + \frac{by}{\kappa} \right)$$

Here, if E the stretch modulus vary, we must put

$$\omega = \frac{\sum E \delta \omega}{\sum E}$$

κ will also change if the cross section be supposed to vary *slightly*. As a rule it will be sufficient to tabulate (or exhibit graphically) T for the extrados and intrados. The quantity b may sometimes be obtained with sufficient accuracy by scaling its value from a carefully drawn line of pressure. It can of course be ascertained for any cross-section by an analytical determination of the resultant of the forces acting on the rib to one side of the cross section.

In the following section of the chapter (pp 76—83) Bresse gives two most interesting examples of the calculation of the tractive stress over the cross sections of arched ribs in the cases of a simple arch due to Tritschler (*Pont de Brest*) and of a combination of ribs forming an arch due to Vergniais. I do not think a more instructive study can be found for an engineering student than to work out for himself with Bresse's data, both analytically and graphically, the stresses in one or both of these two cases.

[519] § III (pp 84—95) is entitled *Recherche des deformations de la fibre moyenne sous l'action de forces exterieures supposées toutes connues*. Its object is to find expressions for the shifts at each point of the central axis (*la fibre moyenne*) of the arched rib, and for the change in inclination of the cross-section at any point of the central axis. We may obtain Bresse's equations as follows.

Let α be the angle the cross section at any point of the central axis makes with a given cross section, measured so that α increases with s the length of arc from the given cross section, let ϵ be the 'moment of inertia' and e the 'mass' of the cross section supposing it loaded with a superficial density equal to the stretch modulus E . Then the change in the angle $\delta\alpha$ due to the strain may be represented by $\Delta\delta\alpha$, and that in the arc δs by $\Delta\delta s$, let ρ be the strained, ρ_0 the unstrained curvature at any point s of the central axis, and N the corresponding total normal stress.

Then we easily deduce for the stretch in a 'fibre' distant z from the line through the centroid of the cross section perpendicular to the load-plane

$$\text{stretch} = z \left(\frac{1}{\rho} - \frac{1}{\rho_0} \right) + \left(1 + \frac{z}{\rho} \right) \frac{\Delta\delta s}{\delta s}$$

supposing $(z/\rho)^2$ to be negligible; therefore the bending moment M , taken to increase α , is given by

$$\begin{aligned} M &= \Sigma E z^2 \delta \omega \left(\frac{1}{\rho} - \frac{1}{\rho_0} \right) + \Sigma E \left(1 + \frac{z}{\rho} \right) z \frac{\Delta \delta s}{\delta s} d\omega \\ &= \epsilon \left(\frac{1}{\rho} - \frac{1}{\rho_0} \right) + \frac{\epsilon}{\rho} \frac{\Delta \delta s}{\delta s}. \end{aligned}$$

Putting in for ρ and ρ_0 their values in terms of α and s , we have

$$\begin{aligned} \frac{M}{\epsilon} &= \frac{\Delta \delta \alpha}{\delta s} - \frac{d\alpha}{ds} \frac{\Delta \delta s}{\delta s} + \frac{1}{\rho} \frac{\Delta \delta s}{\delta s} \\ &= \frac{\Delta \delta \alpha}{\delta s} + \left(\frac{1}{\rho} - \frac{1}{\rho_0} \right) \frac{\Delta \delta s}{\delta s}; \\ \therefore \Delta \delta \alpha &= \frac{M}{\epsilon} \delta s - \left(\frac{1}{\rho} - \frac{1}{\rho_0} \right) \Delta \delta s. \end{aligned}$$

Now the second term on the right-hand side may generally be neglected in arches because it is the product of small differences; hence integrating, it follows that:

$$\Delta \alpha - \Delta \alpha_0 = \sum_{s_0}^s \frac{M}{\epsilon} \delta s \dots \dots \dots (i).$$

This agrees with Bresse's equation (8 bis), p. 87. On p. 85 he does not give the second term of the expression above for $\Delta \delta \alpha$, because he appeals to a result on his p. 35, where, however, he has treated the central axis as straight.

We may obtain Bresse's equations (9 bis) and (10 bis), p. 88, as follows:

$$\partial s \cos \alpha = \partial x, \quad \partial s \sin \alpha = -\partial y.$$

Hence, if u and v be the shifts, and β a coefficient of stretch produced by any cause other than the loads, as for example temperature:

$$\begin{aligned} \delta u &= \Delta \partial s \cos \alpha - \partial s \sin \alpha \Delta \alpha \\ &= \frac{dx}{ds} \left(\frac{N}{e} + \beta \right) \delta s + \delta y \left(\Delta \alpha_0 + \sum_{s_0}^s \frac{M}{\epsilon} \delta s \right). \end{aligned}$$

Summing this (the second term on the left by parts), we have

$$u - u_0 = \sum_{s_0}^s \frac{N}{e} \frac{dx}{ds} \partial s + \beta (x - x_0) + \Delta \alpha_0 (y - y_0) + y \sum_{s_0}^s \frac{M}{\epsilon} \delta s - \sum_{s_0}^s y \frac{M}{\epsilon} \partial s.$$

Or rearranging:

$$u - u_0 = \Delta \alpha_0 (y - y_0) + \beta (x - x_0) + \sum_{s_0}^s \left[(y - y_1) \frac{M_1}{\epsilon_1} + \frac{N_1}{e_1} \frac{dx_1}{ds_1} \right] \delta s_1 \dots (ii),$$

where the summation is to apply only to quantities marked with the subscript 1.

Similarly we find:

$$v - v_0 = -\Delta \alpha_0 (x - x_0) + \beta (y - y_0) + \sum_{s_0}^s \left[-(x - x_1) \frac{M_1}{\epsilon_1} + \frac{N_1}{e_1} \frac{dy_1}{ds_1} \right] \delta s_1 \dots (iii).$$

We have retained the sign of summation as it indicates clearly the method of procedure by quadratures, when, as is most frequently the case, the loads and bending moments are not continuous, and so integration cannot be applied.

[520] On pp 90—94 Bresse indicates how the constants $\Delta\alpha_0$, u_0 , v_0 can be determined practically. Thus one or more cross-sections will have their directions unchanged, or one or both terminals will be pivoted or there will be a line of symmetry for the rib, three conditions will always be given which enable us to determine these constants. On pp 95—105 we have the formulae (i) to (iii) applied to several special examples. Thus Bresse deals with

(a) The case of a uniformly loaded rib of circular form and given span with uniform cross-section. The integration of the equations is easy, though the results are long (see our Arts 525—6). He considers this case with a uniform load first along the arc and secondly along the chord, the load being in both instances vertical and the chord horizontal.

(b) The case of a cast-iron circular rib of the railway viaduct at Tarascon over the Rhône (see our Art 527). The deflection as obtained by calculation is 0.642 metres, as obtained from the mean of experiments on the rib before and after erection = 0.650 metres. This is an excellent example of the application of theory to practice, and the nearness of the theoretical and experimental results is remarkable, when one remembers the irregularity of the stretch-modulus across the cross-section and even the doubt as to its mean value.

The theoretical result for the deflection due to a change of temperature of 1° centigrade is worked out on the supposition that β the linear dilatation = 0.0111. It is 0.0159 metres. Experiment gave in the mean 0.0135 metres or a difference of about $1/6$.

[521] The following section of the chapter under discussion is entitled *Recherche des forces inconnues*, and it occupies pp 105—126. In the examples hitherto considered Bresse has supposed the terminal reactions to be known, this is not generally the case, and we now turn to the problem of discovering the unknown reactions when the primitive form, the nature of the terminal fixings and

the superincumbent load are given. We will briefly cite the conditions to be applied to equations (i)—(iii) in order to obtain the unknown reactions :

(a) At a *fixed* or *pivoted* terminal we have $u = v = 0$ to determine the two components of the unknown reaction at that terminal.

(b) At a *built-in* terminal we have $u = v = 0$, and $\Delta\alpha = 0$ to determine the two components of the reaction and the bending moment at that terminal.

(c) When two ribs are fixed or joined together, we have u and v the same for both at that point, which gives two equations to find the components of the mutual reaction.

(d) When two ribs are built into each other, we have three equations arising from the equality of the values of u , v and $\Delta\alpha$ for both ribs at that point; these equations suffice to determine the reaction and the bending moment at the point.

(e) If a terminal be constrained to move along a smooth curve, we have a relation between u and v for that terminal, which suffices to determine the normal reaction of the curve.

In all these cases there will be three equations of statical equilibrium for each rib, which suffice with the above to determine the constants $\Delta\alpha_0$, u_0 , and v_0 ; thus in each case there will be sufficient equations to determine all the unknowns.

Bresse treats a number of general cases of fixed or built-in terminals etc., or of combinations of ribs, by the principles we have laid down above. His method is, however, sufficiently indicated by our statement; the analysis varies in quantity according to the nature of the structure¹. Two of the more interesting cases investigated are those of an arched rib with a horizontal tie-bar parallel to but not coincident with the chord, and a system of three mutually built-in pieces such as form the bridge system of Vergniais (pp. 112—122). On pp. 123—5 Bresse shows the sufficiency of the elastic and statical equilibrium equations to determine all the unknown quantities. On p. 125 is a paragraph entitled: *Du calage des arcs*. I do not understand clearly in what this process of *calage* or wedging, used apparently in building-up an arched rib out of its component parts, may consist. According to Bresse it has the effect of increasing the planned length of the central axis, and produces a uniform stretch in the rib and so a pressure upon the buttresses although the rib be not loaded. He proposes to allow for it by adding to the coefficient β a term having a value independent of the temperature and equal to $\frac{\text{the sum of the breadths of the wedges}}{\text{the planned length of the central axis}}$.

¹ Bresse speaks of a doubly built-in arched rib as having *peu d'importance pratique* (p. 110). This is, however, the type of the remarkable bridge at St Louis, Mass. U. S., which is 518 feet span and formed of doubly built-in steel ribs.

[522] In § VI of this chapter (pp 126—147) we have a very interesting but laborious bit of algebraical work, namely, the application of the results of the previous section to find the mutual actions between the several ribs and the reactions upon the buttresses in the case of a bridge on the Vergniais principle, of which the numerical dimensions are given. It is an excellent application, whose practical suggestiveness is much increased by variations in the treatment according as the ribs are supposed to be either pivoted or built-in to each other and to the buttresses.

[523] The final section of the chapter is entitled *Remarques et theoremes concernant la maniere dont les forces exterieures entrent dans les formules de la flexion. Conséquences* (pp 147—156). The author shows that the shifts as well as the terminal reactions are linear functions of the loads and of the thermal stretch coefficient β . This of course is a result of the general principle of 'perfect elasticity'. It gives us a means, however, of calculating the parts of the shifts or of the reactions due to each individual load and then by adding the parts of ascertaining the totals,—a method which will often be found very convenient. These results depend of course on β being independent of the loads. They would fail

Par exemple, si la chaleur ne dilatait pas également une barre tendue et une barre comprimée, ce que, à notre connaissance, les physiciens n'ont pas vérifié (p 149).

The point is of interest. I have only come across Pictet's remark on this subject see our Art 876* (3).

[524] Pp 153—156 deal with a property of symmetrical arched ribs asymmetrically loaded, and with a special application of it. This property is thus stated by Bresse—it being assumed that the axis of v is that of symmetry and that of u perpendicular to v .

If symmetry be given to the load system

1° En y ajoutant pour chaque force manquant de sa symétrique une force égale et située symétriquement, 2° en supprimant les forces dont les symétriques manqueraient, que dans ces deux hypothèses on détermine soit l'une des variations u , v , $\Delta\alpha$ qui caractérisent la flexion en un point, soit l'une des composantes, parallèlement aux axes, d'une réaction inconnue, soit son moment, la somme des deux quantités ainsi déterminées sera égale à la somme ou à la différence des quantités analogues

qui, sous l'action du système primitif des forces, se produisent au point considéré et en son symétrique ;...on doit, de plus, prendre la différence des quantités analogues pour deux points symétriques, lorsque, tout en étant symétriques, elles ont des directions contraires (p. 155).

For example, let an arch have a vertical axis of symmetry and let the load be parallel to this axis. Let Q, Q' be the horizontal thrusts on the terminals, then for any load :

$$Q + Q' = 0.$$

Suppose the load to be made symmetrical, so that Q, Q' become $Q_1, -Q_1$ when we add to make symmetry, and become $Q_2, -Q_2$ when we subtract to make symmetry. Then according to the above principle

$$Q_1 + Q_2 = Q - Q',$$

or

$$Q = \frac{1}{2} (Q_1 + Q_2).$$

Thus if we can obtain results for symmetrical loading, we can deduce results for asymmetrical loading.

[525.] Chapter IV. (pp. 157—217) deals with the thrust of arched ribs of uniform cross-section, for which the central axis, originally circular, remains after flexure in one and the same plane. Bresse's method is direct and simple.

He supposes (§ 81) a single isolated load Π at any point acting perpendicular to the span $2a$ of an arched rib. The vertical reactions at the terminals are given by the equations of Statics, the thrust Q is obtained by an application of the principle referred to in our Art. 524, to the equation deduced from constant length of the span : see our Art. 521. Thus Bresse finds :

$Q =$

$$\frac{\frac{1}{2}(\sin^2\phi - \sin^2\theta) + \cos\phi(\cos\theta + \theta\sin\theta - \cos\phi - \phi\sin\phi) - \frac{1}{2}\frac{G^2}{a^2}\sin^2\phi(\sin^2\phi - \sin^2\theta)}{\phi + 2\phi\cos^2\phi - 3\sin\phi\cos\phi + \frac{G^2}{a^2}\sin^2\phi(\phi + \sin\phi\cos\phi)} \dots\dots\dots(i),$$

where

2ϕ = the central angle of arched rib,

θ = the angle the radius to the loaded point makes with the radius to mid-point of rib, and

G = the swing-radius of the cross-section superficially loaded with the stretch-modulus. See our Arts. 1458* and 1573*.

Similarly (§ 82) if there be an isolated load S , at a point determined by θ , acting parallel to the chord of the arch, the terminal thrusts

$$= \frac{1}{2}Q_1 + \frac{1}{2}S \quad \text{and} \quad \frac{1}{2}Q_1 - \frac{1}{2}S,$$

where

$$\frac{1}{2}Q_1 = S \frac{\frac{1}{2}\theta - \frac{1}{2}\theta \sin \theta \cos \theta - \sin \theta \cos \phi + \theta \cos \theta \cos \phi + \frac{1}{2} \frac{G}{a} \sin^2 \phi (\theta + \sin \theta \cos \theta)}{\phi + 2\phi \cos \phi - 3 \sin \phi \cos \phi + \frac{G}{a} \sin^2 \phi (\phi + \sin \phi \cos \phi)} \quad (ii)$$

Next (§ 83) if a couple L with its axis perpendicular to the plane of the central-axis be applied to an element of the rib at the point θ

$$Q = -\frac{L}{a} \frac{\sin \phi (\sin \theta - \theta \cos \phi)}{\phi + 2\phi \cos^2 \phi - 3 \sin \phi \cos \phi + \frac{G^2}{a^2} \sin \phi (\phi + \sin \phi \cos \phi)} \quad (iii)$$

Lastly (§ 84), if there be a change in the length of the central axis due to temperature or any other cause and having a stretch-coefficient β (p 163),

$$Q = \frac{2e\beta \sin^3 \phi \frac{G^2}{a^2}}{\phi + 2\phi \cos^2 \phi - 3 \sin \phi \cos \phi + \frac{G^2}{a} \sin^2 \phi (\phi + \sin \phi \cos \phi)} \quad (iv),$$

where e = mass of area of cross section loaded with the stretch modulus E

By applying the principle of superposition of stress we are able from Equations (i) to (iv) to ascertain the thrust due to any conceivable system of isolated loads. Any continuous load may be concentrated over small elements and treated as a system of isolated loads. Or, on the other hand we may replace Π or S by $f(\theta) d\theta$ and integrate along the central axis. This is done by Bresse in the following three cases¹

(i) Thrust due to $2pp\phi$ being the weight of the arch (radius ρ) or a load distributed uniformly along its length (§ 87),

$$Q = 2pp\phi a \frac{\frac{1}{4} - \frac{a}{2} \cos \phi - \phi \sin \phi \cos \phi + \frac{a}{4} \frac{\sin \phi}{\phi} \cos \phi - \frac{1}{2} \frac{G}{a} \sin \phi (\sin \phi - \frac{1}{2} + \frac{1}{2} \frac{\sin \phi}{\phi} \cos \phi)}{\phi + 2\phi \cos^2 \phi - 3 \sin \phi \cos \phi + \frac{G}{a} \sin \phi (\phi + \sin \phi \cos \phi)} \quad (v)$$

(ii) Thrust produced by a load $2p'a$ distributed uniformly along the chord of the arc (§ 88),

$$Q' = 2p'a \frac{-\frac{1}{4} + \frac{7}{12} \sin^2 \phi + \frac{1}{4} \frac{\phi}{\sin \phi} \cos \phi - \frac{1}{2} \phi \sin \phi \cos \phi - \frac{1}{2} \frac{G}{a} \sin^2 \phi}{\phi + 2\phi \cos \phi - 3 \sin \phi \cos \phi + \frac{G}{a} \sin \phi (\phi + \sin \phi \cos \phi)} \quad (vi)$$

¹ He also gives results for (i) and (ii) when the uniformly distributed loads do not cover the whole of the arch

(iii) Thrust produced by a fluid pressure along the extrados of the arch (§ 89). The result is too complex to be cited here.

[526.] The most important case is that represented by Equation (i). Bresse throws it into the form

$$Q = \Pi k_1 \frac{1 - K \frac{G^2}{a^2}}{1 + K' \frac{G^2}{a^2}},$$

where, if

$$A = \frac{1}{2} (\sin^2 \phi - \sin^2 \theta) + \cos \phi (\cos \theta + \theta \sin \theta - \cos \phi - \phi \sin \phi),$$

$$\text{and } B = \phi + 2\phi \cos^2 \phi - 3 \sin \phi \cos \phi,$$

$$k_1 = A/B,$$

$$\text{and } K = \frac{1}{2} \frac{\sin^2 \phi (\sin^2 \phi - \sin^2 \theta)}{A}, \quad K' = \frac{\sin^2 \phi (\phi + \sin \phi \cos \phi)}{B}.$$

The quantities k_1 , K , K' are expanded in powers of $2\phi/\pi$ and $r \equiv \theta/\phi$ on pp. 173—191, and their values tabulated in Tables I. to IV. at the end of the volume. The entries give the values of k_1 for values of $2\phi/\pi$ from .12 to 1 rising by .01 at first, then by .02 and ultimately by .04; and for values of r rising by .05 from 0 to .95 (Table I.). The mean values of K and K' are given (i.e. the mean for all values of θ for any angle ϕ since they vary little with θ) for values of $2\phi/\pi$ from .12 to 1 (Table III.), and finally the values of $\left(1 - K \frac{G^2}{a^2}\right) / \left(1 + K' \frac{G^2}{a^2}\right)$ for the same range of values of $2\phi/\pi$ and five values of G^2/a^2 , namely .0005 to .0025 inclusive rising by .0005 (Table IV.).

Bresse points out on p. 172 that the value of G^2/a^2 varies for seven French bridges between .000106 and .000795, and that its maximum value .0025 in Table IV. is probably seldom approached in practice. As most of the bridges have a value of G^2/a^2 lying between .0003 and .0004, the value of Table IV. would have been increased had additional entries been made for values of G^2/a^2 less than .0005.

[527.] Bresse shows that if a load p be put upon the arched rib per unit length of the *central axis*:

$$Q = 2p\rho\phi \times m_1 \frac{1 - K G^2/a^2}{1 + K' G^2/a^2} \dots\dots\dots (v)',$$

where ρ is the radius of the central axis.

If a load p' be put upon the arched rib per unit length of the *chord*:

$$Q' = 2p'a \times n_1 \frac{1 - K G^2/a^2}{1 + K' G^2/a^2} \dots\dots\dots (vi)'.$$

If there be a coefficient of thermal or other stretch β :

$$Q_1 = q_1 \frac{\beta e G^2/a^2}{1 + K' G^2/a^2} \dots\dots\dots (vii),$$

where $e = \Sigma E \delta \omega$ as before.

The values of m_1 , n_1 and q_1 are tabulated for values of $2\phi/\pi$ from 12 to 1 in Table II. Unfortunately q_1 by a printer's error appears as τ_1 in that Table and the error is nowhere pointed out.

Bresse's first four tables thus give us a means of ascertaining the thrust in many practically important cases of circular ribs of uniform cross section. The method of using the Tables is exemplified on pp 212—217 by their application to the bridges at Brest and Tarascon. The discussion on the former bridge brings out clearly the smallness of the error introduced by concentrating into a series of isolated loads the parts of a continuous load which act upon even considerable portions of the arch.

[528] We may note one or two other points brought out in the course of this chapter.

(i) On pp 193—196 it is shown that Equation (vii) may be replaced with sufficient approximation in practice by taking the formula

$$Q_1 = \frac{\beta e G}{G + \frac{8}{15}f^2}$$

where f , the rise of the arch, is measured for the central axis.

(ii) If the same load ($2pp\phi = 2ap'$) be distributed uniformly along the central axis or uniformly along the chord, then the ratio of Q to Q' as determined by Equations (v) and (vi) may for most practical purposes be taken as unity. Bresse gives the following values (p. 203)

$2\phi/\pi =$	12	2	3	4	5	6	7	8	9	1
$Q/Q' =$	997	993	984	971	953	930	900	863	814	750

(iii) If Q'' be the horizontal tension of the cables of a suspension bridge which is of span $2a$, rise f , and loaded with p' lbs per foot run, then the ratio of Q as given by (vi) to Q'' ($= \frac{p'a}{2f}$) is very nearly unity if G/a' be small. Thus if G/a be less than .0005 we have sensibly for

$2\phi/\pi =$	12	2	3	4	5	6	7	8	9	1
$Q/Q'' =$	999	996	992	985	975	962	946	922	893	849

Hence for most practical problems we may calculate Q' from the tension in the cables of a suspension bridge of the same span and rise. We note that Q' is always less than Q see our Art 1459^π.

[529] Chapter V is entitled *Resistance d'un arc circulaire à section constante, chargé dans toute sa longueur de poids uniformément répartis suivant l'horizontale* (pp 218—249). The object of this chapter is to calculate the maximum traction at any point of

an arched rib due to a uniform loading of the rib of p' lbs. per foot run of the horizontal chord. This is practically the loading which would occur, if the bridge were tested by a train of locomotives or a uniform pile of iron rails (*l'arc sous l'action de la charge d'épreuve*, pp. 218—9).

Let E be the stretch-modulus of any fibre, N the normal force on a cross-section making an angle α with the central cross-section; e the mass of the cross-section of superficial density E , and ϵ the moment of inertia of the mass of this cross-section about an axis through the central axis perpendicular to the load-plane. Then the traction in a fibre at distance y from that axis is given (pp. 220—2) by :

$$E \left(\frac{N}{e} + \frac{My}{\epsilon} \right) \dots \dots \dots (i).$$

It is easy to show, ρ being the radius of the arch, that :

$$N = -Q \cos \alpha - p' \rho \sin^2 \alpha \dots \dots \dots (ii),$$

$$M = Q \rho (\cos \alpha - \cos \phi) - \frac{1}{2} p' \rho^2 (\sin^2 \phi - \sin^2 \alpha) \dots \dots \dots (iii);$$

or, if $Q = n \times 2p'a$, n being a certain function of ϕ and G^2/a^2 (compare our Art. 527),

$$N = -p' \rho (2 \cos \alpha \sin \phi + \sin^2 \alpha) \dots \dots \dots (ii)',$$

$$M = \frac{1}{2} p' \rho^2 (\cos \alpha - \cos \phi) (4n \sin \phi - \cos \alpha - \cos \phi) \dots \dots (iii)'.$$

We thus know the traction at any point by substituting (ii)' and (iii)' in (i).

Bresse assumes that in an arched rib it is the pressure or traction, which first reaches the elastic limit, he therefore seeks the greatest negative value of the expression $E(N/e + My/\epsilon)$. I do not think that this is justifiable. What we really want is the greatest positive stretch of the material, and accordingly the proper condition seems to be to find the greatest positive and negative values of $N/e + My/\epsilon$, then to choose the maximum numerical value from either the positive values, or the negative multiplied by η the stretch-squeeze ratio, and equate that maximum to the safe elastic stretch. Bresse really assumes that the elastic limit is reached in compression and extension with the same numerical strain, and therefore as the squeezes are always greater than the stretches, we have only to deal with the former. But we ought I think to investigate whether $\eta \times$ the maximum squeeze is greater than the maximum stretch. If η be, say, $\frac{1}{3}$ or $\frac{1}{4}$, then it by no means follows that Bresse's condition is correct. For example in the results given by him for the *Pont de Brest* and represented graphically in Fig. 23 of Plate II, the maximum positive traction is in the extrados of the arch and very sensibly greater than one-third of the maximum negative traction, which here occurs at the same cross-section in the intrados. Similarly in the stresses for the *Système Vergniais* given in Fig. 26 (B) Plate III, the maximum positive traction in the extrados of the *contrefort* is greater than the

maximum negative traction in the same rib, and is about as great as the maximum negative traction in the main arch. Thus in these actually existing bridges, it is obvious that Bresse's method of seeking for the maximum negative traction would be deceptive. The true criterion must in each case be deduced from the situation of the load-point (or stress centre), i.e. whether it lies inside or outside the whorl of the cross section. Bresse's method only applies if all the load points lie inside the whorls. see Vol I p 879

[530] Pp 221—230 are occupied with a discussion of the possible magnitudes and positions of the maximum negative traction. These depend largely on the sign of M as given by Equation (iii)', and Bresse shows that if $n > \frac{1}{2} \cot \phi$, then M vanishes at either four points or two points besides the 'pivoted' terminals. see our Art 1460*. I will not enter into the details of this investigation, since for the reasons given in the previous article it does not seem to me entirely satisfactory, the graphical construction of curves of thrust and bending moment, of the line of pressure and of the whorl of the cross section is the better treatment of the problem, some allowance being made if necessary for the effect of shearing force. Suffice it to add that if E_1 be the stretch modulus of the 'mean fibre' Bresse reduces the maximum negative traction to the form

$$\zeta \frac{p'a}{e} E_1$$

where ζ is a coefficient depending on $\frac{G}{a^2}$, $\frac{2\phi}{\pi}$ and $\frac{h}{a}$, where h is the distance of the central axis from 'the extreme fibre'. The values of ζ are tabulated on pp 260—269 for a considerable range of values of these arguments, and a horizontal line drawn across Bresse's columns marks whether the maximum negative traction occurs in the extrados or intrados (Table V)

[531] After some numerical examples of this Table on pp 237—8, Bresse concludes his work with a section entitled *Des circonstances qui peuvent influer sur la résistance d'un arc à section constante, chargé uniformément suivant l'horizontale* (pp 238—249). This section deals with general theorems (deduced from the numerical results of Table V and therefore open to the objections of our Art 529) as to the elastic strength of an arch when we vary (1) ϕ , or what is the same thing, vary the ratio of rise to span, (2) the cross section as determined by the ratios of G and h to $2a$ the span.

If G/a be constant, and we take the mean value of h/a (which does not vary much since G/a is constant) we can find a value of the ratio of rise to span, which gives a minimum of ζ , or a maximum elastic resistance. Thus we find approximately for

$G/a =$	0001	0002	0003	0004	0005	0006	0008	0010	0012	0015
$f/2a =$	1212	1490	1581	1668	1756	1859	1980	2117	2164	2210

In § 122 Bresse considers a special case of an arched rib of hollow elliptic cross-section and investigates for what values of the ratio of rise to span it is more advantageous to place the cross-section with its major axis horizontal than with it vertical or *vice versa*.

In § 123 he deals with the problem of the best ratio of the height to the breadth in the cross-section (supposed to be rectangular and of constant area) of an arched rib having a given load, height and span. The laws of ribs with circular central axes differ in respect of relative strength very considerably from those of straight beams.

Although for the reasons stated above, Bresse's results in this section must not be considered as final, still they indicate the existence of numerous very interesting properties varying with the form of the rib. They conclude what is the most thorough investigation hitherto published of the elastic strength of circular arches subjected to uniplanar flexure.


[532.] M. Bresse: *Cours de mécanique appliquée*. The *Première Partie* of this book was published in Paris in 1859 in parts. A second edition of the *Première Partie* appeared in 1866, with, however, few modifications, and a third in 1880. The *Troisième Partie* (*Calcul des moments de flexion dans une poutre à plusieurs travées solidaires*) appeared in 1865. Only the first and third parts deal with topics related to our present subject. The former is entitled: *Résistance des Matériaux et Stabilité des Constructions*, and the chief difference between the first and second editions is that § II. of the third chapter on continuous beams disappears in the later edition, reappearing in a much fuller form in 1865 as the *Troisième Partie* of the work. The *Première Partie* in the second edition from which I cite contains pp. i—xxviii and 1—536. I shall discuss the *Troisième Partie* under the year 1865.

[533.] Chapter I. entitled: *Généralités; Principes fondamentaux*. *Recherche des tensions dans les diverses parties d'un corps prismatique*, pp. 5—89, is occupied with a discussion of the moment of inertia, the neutral axis, the load-point, the core and the distribution of traction over a cross-section when the line of pressure is known. This follows with some amplifications the treatment of the lithographic course and of the work on arched ribs: see our Arts. 813*—5* and 514—6.

[534.] Chapter II. (pp. 90—149) deals with the general equations for the strain of a rod, whose central axis is not necessarily a straight line. It is an amplification of the treat-

ment in the work on arched ribs and the major portion does not call for special remark. The only part which need be noticed is entitled *Des mouvements vibratoires dans les pièces élastiques* and occupies pp 143—9. Bresse deals with the case of the vibrations of a rod, the central axis of which is a plane curve. He supposes this rod to vibrate only in the plane of its own central axis, so that that plane must pass through a principal axis of each cross-section, the cross section itself is considered to be uniform.

Let u, v be the shifts of the centroid G of any cross-section (distant s along the central axis from any fixed point of the rod) measured along the tangent and normal (outwards) to the central axis at G . Let χ be the variation in the angle which the tangent at G makes with any fixed line, positive when taken clockwise. Let m be the mass of the rod per unit length and T, N the external forces per unit of length of the rod at



G, M the clockwise couple round G per unit element (this is introduced by Bresse, but it seems to me that in most conceivable cases M would be zero). Let $1/\rho$ be the curvature, κ the swing radius of the cross section ω at G round an axis through G perpendicular to the plane of flexure, E the stretch and μ the slide modulus, both being supposed uniform for the cross section. Then Bresse obtains the following equations

$$\begin{aligned} m \frac{d u}{d t} &= T + E \omega \frac{d}{d s} \left(\frac{d u}{d s} + \frac{v}{\rho} \right) + \frac{\mu}{\rho} \left(\frac{d v}{d s} + \chi - \frac{u}{\rho} \right), \\ m \frac{d v}{d t} &= N + \mu \omega \frac{d}{d s} \left(\frac{d v}{d s} + \chi - \frac{u}{\rho} \right) - \frac{E \omega}{\rho} \left(\frac{d u}{d s} + \frac{v}{\rho} \right), \\ m \kappa \frac{d \chi}{d t} &= M + F \omega \kappa \frac{d \chi}{d s} - \mu \omega \left(\frac{d v}{d s} + \chi - \frac{u}{\rho} \right) \end{aligned}$$

Here $\mathcal{E}\omega \left(\frac{du}{ds} + \frac{v}{\rho} \right)$ is the total traction and $\mu\omega \left(\frac{dv}{ds} + \chi - \frac{u}{\rho} \right)$ the total shear over the cross-section at G .

These three equations suffice theoretically to determine u , v and χ . Bresse makes the following remarks on them :

Pour le moment, nous ne pousserons pas plus loin l'étude de la question ; dans les cas pratiques les plus simples, la solution présentera généralement de grandes difficultés, comme on le verra ultérieurement par les exemples que nous indiquerons. Nous n'avons voulu, en donnant les calculs précédents, que compléter la théorie générale de la déformation des pièces élastiques, par l'exposé de la méthode à suivre pour mettre en équation le problème des mouvements vibratoires (pp. 148—9).

[535.] The practical part of the *Cours* begins with Chapter III. which is entitled *Problèmes divers concernant les poutres droites* (pp. 150—224). A good deal of this chapter is not novel, but the methods are very clearly and concisely put, and some interesting problems of continuous beams with large numbers of supports are dealt with on pp. 176—188; these should certainly be studied by any one practically interested in this subject. Slide is considered after the manner of Jouravski (see Section III. of our present Chapter) on pp. 206—9, but there is no reference to the work of Saint-Venant. The chapter concludes with an essentially theoretical treatment of the problem of struts (pp. 210—224).

[536.] Chapter IV. deals with the problem of arched ribs (pp. 225—263) after the manner of the work we have already analysed: see our Arts. 514 to 531. Chapter V. is also a continuation of this subject (pp. 264—338)¹. It contains, however, a section on the strength of cylindrical vessels (pp. 323—338) which requires some notice on our part. The first problem dealt with is that of a boiler or flue of right-circular cross-section, and the method adopted is the old hydrostatic process, involving no elastic principle: see our Art. 1012*.

[537.] The second case dealt with is novel. It is entitled: *Résistance d'une chaudière à profil faiblement elliptique* (p. 326), and, if we could trust the investigation, this case might be useful in calculating the dimensions of slightly elliptic flues. Bresse however practically treats his elliptic cylinder as if the portion between two

¹ Matter not in the book of 1854 is chiefly confined to some account of the experiments of Desplaces, Collet-Moygret, and Jules Poirée: see Section III. of our present Chapter.

parallel cross sections at unit distance could be dealt with as if it were a rod. Thus he takes the product of the flexural rigidity and the change in the curvature as equal to the bending moment. Let c be the thickness, supposed uniform, of the flue, l its length, M the moment tending to bend the wall of the flue round any longitudinal section, $\Delta\psi$ the change due to the strain in the angle between two tangents to the central line of the flue's cross section at the ends of an arc δs , then Bresse puts

$$M = Ec \times l \times \frac{c^2}{12} \times \frac{\Delta\psi}{\delta s}$$

Now, if it is legitimate to use any formula of this kind at all, it would seem necessary to at least replace the stretch modulus by the plate-modulus $\{i.e. \text{ by } E/(1-\eta^2)\}$, but I must confess to having grave doubts as to the entire method of treatment. To assume the existence of a neutral axis passing through the centroid of a transverse section in the case of a bent plate subjected to strain seems in itself a very risky proceeding.

If we may adopt Bresse's assumption we arrive at the following results—in which

p = the internal pressure in the flue, e = the eccentricity of the elliptic cross section, $2a$ its internal major axis, x the abscissa of any point measured along this major axis from the centre, c the thickness of the flue, supposed small and uniform, l = the length of the flue

(a) The bending moment of the wall of the flue at points given by x is equal to $\frac{1}{4}pe^2(2x^2 - a)$ per unit length of the flue

(b) The maximum traction, which occurs at the ends of the major axis, is given by

$$T = \frac{pa}{c} + \frac{3pa^2e}{2c}$$

The first term in the traction is due to the internal pressure supposing the flue to be exactly circular, the second term is due to the flexure produced by the slight ellipticity.

The result (b) gives a quadratic to find the proper thickness c for a given value of T and p , the positive root must be taken. Bresse turns this formula into numbers and shows that a very slight value of e^2 (.02) will require the value of c to be increased in the ratio of 5 : 3. Thus the existence of slight ellipticity in a flue is very unfavourable to its strength.

(c) There is a decrease in the semi major axis given by

$$\delta a = -\frac{pa^4e}{Ec^3},$$

and an increase in the semi minor axis of about the same amount (p. 332)

Further the eccentricity e' after strain is given in terms of the eccentricity before strain by

$$e'^2 = e^2 / \left(1 + \frac{4pa^3}{Ec^3} \right).$$

These results would be, perhaps, slightly improved if E were replaced by $E/(1-\eta^2)$.

(d) Bresse next supposes p negative, that is to say that there is an external pressure p . In this case e' will be real or equilibrium possible only if

$$1 > \frac{4pa^3}{Ec^3},$$

or

$$c > a \left(\frac{4p}{E} \right)^{\frac{1}{3}}.$$

This result is independent of the absolute strength T of the material. It is discussed at considerable length by Bresse on pp. 334—7. But the manner in which it has been deduced does not leave an impression of conclusiveness on my mind. Were c even to approach this value, e' would become very great, or the strain exceed the elastic limit.

(e) Bresse points out that the thickness of the elliptic flue will have to be greater for the case of external pressure than for the case of an equal internal pressure, *supposing that the resistances to compression and extension are equal*, (p. 338.)

[538.] The same problem is considered by J. H. Macalpine in the third of *Three Original Papers* (Glasgow, James Maclehoose and Sons) dated in 1889. It is entitled: *On the strength and stiffness of an elliptic cylinder submitted to hydrostatic pressure* (pp. 26—31), and may be referred to here. Macalpine obtains practically the same results as Bresse for the change in the axes, but for the maximum bending moment he finds (instead of $\frac{1}{4}pe^2a^2$) $\frac{1}{4}pe^2a^2 \left\{ 1 + \frac{4p}{E} \left(\frac{a}{c} \right)^3 \right\}$ per unit length. The term $\frac{4p}{E} \left(\frac{a}{c} \right)^3$ arises from the *second* approximation and it can obviously in certain cases sensibly modify Bresse's result. To the first approximation, however, I think the two agree. For on p. 30, l. 10 from the bottom, Macalpine finds *in his own notation*:

$$\theta = \frac{pb^4e^2}{4ac} \sin \phi \cos \phi.$$

But M his bending moment $= c \frac{d\theta}{ds},$

$$\text{or, } M = \frac{pb^4e^2}{4a} (2 \cos^2 \phi - 1) \frac{d\phi}{ds}.$$

Changing to our notation and remembering that, as we are neglect-

ing e^4 , we may put $b = a$, $\frac{d\phi}{ds} = \text{curvature} = 1/a$, and $a \cos \phi = x$, we have

$$M = \frac{pe^2}{4} (2x - a),$$

which agrees with Bresse's result (a) In other respects Macalpine's treatment is neither so full nor so clear as Bresse's He falls into the same error of treating a bent plate as a rod¹

[539] The sixth chapter of Bresse's book is entitled *Problèmes particuliers sur les poutres vibrantes* and occupies pp 339—387 This chapter is perhaps the most interesting in the book It gives a good *résumé* of all the work which had been done in and since the time of Navier and Poncelet on the subject of vibrational stress in bridges

It opens with a discussion after the manner of Poncelet of the longitudinal vibrations of bars variously loaded (cf our Arts 988*—993*), and does not here add much to Poncelet's results The great defect of Poncelet's work is that it leaves us with complex analytical expressions, which require the patience of a Saint-Venant to reduce them to numerical results of practical value see our Arts 401 and 411

Bresse next passes to the transverse vibrations of a uniform beam simply supported at both terminals and uniformly loaded (pp 361—374) I think his work here is original, at any rate I have not come across the same results before It bears of course considerable resemblance to the ordinary theory given in treatises on Sound of the transverse vibrations of a rod

Bresse obtains an equation of the following type (which may easily be deduced as a special case from those of our Art 534) for the transverse shift y of the centroid of a section distant x from one terminal of a beam of length l

$$E\omega\kappa^2 \frac{d^4y}{dx^4} = mg - m \frac{d^2y}{dt^2} + m'\kappa \frac{d^4y}{dx dt^2},$$

where $E\omega\kappa^2$ = the flexural rigidity of the beam,

m = combined mass of beam and load per foot run,

m' = mass of beam only per foot run,

t = the time from any epoch

¹ My objections to this method of treatment have been more fully given in Art 1547'

Bresse obtains a general solution for any initial shifts and any initial velocities: see his p. 369; he also deals with one or two special cases. Thus on pp. 370—1 he shows how the constants may be easily calculated when the shifts and velocities are initially given by integer algebraic functions of x . A further interesting case on p. 372 may be cited here. It practically amounts to an expression for the deflection at any point of a bridge or beam, when a continuous load is suddenly placed upon it.

Bresse finds:

$$\frac{24E\omega\kappa^2}{mg} y = x^4 - 2lx^3 + l^2x - \frac{96l^4}{\pi^5} \sum_{i=1}^{i=\infty} \left(\frac{1}{i^5} \sin \frac{i\pi x}{l} \times \cos \frac{i^2\pi^2 a^2 t}{l \sqrt{i^2\pi^2 b^2 + l^2}} \right),$$

the summation being for all odd integer values of i .

Now $1/i^5 =$ successively $1, \frac{1}{2^5}, \frac{1}{3^5}, \frac{1}{4^5}, \dots$, so that for all practical purposes it is unnecessary to go beyond the first or second term of the summation.

Here $a^2 = E\omega\kappa^2/m$, $b^2 = m'\kappa^2/m$, $= \kappa^2$ if the weight of the load be negligible as compared with that of the bridge.

For $x = l/2$, and $t =$ even multiple of $l \sqrt{\pi^2 b^2 + l^2} / (\pi a^2)$ the summation is very nearly equal to $\frac{5}{16} \cdot \frac{\pi^5}{96}$, and the maximum central deflection is given by

$$y = \frac{5}{192} \frac{mg l^4}{E\omega\kappa^3}, \text{ nearly.}$$

Thus the maximum deflection is almost twice the statical deflection under the same load, an instance of Poncelet's Theorem: see our Art. 988*.

[540.] The following and last section of this chapter is entitled: *Effet produit sur une poutre par une charge roulante* (pp. 375—87). Bresse begins by analysing Phillips' memoir of 1855 (see our Arts. 372—82 and 552—4) and quoting his results. For the case of a doubly-supported beam, he has not, however, noted Phillips' error: see our Art. 375. For the case of the doubly built-in beam he was, as we have noticed in Art. 382, the first to correct Phillips and he gives this correction on p. 376. With the notation of our Arts. 373—4, where it must be remembered $2l$ is the length of the beam, Bresse finds for the maximum bending moment of a doubly built-in beam subjected to a travelling load:

At the centre:

$$\left(\frac{1}{12} Pl + \frac{1}{4} Ql \right) \left(1 + \frac{3}{8} \beta \right),$$

and at the terminals:

$$\frac{1}{6} Pl \left(1 + \frac{3}{16} \beta \right) + \frac{1}{4} Ql \left(1 + \frac{3}{8} \beta \right).$$

The comparatively small practical value of these results has been pointed out in our Art. 382.

[541] Bresse then passes on pp 377—387 to the discussion of his own particular problem in live-load, of which we have already given the statement and chief results in our Art 382 To the results given there we may add the expression for the central deflection f , in the notation of that article

$$f = \frac{Pl^3}{2E\omega\kappa^2} \left\{ -\frac{1}{2}\beta'' + \beta''' (\sec \sqrt{1/\beta'} - 1) \right\}, \quad (\text{p } 382)$$

Bresse discusses, with numerical values for the limiting speeds, cases of plate iron railway girders and shows that the speeds obtained are considerably greater than the usual train speeds The practical value of the investigation is, however, not very great, as the maximum moment is reached (as is pointed out in our Art 382) just as the train covers the whole bridge, and not after a steady deflection is set up by a very long train

[542] The next chapter of the work (*Chapitre septieme*) is entitled *Résultats d'expériences sur l'élasticité des matériaux* and occupies pp 388—422 This portion of the work was at the time of publication a useful *résumé* of the experiments of Hodgkinson and his contemporaries It is now somewhat out of date The remarks, however, on p 393 as to the ill-founded character of the reproaches against the theory of elasticity, based on the fact that formulae depending on the proportionality of stress and strain will not explain rupture, are still to the point We, then, studied we should hear less of the "paradox in the theory of beams" see our Arts 178 and 507

The work concludes with chapters dealing analytically with framework and with the pressure of masses of earth, both topics lie outside the scope of our history

[543] M Painvin *These de Mécanique Études sur les états vibratoires d'une couche solide, homogène et d'élasticité constante, comprise entre deux ellipsoïdes homofocaux*, Paris, 1854 This is a thesis presented to the Faculty of Sciences of Paris for the degree of 'docteur ès sciences mathématiques' The examining commission were Chasles, Lamé, and Delaunay The memoir contains 46 quarto pages and is, I believe, the first attempt to use the equations of elasticity in curvilinear coordinates for the solution of any problem

[544] Lamé in 1841 had published in the *Journal de*

Painvin obtains a solution of the following type

$$\frac{v_1}{h_2 h_3} = \frac{dX}{d\rho_2} \frac{dx}{d\rho_3} - \frac{dX}{d\rho_3} \frac{dx}{d\rho_2} + \frac{dY}{d\rho_2} \frac{dy}{d\rho_3} - \frac{dY}{d\rho_3} \frac{dy}{d\rho_2} + \frac{dZ}{d\rho_2} \frac{dz}{d\rho_3} - \frac{dZ}{d\rho_3} \frac{dz}{d\rho_2},$$

where X, Y, Z are all solutions of the equation

$$\omega^2 \nabla^2 F = d^2 F / dt^2.$$

The twists are shown (pp. 9—17) to be of the type

$$\tau_1 = -\frac{dx}{d\rho_1} \nabla^2 X - \frac{dy}{d\rho_1} \nabla^2 Y - \frac{dz}{d\rho_1} \nabla^2 Z + \frac{d}{d\rho_1} \left(\frac{dX}{dx} + \frac{dY}{dy} + \frac{dZ}{dz} \right).$$

This investigation seems to me unsatisfactory, because the solution is not entirely freed of x, y, z the old Cartesian coordinates.

[548.] In the second portion of his memoir (pp. 17—46) Painvin determines a solution of the equation $\Omega^2 \nabla^2 F = d^2 F / dt^2$, subject to the following conditions. Let $\rho_1 = a$ and $\rho_1 = a'$ be the parametric values for the confocal ellipsoids, then he supposes:

(i) the shears $\widehat{s_1 s_2}$ and $\widehat{s_1 s_3}$ to be zero for $\rho_1 = a$ and for $\rho_1 = a'$, these he terms the *surface conditions*;

(ii) the values of F and dF/dt for $t=0$ to be given functions of ρ_1, ρ_2, ρ_3 except as far as the addition of an arbitrary constant is concerned. This is really equivalent to assuming the initial shifts and initial speeds. These are the *initial conditions*.

The supposition (ii) is perfectly straightforward but it is difficult to grasp the physical meaning of (i). The surface traction $\widehat{s_1 s_1}$ is not put zero for $\rho_1 = a$ and a' , hence there must be a traction varying with the time exerted over the surfaces of the shell, if it is to vibrate solely *longitudinally*. Painvin does not distinctly say so, but I think he supposes the air, which he refers to as surrounding his shell, capable of giving the necessary traction. This is, of course, impossible (see our Art. 1084*); the traction sometimes will be *positive*, and the air could not even provide anything like as great negative traction (pressure) as would be required for many sound vibrations. Physically the only result of the memoir, assuming its analysis complete, is to show that the vibrations of a free shell bounded by confocal ellipsoids must be partly *twist-vibrations*, for Painvin's solution is evidently impossible. At the same time it involves such very pretty analytical investigations, that we wish it had some real physical value.

[549] J Dienger *Studien zur mathematischen Theorie der elastischen Körper* Grunerts Archiv der Mathematik und Physik, Theil 23, 1854, pp 293—359

This is a treatise on the general theory of elasticity, with applications to the theory of vibrations. The writer proceeds on rari-constant lines, basing his work on that of Navier, Poisson and Lamé. He prefers rari constancy to Lamé's method as it indicates

was die jeweils eingeführten Grossen zu bedeuten haben, wie sie folglich zu berechnen und zu behandeln sind—ein Vorthail, der gewiss nicht zu niedrig anzuschlagen ist (p 358)

He proceeds on the supposition of an initial state of stress, like Cauchy (see our Arts 615*—6*), but he retains shift-fluxions up to the fourth order, for this he claims originality. The coefficients of the shift-fluxions of the fourth order are given in terms of molecular summations (pp 300—301). He deals with the relations between these summations on pp 323—6, and obtains for isotropy body shift-equations of the type

$$(G + P) \nabla^2 u + 2P \frac{d\theta}{dx} + (A + K) \nabla^2 (\nabla^2 u) + 4K \nabla^2 \left(\frac{d\theta}{dx} \right) + X = 0,$$

where,

$$G = \frac{1}{2} \sum m f(r) r \cos^2 \alpha$$

$$P = \frac{1}{2} \sum m F(r) r^2 \cos^2 \beta \cos^2 \gamma$$

$$A = \frac{1}{24} \sum m f(r) r^3 \cos^4 \alpha$$

$$K = \frac{1}{24} \sum m F(r) r^4 \cos^2 \beta \cos^4 \gamma = \frac{1}{24} \sum m F(r) r^4 \cos^2 \lambda \cos^4 \beta,$$

where $F(r) = r \frac{d}{dr} \left(\frac{f(r)}{r} \right)$, $f(r)$ being the law of inter-molecular central action, and α, β, γ the direction angles of the molecule m at distance r . If the body be not subjected to initial stresses, G and A are both zero. In this case the equation above agrees with that which may be deduced from Saint-Venant's values of the stresses see our Art 234

The rest of the discussion—notwithstanding the author's claim on p 358—does not seem to me to offer any novelty. Dienger concludes with a remark as to Cauchy's explanation of dispersion which he considers a failure as it would apply to 'empty space'. The promise to explain dispersion in a perfectly natural manner

[550.] L. F. Ménabréa. *Études sur la théorie des Vibrations. Memorie della Reale Accademia delle Scienze*, T. xv., 1855, pp. 205—329. Turin, 1855. The memoir was read June 12, 1853 and published as an offprint in 1854. It commences with a general discussion of the stability and small oscillations of a slightly disturbed group of particles. This occupies pp. 205—225 and the author draws particular attention to the best mode of integrating the equations which arise. The general discussion is followed by special problems, which introduce elastic bodies as limiting cases. Thus a heavy flexible string is treated as the limiting case of a number of particles united by weightless inextensible strings, or again a rod as the limiting case of a number of heavy particles united by rigid links which resist being displaced about their extremities by forces proportional to the angles the adjacent links make with one another. In this method the limits of finite difference equations become the differential equations for the vibrations of elastic strings, rods, membranes etc. The method is due to Lagrange and is used freely in the *Mécanique Analytique*. Examples of it will be found in Lord Rayleigh's *Theory of Sound* Vol. I. § 120, or in Routh's *Rigid Dynamics* 3rd Edition, § 486. It cannot be considered entirely satisfactory as it often involves somewhat arbitrary hypotheses: as for example, in the . of the transverse vibrations of the rod referred to above.

[551.] The following are the contents of the memoir as far as it relates to special cases:

(a) Pp. 226—232: Oscillations of a particle attracted by several fixed centres of force; (b) pp. 232—7: Vibratory motion of a flexible string carrying two heavy particles, the string being fixed at one end only; (c) pp. 238—73: Vibratory motion of a string fixed at one end and carrying several heavy particles;—this is subdivided into several parts dealing with strings whose parts are not homogeneous, etc.; (d) pp. 273—284: Longitudinal vibrations of an elastic rod or string loaded with particles at different points; (e) pp. 285—291: Vibrations of a flexible and inextensible string fixed at its terminals and forming a curve under the action of forces distributed along its length; Ménabréa arrives at formulæ agreeing with those given by Navier on p. 163 of the work referred to in our Art. 272*; (f) pp. 292—297: Vibrations of a funicular polygon formed of flexible and extensible elements; (g) pp. 297—306: Transverse vibrations of a rod composed of diverse heterogeneous parts or having various heavy particles attached to it.

Menabrea besides obtaining the general equation of the vibrations of a rod with a longitudinal tension T , namely

$$F \frac{d^4 y}{dx^4} = T \frac{d^2 y}{dx^2} - m \frac{d^2 y}{dt^2} \quad (\text{see our Art 471}),$$

(where F is here a constant depending on the material of the rod, which remains undefined owing to the vagueness of the hypothesis adopted), also indicates the solution of the following problem

A rod is clamped at its upper end, a particle, the weight of which is great relative to that of the rod, is attached to its lower end, to find the motion of the system when set vibrating (pp 301—2)

The solution is not carried far enough to be of service in dealing with Kupffer's empirical formula for the like case see Section II of the present Chapter

(h) Pp 307—311 Vibrations of a plane rectangular flexible membrane uniformly stretched and composed of two parts of different material, (i) pp 312—22 Radial vibrations of a homogeneous elastic sphere The results in this case agree with those given by Poisson in his memoir of 1828 see our Art 449* *et seq*, (j) pp 323—7 Note on the theory of light, Menabréa deduces Fresnel's equations from his general theory of a particle oscillating under the action of several fixed centres of force

The memoir as a whole contains no new results, but there are some interesting and suggestive analytical processes

[552] E Phillips *Calcul de la resistance des poutres droites, telles que les ponts, les rails, etc sous l'action d'une charge en mouvement Annales des Mines, Tome VII, 1855, pp 467—506*

This is the important memoir to which we have referred in our Arts 372—82

The memoir is divided into three chapters *Chapitre I* (pp 468—87) is entitled *Des poutres encastrees par leurs deux extremités*, and it deals with the case of a load crossing with any given velocity a straight beam of uniform cross-section doubly built-in This problem is not of very much importance, for it is difficult to really build-in the terminals of a girder, and when done there arise several practical disadvantages Phillips' analysis is only approximate, the deflection being expanded in powers of the distance from a terminal, and the coefficients of these powers being given by rather lengthy series in powers of the time These series are simplified by the assumption that $m/(E\omega\kappa^2)$ is a small quantity where m is the mass of the beam per foot-run and $E\omega\kappa$ its

flexural rigidity; only first powers of this expression are then retained.

I have not verified Phillips' analysis and his results as given on pp. 480—6 are too lengthy for citation.

[553.] *Chapitre II.* entitled: *Des poutres reposant librement sur deux appuis*, deals with the like problem for simply-supported terminals (pp. 487—500). The analysis has for practical purposes been much simplified by Saint-Venant, and as the latter has corrected an error of Phillips we merely refer the reader to our discussion of the problem in Art. 372—6.

In both the cases dealt with in these chapters Phillips does not satisfy the initial condition that the velocity of all parts of the girder shall be zero, before the load comes upon it. In the case of the doubly built-in girder, however, the initial velocity given by the approximate solution is of the order $1/\beta^2 \equiv m/E\omega\kappa^2$ and is therefore very small. For the doubly-supported girder the terms neglected are of the order $Vl/(3\beta)$, where l is the length of the girder and V the velocity of the travelling load.

For to ascertain the real effect of this initial velocity Phillips lets the bridge to remain without load and to start from a position with an initial velocity exactly equal to that which must be in his problem. He finds that this initial system of velocities produces a maximum deflection occurring almost at the centre of the bridge and given with sufficient approximation by

$$\frac{2}{\pi\beta} \left(\frac{l}{\pi}\right)^4 \frac{QV}{E\omega\kappa^2},$$

where Q is the weight of the travelling load.

The ratio of this deflection to the maximum deflection at the centre is very nearly

$$\frac{Vl}{3\beta},$$

while the corresponding curvatures (d^2y/dx^2) have very nearly the ratio

$$\frac{Vl}{4\beta}.$$

Phillips then shows that for four actual bridges with a load moving at 108 kilometres per hour the former of these quantities does not exceed $1/20$, and they are thus in practice negligible.

[554.] *Chapitre III.* (pp. 500—6) is entitled: *Conséquences pratiques de la théorie précédente et son extension à d'autres mo-*

blesmes It deals first with the case of the doubly-supported girder. The conclusions drawn with regard to the curvature and stretch are involved in the results of our Arts 372—7, where following Saint-Venant we have corrected Phillips' numerical error.

In the latter part of this chapter (pp 503—6) Phillips deals with the case of the doubly built in girder. He shows that except just when the load is coming on to or leaving the bridge the maximum curvature at the instant is immediately under the load, and that the maximum maximum takes place when the load reaches the centre of the beam, we have then¹

$$1/\rho = \frac{Ql}{8E\omega\kappa^2} \left(1 + \frac{QV^2l}{8E\omega\kappa^2g}\right) + \frac{Pl}{24E\omega\kappa} \left(1 + \frac{QV^2l}{4E\omega\kappa^2g}\right)$$

Evidently then the magnitude of the fraction $\frac{QV^2l}{8E\omega\kappa^2g}$ determines the influence of the speed of the travelling load on the deflection. Phillips takes the case of a rail one metre long and for which the rigidity is 197,600 (sq metre kilogrammes?) and Q is 6000 (kilogrammes? he has kilometres). The value of the fraction is then about 35 for a velocity of 108 kilometres per hour, and about 16 for one of 72.

He remarks in conclusion

Dans tous les cas de la pratique, ce qu'il y aura de plus simple à faire est ceci. Comme il faut toujours que la poutre puisse supporter la charge au repos, on commencera par calculer les dimensions de cette poutre en conséquence, d'après les règles ordinaires. Puis, l'on vérifiera si la quantité $QV^2l/(3E\omega\kappa^2g)$ dans le cas de la poutre appuyée librement par ses deux extrémités, ou $QV^2l/(8E\omega\kappa^2g)$ dans le cas de la poutre encastree par ses deux bouts, est assez petite. Dans ce dernier cas, et si la charge permanente n'était pas negligeable, il faudrait en outre que $Ql/(4E\omega\kappa^2g)$ fût une petite fraction. Dans le cas où ces diverses fractions ne seraient pas assez petites, on diminuerait l'écartement des points extremes ou l'on augmenterait le moment d'élasticité de la poutre jusqu'à ce que la fraction dont il s'agit devienne negligeable (p 505).

[555] Kopytowski *Ueber die inneren Spannungen in einem freiaufhängenden Balken unter einer beweglichen Belastung* 4to, Gottingen, 1865. This is an inaugural dissertation for the doctor's degree and contains 88 pages with a plate of figures. Although falling somewhat outside the period we are considering this memoir is so closely related to that of Phillips dealt with in the three previous articles that we may briefly touch upon it here. The author deals with the case of a uniform beam terminally supported which is crossed by a continuous travelling load. He refers in his preface to the labours in this field of Navier, Willis,

¹ I have not verified the analysis by which Phillips reaches this result but have slightly modified the numerical results which follow.

omitted in the differential equation. Pp. 63—68 are a reproduction of Bresse's problem (see our Arts. 382 and 540) without, however, any acknowledgment of the source from which the material is drawn.

[559.] Pp. 72—78 return to Renaudot's problem and calculate the bending moment at any point for any position of the load, and also the maximum bending moment. The latter value agrees with Renaudot's, but is wrong. The coefficient of the term $PV^2l^2/(\epsilon g)$ in Equation (65) of p. 78 should be $5/32$ and not $1/6$.

The expressions for the total shear (pp. 78—80), the terminal reactions, as well as the maximum total shear at the middle of the beam will also be wrong, so far as the numerical coefficients of the terms in $PV^2l^2/(\epsilon g)$ are concerned. I have not, however, recalculated these coefficients. The values of the principal tractions given in Equation (69) of p. 80 are again erroneous for the reasons given in Art. 556, and that for the deflection (pp. 81—2) has also a wrong coefficient. The same remarks apply to the numerical results on pp. 83—5 and p. 88.

[560.] On pp. 85—7, Table VIII., we have the values of $4/\beta'$, where β' is the constant of our Art. 381, calculated for a certain number of actual bridges. This discussion and table might have been of considerable value had not Kopytowski introduced what seems a very doubtful hypothesis into his calculations; he assumes, namely, that in each case the moment of inertia of the cross-section has been designed so as just to carry without failure the weight of the beam and the continuous load considered as acting *statically*. Thus, suppose $2l$ the length of the beam, p the weight per unit-run of the beam and p' that of the load. Then the maximum statical bending moment at the centre when the beam is fully loaded is:

$$M = \frac{1}{2} (p' + p) l^2.$$

Let h be the vertical diameter of the beam and $E\omega\kappa^2$ its flexural rigidity, then Kopytowski also equates this to

$$\frac{2}{h} T_0 \omega \kappa^2,$$

T_0 being the traction which corresponds to the fail-limit of the material. Hence he finds to determine $\omega\kappa^2$:

$$\omega\kappa^2 = \frac{1}{4} \frac{p' + p}{T_0} l^2 h,$$

or, substituting in $1/\beta'$ of our Art. 381:

$$1/\beta' = \frac{4T_0}{Eg} \frac{p' V^2}{(p + p') h}.$$

See the memoir pp. 74 and 85.

From this formula Kopytowski calculates $4/\beta'$ for the Britannia and Conway bridges and for bridges near Bordeaux, Bern, St Gallen etc.

is no sufficient reason for supposing that the moment of the cross-section of any of these bridges really has the value which is found by this process

On p 87 some remarks occur on the experiments of the *Iron Commissioners* and on Stokes' value for the deflection in the case of an isolated load see our Arts 1417* and 1287* The memoir is a rather more ambitious than satisfactory piece of work

[561] H Resal *Thèse de Mécanique Sur les équations polaires de l'élasticité et leur application à l'équilibre d'une croûte planétaire*, Paris, 1855

This is an academical dissertation occupying 40 quarto pages and dealing with a special case of Lamé's memoir of 1854 see our Art 1111* It is reproduced on pp 395—440 of the *first* edition of Resal's *Traté élémentaire de mécanique céleste* (Paris, 1865) with some of the misprints corrected As the latter work is more readily accessible than the *Thèse*, our references are to its pages

Pp 395—411 are occupied with an investigation of the equations of elasticity in spherical coordinates Resal adopts uni-constant isotropy, noticing, however, that Wertheim's experiments do not seem to be in complete accordance with the relation $\lambda/\mu = 1$ He rather weakly remarks

Dans l'incertitude où nous nous trouvons sur la valeur de ce rapport, dont la connaissance est indispensable pour pouvoir calculer λ et μ en fonctions du *coefficient d'élasticité*, la seule constante que l'on a l'habitude de faire entier dans les questions de résistance des matériaux, nous avons cru devoir continuer à admettre la relation théorique $\lambda = \mu$, trouvée par MM Navier, Poisson et Cauchy (footnote, p 404)

There is no novelty in this part of Resal's investigation except, I think, his application in a footnote (pp 402—4) of Cauchy's *fonctions isotropes* to determine a relation between the elastic constants in the expressions for the stresses The method does not seem to present any advantages

[562] On p 411 we have Resal's problem stated "To determine the elastic equilibrium of the spherical crust of a planet, rotating round a diameter, under the action of the mutual gravitation of its parts and subjected to uniform internal and external normal pressures"

This problem may be termed *Resal's Problem* although as we have seen a portion of it had already been considered by Lamé

Symmetry shows us at once that the shifts lie entirely in the meridian-plane, or reduce to u and v in the notation of our footnote on p. 79. Now these shifts may be divided into two parts $u' + u''$ and $v' + v''$ where u' and v' are due to the radial surface-forces and body-forces (i.e. pure gravity), while u'' and v'' are due to the so-called 'centrifugal force.' Now it is easily seen that we must have $v' = 0$. The value of u' was determined by Lamé for *bi-constant* isotropy in his *Leçons*: see our Arts. 1094*—5* and compare Arts. 1114*—8*, where it is shown that Lamé made some progress towards the solution of *Resal's Problem*.

[563.] The following are the values at distance r from the centre obtained by Lamé's method for u' , for the radial traction $\widehat{rr'}$, and for $\widehat{\phi\phi'}$ ($= \widehat{\psi\psi'}$ in the notation of our p. 79) the meridian traction corresponding to the shift u' :

$$u' = \frac{\gamma}{5} r^3 + \frac{r}{3\lambda + 2\mu} \left\{ \frac{r_0^3 p_0 - r_1^3 p_1}{r_1^3 - r_0^3} - (\lambda + \frac{6}{5}\mu) \gamma \frac{r_1^5 - r_0^5}{r_1^3 - r_0^3} \right\} \\ + \frac{1}{4\mu r^2} \left\{ \frac{r_0^3 r_1^3 (p_0 - p_1)}{r_1^3 - r_0^3} - (\lambda + \frac{6}{5}\mu) \gamma \frac{r_0^3 r_1^3 (r_1^2 - r_0^2)}{r_1^3 - r_0^3} \right\} \dots\dots\dots(i),$$

$$\widehat{rr'} = - \frac{r_0^3 p_0 (r_1^3 - r_0^3) + r_1^3 p_1 (r_0^3 - r_1^3)}{r^3 (r_1^3 - r_0^3)} + (\lambda + \frac{6}{5}\mu) \frac{\Pi \gamma}{r^3 (r_1^3 - r_0^3)} \dots\dots\dots(ii),$$

$$\widehat{\phi\phi'} = \widehat{\psi\psi'} = \frac{r_0^3 p_0 - r_1^3 p_1}{r_1^3 - r_0^3} + \frac{r_0^3 r_1^3 (p_0 - p_1)}{2r^3 (r_1^3 - r_0^3)} - \frac{4}{5}\mu \gamma r^3 \\ - \frac{(\lambda + \frac{6}{5}\mu) \gamma}{r^3 (r_1^3 - r_0^3)} \left\{ \frac{3}{2} (r_1^2 - r_0^2) r_0^3 r_1^3 - \Pi \right\} \dots\dots\dots(iii),$$

where: $\Pi = r^5 (r_1^3 - r_0^3) - r^3 (r_1^5 - r_0^5) + r_0^3 r_1^3 (r_1^2 - r_0^2)$ and is divisible by $(r_1 - r_0) (r - r_0) (r - r_1)$,

p_0 and p_1 = the internal and external pressures at the surfaces of the shell of radii r_0 and r_1 respectively,

$$\gamma = \frac{\rho g}{2(\lambda + 2\mu) r_1}, \quad \rho \text{ being the density, and}$$

g = gravitational acceleration at the outer surface.

The value of $\widehat{\phi\phi'}$ given above does not agree with Lamé's F' (p. 216 of the *Leçons*). The coefficient of Π in his expression should be $-2(\lambda + \frac{2}{5}\mu)$ and not $2(\lambda + 2\mu)$ as he has it. The form we have obtained for $\widehat{\phi\phi'}$ is also more convenient for further calculations than Lamé's. Resal obtains a value for $\widehat{rr'}$ agreeing with ours when $\lambda = \mu$, he does not write down the general value of $\widehat{\phi\phi'}$ or u' .

[564] Both Lamé and Resal proceed to approximations in the special case of a thin crust. We shall examine the true approximations somewhat closely, as it appears that both Lamé and Resal have fallen into error.

Let us put $r_1 = r_0(1 + e)$, $r = r_0(1 + \epsilon)$

and suppose the squares and products of e and ϵ to be small

$$\text{We find} \quad \widehat{rr}' = -p_0 + \frac{\epsilon}{e}(p_0 - p_1)\{1 + 2(e - \epsilon)\} \quad (iv)$$

The lowest term containing g as a factor is of the second order and its value is

$$\frac{5\lambda + 6\mu}{2(\lambda + 2\mu)} g\rho r_0 \epsilon (\epsilon - e)$$

Further

$$\begin{aligned} \widehat{\phi\phi}' = & -p_1 + (p_0 - p_1) \left\{ \frac{1}{2e} - \frac{\epsilon}{2e} + \frac{e}{3} - \epsilon + \frac{\epsilon^2}{e} \right\} \\ & - \frac{g\rho r_0}{2} \left\{ 1 - \frac{3\lambda + 2\mu}{\lambda + 2\mu} \left(\epsilon - \frac{e}{2} \right) \right\} \end{aligned} \quad (v)$$

The value of u' to the same degree of approximation is

$$\begin{aligned} u' = & (p_0 - p_1) r_0 \left\{ \frac{\lambda + 2\mu}{4\mu(3\lambda + 2\mu)} \frac{1}{e} + \frac{\lambda + 2\mu}{2\mu(3\lambda + 2\mu)} + \frac{\lambda + 2\mu}{6\mu(3\lambda + 2\mu)} e \right. \\ & - \frac{\lambda}{\mu(3\lambda + 2\mu)} \epsilon - \frac{\lambda}{2\mu(3\lambda + 2\mu)} \frac{\epsilon}{e} + \frac{1}{4\mu} \frac{\epsilon^2}{e} \left. \right\} \\ & - \frac{g\rho r_0}{2} \left\{ \frac{\lambda + 2\mu}{2\mu(3\lambda + 2\mu)} + \frac{e}{4\mu} - \frac{\lambda}{\mu(3\lambda + 2\mu)} \epsilon \right\} \\ & - \frac{p_0 r_0 (1 + \epsilon)}{3\lambda + 2\mu} \end{aligned} \quad (vi)$$

[565] If we neglect the products of p_0 or p_1 with e or ϵ , as both Resal and Lamé appear to do, we have on rearranging

$$\begin{aligned} u' = & \frac{(\lambda + 2\mu) r_0}{4\mu(3\lambda + 2\mu)} \left(\frac{p_0 - p_1}{e} - g\rho r_0 \right) + (p_0 - p_1) r_0 \left(1 + \frac{2\mu}{\lambda} - \frac{\epsilon}{e} \right) \frac{\lambda}{2\mu(3\lambda + 2\mu)} \\ & - \frac{g\rho r_0}{2} \left(\frac{e}{4\mu} - \frac{\lambda}{\mu(3\lambda + 2\mu)} \epsilon \right) - \frac{p_0 r_0}{3\lambda + 2\mu} \end{aligned} \quad (vii)$$

Putting successively $\epsilon = 0$ and $\epsilon = e$ we find

$$\begin{aligned} u'_0 = & \frac{(\lambda + 2\mu) r_0}{4\mu(3\lambda + 2\mu)} \left(\frac{p_0 - p_1}{e} - g\rho r_0 \right) + \frac{(p_0 - p_1) r_0 (\lambda + 2\mu)}{2\mu(3\lambda + 2\mu)} \\ & - \frac{g\rho r_0 e}{4\mu} - \frac{p_0 r_0}{3\lambda + 2\mu} \end{aligned} \quad (viii)$$

$$u_1' = \frac{(\lambda + 2\mu)r_0}{4\mu(3\lambda + 2\mu)} \left(\frac{p_0 - p_1}{e} - gpr_0 \right) + \frac{(p_0 - p_1)r_0}{3\lambda + 2\mu} - \frac{gpr_0^2 e}{8\mu} \left(1 - \frac{4\lambda}{3\lambda + 2\mu} \right) - \frac{p_0 r_0}{3\lambda + 2\mu} \dots\dots\dots (ix),$$

$$\text{and, } u_0' = u_1' - \frac{gpr_0^2 e}{2} \frac{\lambda}{\mu(3\lambda + 2\mu)} + \frac{(p_0 - p_1)r_0 \lambda}{2\mu(3\lambda + 2\mu)} \\ = u_1' + \{(p_0 - p_1)r_0 - gpr_0^2 e\} \frac{\lambda}{2\mu(3\lambda + 2\mu)} \dots\dots\dots (x).$$

The results (vii)—(ix) differ widely from those given by Lamé and Resal. The equation (x) agrees with one given by the latter author (p. 417) if we put $\lambda = \mu$. The values given by them for the shifts seem to be erroneous.

[566.] Turning to the tractions, our formula (v) gives :

$$\widehat{\phi\phi_1}' = \frac{1}{2e} \{(p_0 - p_1) - gpr_0 e\} \\ - \frac{p_0 + p_1}{2} + e \left\{ \frac{p_0 - p_1}{3} + \frac{3\lambda + 2\mu}{\lambda + 2\mu} \frac{gpr_0}{4} \right\} \dots\dots\dots (xi),$$

$$\widehat{\phi\phi_0}' = \widehat{\phi\phi_1}' + \frac{p_0 - p_1}{2} - e \frac{3\lambda + 2\mu}{\lambda + 2\mu} \frac{gpr_0}{2} \dots\dots\dots (xii).$$

Lamé (*Leçons*, p. 217) has in our notation the results

$$\widehat{\phi\phi_1}' = \frac{1}{2e} \{p_0 - p_1 - gpr_0 e\},$$

$$\widehat{\phi\phi_0}' = \widehat{\phi\phi_1}' - e \frac{\lambda}{\lambda + 2\mu} gpr_0.$$

It is not obvious without further discussion why in the case of a planetary crust $\frac{1}{2}(p_0 + p_1)$ should be neglected as compared with $\frac{1}{2}gpr_0$. The second equation is wrong unless we suppose $e\widehat{\phi\phi_1}'$ necessarily negligible.

Resal (*Mécanique Céleste*, p. 417) gives the same value as Lamé for $\widehat{\phi\phi_1}'$, but for $\widehat{\phi\phi_0}'$ he has

$$\widehat{\phi\phi_0}' = \widehat{\phi\phi_1}' - \frac{5}{8} gpr_0 e.$$

Thus he agrees with the third term on the right of our equation (xii) in the coefficient of $gpr_0 e$, since he puts $\lambda = \mu$, but he disagrees with Lamé. Like Lamé he appears to have dropped entirely the term $\frac{1}{2}(p_0 - p_1)$ and I see no reason for this.

Resal (p. 416) gives for \widehat{rr}' the value

$$\widehat{rr}' = -p_0 + \frac{\epsilon}{e}(p_0 - p_1).$$

This neglects the term $2(e - \epsilon) \frac{\epsilon}{e}(p_0 - p_1)$ of equation (iv). If terms

involving e , like $g\rho r_0 e$, are retained in $\widehat{\phi\phi}'$ this does not seem legitimate. If Lamé and Resal suppose $p_0 - p_1$ and $g\rho r_0 e$ to be of the same order then this would be allowable, but this would still compel them to retain the term $\frac{1}{2}(p_0 - p_1)$ they have cast out of (xii)

[567] Both Lamé and Resal apply these results to the structure of the earth, they thus initiated those investigations in terrestrial physics, which have been still further advanced by Sir William Thomson, G Darwin, Chree and others. Resal closely follows Lamé without, however, so much explanatory statement. Their whole investigation of rupture at the earth's surface is based upon the assumption that rupture takes place where the shear or traction is a maximum. They thus endeavour to explain geological faults. We may note the general drift of their reasoning, modifying it slightly to suit our formulae, as it will be useful for comparison with later work.

(a) Lamé remarks (p 218) that geologists (i.e. those of his day) considered that the thickness of the crust could not be more than $\frac{1}{150}$ of the radius, or $e = \frac{1}{150}r_0$. Hence to a first approximation from (xi),

$$\widehat{\phi\phi}' = 75 \{ (p_0 - p_1) - g\rho r_0 e \}$$

If therefore $p_0 - p_1$ were not very nearly equal to $g\rho r_0 e$, there would be a very sensible horizontal traction at the surface of the earth. There is nothing to show the existence of such stress and accordingly Lamé supposes $p_0 - p_1 = g\rho r_0 e$ very nearly. This obviously means that the difference of the surface pressures just supports the weight of the crust. If it were exactly true we should have to a first approximation $u_0 = u_1$, or the earth would retain the original thickness of its crust¹. If this relation holds we have also from (xii)

$$\widehat{\phi\phi}_0' = - \frac{\lambda}{\lambda + 2\mu} g\rho r_0 e,$$

or the meridian stress at the inner surface of the crust is a pressure.

If $\widehat{\phi\phi}'$ is negative, which it must become in the course of time as p_0 diminishes and e increases, then $\widehat{\phi\phi}_0'$ is a still greater pressure.

(b) Both Lamé and Resal use the stress quadric

$$\frac{x^2}{n^2} + \frac{y + z^2}{\widehat{\phi\phi}} = 1,$$

and the shear cone

$$\frac{x}{n^2} + \frac{y + z}{\widehat{\phi\phi}'} = 0$$

to determine the direction of shearing rupture and the magnitude of the shearing force. They suggest how the magnitude of this force and its direction may be found by experiment and observation of faults.

¹ Lamé (p 220) puts in this case $u_1 = u_1' = 0$ which arises from the error in his

In order that these may vanish for all values of ϕ when $r=r_0$ and $r=r_1$ we must have :

$$\left. \begin{aligned} a_0 &= \frac{5\lambda + 6\mu}{15(3\lambda + 2\mu)(\lambda + 2\mu)} \rho \omega^3 \frac{r_0^5 - r_1^5}{r_0^3 - r_1^3}, \\ b_0 &= \frac{5\lambda + 6\mu}{60\mu(\lambda + 2\mu)} \rho \omega^3 \frac{r_0^3 r_1^3 (r_0^2 - r_1^2)}{r_0^3 - r_1^3} \end{aligned} \right\} \dots\dots\dots(\text{vii});$$

together with the following four relations to determine a_1, b_1, a_2, b_2 :

$$\left. \begin{aligned} \frac{3}{2}a \left\{ \frac{r_0^2}{r_1^2} \right\} + a_1 + \frac{8}{3}b_1 \left\{ \frac{r_0^{-5}}{r_1^{-5}} \right\} + \frac{8\lambda + 7\mu}{3\lambda} a_2 \left\{ \frac{r_0^2}{r_1^2} \right\} + \frac{3\lambda + 2\mu}{3\lambda + 5\mu} b_2 \left\{ \frac{r_0^{-3}}{r_1^{-3}} \right\} &= 0, \\ \frac{7\lambda + 12\mu}{4\mu} a \left\{ \frac{r_0^2}{r_1^2} \right\} + a_1 - 4b_1 \left\{ \frac{r_0^{-5}}{r_1^{-5}} \right\} - \frac{1}{2}a_2 \left\{ \frac{r_0^2}{r_1^2} \right\} - \frac{9\lambda + 10\mu}{3\lambda + 5\mu} b_2 \left\{ \frac{r_0^{-3}}{r_1^{-3}} \right\} &= 0. \end{aligned} \right\} \dots\dots\dots(\text{viii}).$$

[569.] These equations completely solve the problem, but lead to rather lengthy expressions for the constants. Resal confines himself to uni-constant results. Our (vii) corresponds to his (A) p. 434, and our (viii) to the first and third equations in the set at the bottom of his p. 435, except that he has $2A'_2$ in the first, where he ought to have $4A'_2$. He does not, however, obtain the values of the constants even for uni-constancy, but assumes the shell extremely thin and then obtains their values when ϵ/r_0 is negligible. To calculate the constants at least to the first power

thickness is only laborious not difficult, and would I think necessary before any conclusions as to the points of maximum strain could be fairly drawn. If we put $\lambda = \mu$ and neglect ϵ/r_0 , we have to find a_1, b_1, a_2, b_2 from the first of each set of equations in (viii) and the differentials of those equations with regard to r_0 .

Solving the equations so obtained I find :

$$\left. \begin{aligned} a_1 &= -\frac{161}{225} \frac{\rho \omega^2}{\mu} r_0^2, & a_2 &= \frac{37}{350} \frac{\rho \omega^2}{\mu}, \\ b_1 &= \frac{4}{25} \frac{\rho \omega^2}{\mu} r_0^7, & b_2 &= -\frac{112}{225} \frac{\rho \omega^2}{\mu} r_0^5, \end{aligned} \right\} \dots\dots\dots(\text{ix}).$$

while (vii) gives :

$$a_0 = \frac{11}{135} \frac{\rho \omega^3}{\mu} r_0^2, \quad b_0 = \frac{11}{270} \frac{\rho \omega^3}{\mu} r_0^5$$

These results agree with those of Resal's p. 436, if proper changes of notation be made, notwithstanding the error I have noted in his equations corresponding to (viii).

Returning to the values of the shifts in (iii) and (iv) we see that r may now be written r_0 , so that to Resal's degree of approximation the shifts are constant for each latitude right through the crust and no conclusion can be drawn as to whether points inside or outside the crust are those of maximum strain. We find for the complete values of the shifts to this degree of approximation

$$u'' = \frac{\rho \omega^2 r_0^3}{10\mu} (4 - 9 \sin^2 \phi), \quad v'' = -\frac{\rho \omega^2 r_0^3}{2\mu} \sin \phi \cos \phi \quad (x)$$

From (iii) we easily find for the mean radial stretch of the crust in the most general case

$$\begin{aligned} \frac{u_1'' - u_0''}{r_1 - r_0} = & a_0 - b_0 \frac{r_0 + r_1}{r_0 r_1^2} + (\sin^2 \phi - \frac{1}{3}) \left\{ a_1 - b_1 \frac{(r_1^2 + r_0^2)(r_1 + r_0)}{r_1^4 r_0^4} \right. \\ & \left. + a_- (r_1^2 + r_0^2 + r_1 r_0) - b_- \frac{r_0 + r_1}{r_0 r_1^2} \right\} + a (r_1 + r_0^2 + r_1 r_0) (\frac{1}{3} - \cos^2 \phi), \end{aligned}$$

and therefore, when we neglect $(\epsilon/r_0)^2$, we have after some reductions

$$\frac{u_1'' - u_0''}{\epsilon} = -\frac{1}{10} \frac{\rho \omega^2 r_0^3}{\mu} \cos^2 \phi \quad (x_1)$$

This agrees with Resal's result p 437. He appears to deduce it from equation (23) of his p 436, but he has not proved that the value he there gives for his W is correct even to the terms involving ϵ .

[570] Resal draws various conclusions from the results (x) and (x₁) of the previous article on his pages 437—40. Thus he remarks that

(i) The flattening at the poles is $5/4$ of the bulge at the equator

(ii) The radius is not changed for the latitude

$$\phi = \sin^{-1} 2/3 \quad \text{or} \quad = 41^\circ 48' 37''$$

(iii) The thickness of the crust remains unchanged at the poles and decreases gradually towards the equator

(iv) The meridional displacements are towards the equator and are maxima in the latitude 45°

(v) The meridional curve is approximately an ellipse with the semi-axes

$$r_0 \left(1 + \frac{4\rho \omega^2 r_0}{10\mu} \right), \quad r_0 \left(1 - \frac{5\rho \omega^2 r_0^2}{10\mu} \right)$$

(vi) Some geologists consider the flattening at the poles of the earth to have arisen from the rotation after solidification. In

this case we find that the stretch-modulus for the material of the crust supposed thin, homogeneous and uni-constant would have to be about two and half times that of wrought iron; the mean modulus of the predominant kinds of rock of which the terrestrial crust is built-up probably differs very widely from this value.

(vii) The dilatation

$$\theta = \frac{1}{5} \frac{\rho \omega^2 r_0^2}{\mu} \cos^2 \phi.$$

Thus it is zero at the poles and a maximum at the equator.

Resal deals with the principal tractions and the stress-condition of rupture, but for oft cited reasons (see our Arts. 5 (c), 321, etc.) we do not consider this treatment satisfactory.

It is clear that Resal advanced considerably the problem first dealt with by Lamé, and both really laid the foundation of work afterwards done *de novo* by Sir W. Thomson, G. Darwin, Chree and others in applying the theory of elasticity to solve problems connected with the earth's crust.

[571.] E. Lamarle: *Note sur un moyen très-simple d'augmenter, dans une proportion notable, la résistance d'une pièce prismatique chargée uniformément. Bulletin de l'Académie Royale... de Belgique*, Tom. XXII. 1^{re} Partie, pp. 232—52, 503—25. Bruxelles, 1855.

L'objet de cette note est de signaler à l'attention des constructeurs une disposition très-simple qui permet, *en certains cas*, d'augmenter, dans une proportion considérable, la résistance des pièces soumises à la flexion. Cette disposition, que je n'ai vue indiquée nulle part et que je crois nouvelle, consiste essentiellement, soit à remplacer par des encastremens obliques les encastremens horizontaux, soit, plus généralement encore, à établir certaines inégalités de hauteur entre les divers supports d'une même pièce, au lieu de placer tous ces supports à un même niveau, comme on le fait habituellement (p. 232).

[572.] The first part of the memoir deals with the *Cas général de deux supports*, i.e. with simple beams. Lamarle supposes the beam of length l to be uniformly loaded with p lbs. per unit-run and to bend in the plane of loading. It is supported at two points A and B , of which B is not necessarily on the same level as A . Suppose the horizontal through A taken as axis of x and the axis of y taken vertically downwards, then Lamarle shows that:

$$y = \frac{pl^4}{2E\omega\kappa^2} \left[\frac{1}{12} \left(\frac{x}{l} \right)^4 - \frac{a}{6} \left(\frac{x}{l} \right)^3 + \frac{b}{2} \left(\frac{x}{l} \right)^2 \right] + mx \dots\dots (i),$$

where, m and m' being the values of dy/dx at A and B and f the value of y at B ,

$$\left. \begin{aligned} a &= 1 + \frac{12E\omega\kappa}{pl^4} \{2f - (m + m')l\}, \\ b &= \frac{1}{6} - \frac{2E\omega\kappa^2(m - m')}{pl^3} + \frac{6E\omega\kappa}{pl^4} \{2f - (m + m')l\} \end{aligned} \right\} \quad (11)$$

Let h be the distance of the 'extreme fibre' from the neutral axis and s the stretch in it, then $s/h = d^2y/dx^2$ and we find

$$s = \pm \frac{pl^3h}{2E\omega\kappa^2} \left\{ \left(\frac{x}{l} \right)^2 - a \left(\frac{x}{l} \right) + b \right\} \quad (11)$$

Lamaile shows that s will take maximum values when

$$x = 0, = \frac{1}{2}al, \text{ and } = l$$

These give, if $R = \frac{1}{2}pl^3/(E\omega\kappa)$ for the corresponding values of s

$$\left. \begin{aligned} s_0/h &= \frac{R}{6} - \frac{m - m'}{l} + \frac{3}{l} \{2f - (m + m')l\}, \\ s_1/h &= \frac{R}{12} + \frac{m - m'}{l} + \frac{9}{Rl} \{2f - (m + m')l\}^2, \\ s_2/h &= \frac{R}{6} - \frac{m - m'}{l} - \frac{3}{l} \{2f - (m + m')l\} \end{aligned} \right\} \quad (14)$$

If the terminals of the rod had been simply built-in horizontally on the same level, we should have had $m = m' = f = 0$ and therefore the maximum stretch $= \frac{1}{6}Rh$, if the terminals had been simply supported we should have had $s_0 = s_2 = 0$, and therefore

$$2f = (m + m')l \text{ and } \frac{1}{6}R = (m - m')/l,$$

whence the maximum stretch would $= \frac{1}{4}Rh$

[573] Lamaile discusses the values of s_0, s_1, s given by (14) at considerable length and shows that their maximum will be least if

$$2f = (m + m')l$$

We have then so to choose $(m - m')/l$ that the greater of $s_0 (= s)$ and s_1 may be as small as possible. This gives us

$$(m - m')/l = R/24,$$

and

$$s_0 = s_1 = s = Rh/8$$

We are thus able to reduce the stretching effect of the load from $\frac{1}{6}Rh$ (or $\frac{1}{4}Rh$ as the case may be) to $\frac{1}{8}Rh$

Various special cases are considered in which one or both terminals have given slopes, or in which there is a given difference of height. Lamaile shows that as a rule it is possible to reduce the greatest strain due to the load from 50 to 100 per cent by properly building in the ends. (241-9)

He remarks :

Il y a lieu de faire observer que les quantités m , m' et f sont toujours très-petites relativement à l , et que souvent même elles sont de l'ordre des grandeurs dont on néglige de tenir compte dans la pratique. Sous ce rapport, l'influence considérable que peut exercer sur la résistance d'une pièce soumise à la flexion un changement très-minime apporté dans la disposition des supports mérite de fixer toute l'attention des constructeurs. Il est visible, en effet, qu'alors même qu'on voudrait s'en tenir aux conditions généralement adoptées, l'on devrait néanmoins procéder avec une extrême précision, et mettre le plus grand soin à éviter tout défaut de pose dans le sens où l'effet produit serait une diminution rapide de résistance (pp. 248—9).

Lamarle concludes this first part of his *Note* with an extension to the case of a beam passing over three points of support. He shows that if the middle support be lower than the terminal supports by

$$f = \frac{pl^4}{24E\omega\kappa^2} (8\sqrt{2} - 11),$$

the resistance of the beam will be increased by almost 50 per cent. By giving the terminals slopes determined by

$$m = -\frac{pl^3}{48E\omega\kappa^2},$$

... sinking the middle support by

$$f = \frac{pl^4}{96E\omega\kappa^2},$$

we increase the resistance of the beam by 100 per cent.

At the same time I must observe that it would be almost impossible in practice to insure that these slopes and deflections were accurately adjusted, and any slight sinking of the supports, due even to their elasticity, would upset the results entirely.

[574.] The *Deuxième Partie* of Lamarle's memoir is entitled: *Extension générale des résultats précédemment obtenus pour les cas de deux ou trois supports*. We have seen that the strength of the beam for a single span will be a maximum, if

$$2f = (m + m')l, \text{ and } (m - m')/l = R/24,$$

or from equations (ii) $a = 1, \quad b = \frac{1}{8}.$

Hence we find: $\frac{d^2y}{dx^2} = R \left\{ \left(\frac{x}{l} \right)^2 - \frac{x}{l} + \frac{1}{8} \right\} \dots\dots\dots (vi).$

This is true whatever be the value of m , provided we properly select m' and f ; or, the above equations give m' and f as functions of m , and thus enable us to make the resistance of any particular span a maximum. We easily find that the points of inflexion, or those of zero bending moment, are given by

$$x = \frac{2 \pm \sqrt{2}}{2} l \quad (vii)$$

while the deflection

$$= mx - \frac{Rx^2}{48} \left\{ 1 - 4 \left(\frac{l-x}{l} \right)^3 \right\} \quad (\text{viii})$$

Further

$$\left. \begin{aligned} m' &= m - \frac{Rl}{24}, \\ f &= ml - \frac{Rl^2}{48} \end{aligned} \right\} \quad (\text{ix})$$

The equations (ix) must hold for each individual span, whence if m_n denotes the slope of the tangent at the end of the n th span and m_0 the given slope at the first terminal we have

$$\left. \begin{aligned} m_n &= m_0 - n \frac{Rl}{24}, \\ f_n &= m_0 l - (2n-1) \frac{Rl^2}{48} \end{aligned} \right\} \quad (\text{x})$$

and,

Lamarle supposes all the spans equal and equally loaded, but the results may be easily extended to unequal spans. The total depression in the former case of the $(n+1)$ th support below the first is

$$\begin{aligned} F_n &= f_1 + f_2 + \dots + f_n \\ &= nl \left(m_0 - n \frac{Rl}{48} \right) \end{aligned}$$

[575] Lamarle deals with two special cases on his pp 509—13. In Case (1) he supposes everything to be symmetrical about the middle of the beam and the terminals to be built-in at the proper slope. This is given by

$$m_0 = -m_n = n \frac{Rl}{48},$$

if there be n spans each of length l . Further we have

$$F_r = r(n-r) \frac{Rl^2}{48},$$

so that the proper depression of the r th support is determined.

In Case (ii) the terminals are not supposed to be built-in, but simply supported. We may then suppose the last spans in Case (i) to terminate at their points of inflexion. These are given by (vii), or the last spans will have lengths $l = \frac{2+\sqrt{2}}{4} l$, whence, if the total length of the beam be $2L$, we have

$$(n-2)l + 2l' = 2L \quad (\text{xi}),$$

and l' , l and the corresponding differences in height of the points of support are easy to find.

[576.] On pp. 513—7, Lamarle works out the case of a uniformly loaded continuous beam of length $2L$ resting on $\overline{n+1}$ points of support placed at equal distances, and finds for the maximum stretch s :

$$s/h = \frac{pL^2}{n^2 E \omega \kappa^2} \left\{ 1 - \frac{1}{\sqrt{3}} \frac{1 - (\sqrt{3} - 2)^n}{1 + (\sqrt{3} - 2)^n} \right\}.$$

The maximum stretch s' obtained for Case (ii) of the preceding article is (using Equation (xi)):

$$s'/h = \frac{pL^2}{16 E \omega \kappa^2} = \frac{pL^2}{(2n - 2 + \sqrt{2})^2 E \omega \kappa^2},$$

whence
$$s/s' = \left(2 - \frac{2 - \sqrt{2}}{n} \right)^2 \left(1 - \frac{1}{\sqrt{3}} \frac{1 - (\sqrt{3} - 2)^n}{1 + (\sqrt{3} - 2)^n} \right) \dots\dots (xii).$$

Lamarle has the following results:

$n =$	2	3	4	5	6	7	8	∞
$s/s' =$	1.4571	1.3028	1.4724	1.4927	1.5311	1.5517	1.5697	1.6906

Thus the increase of strength is a minimum for $n = 3$ and then increases from 30 to nearly 70 per cent.

Supposing the beam $2L$ to have consisted of n separate simply supported spans we should have had for the maximum stretch s'' :

$$s''/h = \frac{pL^2}{2n^2 E \omega \kappa^2},$$

and therefore¹

$$s''/s' = \frac{1}{2} \left(2 - \frac{2 - \sqrt{2}}{n} \right)^2 = 2 + \frac{1.171573}{n^2} - \frac{1.171573}{n},$$

so that the advantage increases with n from about 46 to 100 per cent. Lamarle gives an interesting comparative table of results on p. 521.

If we wanted to realise the absolute maximum of resistance in the beam it would be necessary to fix the terminals at the slopes given in our Art. 575. This might be done by prolonging the beam over the terminal points of support up to the points of inflexion given by $x = \frac{2 - \sqrt{2}}{4} l$ and then pivoting these new terminals. But it seems to me that this would often be practically difficult.

[577.] The memoir concludes with a brief indication of a similar theory for the case of an isolated load and for continuous beams of unequal span (pp. 524—5). On the whole we may say the memoir is very suggestive as showing what slight changes in the terminal slope and in the relative height of the supports will largely affect the resistance of a simple or continuous beam. It

¹ Lamarle has a misprint here (p. 519).

serves rather as a warning to constructors of the difficulties associated with the realisation of the theoretical stresses in structures of this kind than as a practical means of largely increasing their resistance

[578] L F Ménabréa *Sopra una teoria analitica dalla quale si deducono le leggi generali di varii ordini di fenomeni che dipendono da equazioni differenziali lineari, fra i quali quelli delle vibrazioni e della propagazione del calore ne' corpi solidi* *Annali di Scienze matematiche e fisiche* (Tortolini), T VI Rome, 1855, pp 363—370 This memoir is translated into French, pp 170—180 of *Crelle's Journal für Mathematik*, Bd 54, Berlin, 1857 It contains nothing on the vibrations of elastic solids that is of real importance

[579] O Schlomilch *Die gleichgespannte Kettenbrückenlinie* *Zeitschrift für Mathematik und Physik*, Bd I Leipzig, 1856, pp 51—55 This is an investigation of the proper area of the cross-section of the chains of a suspension bridge in order that the stress may be equal at each point The paper contains references to earlier literature on the subject At the conclusion of the paper the author remarks that an approach to such a suspension-chain exists in *Hungerford Bridge*, London,

doch ist nichts über die ihr zu Grunde liegende Theorie bekannt geworden, wahrscheinlich haben auch die in der Praxis gewandten und kühnen, mit der Theorie aber meistens wenig vertrauten englischen Ingenieure überhaupt nach gar keinen Formeln construirt, sondern sich hier wie bei unzähligen anderen Gelegenheiten auf empirische Versuche und graphische Methoden verlassen

[580] G Mainardi *Note che riguardano alcuni argomenti della Meccanica razionale ed applicata* *Memorie dell' I R Istituto Lombardo di Scienze*, T 6, pp 515—39 Milano, 1856

Pp 519—21 of this memoir are entitled *Equilibrio di un filo elastico*, but the discussion seems to me obscure and does not appear to involve the proper number of elastic constants It certainly adds nothing to the treatment of the problem by Saint-Venant and Kirchhoff see our Arts 1597*—1608*, 198 (f), and Chapter XII

[581] Von Autenheimer *Zur Theorie der Torsion cylindrischer Wellen* *Zeitschrift für Mathematik und Physik*, Bd I Leipzig, 1856, pp 212—216

A circular cylinder built in at one end is subjected to torsion by a couple at the other having for axis the axis of the cylinder. The author endeavours to measure the effect on the resistance of the longitudinal stretch of a fibre owing to the torsion. Let ϕ be the angle of torsion, l the length of the cylinder and a its radius, M the moment of the applied couple. He finds:

$$M = \mu \frac{\pi a^4}{2} \cdot \frac{\phi}{l} + \frac{\pi}{24} E a^6 \left(\frac{\phi}{l} \right)^3.$$

If s be the longitudinal squeeze of the cylinder :

$$s = \frac{a^3}{4} \left(\frac{\phi}{l} \right)^2,$$

and if

$$E = \frac{5\mu}{2}$$

we have

$$M = E \frac{\pi a^4}{5} \frac{\phi}{l} \cdot \left\{ 1 + \frac{5}{6} s \right\}.$$

So long as s lies within the elastic limit it will hardly exceed $1/1000$, hence the effect on the couple of the stretch produced by torsion is negligible in practice. Even if we were to proceed up to $s = 1/50$ before rupture, the effect would only just become measurable experimentally.

The same matter has been dealt with by Wertheim, (Section II. of this Chapter), Saint-Venant (Art. 51), and Clerk-Maxwell (Art. 1549*).

[582.] Carl Holtzmann: *Ueber die Vertheilung des Drucks im Innern eines Körpers. Einladungs-Schrift der k. polytechnischen Schule in Stuttgart zu der Feier des Geburtsfestes seiner Majestät des Königs Wilhelm von Württemberg auf den 27. September, 1856.*

The earlier part of this paper reproduces the analysis of stress due to Cauchy and Lamé, leading up to their stress-ellipsoids and the shear-cone (see our Arts. 610* and 1059*). This occupies pp. 1—9. I do not think there is anything of novelty or importance in the treatment. The latter part of the paper applies the results so obtained to the discussion of stress in three special cases, namely those of:

(a) *A perfect fluid.* The fundamental equation of hydrostatics is deduced and a remark added that the disappearance of the shearing stress is not true for portions of the fluid where capillary action is called into play.

(b) *The stability of earth.* The earth is supposed to be bounded by two horizontal planes and a third vertical one, and the minimum and maximum pressures on the vertical plane are calculated, corresponding to the limits at which the earth will overcome the resistance of the plane, or the pressure on the plane overcome the resistance of the

earth A more general investigation has been undertaken by Lévy and Boussinesq see our Art 242 Rankine published important results in 1856—7 (see our Art 453), but most probably Holtzmann had not seen them, and the special case worked out by him is simply dealt with and is of considerable interest

(c) *A simple beam centrally loaded and subjected at the same time to continuous load on its upper surface* Holtzmann supposes the beam of rectangular section and deals with the stress as uniplanar, in the manner of Jouravski, Bresse, Rankine, Kopytowski, Scheffler and Winkler see our Arts 183 (a), 468, 535, 556, 652 and 665 It is needless to repeat that the method is illegitimate and the results erroneous, except for the case of a section whose breadth is infinitely small as compared with the height (i e in practice the thin webs of girders)

[583] H Resal *Mémoire sur le mouvement vibratoire des bielles Annales des Mines*, Tome ix, pp 233—79, Paris, 1856

This paper contains an important application of the usual theory of the vibrations of bars (due to Bernoulli) to ascertain what influence the vibrations of a connecting rod have upon the forces which it exerts on the crank-pin and piston-head The treatment is only approximate, terms of the third order in the ratio of the length of crank to that of connecting rod being neglected But the results obtained are of very considerable interest, especially the analysis of the origin of the various types of longitudinal and transverse vibrations which occur The danger of isochronism between a free period of vibration of the rod and the time of a complete revolution of the crank is brought out (p 248) see our Art 359 and ftn p 243 Resal considers at some length the effect on the magnitude of the vibrations of the connecting rod produced by putting a counterbalance upon it at or beyond the crank-pin He shows that its influence is to produce a constant dilatation in the connecting rod and also to increase under ordinary conditions the amplitude of the transverse vibrations of the rod by one-third (p 275) His analytic results are, however, too lengthy for citation here, even if their discussion did not carry us beyond the proper limits of our subject They ought certainly to be consulted by those having to deal practically with the stresses in connecting rods

[584] H Resal *Recherches sur les tensions elastiques developpees par le serrage des bandages des roues du materiel des chemins de fer Annales des Mines*, Tome xvi pp 271—86, Paris, 1859

This is an interesting paper although it involves several rather doubtful assumptions. It is well known that the true tire of a wheel is made slightly less in inner circumference than the outer circumference of the false tire (*faux bandage*) upon which it is placed when expanded by heat. On cooling the whole material of the wheel—spokes, false tire and true tire—is in a state of elastic strain, and Resal endeavours to ascertain on the Bernoulli-Eulerian theory of flexure the stresses in these various members. One assumption which his theory requires is that the linear dimensions of the cross-section of the tire must be small as compared with the length of tire between two spokes, and I do not think he has fully regarded this point, when he applies his theory to special cases of very close spokes. He also disregards the sliding effect produced by flexure and neglects the square of the ratio of the linear dimensions of the tire to the radius of the wheel.

[585.] Resal begins with a lemma of the following kind. Suppose a circular arc of radius ρ_0 to receive at the point defined by the radial angle θ the very small displacement towards the centre defined by $\rho_0 e$, then the change in curvature $1/\rho - 1/\rho_0$ at that point is measured by

$$1/\rho - 1/\rho_0 = \left(e + \frac{d^2 e}{d\theta^2} \right) / \rho_0 \dots\dots\dots (i).$$

Let ρ_0 be the initial radius of the external circumference of the false tire, $\rho_0(1 - \epsilon)$ the initial internal radius of the true tire, $\rho_0(1 - e)$ the radius vector corresponding to the polar angle θ (measured from a spoke) of a point on the common circumference after strain, let β be the squeeze of this circumference at the same point, then ω_1 and ω being the cross-sections of the false and true tires, the squeeze in a 'fibre' distant y from this circumference in the false tire is easily found to be

$$\beta + \frac{y}{\rho} - \frac{y}{\rho_0} = \beta + \frac{y}{\rho_0} \left(e + \frac{d^2 e}{d\theta^2} \right) \dots\dots\dots (ii).$$

Hence there is a total negative traction across the section of the false tire given by

$$E\omega_1 \left\{ \beta + \frac{\bar{y}_1}{\rho_0} \left(e + \frac{d^2 e}{d\theta^2} \right) \right\} \dots\dots\dots (iii),$$

and a total moment given by

$$E\omega_1 \left\{ \beta \bar{y}_1 + \frac{\kappa_1^2}{\rho_0} \left(e + \frac{d^2 e}{d\theta^2} \right) \right\} \dots\dots\dots (iv),$$

where \bar{y}_1 is the distance of the centroid of ω_1 from the common circumference and κ_1 , the swing-radius of ω_1 about a line through that circumference

For the true tire we easily deduce the expressions

$$E\omega \left\{ -\beta + \frac{\bar{y}}{\rho_0} \left(e + \frac{d e}{d\theta} \right) + \epsilon \right\} \quad (v),$$

$$E\omega \left\{ -\beta \bar{y} + \frac{\kappa^2}{\rho_0} \left(e + \frac{d e}{d\theta^2} \right) + \epsilon \bar{y} \right\} \quad (vi),$$

for the total positive traction and the moment with a similar notation. We suppose with Resal that the stretch modulus for the material of both tires is the same. Hence subtracting (iii) from (v) and adding (iv) and (vi) we have

For the total traction in the cross section


$$Q = E\Omega \left\{ -\beta + \frac{\bar{Y}}{\rho_0} \left(e + \frac{d^2 e}{d\theta^2} \right) \right\} + E\epsilon\omega \quad (vii)$$

For the total moment

$$M = E\Omega \left\{ -\bar{Y}\beta + \frac{K^2}{\rho_0} \left(e + \frac{d^2 e}{d\theta^2} \right) \right\} + E\epsilon\omega \bar{y} \quad (viii),$$

where $\Omega = \omega_1 + \omega$, \bar{Y} is the distance of the centroid of Ω from the common circumference, and K the swing radius of Ω about an axis through the common circumference perpendicular to the plane of the wheel

[586] Now if we take the cross section cc midway between two spokes which make an angle 2α with each other, the total stress over cc must consist of a couple, Em say, and a thrust at the common cir-



cumference perpendicular to the cross section given by Ep , say. Hence for the cross section aa we find at once from (vii) and (viii), since no forces act on the element $aacc$ except at the cross sections cc and aa

$$-\beta\Omega + \frac{\bar{Y}\Omega}{\rho_0} \left(e + \frac{d e}{d\theta} \right) = p \cos(\alpha - \theta) - \epsilon\omega \quad (ix),$$

$$-\bar{Y}\beta\Omega + \frac{\Omega K}{\rho_0} \left(e + \frac{d^2 e}{d\theta^2} \right) = -p\rho_0(1 - e) \{ \cos(\alpha - \theta) - \cos \alpha \} + m,$$

$$\text{or,} \quad -\bar{Y}\beta\Omega + \frac{\Omega K}{\rho_0} \left(e + \frac{d e}{d\theta} \right) = -p\rho \cos(\alpha - \theta) + m' \quad (x),$$

when we neglect the products of small quantities (e.g. pe) and write m' for the terms on the right which do not involve θ . Eliminating successively β and e we find:

$$\frac{\Omega K_0^2}{\rho_0} \left(e + \frac{d^2 e}{d\theta^2} \right) = -p \cos(\alpha - \theta) \{ \rho_0 + \bar{Y} \} + m' + \epsilon \omega \bar{Y} \dots \dots (xi),$$

$$\Omega K_0^2 \beta = -p \cos(\alpha - \theta) \{ K^2 + \rho_0 \bar{Y} \} + m' \bar{Y} + \epsilon \omega K^2 \dots \dots (xii),$$

where K_0 is the swing-radius of Ω about a line in its plane through its centroid perpendicular to the plane of the tire.

The integral of equation (xi), remembering that $de/d\theta = 0$ for $\theta = \alpha$, is easily found to be

$$\frac{\Omega K_0^2}{\rho_0} e = -\frac{p}{2} (\rho_0 + \bar{Y}) \{ (\alpha - \theta) \sin(\alpha - \theta) + m'' \cos(\alpha - \theta) \} + m' + \epsilon \omega \bar{Y} \dots \dots (xiii),$$

where m'' is an undetermined constant. Equations (xii) and (xiii) contain the complete solution of the problem.

[587.] It remains to determine the constants p , m' and m'' . It is easy to see that the total shear must vanish at the cross-section midway between two spokes, but that at a spoke cross-section it will not vanish but be equal to $p \sin \alpha$. Let σ be the cross-section of the spokes, l their length, then if their stretch-modulus be the same as for the tires, we have for their negative traction the expression

$$E \sigma \rho_0 e_0 / l,$$

where e_0 is the value of e for $\theta = 0$.

Now consider the element of the wheel between two midway cross-sections, we have at once from statical considerations

$$2Ep \sin \alpha = E \sigma \rho_0 e_0 / l,$$

$$\text{or,} \quad p = \frac{1}{2} \frac{\sigma \rho_0 e_0}{l \sin \alpha} \dots \dots \dots (xiv).$$

The shearing force at AB (see figure on our p. 403)

$$= Ep \sin \alpha = \frac{E}{2} \frac{\sigma \rho_0 e_0}{l};$$

but this may be put $= \mu$ times the slide into the cross-section, or

$$\mu \Omega de/d\theta = E \sigma \rho_0 e_0 / (2l) \dots \dots \dots (xv).$$

Resal here *assumes* that the total shear is equal to the continued product of the slide-modulus into the total area of the cross-section into the complement of the angle the strained circumference common to the two tires makes with the radius at the spoke. Saint-Venant, however, finds values from about $\frac{2}{3}$ of this product for a rectangle to $\frac{5}{7}$ for a circle: see our Arts. 90 and 96.

Differentiating (xiii) and applying (xv) we obtain m'' in terms of e_0 , thus since (xiv) gives p in terms of e_0 we have only to find e and m' .

But putting $e=e_0$ and $\theta=0$ in (xiii) we at once obtain m' in terms of e_0 . Thus it remains to find e_0 .

We have not yet made use of the condition that the angle cOA (see figure p 403) retains a constant value or is equal to α . Now if ds be an element of the common circumference of the tires before and ds' after strain, we have obviously

$$\int_0^{a\rho_0} ds = \rho_0 \alpha \quad (\text{xvi})$$

But $(ds - ds')/ds = \beta$ and $ds' = \rho_0(1 - e) d\theta$,
hence $ds = \rho_0(1 + \beta - e) d\theta$,

and substituting in (xvi) we have

$$\int_0^{\alpha} (\beta - e) d\theta = 0 \quad (\text{xvii})$$

Hence from (xii), (xiv) and (xvii) we can find e_0 .

[588] The calculations indicated in the previous article are carried out by Resal, who gives pp 281-2 rather lengthy values for m' and e_0 . He then returns to (ii) and to a similar expression for the squeeze in the true tire in order to find the maximum value of the traction or squeeze in the tire. Equating such value to the safe elastic limit, we find a maximum value for ϵ , or for $\rho_0\epsilon$ the difference in the radii of the two tires (pp 282-3). As special problems Resal treats the case when the spokes are so close that $\sin \alpha$ may be replaced by α and further investigates a minimum safe value for ϵ in the case of a wheel turned by a crank having regard to the necessity of the moment of the friction between the two tires being greater than the moment of the force in the crank about the axis of the wheel. He does not, however, lay stress on this result (p 286).

We have sufficiently indicated Resal's method of dealing with such problems to suggest to the student of this subject how he may complete or extend it.

[589] H Resal *De l'influence de la suspension à lames sur le mouvement du pendule conique* *Annales des Mines*, T XVIII, pp 1-16, Paris, 1860.

This is the application of the simple Bernoulli Eulerian theory of flexure to the problem of the suspension by elastic laminae of a *balancier conique* due to Redier. The paper contains nothing further bearing on the theory of elasticity.

[590] Mahistre *Note sur les vitesses de rotation qu'on peut faire prendre à certaines roues, sans craindre leur rupture sous l'effort de la force centrifuge* *Comptes rendus*, Tome XLIV, pp 236-9, Paris, 1857.

This is only an extract from a longer memoir and the line of

argument is scarcely intelligible from its brevity. As the problem has been satisfactorily dealt with (so far as that is possible on the Bernoulli-Eulerian theory) by Resal, we shall make no attempt to unravel Mahistre's obscure statements. We merely note that if S be the resistance to rupture of the metal in kilogs. per sq. metre, N the number of turns of the wheel per minute, R the mean radius of its rim, D its specific gravity, then Mahistre finds that to avoid rupture we must have a relation of the form :

$$N < \frac{30}{\pi R} \sqrt{\frac{gS}{D}}.$$

See our Art. 646.

[591.] The four memoirs by Poinsot on the impact of bodies published in *Tomes 2 and 4* of the *Journal de Liouville*, 1857 and 1859, have nothing to do with elasticity, although their titles are cited by the writer of the article *Elasticitätstheorie des geraden Stosses* in the *Encyklopädie der Naturwissenschaften: Handbuch der Physik*, (see S. 296, Bd. I., of that work).

[592.] J. H. Koosen: *Entwicklung der Fundamentalgesetze über die Elasticität und das Gleichgewicht im Innern chemisch homogener Körper*. *Annalen der Physik*, Bd. CI., S. 401–52. 3, 1857.

is entitled: *Erste Abhandlung*, but I can find no trace of a *Zweite Abhandlung* having been published; perhaps its non-publication is hardly a loss. The author obtains the equations of elasticity for an isotropic medium practically in the same manner as Cauchy or Poisson, and he finds (S. 419) for the type of tractive stress :

$$\widehat{xx} = A \left(1 + \frac{du}{dx} \right) + (B - A) \left(3 \frac{du}{dx} + \frac{dv}{dy} + \frac{dw}{dz} \right).$$

He apparently thinks there is something novel in this result, but the equation had been long previously obtained by Cauchy, who showed that A measures the initial stress: see our Art. 616* and our account of Saint-Venant, Art. 129. Koosen does introduce novelty, however, by retaining in general the coefficient A and supposing this *Molecularspannung* is somehow equilibrated by temperature exchanges between the elastic body and surrounding bodies (S. 425–6). I do not understand his reasoning on this point, nor in the following pages, and believe it to be incorrect. The equations involving an exponential of the time on S. 425 and

the consequences drawn from them on the following pages are a mystery to me, and I should be inclined to describe the whole of this lengthy paper as no contribution to our subject, were I not obliged to confess that I have frequently been unable to follow its drift

[593] R Hoppe *Ueber Biegung prismatischer Stäbe Annalen der Physik*, Bd 102, S 227–245, Leipzig, 1857 Reprinted in the *Zeitschrift des Vereins deutscher Ingenieure*, Bd 1, S 308–13, Berlin, 1857

This paper opens with the words

Auf den bekannten Erfahrungssatz, nach welchem die zur Dehnung oder Zusammendruckung eines elastischen festen Körpers nach *einer* Dimension hin erforderliche Kraft den Volumincrementen proportional ist, lässt sich die Berechnung der Biegung eines prismatischen Stabes nur unter der Annahme gründen, dass sein Querschnitt weder in seinen Dimensionen, noch in seiner normalen Stellung zu allen Längensfasern eine Aenderung erleide Die Bestimmung jeder ungleichmassigen Dehnung oder Compression nach *mehr* als einer Dimension, welche durch jene Annahme umgangen wird, erfordert die Zuziehung neuer empirischer Grundlagen oder Hypothesen, denn das unveränderte Volum selbst der kleinsten Theile begründet noch nicht das Gleichgewicht der darin befindlichen Spannungen (S 227)

After reading this paragraph and remembering the researches of Saint-Venant and Kirchhoff (see our Chapters X and XII), it hardly seemed needful to study closely the present memoir. On examination, however, Hoppe's *Annahme* does not seem to have made his results any more incorrect than most investigations based on the Bernoulli-Eulerian hypothesis His treatment, however, is somewhat obscure and does not appear to contribute anything of novelty or importance to the subject of flexure It is based on the principle of virtual velocities and indicates the solution in elliptic integrals, but both these had been proposed and adopted previously see the references under *Rods* in the index to our Vol I

[594] J Stefan *Allgemeine Gleichungen für oscillatorische Bewegungen Annalen der Physik*, Bd CII, S 365–87, Leipzig, 1857

This paper deduces in the first place the general equations for the vibrations of an elastic medium when there are three rectangular planes of symmetry by Cauchy's method (S 365–7) see our Art 616*

The author then goes on to investigate the like equations by Green's method, and afterwards considers the special cases of uniaxial symmetry and of isotropy. He deduces the equations which must be satisfied for the reflection and refraction of light at the common boundary of two such media. It seems to me, however, that in the media with biaxial and uniaxial symmetry he is tacitly supposing the crystalline axes to be parallel in the two media: see his equations S. 379-80 and 384. Thus he is really dealing with a very limited case of reflection and refraction at the common boundary. Stefan makes no attempt to solve his equations, and I do not think his paper can be considered as a valuable contribution to either optical or elastic theories.

[595.] E. Phillips: *Des parachocs et des heurtours de chemin de fer. Comptes rendus*, Tome XLV., pp. 624-7, Paris, 1857.

The author commences by citing a formula from his memoir on springs (see our Art. 493 (c)) for the resilience of a spring of any form built-up of elastic laminae. The total elastic work to be obtained from a spring is $EVs^2/6$, where E is the stretch-modulus, V the volume, and s the safe or limiting stretch at the surface of component laminae.

Let w be the weight of a train in French tons, v its velocity in kilometres per hour, g gravitational acceleration, we must have:

$$\frac{1}{2} \frac{w}{g} v^2 = EVs^2/6,$$

if the spring be able to bring the train to rest without the spring being elastically damaged. Phillips takes 7.82 as the mean density of steel, 20,000,000 kilogs. per sq. mm. for E , and .01 as the limit of s for very good steel. Thus he finds if W be the weight of the spring in kilogrammes:

$$W = .0952 \times w \times v^2 \dots\dots\dots(i).$$

In this he neglects the friction of the laminae upon one another. He remarks, that if U' be the work due to this friction, it may be shown by the processes of his memoir of 1852 that:

$$U'/U < 2\phi (n-1) \frac{e}{L}.$$

where $U = EVs^2/6$, ϕ = coefficient of friction for steel on steel, n = number of laminae, e their thickness and L the half length of the spring, so that U' will generally be small as compared with U .

Phillips next takes various values for w and v , for w from 90 to 600 tons and for v from 60 to 20 kilometres per hour, the values for W vary from 21 to 31 tons. Hence he concludes that it would be impossible to protect a train against collisions by causing it to carry at its ends buffers or springs of this enormous weight. On the other hand suitable buffers can be easily constructed to protect the masonry etc. at a terminus from the impact of a train with a small speed. In this case he takes v' to measure the velocity of the train in metres per second, he supposes that, as such springs are repeatedly loaded, s should not be taken greater than 0.04 and he finds in French measure

$$W = 77112 \times w \times v^2$$

For example if $v' = 1$ metre and $w = 30$ tons, W is the fairly reasonable weight of 230 kilogrammes, or about the weight of three ordinary carriage buffer-springs (70 to 80 kilogrammes). The memoir was referred to a commission then sitting to investigate the causes of accidents arising from the impact of railway wagons.

[596] Deloy *Extrait d'une Note relative à l'application de la théorie de M Phillips à la construction d'un ressort de locomotive d'une nouvelle espèce* *Comptes rendus*, Tome XLV, pp 752-5, Paris, 1857

This note gives details of a special kind of spring made by Gouin et Cie for the Lyons railway. Deloy calculated by Phillips' formulae (see our Arts 489-90) the deflection of this spring under a load of 10,000 kilogs and found it 0.478 metres, experiment gave it as 0.48 metres. The experiment was repeated several times with the same result.

Tous les ressorts nouveaux du chemin de fer de Lyon sont construits d'après la théorie de M Phillips. J'ai commence des essais pour déterminer la flexibilité de ces ressorts (p 754)

The results of these experiments show such a noted agreement between experiment and oft abused theory that they deserve citing here. The deflections in metres were as follows

						Experi- ment	Theory
Series of locomotive springs,	12 laminae,	3 matrix laminae				0.377	0.357
"	"	"	11	"	4	0.67	0.646
"	tender	"	9	"	4	0.37	0.3547
"	wagon	"	7	"	—	1.55	1.494

It cannot be denied that this is strong evidence in favour of the practical accuracy of Phillips' theory, more especially so when we consider the irregularities of material and manufacture in such technical products as railway springs.

[597.] E. Phillips: *Du travail des forces élastiques dans l'intérieur d'un corps solide, et particulièrement des ressorts: Comptes rendus*, T. XLVI, pp. 333-6 and *Supplément*, p. 440. Paris, 1858.

In this memoir Phillips remarks that it is generally impossible to apply Clapeyron's Theorem as suggested by its discoverer to springs (see our Arts. 608-9), because the value of the principal tractions cannot be found. He notes that he himself in an earlier memoir has applied the Bernoulli-Eulerian theory to springs and he cites his chief results: see our Arts. 483-508. The last page and the *Supplément* deal with the experimental stress which a steel bar may be subjected to without permanent extension; according to Phillips this stress is 40 to 50 kilogs. per sq. mm. It is difficult to understand whether Phillips means this as the safe load for bars liable to impact, or the real limit to a statically applied elastic stress.

[598.] We must now turn to a series of memoirs published in this decade and dealing with the problem of the reactions of bodies resting on several points of support. We note first:

Francesco Bertelli: *Ricerche sperimentali circa la pressione dei corpi solidi ne' casi in cui la misura di essa, secondo le analoghe teorie meccaniche si manifesta indeterminata e intorno alla relazione fra le pressioni e la elasticità de' corpi medesimi. Memoria Postuma. Mem. dell' Accad. delle Scienze di Bologna*. T. I., pp. 433-461, Bologna, 1850.

The memoir is divided into two parts, of which the first was read to the *Accademia* on February 16, 1843 and the second on March 28, 1844. It relates to the problem of the statically indeterminate reactions which arise when a body rests on more than two colinear or more than three non-colinear points of support. The problem occupied as large a share of attention in Italy in the first half of the present century, as that of solids of equal resistance in the second half of the seventeenth century, and the memoirs relating to it have almost as little permanent scientific value. Bertelli gives a very interesting account of the history

of the problem (pp 436-40 and 447-61)¹, and is apparently of the opinion that its solution cannot be reached without the aid of the theory of elasticity,—a view which had not met with general acceptance at the time when his memoir was read. He also describes a particular kind of dynamometer for measuring the indeterminate reactions (pp 441-3). This he terms *il presimetro*. Some experimental results obtained by means of such dynamometers are cited but no numerical details are given and they are too vague to be of service in testing for example the theory of continuous beams (pp 443-6).

[599] A Dorna *Memoria sulle pressioni sopportate dai punti d'appoggio di un sistema equilibrato ed in istato prossimo al moto* *Memorie dell' Accad. delle Scienze di Torino*, Serie II, T XVIII, pp 281-318, Turin, 1857

This is the first Italian memoir which attempts to deal with

¹ For the history of science the problem is of value as showing how power is frequently wasted in the byways of paradox. I give a list, which I have formed, of the principal authorities for those who may wish to pursue the subject further.

Euler *De pressione ponderis in planum cui incumbit* *Novi Commentarii Academiae Petropolitanae*, T XVIII, 1774, pp 289-329

" *Von dem Drucke eines mit einem Gewichte beschwerten Tisches auf eine Fläche* (see our Art 95*), *Hindenburgs Archiv der reinen und angewandten Mathematik* Bd I, S 74 Leipzig 1795

D'Alembert *Opuscula*, T VIII *Mem* 56 § II, 1780, p 36

Fontana, M *Dinamica*, Parte II

Delanges *Mem della Societa Italiana*, T V, 1790, p 107

Paoli *Ibid* T VI, 1792, p 534

Lorgna *Ibid* T VII, 1794, p 178

Delanges *Ibid* T VIII *Parte I* 1799 p 60

Malfatti *Ibid* T VIII *Parte II*, 1798, p 319

Paoli *Ibid* T IX 1802, p 92

Navier *Bulletin de la Soc philomat*, 1825, p 35 (see our Art 282*)

Anonym *Annales de mathem par Gergonne*, T XVII, 1826-7, p 70

Anonym *Bulletin des Sciences mathematiques* T VII, 1827, p 4

Vene *Ibid* T IX 1828 p 7

Poisson *Mecanique* Tome I, 1833 § 270

Fusinieri *Annali delle Scienze del Regno Lombardo Veneto*, T II, 1832, pp 298-304 (see our Art 396*)

Barilari *Intorno un Problema del Dottor A Fusinieri* Pesano 1833

Paganì *Memories de l'Acad de Bruxelles*, T VIII, 1834 pp 1-14 (see our Art 396*)

Saint Venant 1837-8 see our Art 1572*

1843 see our Art 1585*

Bertelli *Mem dell Accad delle Scienze di Bologna*, T I 1843-4 p 433

Fagnoli *Ibid* T VI, 1842 p 109

Of these writers only Navier, Poisson and Saint Venant apply the theory of elasticity to the problem. Later researches of Dorna, Menabrea and Clapeyron will be referred to in their proper places in this History as they start from elastic principles.

the problem of the body resting on more than three points of support from a rational standpoint,—that is to say, which makes direct appeal to the theory of elasticity. We have already referred to the earlier literature of this subject (see our Art. 598 and ftn.) and a memoir on very similar lines to this by Ménabréa will be considered later (see our Art. 604). Dorna's paper begins so well that we can only regret it does not end better. We say 'it begins well,' for it has not the flavour of mediaeval metaphysics traceable even so late as Fagnoli (see our Art. 509).

[600.] Dorna notes that if we give a virtual displacement to a system consisting of a rigid body resting on any number of points of support, then the sum of the virtual moments of these points of support must be zero independently of the virtual moments of the applied forces of the system. Hence if Q be a reaction and δq its virtual displacement, we must have :

$$\sum Q\delta q = 0 \dots\dots\dots(i).$$

To obtain δq Dorna now makes the following supposition; suppose that each point of support is connected with the rigid body by an elastic string of infinitely small length l and cross-section ω ,—these being the same for all such strings,—and of stretch-modulus E *supposed to vary from string to string and to be that of the material of the supporting body in the neighbourhood of the supporting point* (p. 286), then we shall have

$$\delta q = \frac{l}{E\omega} \delta Q,$$

and consequently (i) will become :

$$\sum \frac{Q\delta Q}{E} = 0 \dots\dots\dots(ii).$$

Other relations between the δQ 's will be given by the statical equations of equilibrium, whence either by eliminating the dependent δQ 's or by the principle of indeterminate multipliers we have sufficient equations to find all the unknown reactions (pp. 291, 300 etc.).

[601.] Dorna's method is perfectly logical if we adopt his hypothesis namely (i) that the supports only are elastic, and the supported body rigid. (ii) that we may really introduce this string-

link with stretch-modulus equal to that of the supporting material to explain what physically does happen at the point of support. Now the first hypothesis is just the reverse of what is usually assumed by practical engineers in calculating the reactions of continuous girders,—they suppose the supports rigid and the supported girder elastic¹. Further the second hypothesis seems to me legitimate only in the case in which the support is a column of uniform cross-section with a reaction in the direction of its length, and even in this case the cross-sections of the column ought to be retained in Equation (11) unless they happen to be all equal. To apply this hypothesis as Dorna does even to cases in which the reaction is perpendicular to the axis of support is to neglect entirely the distinction between the elastic coefficients of stretch and slide. Thus he deduces the extraordinary result

la pressione, riferita all' unità di superficie, che una base piana di sostegno sopporta sotto l' azione di una forza diretta attraverso al suo centro di gravità, è la stessa, sia che questa operi a perpendicolo della base sia che operi nella stessa base (p. 306)

[602] Of the special applications which Dorna makes of his theory we may briefly note the following

Problema II. A heavy rigid body rests on n colinear points of support, (pp. 290–2). This appears correct if the n points be supposed vertical columns of equal height and cross section.

Problema III, (pp. 293–6) and *Problema IV*, (pp. 296–9). These are the general case of distribution of normal pressure over the cross section of an elastic cylinder, and the special case when the cross section is rectangular. The investigations are correct, but present no novelty except in the fact of their deduction from equation (11) of our Art. 600. The results agree with those which flow from the theory of neutral axis and load point and had long before been established by Bresse; see our Arts. 812* and 515–6, and compare Clifford's *Elements of Dynamics*, Book IV, pp. 14–28.

Problema V, (pp. 299–304). This supposes the general case in which any number of isolated points, or of continuous points composing a surface, are connected by elastic string links with points on the surface of a rigid body supposed to be in contact with them. The analysis is not without interest, but I cannot consider that this problem corresponds to any physical reality, certainly not to a rigid

¹ This point has been dealt with by the Editor in a *Note on Clapeyron's Theorem* *Messenger of Mathematics* Vol. xx, pp. 129–35, Cambridge 1890.

surface resting on any number of points or on an elastic surface as Dorna supposes.

Problema VI., (pp. 304-6), *Problema VII.*, (pp. 306-7) and *Problema VIII.*, (pp. 307-8) are absolutely inadmissible applications of *Problema V.*

Problema IX., (pp. 308-14). This is an attempt to generalise the theory of the neutral-axis and the load-point to pressure applied to a curved surface. The results obtained are all based on the hypothesis of *Problema V.*, and are therefore physically inadmissible. Analytically they are not without interest as leading to theorems which are analogous to those which hold for the instantaneous axis of rotation of a rigid body and which were first discovered by Poinsot.

Problema X., (pp. 315-6) supposes a rigid body to rest on a portion of a spherical elastic surface. The results are inadmissible.

The memoir concludes with a *Nota* (pp. 316-8) containing a second demonstration of Equation (ii) of our Art. 600.

[603.] E. Clapeyron: *Calcul d'une poutre élastique reposant librement sur des appuis inégalement espacés: Comptes rendus*, Tome XLV., pp. 1076-1080, Paris, 1857.

This is only a *résumé* of a memoir, which I think was never published. It deals with the problem of a continuous beam and gives the equation of the three moments usually termed "Clapeyron's Theorem." Clapeyron states it only for the case of uniform cross-section. Let M_1 , M_2 , M_3 be the moments at successive supports and l_{12} , l_{23} the intermediate spans, p_{12} , p_{23} their loads per foot-run,—then:

$$l_{12}M_1 + 2(l_{12} + l_{23})M_2 + l_{23}M_3 = \frac{1}{4}(p_{12}l_{12}^3 + p_{23}l_{23}^3).$$

It will be seen that Clapeyron only deals with a very special case of his theorem, which has been much extended by later writers: see Heppel in our Art. 607 or Weyrauch: *Theorie der continuirlichen Träger*, S. 8-9.

Clapeyron mentions Navier as having said a few words on the problem in the *Bulletin de la Société Philomathique*, 1825; I suppose he refers to pp. 35-7. He cites Belanger as having studied in his course of lectures on construction at the *École des Ponts et Chaussées* the case of two spans, and other writers as having propounded the general equation, but left it complicated by the presence of the reactions. His own practical work on French railway bridges led him to investigate a formula free from the reactions.

He then applies his formula to the case of a bridge of seven equal spans. A remark on p 1078 as to a defect in the design of the Britannia Bridge does not as a matter of fact apply as that bridge owing to its mode of construction is not a continuous beam in the theoretical sense see our Art 1489*

[604] L F Ménabréa *Nouveau principe sur la distribution des tensions dans les systemes elastiques Comptes rendus*, T XLVI, Paris, 1858, pp 1056–1060

Ménabréa here states a very important elastic principle, the application of which by Maxwell, Cotterill and others to framework and continuous beams has been of considerable service. I do not think the statement of the principle by Ménabréa sufficiently indicates that his proof only applies to what we now term a 'frame' or bit of 'framework', and that the links of such a frame must be supposed subjected to traction only and to be of uniform cross-section, which may vary, however, from link to link. A generalisation of the principle based upon Clapeyron's Theorem (see our Art 608) is easily obtained and will be considered later.

Ménabréa states what he terms the *principe d'élasticité* in the following words

Lorsqu'un systeme élastique se met en équilibre sous l'action de forces extérieures, le travail développe par l'effet des tensions ou des compressions des liens qui unissent les divers points du systeme est un minimum (p 1056)

The proof given is essentially as follows. Let T be the traction in any element of the frame of length l and section ω . Then applying the principle of virtual work so that none of the points to which external force is applied have virtual displacements we must have

$$\Sigma T \omega \delta x = 0,$$

where δx = variation in the extension x of any link. But

$$T = Ex/l,$$

if E be the stretch modulus of the link. Hence

$$\delta T = \frac{E}{l} \delta x,$$

and

$$\Sigma \frac{l\omega}{E} T \delta T = 0 \quad (1),$$

or,
$$\delta \left(\sum \frac{l \omega T^2}{2E} \right) = 0 \dots \dots \dots (ii).$$

But $l \omega T^2 / 2E$ is the work done by the traction T in the link l . Thus the principle is proved that the variation of the strain energy for the whole frame is zero. Ménabréa does not prove that this energy is a *minimum*. He terms (i) the *équation d'élasticité*.

[605.] Let there be n points united by m links, then there will be $3n$ equations of equilibrium for the n points; suppose in addition p equations of equilibrium between the external forces, then we shall have $3n - p$ equations between the m tractions, hence $m - 3n + p$ tractions will be independent so far as the ordinary equations of statics go and require to be ascertained by (i). The method is indicated by Ménabréa in the following words:

Puisque pendant les variations infiniment petites des tensions qu'on a supposées, l'équilibre subsiste toujours, on pourra différentier, par rapport aux diverses valeurs de T , les $3n - p$ équations précédentes qui fournissent le moyen d'éliminer, de l'équation d'élasticité (i), un égal nombre de variations δT . On égalera à zéro les coefficients des diverses variations δT restantes dans l'équation (i). Ces coefficients seront des fonctions des forces extérieures et des tensions elles-mêmes; ainsi ces nouvelles équations unies à celles d'équilibre seront en nombre égal à celui des tensions à déterminer.

En général ces équations sont du premier degré. Dans bien des cas, l'emploi des coefficients indéterminés peut faciliter la solution du problème (p. 1058).

[606.] Ménabréa indicates how the following case should be dealt with, but I do not feel quite confident as to the exact form of elastic system he is dealing with, or as to the correctness of an assumption he makes. Suppose the system to be resting on a number of fixed points and P, Q, R to be the components of the reaction at such a point a, b, c parallel to the axes. Let X, Y, Z be types of components of applied force at x, y, z . The equations of statics give:

$$\left. \begin{aligned} \sum X + \sum P &= 0; \quad \sum Y + \sum Q = 0; \quad \sum Z + \sum R = 0; \\ \sum (Xy - Yx) + \sum (Pb - Qa) &= 0; \quad \sum (Zx - Xz) + \sum (Ra - Pc) = 0; \\ \sum (Yz - Zy) + \sum (Qc - Rb) &= 0 \end{aligned} \right\} \dots (iii).$$

Now P, Q, R are evidently components of the total traction ωT in the link to the point a, b, c , and therefore we should expect to have

$$\frac{l \omega T \delta T}{E} = \frac{l (P \delta P + Q \delta Q + R \delta R)}{E}.$$

But Ménabréa writes

Pour plus de généralité on peut supposer les *coefficients d'élasticité relatifs* des points fixes différents suivant les trois directions des axes, nous les représenterons par ϵ , ϵ' , ϵ'' , ainsi l'équation d'élasticité sera

$$\sum \left(\frac{1}{\epsilon} P \delta P + \frac{1}{\epsilon'} Q \delta Q + \frac{1}{\epsilon''} R \delta R \right) = 0 \quad (iv) \quad (p. 1059)$$

I do not follow this at all. It would seem as if Ménabréa thought his theorem true for other strains than those produced by longitudinal traction in bars of uniform cross section. This it certainly is *not*, in the form in which he has proved it. He appears further to put $\delta T = 0$ for all links not going to fixed points, or, what is the same thing, to suppose the virtual displacements to be zero for such links. Taking the variation of (iii) we have

$$\left. \begin{aligned} \sum \delta P &= 0, \quad \sum \delta Q = 0, \quad \sum \delta R = 0, \\ \sum (b \delta P - a \delta Q) &= 0, \quad \sum (a \delta R - c \delta P) = 0, \quad \sum (c \delta Q - b \delta R) = 0 \end{aligned} \right\} \quad (v)$$

Multiplying (v) by the indeterminate multipliers A, B, C, D, E, F respectively we have on adding to (iv)

$$\left. \begin{aligned} P &= -\epsilon' [A + Db - Ec] \\ Q &= -\epsilon'' [B + Fc - Da] \\ R &= -\epsilon''' [C + Ea - Fb] \end{aligned} \right\} \quad (vi)$$

Substitute these values of P, Q, R in (iii), and we have six equations from which to find the multipliers and so can determine P, Q, R .

Ménabréa remarks that if we take $\epsilon' = \epsilon'' = \epsilon'''$, and choose our origin and direction of axes so that

$$\sum \epsilon a = 0, \quad \sum \epsilon b = 0, \quad \sum \epsilon c = 0, \quad \sum \epsilon bc = 0, \quad \sum \epsilon ac = 0, \quad \sum \epsilon ab = 0,$$

we obtain the elegant forms for P, Q, R first given by Doina in a memoir of 1857, see our Art. 599.

Here ϵ for any link equals the $E/(lw)$ of our notation.

For earlier researches in this same direction Menabrea refers to Vene, Pagani and Mossotti besides Doina. The memoirs of Vene and Pagani are those probably which we have cited in the footnote to our p. 411, while the reference to Mossotti is possibly to his *Meccanica razionale*. Menabrea concludes by referring to a memoir he is about to publish, dealing more fully with the whole subject. I do not think he published this, or returned to the matter till a memoir of 1869.

[607] J. M. Heppel. *On a method of finding the Strains and Deflections of Continuous Beams, under various Conditions of Load.* *Proceedings of the Institution of Civil Engineers* Vol. XIX, pp. 625-643, London, 1859-60.

This paper deduces, apparently as a novelty, Clapcyron's theorem connecting the bending-moments at three successive

points of support of a continuous beam, when the load system consists for each span of a uniformly distributed load and an isolated central load. The consideration of the latter load is the author's addition to Clapeyron's work. Let l_1, l_2 be the spans and M_1, M_2, M_3 , the successive support bending moments, $p_1 l_1, p_2 l_2$ the total uniform loads and W_1, W_2 the isolated central loads, then:

$$8l_1 M_1 + 16(l_1 + l_2) M_2 + 8l_2 M_3 = 2p_1 l_1^3 + 2p_2 l_2^3 + 3W_1 l_1^2 + 3W_2 l_2^2 \dots (i).$$

Further the reaction R_{12} at the support between the spans l_1, l_2 is given by:

$$R_{12} = \left. \begin{aligned} & \frac{p_1 l_1 + W_1}{2} + \frac{M_2 - M_1}{l_1} \\ & + \frac{p_2 l_2 + W_2}{2} + \frac{M_2 - M_3}{l_2} \end{aligned} \right\} \dots \dots \dots (ii).$$

The author also calculates the points of maximum-stress and of contraflexure (i.e. zero bending moment), and shows how the deflections may be obtained. I do not think there is any novelty in the methods used, but there are some interesting numerical applications to the Britannia Bridge, to a bridge on the Madras Railway and to a 'continuous rail of infinite length'.

[608.] E. Clapeyron: *Mémoire sur le travail des forces élastiques dans un corps solide élastique déformé par l'action de forces extérieures: Comptes rendus*, Tome XLVI, Paris, 1858, pp. 208-212.

This I presume to be only a *résumé* of the original memoir which so far as I can ascertain was never published.

Clapeyron had been led by a study of various kinds of springs to the conclusion that the resilience of an elastic body varies as its volume. He does not appear, however, to have known that Young and Tredgold had long previously reached this result. It led him to consider how the work of an elastic body could be expressed. In a memoir of 1833 Lamé and he had noted that on the uni-constant hypothesis if W be the work and E the stretch-modulus:

$$2W = \frac{1}{E} \iiint [A^2 + B^2 + C^2 - \frac{1}{2}(AB + BC + CA)] dx dy dz,$$

where A, B, C are the principal tractions and the integration is

¹ A long series of memoirs on continuous beams will be found discussed in Section III. of this Chapter.

over the volume of the elastic solid I hold that this result of the memoir of 1833 was due entirely to Clapeyron, for Lamé in his *Leçons*, of 1852, giving the formula in the form

$$2W = \frac{1}{E} \iiint [A^2 + B^2 + C^2 - 2\eta(AB + BC + CA)] dx dy dz,$$

due to bi-constant isotropy (η being the stretch-squeeze ratio), terms it *Clapeyron's Theorem*, and Clapeyron here speaks of it as he would do only if it were entirely due to himself

[609] Clapeyron proceeds after stating this formula in its modified form to suppose only one principal traction T , when we have

$$2W = \frac{1}{E} \iiint T^2 dx dy dz$$

He then applies this to the calculation of W for various simple cases of rods under traction or flexure etc and also for railway springs.

He remarks that if a framework be constructed in such a manner that the cross sections of the various members are proportional to their total stresses, and these stresses are merely longitudinal tractions, then

$$2W = \frac{1}{E} VT^2,$$

where V is the volume of the whole framework. Hence if T be the safe tractional stress, and the load P be applied at one point with a resulting deflection f

$$Pf = \frac{1}{E} VT^2$$

Thus the same volume V of material distributed in different ways will give a maximum P for a minimum f , the resilience, however, will be quite independent of the particular distribution

Un prisme pose de champ sur deux appuis porte plus que posé à plat dans le rapport de la hauteur à la largeur de la section, sa résistance à un choc est la même (pp 210–11)

[610] The remainder of the memoir treats of the question of uni-constancy. Dealing with one experiment of Coulomb's and eleven of Duleu's on torsion (see our Arts 119*, 229* and Vol I, p 873) Clapeyron finds that for iron $E = 5\mu^2$, or $\lambda = \mu$, very closely indeed. But from some experiments made in the work

shops of the *Chemin de fer du Nord* on the compressibility of caoutchouc and on its stretch-modulus, Clapeyron concludes that for this substance

$$\lambda/\mu = 2201.$$

Thus while uni-constancy is very nearly true for the metals usual in construction, it appears to be quite impossible for caoutchouc. This is the well known argument from "squeezing india-rubber",—but it is one the validity of which is very doubtful: see our Arts. 924*, 1322*, 192 (b) and fn. Vol. I., p. 504. We cannot accept it as a conclusive demonstration of bi-constant isotropy, until india-rubber has been demonstrated to satisfy all the other relations of a bi-constant isotropic *elastic* body¹; this has not been done either by Clapeyron or by the several distinguished scientists who have used this argument. Other experiments on caoutchouc differ widely from Clapeyron's. See our Art. 1322*.

[611.] Clapeyron in the course of his discussion notes that the shear in a case of torsional stress gives rise to two principal tractions making angles of 45° with the direction of the shear, hence he states that the torsional resilience = $\frac{1}{2}T^2V/E$. This is only true for the case of uni-constant isotropy. We see from our Arts. 609 and 609 that in this case the resilienties of torsional, and tensile springs of the same volume and material are 15.

[612.] J. H. Rohrs: *On the Oscillations of a Suspension Chain. Transactions of the Cambridge Philosophical Society*, Vol. IX., pp. 379–98, Cambridge, 1856. This paper was read on December 8, 1851. It does not presuppose elasticity in the chain and so does not properly belong to our subject, but the general conclusions on p. 395 as to the vibrations of suspension bridges are of considerable interest.

[613.] P. van der Burg: *Ueber die Art Klangfiguren hervorzubringen und Bemerkungen über die longitudinalen Schwingungen. Annalen der Physik*, Bd. CIII. S. 620–4, Leipzig, 1858. This paper

¹ For example the slide modulus of india-rubber as determined by torsion and by pure slide experiments must be shown to have the same value as if it had been obtained by experiments on compressibility and traction. Roughly, from Clapeyron's experiments I find $\mu = 5$ kilogrammes per square centimetre.

contains miscellaneous information with regard to vibrating bars and plates. In particular the author recommends the following plan as leading to very correct Chladni-figures

Man stellt nämlich einen Stab senkrecht auf eine Klangscheibe, fasst ihn in der Mitte mit der vollen linken Hand fest an, drückt ihn ziemlich stark auf die Scheibe, und streicht den oberen Theil von oben nach unten mit der vollen rechten Hand mittels eines Tuches, das mit pulverisirtem Haiz bestreut ist, sobald ein reiner Ton entsteht, tritt sogleich die Figur sehr correct hervor (S 621)

[614] V von Lang *Zur Ermittlung der Constanten der transversalen Schwingungen elastischer Stäbe* *Annalen der Physik*, Bd CIII S 624–8, Leipzig, 1858. This does not seem any real contribution to the theory of elastic vibrations of rods. It proves an equation of the well-known form

$$\int_0^l X_r X_s dx = 0,$$

where X_r and X_s are two solutions of Poisson's equation of the type

$$d^4y/dx^4 + m^2y = 0,$$

by the lengthy process of substituting their values and actually integrating through the length l of the rod. see our Art 468*

[615] Edward Sang *Theory of the Free Vibrations of a Linear Series of Elastic Bodies* *Edinburgh Royal Society Proceedings*, Vol III, Part I, p 358, Part VI, (*Alligated Vibrations*) pp 507–8, Edinburgh, 1856–7. The first part is only referred to by title the sixth part is accompanied by a short resume of results, but this is not sufficient to indicate whether the original memoir is of real importance.

[616] J Stefan *Ueber die Transversalschwingungen eines elastischen Stabes* *Sitzungsberichte*, Bd XXXII, S 207–41, Wien, 1858. This paper proves 'by brute force' that the integral along the length of a rod of the product of two of the functions X_r and X_s which occur in Poisson's solution of the equation

$$\frac{d^2y}{dt^2} + a^2 \frac{d^4y}{dx^4} = 0$$

is zero if r and s be different, and evaluates the integral when r and s are equal. The method adopted is longer than Poisson's original method, and I do not see that Stefan has really contributed anything to the previous discussion of the problem by Euler, Poisson, Seebeck and others.

He states that the method of integration by parts will not give the value of $\int X_r^2 dx$ as it leads in this case to an indeterminate form $0/0$. This form, however, can be evaluated by the processes of the differential calculus and we can thus more briefly than by Stefan's laborious integrations deduce the value of $\int X_r^2 dx$. This was pointed out by V. von Lang in a paper entitled: *Einige Bemerkungen zu Herrn Dr T. Stefans Abhandlung: Ueber die Transversalschwingungen eines elastischen Stabes*, which appeared also in the *Sitzungsberichte*, Bd. xxxiv., S. 63–9, Wien, 1859.

[617.] J. Petzval: *Ueber die Schwingungen gespannter Saiten. Denkschriften der mathem. naturwiss. Classe der k. Akademie*, Bd. xvii., S. 91–136, Wien, 1859. An abstract of this memoir is given in the *Sitzungsberichte*, Bd. xxix., S. 160–72, Wien, 1858.

This memoir commences by deducing the differential equations for the vibrations of an elastic string, when its mass per unit length is variable, its weight taken into account, and other not dealt with in ordinary treatments of the subject considered (S. 91–6). The remainder of the memoir is devoted to the case in which two pieces of uniform string of different mass per unit length are united together to form a single piece. The author instead of considering the equality of the displacements and tensions at the joint treats this as a special case of varying mass. He obtains a solution involving a discontinuous function, and investigates at great length of analysis a problem which is easily dealt with by the ordinary equations for a vibrating string. I have not tested the results given for the notes, nodes etc., but these might be useful for purposes of comparison with the same quantities obtained by other processes. The author speaks of his problem as a *bisher nie in Betracht gezogenen Fall*, but this seems to me hardly probable although I am unable to give any reference to its earlier discussion. Possibly Duhamel has treated this case: see our Art. 897*.

[618.] E. Winkler: *Formänderung und Festigkeit gekrümmter*

Körper, insbesondere der Ringe Der Civilingenieur, Bd. iv, S 232-46, Freiberg, 1858

This is an important memoir, both from the theoretical and practical standpoint, although many of its results require correction and modification. Some of these corrections have been made in *Kapitel XL (Ringförmige Körper)* of the author's well-known treatise *Die Lehre von der Elasticität und Festigkeit*, Prag, 1867, but this treatise does not cover anything like the same area as the memoir. I propose therefore to indicate the correct analysis and compare its results with those of Winkler.

The importance of the subject will be sufficiently grasped when I remind the reader that it is the only existing theory of the strength of the links of chains. To investigate the strength of such links by the complete theory of elasticity would involve even for the case of anchor rings an appalling investigation in toroidal and allied functions, while for the oval chain links with studs in ordinary use any successful attempt at a general investigation seems inconceivable. We shall have the less hesitation, however, in applying the Bernoulli-Eulerian theory, if we remember how close an approximation Saint-Venant's researches on flexure have shown it to be in the case of *straight* bars. At the same time, we are certainly going to put it to the very limit of its application, namely to *curved* bars in which the dimensions of the cross-section are not very small as compared with either the length or the radius of curvature of the central axis. It is non-fulfilment of the latter condition which renders Bresse's investigations for curved rods (see our Arts 514 and 519) inapplicable without modification, and the former introduces, failing further experimental confirmation, an element of uncertainty into the results of an undoubtedly important theory.

[619] Remembering that we need not assume adjacent cross-sections of our link to remain undistorted, if we only suppose them to be approximately equally distorted (see our Art 84), we can easily investigate an expression for the stretch at any point by a method akin to that which results from the Bernoulli-Eulerian theory. We assume the central line of the link to lie in one plane and this plane to be that of the system of applied force and further to cut each cross section of the link

in a principal axis. These cross-sections will be supposed uniform, each of area ω and swing radius κ about a line (central axis) through the centroid perpendicular to the plane of the central line. (Central and neutral *axes* are straight lines lying in the plane of the cross-section; central and neutral *lines* the loci of points in which those axes meet the 'plane of the link'.)

We shall use the following notation :

s_v = stretch in a direction perpendicular to the cross-section at distance v from the central axis.

s_0 = stretch at points on the central axis.

v_0 = distance of the neutral axis from the central axis.

E = stretch-modulus of the material (not necessarily isotropic) in the direction of the central line.

$E\omega h^2$ = flexural rigidity of the link (no longer $E\omega\kappa^2$).

ρ_0 = radius of curvature of unstrained central line at any point.

x_0, y_0 = coordinates of a point on central line referred to the axes of symmetry of the link before strain.

x, y = the coordinates of the same point after strain.

$\Delta x, \Delta y = x - x_0, y - y_0$ respectively.

$d\sigma_0, d\sigma$ = elements of arc σ of central line before and after strain.

ϕ_0, ϕ = angles the tangent to the central line at any point makes with axis of x before and after strain, taken to increase with σ_0 ;
 $\Delta\phi = \phi - \phi_0$.

M = the bending moment at any cross-section, being the couple which must be applied (taken positive when it increases ϕ) for equilibrating the stresses if the material beyond the length σ of central line be cut away.

P = the *total* traction (i.e. negative thrust) at the same cross-section.

c_1, c_2 = the distances from the central axis to the 'extreme fibres', or what with an extension of terms we shall venture to call *intrados* and *extrados*. When we do not wish to particularise one or other of these, we shall simply use c for either.

Q = the *total* longitudinal pull on the link; this we shall suppose to be applied in the direction of the axis of y , which axis is taken to coincide with the greater axis of symmetry of the link, if there be one.

$\Delta b, \Delta a$ = increments of length of half the major and minor axes b and a (i.e. axes in directions of y and x respectively) of the link.

R = unknown reaction of the stud of the link supposed to coincide with the axis of x , if the link have one. Clearly

$$R = - \frac{E\omega}{n} \frac{\Delta a}{a} \dots\dots\dots (i),$$

where n is a quantity depending on the dimensions and materials of the stud and link Winkler's result (39) S 236 is really the same as this, although he puts it in a form apparently allowing for variation of the cross-section in the stud

$d\omega$ = an element of the area of the cross-section

$$\omega h^2 = \int \frac{\rho_0 v^2}{\rho_0 + v} d\omega$$

Thus remembering the symmetry of the cross section we have

$$\int \frac{\rho_0 d\omega}{\rho_0 + v} = \omega \left(1 + \frac{h^2}{\rho_0^2} \right) \quad (11),$$

$$\int \frac{\rho_0 v}{\rho_0 + v} d\omega = - \frac{\omega h^2}{\rho_0} \quad (12)$$

Approximately

$$\omega h^2 = \omega \kappa^2 + \frac{1}{\rho_0^3} \int v^4 d\omega + \frac{1}{\rho_0^4} \int v^6 d\omega + \quad (13)$$

In some cases (e.g. Bresse's theory of arches) it is sufficiently approximate to put $h = \kappa$, retaining only the first term in (13)

For a rectangle, I find if $2c$ be its height

$$\left. \begin{aligned} h^2 &= \frac{\rho_0^3}{2c} \log \frac{\rho_0 + c}{\rho_0 - c} - \rho_0^2, \\ &= c^2 \left(\frac{1}{3} + \frac{1}{5} \frac{c^2}{\rho_0^2} + \frac{1}{7} \frac{c^4}{\rho_0^4} + \dots \right) \end{aligned} \right\} \quad (14),$$

which allows of easy calculation

For a circle, if c be its radius

$$\left. \begin{aligned} \omega h &= \frac{\rho_0^4}{2} \int_0^{2\pi} \left(\frac{1}{\sin^2 \theta} \log \frac{\rho_0^2}{\rho_0 - c^2 \sin^2 \theta} - \frac{c^2}{\rho_0^2} \right) d\theta, \\ \text{or, } h^2 &= \frac{c^2}{4} \left\{ 1 + \frac{1}{2} \frac{c^2}{\rho_0^2} + \frac{3}{6} \frac{5}{8} \frac{c^4}{\rho_0^4} + \frac{3}{6} \frac{5}{8} \frac{7}{10} \frac{c^6}{\rho_0^6} + \dots \right\} \end{aligned} \right\} \quad (15)$$

The values of h for some other sections may be easily found¹

[620] Let BOB' , AOA' be the two principal axes of the curve formed by the central line $ABA'B$, L a point on this central line, LT


¹ Its value for a trapezoidal section, symmetrical about the line joining the mid points of the parallel sides is, —if d_1 , d be the lengths of those sides

$$\rho_0 \left(-1 + \frac{\rho_0}{\omega} \left[\left\{ d + \frac{d_1 - d}{c_1 + c} (c_1 + \rho_0) \right\} \log \frac{\rho_0 + c_1}{\rho_0 - c} - (d_1 - d) \right] \right)$$

Cf Bach *Elasticität u. Festigkeit*, S 308-9 This is useful in the case of certain types of hooks

the tangent there, $LTX = \phi_0$, $AL = \sigma_0$, then we readily find on the Bernoulli-Eulerian hypothesis :

$$s_v = \frac{s_0 + v \frac{d(\Delta\phi)}{d\sigma_0}}{1 + \frac{v}{\rho_0}} \dots\dots\dots(\text{vii}).$$



$$P = \int E s_v d\omega,$$

$$M = \int E s_v v d\omega.$$

Whence by (ii) and (iii)

$$P = E s_0 \omega \left(1 + \frac{h^2}{\rho_0^2} \right) - \frac{E \omega h^2}{\rho_0} \frac{d(\Delta\phi)}{d\sigma_0} \dots\dots\dots(\text{viii}),$$

$$M = - \frac{E \omega h^2 s_0}{\rho_0} + E \omega h^2 \frac{d(\Delta\phi)}{d\sigma_0} \dots\dots\dots(\text{ix}).$$

From (viii) and (ix) we find to determine s_0 and $\frac{d(\Delta\phi)}{d\sigma_0}$:

$$E \omega s_0 = P + \frac{M}{\rho_0} \dots\dots\dots(\text{x}),$$

$$E \omega h^2 \frac{d(\Delta\phi)}{d\sigma_0} = M + \frac{P h^2}{\rho_0} + \frac{M h^2}{\rho_0^2} \dots\dots\dots(\text{xi}).$$

We shall represent the right-hand sides of (x) and (xi) by p and m respectively. The usual formulae for arched ribs replace p and m by their first terms P and M : see our Art. 519.

Winkler in his memoir adds the term $P \kappa^2 / \rho_0^2$ to (x) which I think is incorrect. He has the form (x) on S. 270 of his treatise.

Substituting in (vii) we find

$$E\omega s_v = P + \frac{M}{\rho_0} + \frac{M}{h^2} \frac{\rho_0 v}{\rho_0 + v} \quad (\text{xi})$$

Whence if T be the maximum traction in any section (T_1 the safe negative, T_2 the safe positive traction)

$$T\omega = P + \frac{M}{\rho_0} + \frac{M}{h^2} \frac{\rho_0 c}{\rho_0 + c} \quad (\text{xii}),$$

and P and M must be given their values at the section of maximum stress while T is put equal to T_1 or T_2 to obtain the condition of safe loading

Further from (xi) we find for the position of the neutral axis

$$\frac{v_0}{\rho_0} = - \frac{P + \frac{M}{\rho_0}}{P + \frac{M}{\rho_0} \left(1 + \frac{\rho_0}{h^2}\right)} \quad (\text{xiv})$$

For approximate values, if we neglect terms of the order $(v/\rho_0)^3$, we have

$$s_v = \frac{Mv}{E\omega\kappa} \left(1 - \frac{v}{\rho_0} + \frac{\kappa^2}{v\rho_0}\right) + \frac{P}{E\omega} \quad (\text{xv}),$$

$$v_0 = -\kappa \left\{ \frac{P}{M} + \frac{1}{\rho_0} - \frac{P\kappa^2}{M\rho_0^2} \left(2 + \frac{M}{P\rho_0} + \frac{P\rho_0}{M}\right) \right\} \quad (\text{xvi})$$

Winkler in his memoir does not give (xi) to (xiv). He has (xv), but his approximation to s_v to the order $(v/\rho_0)^4$ seems to me wrong, while in his formula corresponding to (xvi) he has 1, where I have 2 in the second bracket. See his pages 234-6. Thus I think his final results cannot be depended upon.

[621] From the consideration that $\cos \phi = dx/d\sigma$, and therefore $x = \int \cos \phi (1 + s_0) d\sigma_0$, we easily deduce

$$\Delta x = - \frac{y_0}{E\omega} \int \frac{m}{h} d\sigma_0 + \frac{1}{E\omega} \int \frac{my_0}{h^2} d\sigma_0 + \frac{1}{E\omega} \int p dx_0 \quad (\text{xvii})$$


Similarly from $\sin \phi = dy/d\sigma$, we find

$$\Delta y = \frac{x_0}{E\omega} \int \frac{m}{h} d\sigma_0 - \frac{1}{E\omega} \int \frac{mx_0}{h} d\sigma_0 + \frac{1}{E\omega} \int p dy_0 \quad (\text{xviii})$$

These equations agree with Winkler's (S 234), except that he has the wrong values for m and p , which ought to have the values given in our (x) and (xi). They further agree with Bresse's approximate equations (see our Art 519) if we put M and P for our m and p .

The above theory is so far perfectly general and not confined to the case of links. We now proceed to the case of a link symmetrical about two axes and with a stud

[622.] Let $4\nu_0$ be the unstrained length of the perimeter of the central line. Then we find if χ be the angle the normal makes with the axis of x :



$$P = \frac{1}{2} (R \sin \chi + Q \cos \chi) \dots \dots \dots (\text{xix}).$$

$$M = M_0 - \frac{R}{2} y + \frac{Q}{2} (a - x) \dots \dots \dots (\text{xx}).$$

Further, $\Delta\phi = 0$ at A and B , whence

$$\Delta\phi = \int_0^{\sigma_0} \frac{m}{E\omega h^2} d\sigma_0 \dots \dots \dots (\text{xxi}),$$

and

$$0 = \int_0^{\nu_0} \frac{m}{E\omega h^2} d\sigma_0 \dots \dots \dots (\text{xxii}).$$

We also find from (xvii), (xviii) and (xxii):

$$\Delta a = - \frac{1}{E\omega} \int_0^{\nu_0} \frac{m y_0}{h^2} d\sigma_0 + \frac{1}{E\omega} \int_0^a p dx_0 \dots \dots \dots (\text{xxiii}),$$

$$\Delta b = - \frac{1}{E\omega} \int_0^{\nu_0} \frac{m x_0}{h^2} d\sigma_0 + \frac{1}{E\omega} \int_0^b p dy_0 \dots \dots \dots (\text{xxiv}).$$

These values agree with those of Winkler's treatise but not with those of his memoir (S. 236).

[623.] Let us first apply these results to the case of a circular link of radius a . Here h^2 is constant and given, if the cross-section be as usual circular and of radius c , by (vi) with ρ_0 put equal to a .

Finding m from (x1), (x1x) and (xx), and substituting in (xxii) we have

$$\left(M_0 + \frac{Qa}{2}\right) \frac{\pi}{2} \left(1 + \frac{h^2}{a^2}\right) = \frac{Qa}{2} + \frac{Ra}{2} \quad (\text{xxv})$$

Case (1) Suppose there to be no stud (e.g. an anchor ring) Then $R=0$, and we find from (x1x) and (xx),

$$\left. \begin{aligned} P &= \frac{Q}{2} \cos \chi, \\ M &= \frac{Qa}{2} \left(\frac{1}{\frac{\pi}{2} \left(1 + \frac{h}{a}\right)} - \cos \chi \right) \end{aligned} \right\} \quad (\text{xxvi}),$$

while
$$p = \frac{Qa^2}{\pi(a^2 + h)}, \quad m = Qa \left(\frac{1}{\pi} - \frac{1}{2} \cos \chi \right)$$

Further from (xxiii) and (xxiv) we have

$$\left. \begin{aligned} \Delta a &= -\frac{Qa^3}{E\omega h^2} \left(\frac{1}{\pi} - \frac{1}{4} \right) + \frac{Qa^3}{E\omega\pi(a^2 + h)} \\ \Delta b &= \frac{Qa^3}{E\omega h^2} \left(\frac{\pi}{8} - \frac{1}{\pi} \right) + \frac{Qa^3}{E\omega\pi(a^2 + h^2)} \end{aligned} \right\} \quad (\text{xxvii})$$

Putting $h^2 = \kappa^2$ and neglecting the second terms as compared with the first, the results in (xxvii) agree with Saint-Venant's of 1837 (see our Art 1575*) They differ by a factor $\frac{1}{2}$ in the second terms from those of Winkler's memoir even when h^2 is put equal to κ in the first and neglected in the second terms They agree except in the sign of the first term in the value of Δb with those of Winkler's treatise, S 373 Winkler's results in the memoir for P and M agree to a first approximation with our (xxvi) See his S 237-40

For the position of the neutral axis we have from (xiv)

$$v_0 = -\frac{ah^2}{a + h^2} \frac{1}{1 - \frac{\pi}{2} \cos \chi} \quad (\text{xxviii})$$

This agrees with the result in the memoir, if h be neglected in the denominator

Lastly we find from (xiii) for the traction

$$T\omega = \frac{Qa^2}{\pi(a + h^2)} \pm \frac{ca}{a \pm c} \frac{Qa}{h^2} \left(\frac{a^2}{\pi(a + h)} - \frac{1}{2} \cos \chi \right) \quad (\text{xxix}),$$

the upper sign referring to the extrados and the lower to the intrados The result given in the memoir does not agree with this even to a first approximation

[624] Winkler traces in his Fig 5, *Tafel* 33, for $a = 6c$ the form of the neutral line, and in Fig 6 the tractions in extrados and intrados

The latter are certainly incorrect. I have retraced both figures in the accompanying plate, where the stress is measured from the central axis along the radii in the scale: $T\omega/Q = \frac{1}{8}$ inch. The dotted lines are the curves obtained from the usual formula

$$T\omega = \pm \frac{Mc}{\kappa^2}.$$

It will be seen to give results often very divergent from those calculated from (xxix). The following are the numerical results for this case:

$$h^2 = \frac{c^2}{4} \times 1.014,135; \quad \frac{v_0}{c} = - \frac{.026,651}{.636,620 - \cos \chi};$$

$$v_0 = \infty, \text{ for } \chi = 50^\circ 27' 35'';$$

$$\frac{\Delta a}{a} = - \frac{Q}{E\omega} \times 9.383,44;$$

$$\frac{\Delta b}{a} = \frac{Q}{E\omega} \times 10.878,80;$$

$$\text{For extrados: } \frac{T\omega}{Q} = 6.727,75 - 10.142,35 \cos \chi;$$

$$\text{For intrados: } \frac{T\omega}{Q} = -8.660,27 + 14.199,29 \cos \chi;$$

$$\text{Old formula: } \frac{T\omega}{Q} = \pm (7.586,75 - 12 \cos \chi).$$

For extrados $T = 0$ for $\chi = 48^\circ 27'$ (old formula $50^\circ 47'$);

Maximum positive traction ($\chi = 90^\circ$) = $\frac{Q}{\omega} \times 6.727,75$,

Maximum negative traction ($\chi = 0$) = $-\frac{Q}{\omega} \times 3.414,60$.

The old formula gives $\frac{Q}{\omega} \times 7.586,75$ and $-\frac{Q}{\omega} \times 4.413,25$ respectively.

For intrados $T = 0$ for $\chi = 52^\circ 25'$ (old formula $50^\circ 47'$);


Maximum positive traction ($\chi = 0$) = $\frac{Q}{\omega} \times 5.539,02$;

Maximum negative traction ($\chi = 90^\circ$) = $-\frac{Q}{\omega} \times 8.660,27$.


The old formula gives the same values of the traction for intrados as for extrados with the signs reversed.

[625.] It may be shown that the absolutely greatest traction is negative one and occurs in the intrados at B and B' . For wrought iron, of which the links of chains are usually made, it would be sufficient to consider this traction¹, but there would have to be an investigation of the positive tractions in the case of cast iron.

¹ The 'fibrous' character of wrought-iron causes bars of this material to have a safe limit higher in tensile than in compressive stress, although for practical purposes they are frequently taken equal.



Link without stud



Link with stud



The maximum negative traction in the intrados occurs at $\chi = 90^\circ$, and equals $\frac{Qa^2}{\omega\pi(a^2+h^2)} \left\{ \frac{ca^2}{(a-c)h^2} - 1 \right\}$

The maximum positive traction in the intrados occurs at $\chi = 0$, and equals $\frac{Qa^2}{\omega\pi(a^2+h^2)} \left(1 - \frac{ca^2}{(a-c)h^2} \right) + \frac{Qa^2c}{2\omega(a-c)h^2}$

The maximum positive traction in the extrados occurs at $\chi = 90^\circ$, and equals $\frac{Qa^2}{\omega\pi(a^2+h^2)} \left\{ 1 + \frac{ca^2}{(a+c)h^2} \right\}$

The latter will be greater than the former if

$$4a^3 > \pi(a^2+h^2)(a+c),$$

which will generally be the case, e.g. if $a = 6c$

In wrought iron our condition for safety is thus

$$T_2 > \frac{Qa^2}{\pi^2 c^2 (a^2+h^2)} \left\{ \frac{ca^2}{(a-c)h} - 1 \right\} \quad (\text{xvix}),$$

or, to a first approximation, the diameter

$$2c > \sqrt{\frac{32Qa}{\pi T}} \quad (\text{xxxi})$$

This value of $2c$ may then be substituted in the small terms of (xvix), and a new approximation found. The result (xxxi) agrees with that given on S 372 of the treatise, but the other results of this article are not given in it, and are erroneously given in the memoir. More exactly, neglecting only terms of the order $\left(\frac{c}{a}\right)^4$, I find that the cubic to determine the limiting value of c/a is

$$\left(\frac{\pi^2 T_2 a^2}{4Q} - \frac{5}{16} \right) \left(\frac{c}{a} \right)^3 - \frac{1}{4} \left(\frac{c}{a} \right) - \frac{3}{4} \left(\frac{c}{a} \right) - 1 = 0 \quad (\text{xxxi})$$

This differs entirely from the cubic given in the memoir, and in the treatise (S 372) Winkler has $\frac{3}{16}$ instead of $\frac{5}{16}$ for the second term of the first bracket

[626] Case (ii) Suppose the circular link has a stud

Then we have from (xix), (xx) and (xxv),

$$P = \frac{1}{2} (R \sin \chi + Q \cos \chi) \quad (\text{xxviii}),$$

$$M = \frac{1}{\pi} \frac{a(Q+R)}{1 + \frac{h}{a}} - \frac{a}{2} (R \sin \chi + Q \cos \chi) \quad (\text{xxix}),$$

$$\text{whence } m = \frac{a}{\pi} (Q+R) - \frac{a}{2} (R \sin \chi + Q \cos \chi) \quad (\text{xxx}),$$

$$p = \frac{Q+R}{\pi} \frac{a}{a+h} \quad (\text{xxxii})$$

From (i) and (xxiii) we find :

$$R = \xi Q,$$

where

$$\xi = \frac{\frac{a^2}{h^2} \left(1 - \frac{\pi}{4}\right) - \frac{a^2}{a^2 + h^2}}{n\pi + \frac{a^2}{h^2} \left(\frac{\pi^2}{8} - 1\right) + \frac{a^2}{a^2 + h^2}} \dots\dots\dots(\text{xxxvii}).$$

This value is not given in the treatise ; it differs, even when we take only the first approximation, from the value given by Winkler in the memoir.

From (xxiv) we have :

$$\Delta b = \frac{aQ}{E\omega} \left\{ \frac{a^2}{h^2} \left(\frac{\xi}{4} + \frac{\pi}{8} - \frac{\xi+1}{\pi} \right) + \frac{\xi+1}{\pi} \frac{a^2}{a^2 + h^2} \right\} \dots\dots(\text{xxxviii}),$$

while,

$$\Delta a = - \frac{aQ}{E\omega} n\xi \dots\dots\dots(\text{xxxix}).$$

Let $\xi = \tan \epsilon$, then we easily find for the position of the neutral line from (xiv) :

$$\frac{v_0}{a} = - \frac{\frac{2\sqrt{2} \sin(45^\circ + \epsilon)}{\pi} \frac{h^2}{a^2 + h^2}}{\frac{2\sqrt{2} \sin(45^\circ + \epsilon)}{\pi} - \cos(\chi - \epsilon)} \dots\dots\dots(\text{xl}).$$

Finally for the tractions in extrados and intrados from (xiii) we

$$\frac{-\omega}{Q} = \frac{\xi+1}{\pi} \frac{a^2}{a^2 + h^2} \left\{ 1 \pm \frac{a^2 c}{h^2 (a \pm c)} \right\} \mp \frac{a^2}{2h^2} \frac{c}{a \pm c} \frac{\cos(\chi - \epsilon)}{\cos \epsilon} \dots\dots(\text{xli}),$$

where the upper sign refers to the extrados.

[627.] Now ξ is positive, hence ϵ will be found to be an angle in the first quadrant ; $\cos(\chi - \epsilon)$ cannot thus be negative and we shall get the maximum positive traction in the extrados by making $\cos(\chi - \epsilon)$ as small, or $\chi - \epsilon$ as large as possible, irrespective of sign. Thus we must put $\chi = \pi/2$ or 0 according as ϵ is $<$ or $> 45^\circ$, or $\xi <$ or > 1 ; the former generally holds. Hence the maximum positive traction in the extrados

$$= \frac{Q}{\omega} \left\{ \frac{\xi+1}{\pi} \frac{a^2}{a^2 + h^2} \left(1 + \frac{a^2 c}{h^2 (a + c)} \right) - \frac{a^2}{2h^2} \frac{c}{a + c} \xi \right\} \dots\dots\dots(\alpha).$$

The maximum negative traction in the extrados will be at $\chi = \epsilon$ and so equals :

$$\frac{Q}{\omega} \left\{ \frac{\xi+1}{\pi} \frac{a^2}{a^2 + h^2} \left(1 + \frac{a^2 c}{h^2 (a + c)} \right) - \frac{a^2}{2h^2} \frac{c}{a + c} \frac{1}{\cos \epsilon} \right\} \dots\dots\dots(\beta).$$

For the intrados the maximum positive traction will be obtained by putting $\chi = \epsilon$, and so equals :

$$\frac{Q}{\omega} \left\{ \frac{\xi+1}{\pi} \frac{a^2}{a^2 + h^2} \left(1 - \frac{a^2 c}{h^2 (a - c)} \right) + \frac{a^2}{2h^2} \frac{c}{a - c} \frac{1}{\cos \epsilon} \right\} \dots\dots\dots(\gamma).$$

For the maximum negative traction in the intrados we must have $\chi - \epsilon$ as great as possible, or as a rule we put $\chi = \pi/2$. Thus it equals

$$\frac{Q}{\omega} \left\{ \frac{\xi + 1}{\pi} \frac{a^2}{a^2 + h^2} \left(1 - \frac{a^2 c}{h(a-c)} \right) + \frac{a^2}{2h} \frac{c}{a-c} \xi \right\} \quad (\delta)$$

These values (a)–(δ) must be calculated for any given link of definite material. (δ) has in general, regardless of sign, the greatest value. Hence, if the links be made of wrought iron for which the safe tensile and compressive stresses may be taken as equal (see our Art 625), we have, if T_c be the safe maximum compressive stress

$$Q < \frac{\omega T_c}{\frac{\xi + 1}{\pi} \frac{a^2}{a^2 + h^2} \left(1 - \frac{a c}{h(a-c)} \right) + \frac{a^2}{2h} \frac{c \xi}{a-c}} \quad (\text{xlii})$$

This equation also gives us the proper ratio of c to a when the value of Q is given.

Results (xxxviii) to (xlii) differ very considerably from Winkler's. He makes the maximum stress to be tensile and not compressive.

[628] Let us suppose the link of our Art 624 to have a cast iron stud placed in it, and let us take its modulus to be one half that of the wrought iron link and its mean cross section to be two thirds that of the link¹, then

$$n = E\omega / (E'\omega') = 3,$$

and we find

$$\xi = 676,098$$

For a special elliptic link I find in Art 640, $\xi = 359,813$. Winkler finds in his treatise (§ 372) for an oval link $\xi = 5612$, but I have not verified his arithmetic. Thus it appears that in the stud of a circular link there may be nearly double the stress that there is in that of an elliptic link.

For the stretches in the two axes we have from (xxxviii) and (xxxiv),

$$\frac{\Delta a}{a} = -\frac{Q}{E\omega} \times 2,028,295,$$

$$\frac{\Delta b}{a} = \frac{Q}{E\omega} \times 4,534,677$$

The first is less than a fourth, the second less than a half of the values for the same link without stud. The total extension of a chain made of links having studs would only be about $\frac{1}{11}$ of the extension of a chain of the same length under the same load having the same links without studs. We may note that in general

$$\xi = -\frac{\Delta a_0}{a} \frac{E\omega}{Q} \bigg/ \left(n + \frac{\Delta b_0}{a} \frac{E\omega}{Q} \right), \text{ and } \frac{\Delta b}{a} = \frac{\Delta b_0}{a} - \xi \frac{\Delta a}{a},$$

¹ These agree pretty closely with the numbers chosen by Winkler in his treatise § 372, for an oval ring with stud.

where $\frac{\Delta b_0}{a}$ and $\frac{\Delta a_0}{a}$ are the stretches in the semi-axes of an equal link without stud. These simplify the calculations for a link with stud.

For the neutral line from (xl) :

$$\frac{v_0}{c} = - \frac{.037,091}{.883,962 - \cos(\chi - \epsilon)}, \text{ where } \epsilon = 34^\circ 3' 45'',$$

and it passes to infinity when

$$\chi = 61^\circ 56' 20'' \text{ and } 6^\circ 11' 14''.$$

I have traced the neutral line in the lower figure of the plate, p. 430.

Finally for the tractions in extrados and intrados (T and T' say) we have :

$$T = \frac{Q}{\omega} \{11.276,31 - 12.242,90 \cos(\chi - \epsilon)\},$$

$$T' = \frac{Q}{\omega} \{-14.515,44 + 17.140,06 \cos(\chi - \epsilon)\}.$$

The maximum value of T is positive and occurs at $\chi = 90^\circ$, its value being $\frac{Q}{\omega} \times 4.419,13$. The maximum numerical value of T' is negative,

and occurs also when $\chi = 90^\circ$, its value being $-\frac{Q}{\omega} \times 4.915,34$. In the case of wrought iron the latter gives the limit to strength. Thus we see that the circular link with a stud of the above character in it is about 1.76 times as strong as the link without stud. Winkler in his memoir makes it 2.5 times as strong, but his analysis leading to a tensile limit is, I think, incorrect. In the treatise the only case of a link with a stud which he works out is an oval link. Here he finds his maximum stress compressive and the ratio of strengths with and without stud = 2.088. I have not verified his arithmetic, but the results of the treatise seem more probable than those of the memoir.

The traction in the extrados vanishes for

$$\chi = 11^\circ 8' 33'' \text{ and } 56^\circ 58' 57'',$$

that in the intrados for

$$\chi = 1^\circ 56' 8'' \text{ and } 66^\circ 11' 22''.$$

The curves of stress in extrados and intrados will be found traced on the right-hand side of the lower figure of the plate, p. 430. These curves are very interesting especially when compared with the curves in the upper figure, as they show the influence of the stud. The dotted curves give the values of the tractions calculated from the formula, $T\omega = \pm Mc/\kappa^2$, where M is given its value from (xxxiv) after h^2 has been put equal to κ^2 . We find :

$$T = \pm \frac{Q}{\omega} \{12.716,77 - 14.485,38 \cos(\chi - \epsilon)\},$$

which vanishes for

$$\chi = 5^{\circ} 27' 10'' \text{ and } 62^{\circ} 40' 20''$$


We see that the old formula gives results diverging considerably from the true ones

[629] The diagrams on the plate, p 430, referred to in Arts 624 and 628, indicate a useful rule for welding anchor rings and others of circular form. The weld ought to be subjected to the least positive traction, hence the proper place to weld them does not seem to be at the section to which load is applied, but in the case of a ring without a stud about 40° from this section, in the case of a ring with a stud about 30° from the same section. As in the former case the ring can generally slip round so that the load may be applied at every section, we ought to provide for the welded section being able to sustain easily a traction equal to the greatest traction, which occurs in this case when the welded joint is the loaded section.

[630] The next portion of Winkler's memoir is entitled *Ring dessen Axe aus zwei geraden und zwei halbkreisförmigen Theilen besteht* (S 240-2). The analysis of this as that of the previous cases is incorrect, it is not reproduced in the treatise. There is also a difficulty about this case which does not seem to have been noticed by Winkler and which also reappears in the case of the oval link formed of four circular arcs which he discusses in the treatise¹. The difficulty arises from the discontinuity in the tractions at the sections for which there is an abrupt change of curvature, thus, while to satisfy the statical conditions we make a continuous change of bending moment and thrust at these sections, there is an abrupt change of traction owing to the application of the Bernoulli-Eulerian hypothesis. The exact distribution of the stress over such sections seems on that hypothesis to be arbitrary, but it probably may be safely taken equal to the mean of the tractions on either side. I do not think this peculiarity invalidates the solution for sections at small distances from those of discontinuity. An interesting but I expect difficult problem would be to analyse the nature of the stress at such a section by the general theory of elasticity.

¹ I have not verified Winkler's analysis for this oval link which replaces the link with straight sides and the elliptic link of the memoir. It is worked out for special numerical cases with and without a stud but no attempt is made in the treatise to draw stress curves as in the memoir.

[631.] I shall give my own analysis of the link with semi-circular ends and flat sides and compare the results with Winkler's. Let a be



the radius of the semicircular ends, $2e$ the length of each of the straight parts, $b = a + e$; Δa_1 = change in semi-diameter of the link, between the mid-points of the straight parts; Δa_2 = change in semi-diameter of base of semi-circular part; M_0 the bending-moment at the joint of semi-circular and straight parts, and let the rest of the notation be as before except that subscript $_1$ refers to the straight and $_2$ to the circular parts.

We easily find :

$$M_1 = M_0, \quad P_1 = \frac{1}{2}Q, \quad m_1 = M_0, \quad p_1 = \frac{1}{2}Q,$$

since $\rho_0 = \infty$ for the straight parts. Further

$$h_1^2 = \kappa^2,$$

$$M_2 = M_0 + \frac{Q}{2}a(1 - \cos \chi), \quad P_2 = \frac{Q}{2} \cos \chi \dots\dots\dots(\text{xliii}),$$

whence

$$m_2 = \left(M_0 + \frac{Qa}{2} \right) \left(1 + \frac{h_2^2}{a^2} \right) - \frac{Qa}{2} \cos \chi, \quad p_2 = \frac{M_0}{a} + \frac{Q}{2} \dots\dots\dots(\text{xliv}).$$

Let $h_2^2 = q\kappa^2 = qh_1^2$, where q is given by Equation (vi) of our Art. 619. Then from Equation (xxii) we have :

$$M_0 + \frac{Qa}{2} = \zeta \frac{Qa}{2}$$

where

$$\zeta = \frac{qe + a}{\frac{a\pi}{2} \left(1 + \frac{h_2^2}{a^2} \right)} \left. \dots\dots\dots(\text{xlv}) ; \right\}$$

whence

$$\left. \begin{aligned} m_2 &= \frac{Qa}{2} \left\{ \zeta \left(1 + \frac{h_2^2}{a^2} \right) - \cos \chi \right\}, \\ p_2 &= \zeta \frac{Q}{2}, \\ M_2 &= \frac{Qa}{2} (\zeta - \cos \chi), \quad M_1 = \frac{Qa}{2} (\zeta - 1) \end{aligned} \right\} \dots\dots\dots(\text{xlvi}).$$

For the tractions we have from equation (xiii),

$$\left. \begin{aligned} T\omega &= \frac{Q}{2} \left\{ \zeta \pm \frac{a^2}{h^2} \frac{c}{a \pm c} (\zeta - \cos \chi) \right\} \text{ for the curved parts} \\ T\omega &= \frac{Q}{2} \left\{ 1 \pm \frac{ac}{\kappa^2} (\zeta - 1) \right\} \text{ for the straight parts} \end{aligned} \right\} \quad (\text{xlvii})$$

It may be shown that, since $\zeta < 1$, the greatest positive traction occurs as a rule at $\chi = \pi/2$, but that the negative traction at the same section is greater. Hence for wrought iron this negative traction becomes the measure of safe loading. If T_2 be the limit to safe compressive stress, we must have

$$Q < \frac{2\omega T_2}{\zeta \left\{ \frac{a^2}{h^2} \frac{c}{a-c} - 1 \right\}} \quad (\text{xlviii})$$

For a circular link without stud we have from (xxx)

$$Q < \frac{2\omega T_2}{\frac{2a}{\pi(a^2 + h^2)} \left\{ \frac{a}{h} \frac{c}{a-c} - 1 \right\}}$$

The latter, if we take $h = h^2$, will therefore give a greater permissible value than the former for Q , if, $\frac{2a}{\pi(a+h)}$ be $< \zeta$, which is easily seen to be always true whatever e may be. Hence we do not gain increased strength when we elongate a given circular link by inserting straight pieces at the sides. In fact the longer pieces the weaker the link, till the weakness reaches a maximum with $\zeta = 1$, for $e = \infty$.

[632] For the neutral line I find

$$\left. \begin{aligned} \frac{v_0}{a} &= -\frac{h}{a} \frac{\zeta}{\zeta \left(1 + \frac{h}{a} \right) - \cos \chi} \text{ for the curved parts,} \\ \frac{v_0}{a} &= -\frac{\kappa}{a} (\zeta - 1) \text{ for the straight parts} \end{aligned} \right\} \quad (\text{xlii})$$

Further for the change in the semi axes we have by (xliii) to (xlii)

$$E\omega \Delta a_1 = - \int_0^e \frac{m_1 y_0}{h_1} dy_0 - \int_0^{\pi/2} m \frac{(e + a \sin \chi)}{h} \frac{a d\chi}{h} - \int_0^e p d\chi,$$

whence

$$E\omega h \Delta a_1 = \frac{Qa}{2} \left\{ \frac{1}{2} qe + ae + \frac{1}{2} a - \zeta \left(\frac{a}{2} + a + q\kappa \frac{e\pi}{2a} + \frac{1}{2} qe \right) \right\} \quad (1)$$

This result would agree with Winkler's were we to put $q=1$, or $h = \kappa$, throughout

We easily find :

$$\Delta a_1 - \Delta a_2 = \frac{M_0 e^2}{2 E \omega \kappa^2},$$

or,
$$E \omega h_2^2 \Delta a_2 = E \omega h_2^2 \Delta a_1 + \frac{Q a}{4} (1 - \zeta) q e^2 \dots\dots\dots (li).$$

For Δb we have:

$$E \omega h_2^2 \Delta b = \frac{Q a}{2} \left\{ q \kappa^2 \frac{e}{a} + q a e + \frac{\pi}{4} a^2 - \zeta (q a e + a^2) \right\} \dots\dots (lii).$$

To a first approximation (i.e. if $q = 1$) (lii) agrees with Winkler's result, but my value for Δa_2 appears to be quite different from his.


Winkler traces the neutral line and stress-curves for the particular numerical case of $a = \frac{5}{2}c$ and $b = 4c$, or the length of the straight piece $\frac{3}{4}$ of the diameter of the cross-section of the link. Equation (xlix) shows us that the neutral axis for the curved part is similar to that for a circular link without stud, while for the straight piece, it is a straight line parallel to the straight piece and outside the link, since ζ is < 1 . The stress curves are thus similar to those of the upper figure on the plate, p. 430, for the curved parts, and are straight lines for the straight pieces. I have not redrawn Winkler's curves, which are wrong owing to his erroneous formulae. They present, however, no novelty beyond those we have already dealt with.

[633.] The concluding pages of the memoir (S. 242-6) are entitled: *Ring mit elliptischer Axis*, and deal with elliptic links with and without studs. Not only is Winkler's analysis incorrect, but even as an approximation the terms he neglects are of equal importance with those he retains. He expands also certain expressions in terms of the eccentricity in very slowly converging series, which would be better replaced by elliptic integrals, whose values could be found in Legendre's tables. The case of an elliptic link is not dealt with in the treatise.

The following considerations by which Winkler selects a numerical case will, perhaps, show the difficulty I feel in accepting his analysis. He argues that to prevent the jamming of two links we must have for elliptic links (axes $2a$, $2b$) of circular cross-section (diameter $2c$) $c = < \frac{a^2}{b} - c$, whence $a/b > = 2c/a$. Redtenbacher, for a link without stud, says b should equal $3.6c$, or we must have $a/b > = .745$. He further takes for a link with stud $b = 4c$ (whence a/b should be $> = .71$). In both cases, however, he puts $a/b = .69$ which allows jamming. Winkler takes $a/b = .71$ and $b = 4c$, whence he finds $a = 2.82c$, and the eccentricity

$e = 709,22^1$ Thus e is not a small quantity and his series converge very slowly Further his least radius of curvature $= a^2/b = 2c$ nearly But he puts throughout $h^2 = \kappa^2$, or by our Equation (v1) he neglects terms of the order $\frac{1}{2} \frac{c^2}{\rho_0^2}$ or $1/8$ of those he retains, thus his expansions of the elliptic integrals to high powers of e are futile, for his results on other grounds are not necessarily correct to the first place of decimals To retain the term in $(c/\rho_0)^4$ in h^2 leads to enormous complexity of calculation, but I propose to retain the term $(c/\rho_0)^2$ neglected by Winkler so that even in the very eccentric link chosen by him, we may hope to get within two per cent of the true result, while for values of a/b large as compared with c we shall have all the accuracy requisite in practice In what follows I indicate only the general outlines of my analysis

[634] Let χ be the angle the normal at any point of the elliptic central axis makes with the minor axis a , and let the radius to the corresponding point of the auxiliary circle make an angle ψ with a , let e equal the eccentricity $= \sqrt{1 - a^2/b^2}$



Then we easily find, with the notation of the previous articles

$$\left. \begin{aligned} \tan \chi &= \frac{a}{b} \tan \psi, & \rho_0 &= \frac{b}{a} (1 - e \sin \psi)^{\frac{1}{2}}, \\ d\chi &= \frac{a}{b} \frac{d\psi}{1 - e \sin \psi}, & d\sigma_0 &= b \sqrt{1 - e \sin \psi} d\psi \end{aligned} \right\} \quad (111)$$

¹ His values for a and c do not seem to agree with those he has chosen for a/b and b/c !

If there be a stud with resistance $R = \xi Q$, we have from (xix) and (xx):

$$P = \frac{Q}{2} (\xi \sin \chi + \cos \chi) = \frac{Q}{2} \frac{\xi \sqrt{1 - e^2} \sin \psi + \cos \psi}{\sqrt{1 - e^2 \sin^2 \psi}} \dots\dots (liv),$$

$$M = M_0 - \frac{R}{2} y + \frac{Q}{2} (a - x) = \frac{Q}{2} (\eta a - \xi b \sin \psi - a \cos \psi), \left. \begin{array}{l} \\ \end{array} \right\} \dots\dots (lv).$$

where

$$M_0 + \frac{Qa}{2} = \eta \frac{Qa}{2}$$

Further from (vi) since $\kappa^2 = c^2/4$:

$$1/h^2 = 1/\kappa^2 \left(1 - \frac{1}{2} \frac{c^2}{\rho_0^2} - \frac{1}{18} \frac{c^4}{\rho_0^4} \right),$$

so that neglecting quantities of the order (c/ρ_0^4) we have:

$$1/h^2 = 1/\kappa^2 \left\{ 1 - \frac{1}{2} \frac{c^2 a^2}{b^4} \frac{1}{(1 - e^2 \sin^2 \psi)^3} \right\} \dots\dots\dots (lvi)$$

Further $m = M + \frac{Ph^2}{\rho_0} + \frac{Mh^2}{\rho_0^3}$ and therefore:

$$\frac{m}{h^2} = \frac{Q}{2} \left\{ \frac{\eta a - \xi b \sin \psi - a \cos \psi}{\kappa^2} - \frac{a^2}{b^4} \frac{\eta a - \xi b \sin \psi - a \cos \psi}{(1 - e^2 \sin^2 \psi)^3} + \frac{a}{b^3} \frac{\xi a \sin \psi + b \cos \psi}{(1 - e^2 \sin^2 \psi)^2} \right\} \dots\dots\dots (lvii).$$

Whence from (xxii) with the notation of the footnote below¹ we have

$$\eta \left(\frac{b^2}{\kappa^2} \gamma_1 - \frac{a^2}{b^2} \gamma_{10} \right) = \xi \left\{ \frac{b^3}{\kappa^2 a} \gamma_3 - \frac{a}{b} (\gamma_{11} + \gamma_9) + \frac{b^2}{\kappa^2} \gamma_4 - \frac{a^2}{b^2} \gamma_{12} - \gamma_9 \right\} \dots\dots\dots (lviii).$$

¹ The following integrals ($\Delta\psi = \sqrt{1 - e^2 \sin^2 \psi}$) will be of value in this discussion; the γ 's are their values for the special case of our Arts. 636-40 where $e^2 = 1/2$:

$$\gamma_1 = \int_0^{\pi/2} \Delta\psi d\psi; \gamma_1' = 1.350,644.$$

$$\gamma_2 = \int_0^{\pi/2} \frac{d\psi}{\Delta\psi}; \gamma_2' = 1.854,075.$$

(These are the ordinary complete elliptic integrals, their usual symbols E and F being discarded to avoid confusion with the elastic moduli.)

$$\gamma_3 = \int_0^{\pi/2} \sin\psi \Delta\psi d\psi = \frac{1}{2} + \frac{1 - e^2}{4e} \log \frac{1 + e}{1 - e}; \gamma_3' = .811,613.$$

$$\gamma_4 = \int_0^{\pi/2} \cos\psi \Delta\psi d\psi = \frac{\sqrt{1 - e^2}}{2} + \frac{1}{2e} \sin^{-1} e; \gamma_4' = .908,914.$$

$$\gamma_5 = \int_0^{\pi/2} \frac{\sin^2 \psi}{\Delta\psi} d\psi = \frac{\gamma_2 - \gamma_1}{e^2}; \gamma_5' = 1.006,862.$$

$$\gamma_6 = \int_0^{\pi/2} \frac{\cos^2 \psi}{\Delta\psi} d\psi = \frac{\gamma_1}{e^2} - \left(\frac{1}{e^2} - 1 \right) \gamma_2; \gamma_6' = .847,213.$$

For a link without stud we have only to put $\xi=0$, and we find

$$\eta = \frac{\frac{b^{\circ}}{\kappa^2} \gamma_4 - \frac{a^2}{b^2} \gamma_{12} - \gamma_9}{\frac{b^2}{\kappa^2} \gamma_1 - \frac{a^{\circ}}{b^2} \gamma_{10}} \quad (\text{lx})$$

Winkler retains only the first terms in the numerator and denominator, thus he should have $\eta = \gamma_4/\gamma_1$

$$\gamma_7 = \int_0^{\pi/2} \frac{d\psi}{(\Delta\psi)^3} = \frac{\gamma_1}{1-e^2}, \quad \gamma_7' = 2\,701,288$$

$$\gamma_8 = \int_0^{\pi/2} \frac{\sin\psi}{(\Delta\psi)^3} d\psi = \frac{1}{1-e^2}, \quad \gamma_8' = 2$$

$$\gamma_9 = \int_0^{\pi/2} \frac{\cos\psi}{(\Delta\psi)^3} d\psi = \frac{1}{\sqrt{1-e^2}}, \quad \gamma_9' = 1\,414,214$$

$$\gamma_{10} = \int_0^{\pi/2} \frac{d\psi}{(\Delta\psi)^5} = \frac{1}{8(1-e^2)} \left(\frac{4-2e^2}{1-e^2} \gamma_1 - \gamma_9 \right), \quad \gamma_{10}' = 4\,166,526$$

$$\gamma_{11} = \int_0^{\pi/2} \frac{\sin\psi}{(\Delta\psi)^5} d\psi = \frac{1}{8} \frac{3-e^2}{(1-e)^3}, \quad \gamma_{11}' = 3\,333,333$$

$$\gamma_{12} = \int_0^{\pi/2} \frac{\cos\psi}{(\Delta\psi)^5} d\psi = \frac{1}{8} \frac{3-2e^2}{(1-e)^3}, \quad \gamma_{12}' = 1\,885,618$$

$$\gamma_{13} = \int_0^{\pi/2} \frac{\sin^2\psi}{(\Delta\psi)^3} d\psi = \frac{1}{e} \left(\frac{\gamma_1}{1-e} - \gamma_2 \right), \quad \gamma_{13}' = 1\,694,426$$

$$\gamma_{14} = \int_0^{\pi/2} \frac{\cos^2\psi}{(\Delta\psi)^3} d\psi = \frac{\gamma_2 - \gamma_1}{e}, \quad \gamma_{14}' = 1\,006,862$$

$$\gamma_{15} = \int_0^{\pi/2} \frac{\sin\psi \cos\psi}{(\Delta\psi)^3} d\psi = \frac{1}{e} \left(\frac{1}{\sqrt{1-e}} - 1 \right), \quad \gamma_{15}' = 828,427$$

$$\gamma_{16} = \int_0^{\pi/2} \frac{\sin^2\psi}{(\Delta\psi)^5} d\psi = \frac{1}{3e(1-e)} \left(\frac{1+e^2}{1-e} \gamma_1 - \gamma_9 \right), \quad \gamma_{16}' = 2\,930\,476$$

$$\gamma_{17} = \int_0^{\pi/2} \frac{\cos\psi}{(\Delta\psi)^5} d\psi = \frac{1}{3e} \left(\gamma - \frac{1-2e^2}{1-e} \gamma_1 \right), \quad \gamma_{17}' = 1\,236,050$$

$$\gamma_{18} = \int_0^{\pi/2} \frac{\cos\psi \sin\psi}{(\Delta\psi)^5} d\psi = \frac{1}{3e} \left\{ \frac{1}{(1-e)^{\frac{3}{2}}} - 1 \right\}, \quad \gamma_{18}' = 1\,218,951$$

$$\gamma_{19} = \int_0^{\pi/2} \frac{\cos\psi \sin\psi}{\Delta\psi} d\psi = \frac{1}{e} (1 - \sqrt{1-e^2}), \quad \gamma_{19}' = 580\,786$$

$$\gamma_{20} = \int_0^{\pi/2} \sin\psi \Delta\psi d\psi = \frac{1}{3e} \{ (1-e) \gamma - (1-2e^2) \gamma_1 \}, \quad \gamma_{20}' = 618\,020$$

$$\gamma_{21} = \int_0^{\pi/2} \cos\psi \Delta\psi d\psi = \frac{1}{3e} \{ (1+e) \gamma_1 - (1-e) \gamma \}, \quad \gamma_{21}' = 732\,619$$

$$\gamma_{22} = \int_0^{\pi/2} \cos\psi \sin\psi \Delta\psi d\psi = \frac{1}{3e} \{ 1 - (1-e)^{\frac{3}{2}} \}, \quad \gamma_{22}' = 430\,964$$

[635.] The second relation between ξ and η must now be found from (xxiii). After some reductions we have since :

$$E\omega\Delta a = -nRa = -n\xi Qa$$

$$2n\xi = \eta \left(\frac{b^2}{\kappa^2} \gamma_3 - \frac{a^2}{b^2} (\gamma_{11} + \gamma_8) \right) + \xi \left(-\frac{b^3}{a\kappa^2} \gamma_{20} + \frac{a}{b} (\gamma_{18} + 2\gamma_{13} - \gamma_5) \right) \\ - \frac{b^3}{\kappa^2} \gamma_{22} + \frac{a^2}{b^2} (\gamma_{18} + \gamma_{15}) + \gamma_{15} - \gamma_{19} \dots\dots\dots (1x).$$

Equations (lviii) and (1x) enable us to completely solve the problem. If there be no stud we put $\xi = 0$ on the right and replace $n\xi$ by $-\frac{E\omega}{Q} \frac{\Delta a}{a}$ on the left of (1x), using (lix) with it. If there be a stud (lviii) and (1x) give the values of ξ and η .

The following is the value of Δb

$$\frac{2E\omega}{Q} \frac{\Delta b}{b} = \eta \left\{ -\frac{a^2}{\kappa^2} \gamma_4 + \frac{a^4}{b^4} \gamma_{12} + \frac{a^2}{b^2} \gamma_9 \right\} + \xi \left\{ \frac{ab}{\kappa^2} \gamma_{22} - \frac{a^3}{b^3} (\gamma_{18} + \gamma_{15}) - \frac{a}{b} (\gamma_{15} - \gamma_{19}) \right\} \\ + \frac{a^2}{\kappa^2} \gamma_{21} - \frac{a^4}{b^4} \gamma_{17} - 2 \frac{a^2}{b^2} \gamma_{14} + \gamma_6 \dots\dots\dots (1xi).$$

Further the neutral line is given by

$$v_0 = - \frac{\frac{b^2}{a} \left\{ \frac{\eta a}{b} - e^2 \left(\xi \sin^3 \psi - \frac{b}{a} \cos^3 \psi \right) \right\} (1 - e^2 \sin^2 \psi)^{\frac{3}{2}}}{\frac{\eta a}{b} - e^2 \left(\xi \sin^3 \psi - \frac{b}{a} \cos^3 \psi \right) + \left(\frac{\eta a}{b} - \xi \sin \psi - \frac{a}{b} \cos \psi \right) \left(\frac{b^4}{a^3 \kappa^2} (1 - e^2 \sin^2 \psi)^3 - 2 \right)}, \dots\dots\dots (1xii),$$

and the traction in extrados and intrados by

$$T\omega = P \pm \frac{M}{c} \left(4 \mp \frac{3c}{\rho_0} + \frac{2c^2}{\rho_0^2} \mp \frac{2c^3}{\rho_0^3} \right) \dots\dots\dots (1xiii)^1,$$

P , M , and ρ_0 being substituted from (lii)-(lv).

The values of these quantities might be traced for a link either with or without stud as in the case of the circular link, but the discussion must be omitted here, and we confine ourselves to the consideration of a numerical example.

¹ The full discussion of these tractions would be complex, but the maximum maximum after the investigations of Arts. 625, 627-8, and 631 may be assumed to exist at the loaded sections, $\psi = \pm \pi/2$. We have then, if cb/a^2 be small :

for the extrados :

$$\frac{T\omega}{Q} = \frac{1}{2}\xi + \frac{\eta a - \xi b}{2c} \left(4 - \frac{3cb}{a^2} + \frac{2c^2b^2}{a^4} - 2 \frac{c^3b^3}{a^6} \right),$$

for the intrados :

$$\frac{T\omega}{Q} = \frac{1}{2}\xi - \frac{\eta a - \xi b}{2c} \left(4 + \frac{3cb}{a^2} + \frac{2c^2b^2}{a^4} + \frac{2c^3b^3}{a^6} \right).$$

These do not appear to agree with the results on S. 245 of Winkler's memoir even when we neglect c^2/a^2 .

[636] As a numerical example we cannot take exactly Winkler's case because his numbers do not appear to be consistent. Suppose we put $c = a^2/b - c$ and $b = 4c$, then $a/b^2 = 5$, or $e = 1/2$, whence $a/b = e = 707,107$ and $a = 2,828,427c$

[637] Applying these values and those of the footnote on pp 440-1 to equations (lxvii) and (lx), we find

$$84\,357,945\,\eta = 69\,687,551\,\xi + 55\,813,461 \quad (\text{lxiv}),$$

$$49\,276,540\,\eta = (2n + 52\,180,746)\,\xi + 26\,315,392, \quad (\text{lxv}),$$

or, if the link be of wrought-iron and the stud of cast-iron of the same relative dimensions as in our Art 628, $n = 3$ and

$$49\,276,540\,\eta = 58\,180,746\,\xi + 26\,315,392 \quad (\text{lxvi})$$

[638] First suppose $\xi = 0$ in (lxiv), then we have for η

$$\eta = 661,627 \quad (\text{lxvii}),$$

while Winkler has for the corresponding quantity 670,32. I believe that 662 is very near the correct value

Putting $n\xi = -\frac{E\omega}{Q} \frac{\Delta a}{a}$ and $\xi = 0$ in (lxv) I find

$$\frac{\Delta a}{a} = -3\,143,638 \frac{Q}{E\omega} \quad (\text{lxviii})$$

Winkler's result after some reductions yields with considerable divergence from mine

$$\frac{\Delta a}{a} = -3\,568,917 \frac{Q}{E\omega}$$

$$\text{From (lxv),} \quad \frac{\Delta b}{b} = 2\,255,656 \frac{Q}{E\omega} \quad (\text{lix}),$$

while Winkler has $\frac{\Delta b}{b} = 2\,134,83 \frac{Q}{E\omega}$. For the oval link in the treatise

he finds $\frac{\Delta b}{b} = 2\,252,5 \frac{Q}{E\omega}$

Lastly for the maximum positive and negative tractions we have

$$T\omega = 2\,641\,Q \quad \text{and} \quad T\omega = -6\,050\,Q$$

of which the latter is the greater and may therefore be taken to measure the strength of a wrought iron link of these dimensions

Winkler's numbers give $T\omega = -5\,204\,Q$, a result which appears much too small. The fact is that for our present case neither (lxvii) nor the series in the footnote on p 442 are sufficiently approximate. Supposing the value of η to be correct, I have obtained the value above by using (lxv). For an oval link with $a = 2.5c$, $b = 4c$, made up of four circular arcs Winkler in his treatise (p 375) finds $T\omega = -6\,373.5\,Q$, which tends to confirm the result we have found for the elliptic link

[639.] Let us compare the strengths, weights and longitudinal extensions of three links, one elliptic, one circular and the third with circular ends and flat sides. Suppose them all to have a longitudinal semi-axis $b = 4c$, and for the ellipse suppose $a/b = 1/\sqrt{2}$ as above; for the flat-sided link suppose the curvature of its circular ends equal to that of the ellipse at the ends of its longer axis; this involves in the notation of our Art. 631, $a = e = \frac{1}{2}b$.

If T' , T'' , T''' be the maximum compressive stresses, w' , w'' , w''' the weights of the links, $\Delta b'$, $\Delta b''$, $\Delta b'''$ the semi-extensions we find from Equations (xxvii), (xxix), (xlviii), (lii) and Art. 638:

$$\begin{aligned} T' : T'' : T''' &:: 6.050 : 6.159^1 : 4.904 \\ w' : w'' : w''' &:: 5.4026 : 6.2832 : 5.1416 \\ \Delta b' : \Delta b'' : \Delta b''' &:: 2.2557 : 4.9242 : 1.3085. \end{aligned}$$

Whence, generalising from the results of these particular links, it would appear that elliptic and circular links of *the same length* are not very different in strength, that the elliptic link stretches about only one half of what the circular one does and weighs less; but that the link with flat sides and circular ends is, *if of the same length*, stronger than either of the others, less heavy and stretches considerably less than the elliptic one. Thus such is distinctly the best of the three forms considered, and in is frequently adopted in practice.

[640.] Suppose the link to have a cast-iron stud. Then we find the following values of η and ξ from equations (lxiv) and (lxvi).

$$\eta = .958,866, \quad \xi = .359,813,$$

values certainly not to be trusted beyond the third decimal place. Winkler (S. 244-6) finds the very different values:

$$\eta = 1.211,500, \quad \xi = .631,804.$$

We have also from equations (lx) and (lxi):

$$\frac{\Delta a}{a} = -1.079,440 \frac{Q}{Ew}, \quad \frac{\Delta b}{b} = 1.455,831 \frac{Q}{Ew}.$$

Winkler has for the numerical coefficients for the case of the ellipse in the memoir .055,353 and .866,752 and for the oval link in the treatise 1.808,305 and .743,774. I think these coefficients in both the memoir and treatise are incorrect. For the oval link Winkler has Δb actually $< \Delta a$ (S. 376) and this seems extremely improbable for a

¹ This value differs in the first place of decimals from that given by Winkler in his treatise, S. 372, but his approximations are very rough.

link with a stud We notice that the effect of studs of the character considered above on elliptic links is to reduce the stretch of the chain to less than two-thirds of the stretch in a chain made of links without studs

Finally for the maximum compressive stress I find from (xiii)

$$T\omega = -3\,9353\,Q$$

Winkler in his memoir has (S 246)

$$T\omega = -2\,092,872\,Q,$$

a value, I think, much too small For the oval link of his treatise he finds (S 376)

$$T\omega = -3\,082,472\,Q,$$

which differs more widely than I should have anticipated from my result for the elliptic link It will be noticed that the strength of the elliptic link with stud is more than 1.5 times as great as that of the link without stud

[641] In the above articles I have corrected and developed Winkler's theory as the best yet available for stress and strain in the links of chains The calculations have been laborious and I cannot hope they are even now absolutely free from error, still I believe that I have avoided some of the slips of Winkler The theory can only be approximate at best, and the six places of decimals to which some of the results are calculated must not be supposed to suggest any real accuracy beyond the first two or three figures, unless the dimensions of the cross-section are small as compared with the radius of curvature of the link This remark applies particularly to Winkler's numerical example of an elliptic link, which with certain modifications we have followed More accurate results would have been obtained by taking the eccentricity still $= 1/\sqrt{2}$, but b equal to 6 or even 10 times c The formulæ we have given for the ellipse may be readily applied to centrally loaded elliptic arches as well as to complete elliptic springs

The *absolute strength* of chains will be found in reality to be greater than would be given by the above formulæ for the maximum compressive stress Such formulæ ought only to be applied to obtain the *fail limit* see our Arts 5 (e) and 169 (g) Before rupture is reached set has changed the shape of the link, and the links press upon and hold each other, till in some cases the absolute strength of a chain appears to be close upon the absolute shearing or even tensile strength of the material see Section III of this Chapter

[642.] E. Winkler: *Festigkeit der Röhren, Dampfkessel und Schwungringe. Der Civilingenieur*, Bd. VI., S. 325-62 and S. 427-62. Freiberg, 1860. This is a lengthy analytical memoir, which so far as its methods are concerned is more likely to be intelligible to the mathematician than to the practical engineer. It commences with a brief reference to Scheffler's memoir on tubes, remarking that his hypotheses, that there is no longitudinal expansion resulting from lateral pressure, and that the maximum traction is the measure of strength, are both alike unacceptable: see our Art. 654.

[643.] The first section of the paper entitled: *Allgemeines* (S. 326-38) contains a general discussion of the resolution of stress and strain, remarks on the value of the stretch-squeeze ratio (η)—which Winkler proposes to take either $\frac{1}{4}$ or $\frac{1}{3}$ according to the material,—the consideration of a stretch limit of strength, and finally expressions for the stresses in terms of the shifts in the case of cylindrical coordinates and bi-constant isotropy.

[644.] Section II. (S. 338-47) contains the theory of right cylindrical tubes with open ends; there is nothing of real importance in the section which had not already been given by Saint-Venant. The section has not reproduced in a more general and complete form than that of Saint-Venant: see our Arts. 1012*, 1087*-8*

Section III. (S. 348-62) deals with the same form of tubes with closed ends either hemi-spherical or plane. The treatment of spherical shells presents no novelty and Winkler seems to have missed Lamé's method of fitting the cylindrical and spherical parts of a boiler by a proper choice of thicknesses: see our Arts. 1038* and 125.

The treatment of the flat ends, or of circular plates (S. 355-62) under a uniform surface pressure, is based upon the assumption that lines in the plate perpendicular to the mid-plane before strain, remain perpendicular to that plane after strain.

This problem had already been fully worked out for a thin plate by Poisson (see our Arts. 495* and 502*), and another problem very like it for plate of moderate thickness (2ϵ) has been considered in our Arts. 329-30. Winkler assumes that even with surface pressure (cf. our Art. 325) we may neglect the traction perpendicular to the mid-plane of our

plate, or put in the notation of our Art 329, $\widehat{rz} = 0$, this leads to the equation

$$\frac{d\widehat{rz}}{dr} + \frac{\widehat{rz}}{r} = 0,$$

whence as in Art 330 we ought to have \widehat{rz} of the form

$$\widehat{rz} = \text{const} \times \frac{\epsilon^2 - z^2}{r}$$

Winkler by not very intelligible reasoning deduces

$$\widehat{r} = \text{const} \times r (\epsilon - z^2),$$

or, a value which does not satisfy the body stress equations. It follows that his values for \widehat{rr} , $\widehat{\phi\phi}$ and for u , w are all wrong. Thus neither his results nor the inferences he draws from them as to the thickness for the plane ends of cylindrical boilers need further consideration.

[645] The fourth section of the memoir (S 427-48) is entitled *Einfluss der Endflächen, des Gewichts der Röhre und des ungleichen Wasserdruckes*. This investigation seems to me absolutely unreliable and quite as nugatory as that of Scheffler. In the first place (with the notation of our footnote p 79) Winkler neglects the traction $\widehat{\phi\phi}$, i.e. the traction perpendicular to a meridian plane of the cylinder (mean radius a), in the next place he assumes w to be of the form $f_1(z) + f_2(z)r$, then he takes u to be independent of r , which he says is legitimate if 2ϵ , the thickness of the cylindrical wall, be very small. Lastly he neglects

$16\eta \frac{\epsilon^2}{a^4} \frac{d^2 u}{dz^2}$ as compared with $d^4 u/dz^4$ on the ground that ϵ/a^4 is very small (Equation 119, S 430). On his own showing the ratio of $d^4 u/dz^4$ to $d^2 u/dz^2$ is of the order $1/l^2$ where l is the length of the cylinder, hence for a cylinder in which l/a is great his results will not be correct, and were it only for this assumption, i.e. they would not be true for flues.

In the part of the memoir which deals with the influence of the weight of the cylindrical tube, Winkler supposes a ring cut out of the cylinder by two planes perpendicular to its axis at unit distance and calculates the effect of the weight of this ring in deforming itself after the manner of his memoir of 1858 (see our Art 622). But I have elsewhere given reasons (see our Arts 1547*, 537) for questioning such a method of treatment. We might just as fitly apply it to solve the problem of the cylindrical shell subjected to external and internal pressures. All Winkler really works out in these pages is the effect of weight in distorting a thin circular belt of unit breadth placed in a vertical plane. In doing this he neglects quantities of the order (thickness diameter).

If a be the radius of the circular ring, 2ϵ its thickness supposed of rectangular cross section ($2\epsilon \times 1$) ρ its density Winkler finds for the

maximum bending moment M' , which is found at the lowest point, or point of support:

$$M' = -3\alpha^2 \epsilon g \rho.$$

Further he has :

$$\text{Maximum compressive stress} = \frac{3M'}{2\epsilon^2} = -\frac{9\alpha^2 g \rho}{2\epsilon},$$

$$\text{Extension of horizontal diameter} = 3(4 - \pi) \frac{\alpha^4 g \rho}{2E\epsilon^2},$$

$$\text{Compression of vertical diameter} = 3(8 - \pi^2) \frac{\alpha^4 g \rho}{4E\epsilon^2}.$$

These results are correct for a slender belt resting on its lowest point and subjected only to the action of its own weight, i.e. when terms, whose ratio to those retained equals ϵ^2/α^2 , are neglected¹. They have no legitimate application to the case of a heavy cylindrical shell. (S. 442.)

Winkler's further investigation by a similar process of the strain in a cylinder which is only partially filled with water and is thus subjected to different internal pressures in its lower and upper portions seems to me equally questionable. (S. 442-46.)

Allowing for the weight of the cylinder and of the water in it, Winkler finally gives for the thickness 2ϵ of a cylindrical boiler of internal radius r_1 , σ being the density of water (S. 447):

$$2\epsilon = r_1 \left[\frac{29}{48} \frac{P}{T} + \frac{12}{n} \frac{r_1 g \rho}{T} + \sqrt{\left(\frac{29}{48} \frac{P}{T} + \frac{6}{n} \frac{r_1 g \rho}{T} \right)^2 + \frac{15 g \sigma r_1}{4nT}} \right] + \tau.$$

is a constant added to allow for wear and tear (see Section Chapter), and n is a factor (which Winkler puts = 3) taken the values calculated for the effects of the weights of the and of the water inside it. P is the steam pressure and T the tensile stress of the material. The author says (S. 446):

Diese Werthe sind allerdings zu gross, da die Deformirung des Kessels durch die Einmauerung, durch die Boden, sowie durch etwaige Bänder, welche man um die Kessel legt und welche zur Erhöhung der Sicherheit sehr zu empfehlen sind, geschwächt wird.

A theory which gives such *large* values that they have to be corrected by arbitrary factors can hardly be considered satisfactory. I give the result for what it may be worth, but express no confidence whatever even in its approximate accuracy. Winkler reduces it to numbers and compares it with a formula which he says is usual in Prussia (Brix's formula with an exponential: see Section III. of this Chapter). The two frequently give very divergent results.

¹ I find for such a ring of any cross-section ω in the notation of this work :

$$\text{Maximum bending moment} = -\frac{3\omega \rho g a^2}{2},$$

$$\text{Stretch of horizontal diameter} = \frac{\rho g a}{E} \frac{a^2}{\kappa^2} \left(1 - \frac{\pi}{4} \right),$$

$$\text{Squeeze of vertical diameter} = \frac{\rho g a}{E} \frac{a^2}{\kappa^2} \left(2 - \frac{\pi^2}{4} \right),$$

which agree with Winkler's results for the special case.

[646] Section V of the memoir is entitled *Schwungringe* (S 448–62) Winkler first gives a theory of fly wheels in which the influence of the spokes is neglected. He further supposes the traction perpendicular to the meridian plane uniform across the cross section whence he easily finds for its value

$$\phi\phi = \rho a \left(1 + \frac{\kappa}{a}\right) \omega^2,$$

ω being the spin of the wheel, ρ the density of its material, and κ the swing radius of the cross section about an axis in its plane through its centroid and a the distance of that centroid from the axis of the wheel. Winkler (S 450) goes even so far as to apply this formula to mill and grind stones! Compare our Art 590.

In a *genauere Theorie* (S 451–4) Winkler puts $\omega = 0$ and $\phi = 0$. This appears to be really identical with Maxwell's theory (see our Arts 1550*–51*) Winkler finds, if T be the safe limit of tractive stress that

$$\omega < 2 \sqrt{\frac{T}{\rho [(1-\eta)r_1^2 + (3+\eta)r^2]}}$$

r_1 and r being the inner and outer radii of the rim. This theory for $\eta = 1/4$ gives a result for an entire disc almost in agreement with that given by the first theory (S 454).

[647] Finally (S 454–62) Winkler attempts to take into account the influence of the spokes. He practically follows the lines of Resal's investigation (see our Art 584), except that he treats first the case when the portion of the rim of the wheel between two spokes can be considered as pivoted at the spokes. Winkler's results are complex and not put into a form which permits of easy citing. I have not verified them. He takes the values of s_0 and d ($\Delta\phi$) $d\sigma_0$ given in his memoir of 1858 (see our Art 620, Equations (2) and (11)), thus his results if his analysis be correct, might be more exact than Resal's for the case when Resal's ϵ (see our Art 585) is not negligible. It usually will be negligible in practice.

The memoir is rather cumbersome and while containing some interesting points is spoiled by a number of assumptions for which no strong reasons are given, if indeed they exist.

[648] Hermann Scheffler *Theorie der Festigkeit gegen das Zerknicken nebst Untersuchungen über die verschiedenen inneren Spannungen gebogener Körper und über andere Probleme der Biegungstheorie mit praktischen Anwendungen*. Braunschweig 1858, S 1–138.

The author of this book—a practical architect—had already published a volume entitled *Theorie der gewölbten Futtermauern und eisernen Brücken* (see Section III of our present Chapter)

of which he writes that the object was identical with that of the present work—namely to bring more closely together the scientific and practical sides of the subject. The present volume deals with the buckling load and strength of struts, the slide of beams under flexure, and the calculation of the stresses in continuous beams—all problems which have much exercised the practical engineer. Two of these problems had received fairly complete theoretical solutions before 1858, but, as so often occurs, the mathematical investigation failed to reach the hands of the technologists.

[649.] S. 1-58 of the work are devoted to the discussion of the strut problem. We have already seen what erroneous results Euler's theory for the buckling load of struts gives when the length is not very much greater than the diameter of the cross-section. This fact caused Hodgkinson to entirely discard that theory in favour of an empirical formula, and led Lamarle to limit the theory to such struts as had not passed the elastic limit before the buckling load was reached: see our Arts. 958*-961*, 1258*. Lamarle's limitation is quite unrecognised by Scheffler. He starts from Euler's formula for the buckling load P of a column (see Arts. 67* and 74*), or

$$P = E\omega\kappa^2\pi^2/l^2$$

and shews that this does not agree with experiment. He modifies the theory as given by Euler and Lagrange by placing, as a result of the compression, the 'neutral axis' in an eccentric position, he thus obtains for a doubly-pivoted strut the formula

$$P = E\omega \frac{1}{1 + \frac{l^2}{\pi^2\kappa^2}}.$$

See *Corrigenda* to our Vol. i. p. 2.

But this formula does not give absolute values agreeing with experiment, so that Scheffler after citing one or two other semi-empirical formulae by various authors, proceeds to propound a modified theory of his own. Briefly the modification consists in the hypothesis that the longitudinal load on the terminal sections of the column or strut is not exactly *central*. By this means he endeavours to explain the discrepancy between theory and experiment. In doing this he adopts a true eccentric position for the neutral axis, but assumes in comparing his theory with Hodgkinson's experiments that the proportionality of stress and strain holds up to rupture. We will examine one of Scheffler's results somewhat at length:

Let the longitudinal load P applied at a distance b from the axis of the strut, produce a deflection at the mid-point $= a - b$. Let l be the length of the strut, which will be supposed doubly-pivoted, and $\omega\kappa^2$ the moment of inertia of the cross-section about a line through its centroid perpendicular to the load plane. Then if we take as axes the direction

of the vertical load (x) and the perpendicular upon this from the mid point of the central line of the strut (y), we easily deduce for the equation to the distorted central line

$$y = b \sec \frac{l}{2\beta^{\frac{1}{2}}} \cos \frac{x}{\beta^{\frac{1}{2}}} \quad (1),$$

where

$$\beta = \left(\frac{E\omega}{P} - 1 \right) \kappa$$

The curvature at the mid section of the central line

$$= 1/R_0 = - \left(\frac{d^2 y}{dx^2} \right)_0 = \frac{b}{\beta} \sec \frac{l}{2\beta^{\frac{1}{2}}} \quad (11),$$

and the deflection ($a - b$) is obtained from

$$a = b \sec \frac{l}{2\beta^{\frac{1}{2}}} \quad (111)$$

Equation (111) gives a relation between the load and the deflection which, introducing the value of β , leads to

$$P = \frac{E\omega}{1 + \frac{l}{4\kappa \left(\cos^{-1} \frac{b}{a} \right)^2}} \quad (1V)$$

If $b = 0$, this coincides with the value given for the buckling load on the hypothesis of the eccentric neutral axis

To find the elastic strength of the strut, if the elastic limit be reached first in compressive stress, say at the value C , we have to equate C to the maximum compressive stress which arises in the extreme 'fibre' at the mid cross section. Let the distance of this fibre from the central axis be h , then the stress

$$= \frac{P}{\omega} + E \frac{h}{R_0} = C,$$

$$\text{or,} \quad h = R_0 \left(\frac{C}{E} - \frac{P}{E\omega} \right) = \frac{\beta}{b} \left(\frac{C}{E} - \frac{P}{E\omega} \right) \cos \frac{l}{2\beta^{\frac{1}{2}}}$$

Substituting for β and remembering that unity in all practical cases may be neglected as compared with $E C$ or $E\omega P$ we find

$$\frac{hb}{\kappa} = \left(\frac{C\omega}{P} - 1 \right) \cos \frac{l}{2\beta^{\frac{1}{2}}}$$

Let us put $P/\omega = p$, and $p_0\omega$ equal the value of the buckling load as given by Euler's theory, then we have

$$\frac{hb}{\kappa} = \left(\frac{C}{p} - 1 \right) \cos \left(\frac{\pi}{2} \sqrt{\frac{p}{p_0}} \right) \quad (V)$$

This equation (V) agrees with Scheffler's equation (53) & 25, and gives the limiting safe load p per unit section for any doubly pivoted strut. At the same time it must be noted that b is a perfectly

arbitrary constant. Till some hypothesis is made with regard to it (v) only shews us that non-central application of the thrust does influence the value of p , but does not indicate the amount.

Scheffler supposes the terminals hemispherical. In this case, if ϕ be the angle between the central line and the direction of the load :

$$\tan \phi = -\frac{dy}{dx} = \frac{b}{\beta^{\frac{1}{2}}} \tan \frac{l}{2\beta^{\frac{1}{2}}}.$$

Further

$$b = h \sin \phi,$$

whence we find

$$b = h \sqrt{1 - \frac{\beta}{h^2} \cot^2 \frac{l}{2\beta^{\frac{1}{2}}}} \dots\dots\dots (vi).$$

Scheffler takes $b = \frac{h}{n} \sin \frac{l}{2\beta^{\frac{1}{2}}}$ and says n is a constant depending only on the material and form of the end (S. 26). It is quite true that (vi) substituted in (v) leads to a very complicated expression for p , but why this is capable of being "replaced practically" by the simpler formula Scheffler takes, I fail to understand. I am compelled to look upon his 'coefficient of correction' n as a function of the load p . Substituting his value of b in (v) we have :

$$\frac{h^2}{n\kappa^2} = \left(\frac{C}{p} - 1\right) \cot \left(\frac{\pi}{2} \sqrt{\frac{p}{p_0}}\right) \dots\dots\dots (vii).$$

From this formula he calculates the value of p , putting for :

Cylindrical columns of cast	iron	$n = 6,$
„ wrought	„	$n = 24,$
„ oak		$n = 6,$
„ „ deal		$n = 3.$

When these are compared, *not* with the numbers of Rankine's experiments but with the results calculated from Rankine's empirical formulae. There is a general agreement, but it does not seem to me sufficient to overcome the difficulties I feel with regard to the value chosen for b : see S. 29-39 of the book.

[650.] Scheffler makes the eccentricity of the load a function of the material, which it must be confessed is difficult to understand. Further the eccentricity is *not small* as compared with the linear dimensions of the cross-section. Supposing it were and the ends truly hemispherical, then we should have: $\tan \phi = \phi = \sin \phi = b/h$ and therefore,

$$\beta^{\frac{1}{2}}/h = \tan l/(2\beta^{\frac{1}{2}}),$$

or,

$$\cot \left(\frac{\pi}{2} \sqrt{\frac{p}{p_0}}\right) = \frac{2h}{l} \left(\frac{\pi}{2} \sqrt{\frac{p}{p_0}}\right).$$

Hence, if $d = 2h$ be the diameter and this be small as compared with l , we have after some approximations :

$$p = p_0 \left(1 - \frac{2d}{l}\right) \dots\dots\dots (viii).$$

This, however, gives as a rule far too large results, i.e. values of p which far exceed those given by Hodgkinson's experiments for *rupture*. Thus we cannot suppose the load applied close to the centre of the terminal cross section, if the eccentricity is to account for the observed differences.

We may, however, obtain what is, perhaps, theoretically a better formula than Scheffler's in the following manner. We do not know what function b is of the deflection, but as we attempt to centre the load, when the deflection is zero, we will assume the eccentricity b of the loading to be proportional to the deflection $(a-b)$, and thus

$$b = b_0 \left(1 - \frac{b}{a}\right)$$

For a very long strut b is insensible as compared with the deflection $(a-b)$ and therefore as compared with a . Hence b_0 is the value of b for a very long strut. The terminal section of such a strut, in whatever manner the load be distributed over it, cannot have any 'fibres' in tension, hence the limiting position of the load point must correspond to the neutral axis just touching the section. This would be the farthest distance of the load point from the centre, and would I think be not an unreasonable condition of things to assume as existing in a long strut just before the limiting stress is reached. In this case $h \times b_0 = \kappa$, and therefore $b = (\kappa^2/h)(1 - b/a)$. Using (iii) and (v) we have

$$1 - \cos \left(\frac{\pi}{2} \sqrt{\frac{p}{p_0}} \right) = \left(\frac{C}{p} - 1 \right) \cos \left(\frac{\pi}{2} \sqrt{\frac{p}{p_0}} \right),$$

whence
$$p/C = \cos \left(\frac{\pi}{2} \sqrt{\frac{p}{p_0}} \right) \quad (1x)$$

For a very short strut p_0 is immensely greater than p , or we have as we should expect $p = C$.

For a short strut in which p/p_0 is small we may expand the cosine and we have after some reductions

$$p = \frac{p_0 C}{p_0 + \frac{\pi^2}{8} C} \quad (2x)$$

This agrees very fairly with the Gordon Rankine formula—see our Art 469. For example that formula in our present notation gives

$$p = \frac{p_0 C}{p_0 - \frac{E}{nC} \pi^2 C},$$

where n is a certain constant empirically selected. For cast iron we have $E = 16,000,000$, $C = 80,000$ and $n = 1,600$ (according to Rankine), hence it follows $\frac{E}{nC} = \frac{1}{8}$. For wrought iron we have $\frac{1}{10}$ instead of $\frac{1}{8}$, and for timber (taking $E = 2,000,000$, say) about the same.

When p/p_0 is not small we must use (ix) as it stands, unless $p = p_0$ nearly. In this case p_0 must be small, i.e. l very large. Hence p/C is small, and putting $\sqrt{p/p_0} = 1 - x$ we find

$$\sin \frac{\pi x}{2} = p/C, \text{ or } x = \frac{2}{\pi} p/C.$$

Thus we deduce

$$p = \frac{p_0 C}{C + \frac{4}{\pi} p_0} \dots\dots\dots (xi),$$

which gives the correction on $p = p_0$ for a large value of l . Corresponding formulae for the cases of doubly-built-in and built-in pivoted struts are easily deduced.

[651.] On S. 43–58 Scheffler deals with a variety of cases in which the terminal loads on the strut are inclined to its central line as well as eccentric. His results are all fairly easy deductions from the ordinary theory, but some of them—e.g. those for rods under the action of three forces (S. 48–49)—are very interesting and would probably give accurate forms for metal ribbons under such loading. S. 58–73 deal with braced girders with parallel straight booms. The calculation of the stresses in the bracing bars would as a rule be now dealt with graphically. It is difficult to understand how any of the bracing bars in Fig. 28 can be in tension, yet I imagine the alternate ones ought to be. The whole investigation does not seem in the light of recent work

Scheffler points out that for bracing bars the length not more than 24 times the least diameter of the cross-section, but that for this ratio the buckling strength of wrought-iron struts is $\frac{2}{3}$ the compressive strength and therefore very nearly equal to the tensile strength. Hence for practical purposes the tensile strength can always be taken to determine the dimensions of a bar. As in most practical cases bracing bars are subject to alternate stress, this, if correct, would give the convenient rule that the dimensions are to be determined from the maximum load without regard to its sign.

[652.] Scheffler next endeavours to introduce the conception of slide into the theory of beams under flexure. This is done very much on the lines of Jouravski and Bresse: see our references Art. 582 (c). If x be the direction of the central axis of the beam, y perpendicular to the plane of flexure and z in that plane, this theory fails because it deals only with the shear \widehat{xy} and omits to consider the shear \widehat{yz} ; it likewise omits all consideration of \widehat{xy} . As Saint-Venant's great memoir

of 1854 had solved the problem, there is no need to enter into Scheffler's struggles of four years later date. It is characteristic of his method that the equality $\bar{x} = \bar{x}$ is announced as "die bemerkenswerthe That sache dass in jedem Punkte des Balkens die horizontalen und vertikalen Abscherungskräfte pro Flächeneinheit einander gleich sind" (S 79), and the discovery of this remarkable fact is attributed to Laissle and Schubler!

The discussion of the distribution of stress in a beam under flexure (S 82-92) is historically interesting as one of the early attempts in this direction, and is quite as accurate as those which are still to be found in several English textbooks.

On S 112-138 Scheffler returns to the influence of slide in beams under flexure. His results here seem to be entirely erroneous. Thus in the notation of our Art 83, he finds that for a rectangular cross section we must have

$$\mu \frac{d^2 u}{dz^2} + E \frac{d^2 u}{dx^2} = 0 \quad (\text{S } 120),$$

which equation leads to an absurdity when we combined it with the result of substituting the value of F from (18') in the first equation of (19') of the same article. I have not thought it worth while to follow out the whole of Scheffler's analysis. His first assumption that u is independent of y is at least one fruitful source of error.

[653] On S 95-109 we have a method described for dealing with the problem of continuous beams, or beams passing over several points of support and having only transverse loading in a vertical plane. The method depends upon certain fairly obvious relations between the position of the points of support, the points of inflexion, and the points of maximum or minimum curvature on the central axis. Scheffler obtains an easy geometrical construction for the points of maximum and minimum curvature in the case of a *uniformly loaded beam* (S 103), which might find its way into practical textbooks. For any general system of loading the graphical methods of Mohr, Culmann and Ritter or the application of Clapeyron's Theorem (see our Art 605) are, I think, superior to what is here suggested. Three pages (109-111) on the bending of a beam into a given shape present no novelty and seem of no practical interest.

A criticism of Scheffler's work by Grashof will be found in the *Zeitschrift des Vereins deutscher Ingenieure* Dritter Jahrgang, 1859, S 338-43. Grashof rejects Scheffler's theory of buckling and his treatment of braced bus (S 75-75). On the other hand he praises certain of the later portions of the work.

[654] H. Scheffler *Die Elastizitätsverhältnisse der Röhren welche einem hydrostatischen Drucke ausgesetzt sind insbesondere die Bestimmung der Wanddicke desselben. Eine für das Ingenieurwesen wichtige Erweiterung der Biegungstheorie* Wiesbaden, 1859,

S. 1-67. This is a reprint from the *Organ für die Fortschritte des Eisenbahnwesens* for 1859.

The memoir deals with a very important problem in hydraulics and gunnery, namely the strength of tubes subjected to internal pressure and the effect obtained by strengthening them by belts or bands of very inelastic metal. If the author's analysis could be trusted such belts while reducing the stress at certain points increase it at others. Accordingly, as he takes a stress limit instead of a stretch limit for safety, he concludes that such bands have in reality no strengthening effect. Whether they have or not is certainly not determined by the present memoir for the analysis is vitiated by errors of a most vital kind, so that I do not see any reason for supposing the results to be even approximately true.

[655.] The author begins by referring to the paper by Blakely (see Section III. of this Chapter). He then shews why certain empirical formulæ proposed by Barlow and Brix for the strength of an endless tube subjected to external and internal fluid pressure are erroneous. He next proceeds to deduce the formula of Lamé, which is curiously enough given quite correctly although the method of deducing it is entirely erroneous. With the notation of the footnote on our p. 79, he is really assuming:

$$\phi\phi = E \frac{u}{r} \quad \text{and} \quad \widehat{rr} = E \frac{du}{dr},$$

or in other words he puts the tractions equal to the stretches multiplied by the stretch-modulus although he is not dealing with a rod under pure traction. This error he repeats, when he considers a tube surrounded by rigid belts. Compared with this it is a small matter that he considers it justifiable to neglect the shear $\widehat{r\theta}$. The algebra is prodigious, but the results so pretty, that we might well wish them to be true, but the writer is hopelessly at sea in his physical conceptions of elasticity. His hypotheses lead in fact to

$$\widehat{\phi\phi} - \widehat{rr} = E \left(\frac{u}{r} - \frac{du}{dr} \right) = 2\mu \left(\frac{u}{r} - \frac{du}{dr} \right),$$

since he supposes symmetry round the axis of the cylindrical tube. Hence we are compelled to suppose $E=2\mu$, or du/dr a constant, both incompatible with other results of the investigation. The real solution for the case Scheffler proposes requires the two types of Bessel's functions of zero order, and then the conditions at a belt will tax the powers of a very first-rate analyst¹.

So far as the results of the earlier portions of the memoir are concerned, Saint-Venant has completed the subject in his paper of 1860:

¹ The 'indestructibility of error' is suggested by the fact that Virgile makes precisely the same mistakes five years later. See *Comptes rendus*, T. LX, 1865, p. 960.

see our Arts 120-2 The latter part of the memoir involves problems hitherto still unsolved, and of first-class importance for the theory of ordnance

[656] Eduard Zetzsche *Zur Bestimmung des Querschnitts eines Körpers dessen absolute Festigkeit in Anspruch genommen wird* Schumacher's Zeitschrift für Mathematik u Physik, Bd. IV, S 341-52 Leipzig, 1859 The author applies the theory of a uniform vertical prism under terminal traction to the case where there is not only terminal traction but also weight as a body-force He then investigates the proper form for a solid of equal resistance subject to terminal traction and gravitational body-force He does not notice that his method is one only of approximation, for in both his cases the cross-sections no longer remain plane, and in the first the sides of the prism no longer remain vertical see our Arts 1070* and 74

We indicate all the contents of this article which are of any value in the following remarks,—supposing that the stretch is uniform across each cross section,—which is obviously not the case

Let ω_0 = terminal cross section to which a traction P is applied, let ω = section at distance x from this terminal, $g\rho$ = weight of unit volume of the material, and s_x = stretch across any cross section, then by resolving vertically we have

$$\int_0^x g\rho\omega dx \pm P\omega_0 = \omega \times Es_x$$

For equal resistance Es_x must be a constant $= T$, the limit of safe elastic traction, therefore

$$\int_0^x g\rho\omega dx \pm P\omega_0 = \omega T \quad (1)$$

Or, differentiating,

$$g\rho\omega = Td\omega/dx,$$

$$\omega = Ce^{\beta x}, \text{ where } \beta = g\rho/T$$

But

$$x = 0, \quad \omega = \omega_0,$$

hence

$$\omega = \omega_0 e^{\beta x} \quad (11)$$

Now if $x=0$ in equation (1), $\omega = \omega_0$ and therefore we must have $P=T$, this is only possible if we take the positive sign, which is obviously a condition for the material being entirely in a condition of limiting traction Thus equation (11) gives us the area of the cross sections, and if we know their form we can determine the curve which by its revolution generates the form of the column of 'equal resistance'

[657] Gustav Zehfuss *Ueber die Festigkeit einer am Rande aufgelotheten kreisförmigen Platte* Schumacher's Zeitschrift für Mathematik u Physik Bd. V, S 14-24 Leipzig, 1860

This paper involves, S. 16–21, an investigation of the equation for the elastic equilibrium of a plate on the hypotheses proposed by Kirchhoff in 1852, i.e. the equation is not deduced from the general principles of elasticity. I do not think anything in this investigation calls for special notice, or is of any particular value. There is a statement at the commencement of the article which is not absolutely true, namely: that, when a body is strained beyond the elastic limits, its stretch-modulus varies with the strain. The stretch-modulus of a body may remain sensibly constant and practically equal to its original value nearly up to rupture: see pp. 441, 887, 889 of our Vol. I.

[658.] On S. 14–15 we have results of the following kind. If $K' = \lambda$, $K = \lambda + 2\mu$ of our notation, then

$$K = \frac{\epsilon^2 + \epsilon'^2}{\epsilon^3 - 2\epsilon'^3 - 3\epsilon\epsilon'^2}, \quad K' = \frac{\epsilon\epsilon' + \epsilon'^2}{\epsilon^3 - 2\epsilon'^3 - 3\epsilon\epsilon'^2},$$

where ϵ is the stretch produced by unit traction ($= 1/E$ of our notation), and $\epsilon' =$ the corresponding transverse squeeze ($= \eta/E$). These results had already been given by Cauchy in a somewhat different form.

[659.] S. 22–23 give the solution of the differential equation for a plate, supposing it to be uniformly loaded with a total load $\pi l^2 Q$, to l and to be built-in at its edge. The result since r from the centre is (see our Art. 398),

$$z = \frac{3}{16} \frac{Q}{h^3} \frac{K}{K^2 - K'^2} (l^2 - r^2)^2.$$

This gives for the stretches at the surface (see our Art. 398):

$$s = \frac{h}{2} \frac{d^2 z}{dr^2}.$$

Whence if s_0 be the safe stretch limit we have, to determine the proper thickness for a given load Q from:

$$h = l \sqrt{\frac{3}{4} \frac{Q}{s_0} \frac{K}{K^2 - K'^2}}.$$

This seems to me the proper condition of safety, but my numbers do not agree with those of Zehfuss. I do not think the remarks of his concluding paragraph are correct.

[660.] E. O. Winkler: *Die inneren Spannungen deformirter, insbesondere auf relative Festigkeit in Anspruch genommener Körper. Erbkams Zeitschrift für Bauwesen*, Jahrgang x., S. 93–108, 221–36, 365–80, Berlin, 1860.

The first part of this memoir only reproduces general results such as the body stress equations and the analysis of traction and shear given long before by Cauchy and Lamé. The republication at this date may have been serviceable in Germany considering the ignorance of the general theory of elasticity manifested by Scheffler and by Laissle and Schubler, but it has not historical importance.

[661] The second part of the memoir is entitled *Theorie der relativen Festigkeit*. Winkler takes as his elastic body that which would be generated by a plane closed figure whose centroid described a plane curve (*central line*) so that the plane of the figure was perpendicular to the plane of the curve, the form of the figure changing during the motion in any arbitrary manner. At any given section he takes for axis of x the tangent to the plane curve, which lies in the plane of xy and he supposes this plane to contain the direction of gravity and that of the load system.

He then says that the ordinary theory of flexure has neglected \widehat{yy} and \widehat{zz} or found erroneous values for them, and cites in this respect the researches of Poncelet, Scheffler, Laissle and Schubler. He further states that Scheffler, and Laissle and Schubler have attempted to take into account \widehat{yz} , but neglected \widehat{xy} and \widehat{xz} . He declares that in general all these stresses differ from zero, but remarks that \widehat{yz} will usually be quite negligible and proceeds to neglect it. He thus reduces his body-stress equations to the form

$$\begin{aligned}\frac{d\widehat{xx}}{dx} + \frac{d\widehat{xy}}{dy} + \frac{d\widehat{xz}}{dz} + X_0 &= 0, \\ \frac{d\widehat{xy}}{dx} + \frac{d\widehat{yy}}{dy} + Y_0 &= 0, \\ \frac{d\widehat{xz}}{dx} + \frac{d\widehat{yz}}{dz} &= 0\end{aligned}$$

He then writes down the body surface equations on the assumption that there is a uniform surface pressure p (S. 223). The equations thus obtained he cannot solve, and so he takes refuge in hypotheses almost as incorrect as those of the writers he has previously cited. He first assumes \widehat{xx} to have the same value for all points on a line in the cross section perpendicular to the load plane (or parallel to the axis of z). He further takes \widehat{xy} or the shear in the cross section parallel to the load plane uniform along the same line, although the breadth of the cross section changes continuously with the height (i.e. with y).

wie z. B. beim rechteckigen und kreisförmigen Querschnitt. Bei dem ersten unterliegt diese und die vorige Annahme überhaupt keinem Zweifel (S. 223).

It is perhaps needless to remind the reader that Saint Venant five years before the publication of this paper had shown that these hypotheses which 'admit no doubt' are absolutely untenable for the cross sections in question. Further for a thin rib Winkler takes \widehat{yz} constant

for the whole length of the rib—'In den übrigen Theilen kann natürlich die vorige Annahme beibehalten werden' (S. 223).

[662.] It is needless to follow Winkler's analysis further. It seems to me that the modifications he introduces into the Bernoulli-Eulerian theory do not tend to correct it in the case in which the cross-sections are incapable of treatment by Saint-Venant's method (T and I cross-sections etc), while when the cross-sections fall under the cases treated by Saint-Venant the true theory is not a bit more complex than Winkler's lengthy process (see our Arts. 87-98). As for the case in which central line is not a straight line and the cross-section varies, I doubt whether he has found even an approach to an approximate solution.

[663.] The second part of the memoir discusses principal tractions and applies them to the theory of rupture. The work is inferior to what had been done several times previously and takes a tractive and not a stretch limit of strength (S. 229-30). Winkler applies this discussion of traction to several examples (S. 230-3) and concludes this part by the consideration of the effect of a rapidly moving load on the deflection of a girder or beam. Here he has to return to the Bernoulli-Eulerian theory for a solution. He considers first an isolated load.

His reasoning in this case is the following. Suppose M the mass of the moving load, ρ the radius of curvature of the central line of the beam under the load supposed at the centre, v the velocity of the load, l the length and m the mass of the beam. Then there is a centrifugal force Mv^2/ρ acting downward and consequently the central reaction R is given by:

$$R = \frac{1}{2} \left(Mg + mg + \frac{Mv^2}{\rho} \right) \dots \dots \dots (i).$$

But the bending moment at the centre or

$$\begin{aligned} E\omega\kappa^2/\rho &= \frac{1}{2}Rl - \frac{1}{8}mgl \\ &= \frac{1}{8}mgl + \frac{1}{4}Mgl + \frac{1}{4}\frac{Mlv^2}{E\omega\kappa^2} \frac{E\omega\kappa^2}{\rho}, \end{aligned}$$

whence

$$E\omega\kappa^2/\rho = \left(\frac{1}{8}mgl + \frac{1}{4}Mgl \right) \left(1 + \frac{1}{4}\frac{Mlv^2}{E\omega\kappa^2} \right), \text{ approximately } \dots \dots (ii),$$

since $\frac{Mlv^2}{E\omega\kappa^2}$ is very small.

R can then be found from (i), and Winkler gives for the approximate central deflection¹

$$f = \frac{5}{32} \frac{mgl^4}{E\omega\kappa^2} + \frac{1}{4} \frac{Mgl^4}{E\omega\kappa^2} \left\{ 1 + \frac{1}{4} \frac{v^2}{E\omega\kappa^2} (M + \frac{1}{2}m)l \right\}.$$

¹ Winkler has $\frac{5}{32}$ and $\frac{1}{8}$ for the numerical coefficients, but I presume these to be misprints for $\frac{5}{32}$ and $\frac{1}{4}$.

These results shew that Winkler was quite unaware of the labour of Stokes and Phillips (see our Arts 1276*-91* and 372-7, 552—to say nothing of Homersham Cox, who had proceeded on these lines, with the like inexact results see our Art 1433* He concludes

Wirkliche numerische Berechnungen zeigen, dass selbst bei bedeutend Lasten und sehr grossen Geschwindigkeiten die Vermehrung der Beanspruchung nur ausserst gering ist (S 234)

This is hardly however experimentally confirmed see our Art 1418*, 1420* and 1375*

[664] The last section of the second part (S 234-6) is entitled *Einfluss eines bewegten Zuges* It deals with what we have termed Bresse's problem (see our Arts 382 and 540), and presents no novelty Winkler's results agree with those previously obtained by Bresse, but he does not refer to him Some numerical calculations are given to show that the increment of bending moment and deflection due to the velocity of the load are very small

[665] In the third and last part of his memoir, Winkler applies the formulae of his second part to various special cases Thus he finds (S 365) for a cantilever of rectangular cross section ($h \times b$) under bending moment M and total shear Q that

$$\overline{xx} = \frac{12My}{bh^3}, \quad \overline{xz} = 0, \quad \overline{xy} = \frac{3}{2}Q \frac{h^2 - 4y^2}{bh^3}$$

Comparing these with Saint-Venant's results (Art 95) we see that they are incorrect

I have again no confidence in the results Winkler gives for beams with varying cross sections or with Γ sections Thus I think the paper failed in achieving the purpose proposed by its author

[666] In conjunction with Winkler's attempt to solve an already solved problem I may briefly refer to the following somewhat later memoir in this place

George Biddell Airy *On the Strains in the Interior of Beams* *Phil Trans* 1863, pp 49-80 This memoir was received on November 6 and read December 11, 1862 By 'strains' the late Astronomer Royal here understands what we now term stresses Having regard to the full and able treatment of the flexure of rectangular beams by Saint-Venant in his memoir on flexure of 1854 (see our Art 69) it seems unnecessary to analyse this paper at any length It may suffice to remark in this place that a solid rectangular beam cannot be considered as built up of a number of parallel plates, still less can the stresses be expanded in integer powers of x and y (Cartesian coordinates in the cross

section) in the manner adopted by Airy in § 14. The tables and diagrams of the memoir cannot be considered of value, but fortunately the plaster models and tabulated numbers of Saint-Venant effectually accomplish the objects Airy had in view when writing the paper.

667. C. Neumann: *Zur Theorie der Elasticität. Journal für Mathematik*, Vol. 57, S. 281–318, Berlin, 1860.

The object of this memoir is not to add anything to the theory of elasticity, but to obtain the fundamental equations of elasticity in a new way. The memoir consists of two parts: in the first the ordinary equations referred to rectangular axes are obtained; in the second these are transformed so as to give the equations referred to a system of triple orthogonal surfaces, which were first investigated by Lamé.

The first paragraph of the memoir explains its object:—

Es existiren bekanntlich zwei Methoden, um die für das Gleichgewicht und die Bewegung eines elastischen Körpers geltenden Differential-Gleichungen abzuleiten, von denen die eine von Navier, die andere von Poisson herrührt. Die erste geht von der Berechnung der Kraft aus, welche ein einzelnes Molecül des Körpers von allen übrigen Molecülen empfängt, die zweite von der Berechnung des Druckes, welchen ein Flächen-Element im Innern des Körpers erleidet. Im vorliegenden Aufsatze gebe ich eine dritte Methode zur Ableitung ich bestimme zuerst das Potential der auf ein Molecül von allen übrigen Molecülen ausgeübten Wirkung; dann berechne ich für das Potential aller, im ganzen Körper stattfindenden, Molecular-Wirkungen zusammengenommen ein dreifaches, über den Raum des Körpers ausgedehntes, Integral; und gelange dann durch Variation dieses Integrals—in ähnlicher Weise also wie Gauss in der Theorie der Capillarität—zu den Bedingungs-Gleichungen, welche erfüllt sein müssen, wenn sich der elastische Körper unter der Einwirkung ausserer Kräfte im Gleichgewicht befinden soll.

The memoir is a fine piece of mathematical analysis¹.

[668.] Neumann supposes his material homogeneous and isotropic. Further he assumes uni-constant isotropy or he uses only one *elastic* constant in his results (Poisson's k = our λ). He

¹ The following misprints may be noted:

On S. 285 observe that Neumann assumes the result in Moigno's *Statique*, p. 703. S. 294, at the top, for the first K read H . S. 297, equation (26): for $2u_1 + \Theta$ read $2u_1 + \Theta$. S. 315, in (55): for $\frac{1}{a}, \frac{1}{b}, \frac{1}{c}$, read in each case $\frac{1}{abc}$.

starts indeed from the assumption that intermolecular force is a function only of the individual molecular distance thus he neglects *aspect* and *modified action*. The second constant K which appears in his results is not an elastic constant, but an initial stress equivalent to the \bar{x}_0 of our Art 616* (see second set of formulae on our p 329). The following remark shows how it arises and why its value is taken to be the same in all directions

Während der primitiven Lage sollen die Molecule gleichförmig und ohne Bevorzugung irgend welcher Richtungen durch den Raum hin vertheilt gewesen sein. Ob damals Gleichgewicht herrschte, oder ob es ausserein Käfte bedurft hatte, um die Molecule während jener Lage festzuhalten, mag dahin gestellt bleiben (S 282)

[669] Neumann's work, as an investigation on the grounds of uni-constant isotropy, is extremely good,—only alas! such an investigation has not much practical value now that more and more bodies are observed to be aeolotropic. Perhaps the part which will best repay study is the method by which he surmounts the difficulties attaching to the expression of the surface-forces in terms of the strains, when we cannot sum over the whole of a sphere of molecular action. These difficulties had been noticed by Jellett see our Arts 1532*–3*, but Neumann, I think, surmounts them and shows that surface-forces can be really expressed in terms of elastic constants having the same values as at points of the body remote from the surface (S 289–92)

[670] It will not be without interest to compare Neumann's and Sir W Thomson's methods of reaching the general equations of elasticity

Let $2mF$ be the potential of the molecular forces on the molecule m , or the total influence of all the other molecules on m . Then Neumann's results on S 292–3 are, I believe, really perfectly general and have no relation to any particular law of molecular force, or to any magnitude of strain. We may state them in the language and notation of the present work as follows. Let $u_x, u_y, u_z, v_x, v_y, v_z, w_x, w_y, w_z$ represent the nine first fluxions of the shifts, u, v, w , the initial density, $1/\nabla$ the determinant

$$\begin{vmatrix} 1+u & u_x & u_y & u_z \\ v & 1+v_x & v_y & v_z \\ w & w_x & 1+w_y & w_z \end{vmatrix},$$

* The total potential energy of the system = $\Sigma 2mF = \Sigma mF$ or $F = u$ the work of the elastic strain per unit mass of the body at m

Let Q_x be the x component of the force necessary to hold the molecule in equilibrium when it lies within the volume of the body, and P_x the corresponding component when the molecule is near the surface of the body, then if n be the direction of the normal to the surface measured outwards and \overline{nx} , \overline{ny} , \overline{nz} the angles it makes with the axes, we have:

$$\left. \begin{aligned} Q_x &= \frac{d}{dx} \left(\frac{dF}{du_x} \right) + \frac{d}{dy} \left(\frac{dF}{du_y} \right) + \frac{d}{dz} \left(\frac{dF}{du_z} \right), \\ P_x &= \rho_0 (A_x \cos \overline{nx} + A_y \cos \overline{ny} + A_z \cos \overline{nz}) \end{aligned} \right\} \dots\dots\dots (i),$$

here

$$\left. \begin{aligned} A_x &= \left(\frac{dF}{du_x} (1 + u_x) + \frac{dF}{du_y} u_y + \frac{dF}{du_z} u_z \right) \nabla, \\ A_y &= \left(\frac{dF}{du_x} v_x + \frac{dF}{du_y} (1 + v_y) + \frac{dF}{du_z} v_z \right) \nabla, \\ A_z &= \left(\frac{dF}{du_x} w_x + \frac{dF}{du_y} w_y + \frac{dF}{du_z} (1 + w_z) \right) \nabla \end{aligned} \right\} \dots\dots\dots (ii).$$

Similar values hold for Q_y , Q_z and for P_y , P_z in terms of the corresponding quantities B_x , B_y , B_z , C_x , C_y , C_z , obtained from (ii) by cyclical interchanges. These results are deduced by assuming F a function of the first nine shift fluxions and applying the method of virtual moments.

It must be noted that Q_x is the *force per unit of mass* of the material at the point $x + u$, $y + v$, $z + w$, while P_x is the force per unit area of the surface of the material. In the course of his work Neumann shows that if ξ , η , ζ be the displaced coordinates of the point x , y , $z = x + u$, $y + v$, $z + w$) then:

$$Q_x = \frac{1}{\nabla} \left(\frac{dA_x}{d\xi} + \frac{dA_y}{d\eta} + \frac{dA_z}{d\zeta} \right) \dots\dots\dots (iii).$$

A_x , A_y , A_z are what are generally termed
face perpendicular to the axis of x .
under what conditions we shall have

— y — z —

[671.] Sir W. Thomson (*Phil. Trans.* 1863, p. 610, or Thomson and Tait's *Natural Philosophy*, Second Edition, Part II. p. 462) takes the work w a function of the six quantities $2\epsilon_x$, $2\epsilon_y$, $2\epsilon_z$, $2\eta_{yz}$, $2\eta_{zx}$, $2\eta_{xy}$ of our Art. 1619* which he represents by $A - 1$, $B - 1$, $C - 1$, a , b , c respectively. He deduces the general equations for the equilibrium of a body under no body-forces and finds they are of the type

$$\frac{dA'_x}{dx} + \frac{dA'_y}{dy} + \frac{dA'_z}{dz} = 0 \dots\dots\dots (iv),$$

here

$$A'_x = 2 \frac{dw}{dA} (u_x + 1) + \frac{dw}{dc} u_y + \frac{dw}{db} u_z$$

$= \frac{dF}{d\epsilon_x} (1 + u_x) + \frac{dF}{d\eta_{xy}} u_y + \frac{dF}{d\eta_{xz}} u_z$ in our notation,

$$\begin{aligned}
&= \frac{dF}{d\epsilon_x} \frac{d\epsilon_x}{du_x} + \frac{dF}{d\eta_{xy}} \frac{d\eta_{xy}}{du_x} + \frac{dF}{d\eta_{xz}} \frac{d\eta_{xz}}{du_x} \\
&= \frac{dF}{du_x}
\end{aligned}$$

Thus Thomson's equation given as (iv) above becomes

$$\frac{d}{dx} \left(\frac{dF}{du_x} \right) + \frac{d}{dy} \left(\frac{dF}{du_y} \right) + \frac{d}{dz} \left(\frac{dF}{du_z} \right) = 0,$$

and is only a special case of Neumann's (1) cited in our previous article

It seems more symmetrical and concise to write the quantities A'_x, A'_y, B'_x, B'_y , as $dF/du_x, dF/du_y, dF/dv_x, dF/dv_y$, as Neumann has done. We must be careful to note that these expressions (A'_x) are not the stresses, except for very small strains when

$$A_x = \frac{dF}{du_x} = A'_x$$

$$\begin{aligned}
\text{Generally} \quad & \left. \begin{aligned} A_x &= (1 + u_x) A'_x + u_y A'_y + u_z A'_z, \\ A_y &= v_x A'_x + (1 + v_y) A'_y + v_z A'_z, \end{aligned} \right\} \quad (\text{v}),
\end{aligned}$$

whence we can at once express the stresses in Thomson's notation

I believe that Neumann was the first to give these generalised equations and the generalised expressions for stress

[672] Supposing the strain to be small and in particular unconstant isotropy to hold, Neumann shows (p 285) that we may express F by

$$\begin{aligned}
2F &= H + 2K\theta + (K + 3k)\theta^2 + (K + k)T + (2K + 4k)V, \\
\text{where } \theta &= u_x + v_y + w_z, \\
T &= (v_x - w_y)^2 + (w_x - u_z)^2 + (u_y - v_z)^2 \\
&= 4\tau^2 \text{ if } \tau \text{ be the resultant twist,} \\
V &= (v_z w_y - v_y w_z) + (w_x u_z - w_z u_x) + (u_y v_x - u_x v_y)
\end{aligned} \quad \left. \vphantom{\begin{aligned} 2F &= H + 2K\theta + (K + 3k)\theta^2 + (K + k)T + (2K + 4k)V, \\ \theta &= u_x + v_y + w_z, \\ T &= (v_x - w_y)^2 + (w_x - u_z)^2 + (u_y - v_z)^2 \\ &= 4\tau^2 \text{ if } \tau \text{ be the resultant twist,} \\ V &= (v_z w_y - v_y w_z) + (w_x u_z - w_z u_x) + (u_y v_x - u_x v_y) \end{aligned}} \right\} \quad (\text{vi}),$$

and H, K, k are constants depending on the molecular summations. The value of K is physically explained at once as the value of the stress A_x (or B_y or C_z) when the strains are all zero.

Writing $\phi = F + KV$, and neglecting squares of small quantities, we may put as types

$$\begin{aligned}
Q_x &= \frac{d}{dx} \left(\frac{d\phi}{du_x} \right) + \frac{d}{dy} \left(\frac{d\phi}{du_y} \right) + \frac{d}{dz} \left(\frac{d\phi}{du_z} \right), \\
P_x &= \rho_0 \left\{ \frac{d\phi}{du_x} \cos \overline{nx} + \frac{d\phi}{du_y} \cos \overline{ny} + \frac{d\phi}{du_z} \cos \overline{nz} \right\} \quad (\text{vii}),
\end{aligned}$$

whence the ordinary unconstant equations of elasticity can be at once deduced

[673] The *Zweiter Abschnitt* of Neumann's memoir is occupied by a transformation of the equations and results given above

o an-orthogonal, and ultimately as a limitation to orthogonal curvilinear coordinates. The deduction of the equations in curvilinear coordinates is hardly likely to be a short process. Neumann's possesses an elegance which can hardly be postulated of Lamé's original investigation, but at the same time the latter part of it requires considerable modification, if it is to be adapted to bi-constant isotropy. We have already referred to Bonnet's investigation of the uni-constant curvilinear equations (see our Art. 1241*), and we shall have occasion to refer to others, *e.g.* that of Borchardt in Crelle's *Journal der Mathematik*, Bd. 76, S. 45-58, 1873.

[674.] E. Phillips: *Mémoire sur le spiral réglant des chronomètres et des montres*. *Journal de Mathématiques*, Deuxième Série, T. v., pp. 313-366. Paris, 1860. This memoir¹ was presented to the Academy and was favourably reported on by Lamé, Mathieu and Delaunay on May 28, 1860.

Phillips introduces his memoir with the following remarks :

Quelque important que soit le régulateur dont il s'agit, sa théorie n'avait pas encore été établie, la forme essentiellement complexe de ce ressort introduisant dans l'application de la théorie de l'élasticité des équations différentielles tellement compliquées, qu'il serait absolument impossible de les intégrer. J'ai pourtant été assez heureux, par des raisons particulières, pour vaincre ces difficultés dans tout ce qui se rapporte au problème, et c'est cette théorie qui fait l'objet de ce Mémoire (p. 314).

Phillips, as in his memoir on railway-springs, adopts the Bernoulli-Eulerian theory of flexure; that is to say he puts the bending moment equal to the product of the flexural rigidity ($E\omega\kappa^2$) and the change in curvature. He thus supposes the flexure to take place without slide. Of this assumption he writes :

Je me hâte d'observer que, dans une Note placée à la fin du Mémoire que j'ai présenté à l'Académie des Sciences, je démontre que, dans le problème actuel, ce principe est une conséquence rigoureuse de la théorie mathématique de l'élasticité (p. 315).

The note referred to is printed in an extended version of the memoir published in the *Annales des mines*: see our Arts. 677-8.

¹ As an earlier research in this direction I may refer to G. Atwood: *Investigations, founded on the Theory of Motion, for determining the Times of Vibration of Watch Balances*. *Phil. Trans.*, 1794, p. 119.

Let G be the couple, X, Y the components of force applied to one end of the spiral spring taken as origin of coordinates. Let $1/\rho - 1/\rho_0$ be the change in curvature due to strain at the point x, y of the spring. Then we easily see that we must have on the Bernoulli Eulerian hypothesis

$$E\omega\kappa^2\left(\frac{1}{\rho} - \frac{1}{\rho_0}\right) = G + Yx - Xy \quad (1)$$

Suppose l the length of the spiral, then integrating equation (1) along the length we easily find

$$E\omega\kappa^2(\phi - \phi_0) = Gl + l(Y\bar{x} - X\bar{y}) \quad (11),$$

where $\phi - \phi_0$ is the angle between the new and old positions of the tangent at the force end of the spring, and \bar{x}, \bar{y} are the coordinates of the centroid of the spiral. If the force end of the spiral be fixed at a constant angle to the balance of the watch attached to the spring, $\phi - \phi_0$ is the angle through which the balance has turned. Hence if we can put $Y\bar{x} - X\bar{y} = 0$, we have the couple $G = E\omega\kappa^2(\phi - \phi_0)/l$, or it is proportional to the angle through which the balance has turned. Isochronism thus follows.

Phillips investigates at some length the conditions under which we may put $Y\bar{x} - X\bar{y} = 0$, for example it would obviously be satisfied if the spiral so moved that its centroid remained at the fixed end of the spring. He also deals with a number of problems bearing on watch and chronometer springs which have, however, more interest for the historian of mechanics than for the historian of elasticity.

[675] On pp 352—4 an expression is deduced for the strain energy of the spiral or the work required to displace its normal at the 'balance' end through any given angle. If s, s_0 be the stretches in the spiral, then the work needful to carry it from the one state of strain to the other is $EV(s^2 - s_0^2)/6$, where V is the volume. This is an illustration of Young's theorem in resilience, see p 875 of Vol I and our Arts 1384*, 493 and 609.

[676] E Phillips *Mémoire sur le spiral réglant des chronomètres et des montres Annales des mines*, Tome XX, pp 1—107 Paris, 1861. This is the completed form of the memoir recommended by a Commission of the Academy for publication in the *Recueil des savants étrangers*. We have already referred to the portion published in Liouville's *Journal* see our Art 674, and touched on those parts more closely associated with the theory of elasticity. There is a good deal of additional matter here of a very interesting kind, thus the influence on isochronism of temperature and of friction in the balance are taken into account, and a considerable number of curves which are theoretically suitable forms for the terminal of the spiral are given. By aid of these the

centre of gravity of the spiral may be retained in the axis of the balance, one of the conditions for its efficient working. *Chapitre II.* entitled: *Des expériences faites à l'appui de la théorie précédente* (pp. 76-95) is remarkably interesting; it gives a very considerable number of experiments on the isochronism of spirals with or without terminals curved to the theoretical forms. The memoir is an excellent example of a high standard of theoretical knowledge applied to an important practical problem.

[677.] To the memoir as it stands in the *Annales* is attached a *Note* entitled: *Pour faire voir que, dans les circonstances que présente le problème actuel, les principes sur lesquels est fondée sa solution et qui rentrent dans la théorie de l'axe neutre, sont non-seulement parfaitement d'accord avec l'expérience, mais avec la théorie mathématique de l'élasticité* (pp. 95-107). Phillips remarks in a footnote that his demonstration is an extension of that which Saint-Venant has applied to the strain of a straight rod bent by a couple: see the *Leçons de Navier*, p. 34 and our Art. 170. It somewhat resembles the general treatment of the rod problem due to Kirchhoff: see our Chapter XII.

The assumptions made by Phillips in his theory of the spiral spring are that, when a couple is applied to its terminal the strain is such that: 1° all the points primitively in a cross-section remain in the same cross-section and that the strained cross-section remains perpendicular to the central line, 2° the central line remains unstretched. It is obvious that these are the ordinary assumptions of the Bernoulli-Eulerian theory extended to rods with an initially curved central axis. The problem is how far are they true for a spiral acted upon by a couple. Let us assume them to be true and investigate the resulting shifts and consequent stresses. In addition to 1° and 2° above Phillips makes the further assumptions involved in the following remarks:

J'appelle ligne neutre le lieu géométrique des centres de gravité de toutes les sections transversales, ce lieu étant une courbe quelconque, mais que je suppose plane, en négligeant, pour le spiral cylindrique, la très-faible inclinaison des spires. J'admets que toutes les sections transversales sont égales et qu'elles sont partagées symétriquement par un plan, que j'appellerai plan horizontal, passant par la ligne neutre.

J'imagine que sans changer la longueur de la ligne neutre, et tout en satisfaisant aux conditions de position et d'inclinaison assignées à ses deux extrémités, on déforme celle-ci dans son plan, d'après la

loi $1/\rho - 1/\rho_0 = \text{constante}$, ρ_0 et ρ étant les rayons de courbure en un quelconque de ses points le premier avant la déformation et le second après. On a vu précédemment qu'il est possible de satisfaire géométriquement à cette condition en donnant aux courbes extrêmes une forme déterminée (pp 95-6)

[678] At any point O of the central line let its tangent be taken as axis of x , its normal as axis of z and the axis of y perpendicular to the horizontal plane containing these and defined above. Let u, v, w be the shifts parallel to these axes of a point P on a cross section, infinitely near to that through O , and u_0, v_0, w_0 the shifts of the centroid of this latter cross section. Then Phillips shows by easy geometrical analysis that we must have

$$u = xz (1/\rho - 1/\rho_0), \quad v = v_0, \quad w = w_0 - \frac{1}{2}x^2 (1/\rho - 1/\rho_0)$$

To determine v_0 and w_0 he assumes that the three stresses \widehat{yy} , \widehat{zz} and \widehat{yz} are zero as in Saint-Venant's theory of flexure see our Art 77. This leads him to the values

$$v_0 = -\eta yz (1/\rho - 1/\rho_0), \quad w_0 = \frac{1}{2}\eta (y^2 - z^2) (1/\rho - 1/\rho_0)$$

The values of u, v, w are now completely known. They will be found 1° to satisfy the body shift equations, 2° to give \widehat{xz} and \widehat{yz} zero values, and make

$$\widehat{xx} = Ez (1/\rho - 1/\rho_0)$$

Hence obviously if the neutral axis goes through the centroid of each cross section, there will be a zero total traction and the total system of stress over a cross section will be represented by the couple, i.e. the bending moment

$$E\omega\kappa^2 (1/\rho - 1/\rho_0),$$

which is constant since $(1/\rho - 1/\rho_0)$ is assumed constant. Further the surface stress equations are satisfied at every point. Thus if the force given by $Ez (1/\rho - 1/\rho_0) d\omega$ be applied to each element $d\omega$ of the cross sections which bound a small portion of the spiral, this portion will be in elastic equilibrium, but since the cross sections remain *plane* any number of such portions can be put together, and it is only necessary to apply such forces to the terminal cross sections of any length of spiral. Thus by the principle of the elastic equipollence of statically equivalent loads (see our Arts 8-9, 21 and 100) we see that Phillips' solution on the basis of the Bernoulli-Eulerian theory is really rigid on the complete mathematical theory, provided the terminals of his spiral are acted upon by couples of the magnitude

$$E\omega\kappa (1/\rho - 1/\rho_0) \quad (\text{pp 106-7})$$

[679] It will be noted that the above investigation is in no wise dependent on the central line being initially a spiral. It would seem that the above values of the shifts would apply to a rod with its central line in the form of any plane curve whatever,

when its terminals were acted upon by equal and opposite couples. Their effect is to produce a constant change of curvature, and the Bernoulli-Eulerian theory is rigidly true.

[680.] Another interesting memoir by Phillips may be not unfitly considered here, although it belongs to a somewhat later date. It is entitled: *Solution de divers problèmes de Mécanique, dans lesquels les conditions imposées aux extrémités des corps, au lieu d'être invariables, sont des fonctions données du temps, et où l'on tient compte de l'inertie de toutes les parties du système*, *Journal de Mathématiques*, Tome IX., pp. 25–83. Paris, 1864. This interesting paper unfolds a valuable method for the treatment of various mechanical problems involving the longitudinal and transverse vibrations of rods. The author deals with the solution of problems in which the *shift at one end of the rod is a given function of the time*, or in which the rod itself, subject to a given system of load, is moving in space. The value of such solutions lies in their application to the stresses in various moving portions of machines. The mode of solution adopted is the determination of the special arbitrary functions involved in the general solution $u = F(x + at) + f(x - at)$.

[681.] The memoir is divided into two chapters: the first deals with the following problems:

Problem (i). *To determine the relative shifts of the parts of a rod, one end of which is subjected to a given motion, and the other is free when each point of the rod moves parallel to its axis* (pp. 25–38). Phillips treats in detail the cases when the motion imposed on the end is uniformly accelerated ($u_0 = \frac{1}{2}ft^2$), p. 29, and when it is harmonic ($u_0 = \alpha - \alpha \cos at$), p. 35.

Problem (ii). *To find the stresses in AB a connecting rod, AC and BD being two parallel revolving cranks of equal length r and having a spin ω . The section, length and weight of the connecting rod are given and the constant resistance Q is supposed to be applied at B tangentially to the circumference of BD.* (pp. 38–45.)

Problem (iii). *To find the stresses in a rod one end of which is subjected to a harmonic motion, while the other is attached to a piston under the action of steam.* (pp. 45–55.)

Phillips to simplify matters replaces the compound harmonic

action of the steam, by a single harmonic term of the same period but of different phase from the harmonic motion of the other terminal (difference equal to $\pi/4$) He supposes this to represent simply and approximately the mean action of the steam

Problem (iv) *A crank OM turns uniformly round O, which is fixed. A force, for example that of steam, acts upon the extremity M in a constant direction MC. The law of this force being given by a harmonic term of the same period as the rotation, to determine the strain in the crank* (pp 55-61)

Problem (v) *One end of a cord being fixed and the other caused to vibrate ' ' ' ' with harmonic motion, it is required to find the transverse vibrations of the string* (pp 61-65)

This is the case for example of a string one end of which is fixed to a massive tuning-fork set vibrating harmonically

The following two problems (vi) and (vii) treat the same string when *both* ends are caused to vibrate in a certain manner,—not however the most general possible

[682] In the second chapter Phillips adopts the solution in Fourier's series of the partial differential equation for the longitudinal vibrations of rods, but he first breaks up his shift u into two components

$$u = u_1 + U$$

and chooses u_1 in such a manner that it causes the terms resulting from the special terminal conditions, which are functions of the time, to disappear from his equations, U will then be found by the ordinary methods for evaluating the coefficients of Fourier's series

Thus in his Problems (i) to (iii) (pp 71-79) Phillips verifies results of his first chapter. In his last Problem (iv), however, he passes to somewhat different considerations. He makes use of Poisson's solution for the transverse vibrations of a rod to solve the following problem

The two terminals of a connecting rod receive the same harmonic motion perpendicular to its length. It is required to find the strain (pp 80-3)

Analytically this amounts to solving the equation

$$\frac{d^2 u}{dt^2} = -k^2 \frac{d^4 u}{dx^4} \quad (1),$$

subject to the conditions :

$$u = r \sin \omega t, \quad d^2 u / dx^2 = 0 \text{ when } \left\{ \begin{smallmatrix} x=0 \\ x=l \end{smallmatrix} \right\} \dots\dots\dots(\text{ii}).$$

In addition Phillips supposes that initially, or for $t = 0$,

$$u = 0, \quad du/dt = \omega r \text{ for all points from } x = 0 \text{ to } x = z \dots(\text{iii}).$$

The form of the special integral, which removes the time terms from the terminal conditions, is easily found to be

$$u_1 = \{A_1 \sin(\sqrt{\omega/k} x) + B_1 \cos(\sqrt{\omega/k} x) + C_1 \sinh(\sqrt{\omega/k} x) + D_1 \cosh(\sqrt{\omega/k} x)\} \sin \omega t.$$

Thus if, $u = u_1 + U$ we easily find U by Poisson's process (see our Art. 468*), while A_1 , B_1 , C_1 , D_1 are determined from the four equations (ii). Equations (iii) give the constants of Poisson's solution.

SECTION II.

Physical Memoirs including those of Kupffer, Wertheim and others.

GROUP A.

Memoirs on the correlation of Elasticity to the other physical properties of bodies.

[683.] A. J. Ångström: *Om de monoklinoedriska kristallernas molekulära konstanter. Kongl. Vetenskaps-Akademiens Handlingar för år 1850, Sednare Afdelningen*, Vol. 38, pp. 425-61, Stockholm, 1851. This memoir¹ was presented on March 7, 1851. It is an important contribution to a subject still very obscure, notwithstanding the investigations of Plücker, Sénarmont, Wiedemann and Ångström: see the references in our Chapter XII., Section I. Its topic is the exact nature of the relation between the various axes of a crystal—the axes of figure, of elasticity, of electrical conductivity, the thermal, the optic, and the magnetic axes. French and German translations of parts of Ångström's paper

¹ There is an earlier memoir by Ångström in the Upsala memoirs of the previous year, which I have not examined. It belongs to the theory of light, and endeavours to show that the optical properties of gypsum and of crystals of the monoclinohedric system can only be explained by supposing the elasticity of the ether has relation to a system of oblique axes.

will be found in the *Annales de Chimie*, T 38, pp 119–127, 1853, (by Verdet) and *Poggendorffs Annalen der Physik*, Bd 86, pp 206–237, 1852

[684] Neumann's identification of the principal crystalline axes had been, at least for certain types of crystals, discovered in later researches to be inaccurate see our Arts 788*–793* and Chapter XII, Section I Ångström's investigations with regard to gypsum are some of the most important in this direction

Detta studium bör dessutom för de kliniska kristallerna blifva så mycket mera fruktbarande, som hos dessa ett nytt bestämnings-element framträder, nämligen den olika riktningen af de principala elasticitetsaxlarna (p 427)

[685] The first section of the memoir is occupied with the determination of the optic axes of gypsum (pp 428–38) Ångström shows like Neumann in his later work, that the optical axes of elasticity are not fixed but vary with the temperature and the colour of the light see our Chapter XII, Section I

The second section of the memoir (pp 438–49) is entitled *Klangfigurer hos gipsen* and investigates the axes of acoustic symmetry by means of Chladni's figures The theory of the nodal lines for a substance of the elastic complexity of gypsum has not I think been worked out, Ångström takes rather arbitrary curves to represent the lines, although very possibly they give close enough approximations to the acoustic axes

The third section of the memoir (pp 449–51) is entitled *I förhållande till värmet* This confirms in part Sénarmont's results, but the author believes that the isothermals change with change of temperature

Ännu försöken teckna ut all den noggrannhet man kunde önska, tror sig dock författaren kunna sluta, att isothermerna i det symmetriska planet hos gipsen verkligen förändra ligen med temperaturen, och att denna förändring sker åt samma led och är tillika af ungefärligen samma storlek som de optiska elasticitetsaxlarnas förändring vid en lika temperaturförändring (p 451)

The fourth section entitled *Gipsens utvidgning genom värme* (pp 451–3) cites Neumann's results and determines the absolute extension of gypsum It shows that there is a direction in which gypsum apparently shrinks with increasing temperature (p 453)

The fifth section entitled *Gipsens hårdhet* (pp 453–5) cites

Frankenheim's results: see our Art. 825*. Ångström's results in part confirm, in part modify Frankenheim's. Those of Franz he rejects as unsatisfactory: see our Art. 839.

The sixth section is entitled: *Gipsens förhållande till elektricitet och magnetism* (pp. 455–6) and cites the results of Plücker, Wiedemann etc.: see our Chapter XII., Section I. Ångström's researches confirm Wiedemann's for electricity, but he could not confirm Plücker's for magnetism.

In the seventh section (pp. 457–8) we have a *résumé* of the results¹ for axes of all kinds:

Sammanföras de resultater, vi i det föregående erhållit, bekommer man följande öfversigt af de olika axelsystemernas läge i det symmetriska planet, hvarvid α betecknar lutningen emellan den *fibrösa* genomgången och den axeln, som faller inom de båda genomgångarnes spetsiga vinkel:

	α
Optiska axlarnes medellinie	14°
Minsta utvidgningen för värme	12°
Största hårdheten omkring.....	14°
Magnetisk attraktion omkring	14°
Största ledningsförmågan för värmets	50°
Största elasticitets axeln i akustiskt hänseende.....	53°
Minsta ledningsförmågan för elektricitet	62°

It will thus be seen that these axes group themselves in two distinct sets which probably connotes some inter-relation of the corresponding physical quantities. Ångström makes some not very conclusive remarks on the reason for these groupings (pp. 457–8).

[686.] Section VIII. is devoted to felspar (pp. 458–60). On p. 460 a system of results for this crystal is given, partly based on the experiments of Brewster, Sénarmont and Plücker, partly on Ångström's own experiments. We have for the angle α between the given directions and the base of the fundamental prism of felspar:

	α
Optiska polarisationsaxeln	4°, 1
Diamagnetiska axeln	4°, 1
Hårdheten ..	4°, 1 ?

¹ I have purposely refrained from translating the Swedish as there seems to me a certain amount of vagueness in the expressions used by Ångström.

Stoista ledningsformågan för varmet
 Akustiska axeln
 Minsta ledningsformågan för elektricitet

60°
 63° +
 63°

Thus the like two groups recur

Further discussion of results is given in Section ix (pp 460–1), while Section x (p 461) sums up as follows

Slutligen och såsom hufvudresultat af det foregående anser sig författaren hafva på experimentel väg bevisat *oriktigheten af det vanliga antagandet, att kristaller hafva 3ne ratvinklga elasticitetsaxlar*, så vidt nemligen satsen galler de monoklinoedriska kristallerna, och att tveitom ej blott *kristallernas form utan afven deras optiska, thermiska och akustiska fenomen* ovillkorligen hantya på tillvaron af *snedvinklga elasticitetsaxlar, konjugataxlar*

[687] The theoretical relation of three rectangular and unequal axes of elasticity supposing them to exist to the various physical vectors the position of which is given by Ångström seems in the present state of our knowledge of the correlation of the various branches of physics somewhat obscure. The planes of cleavage at any rate would probably take up a variety of positions relative to the three axes of elasticity depending on the exact relative magnitude of the constants of cohesion, and we should hardly expect them to make any definite angle (such as 45° or 90°) with these axes. How far Ångström's opinion that it is impossible to admit three rectangular axes of elasticity in crystals of the monoclinohedric system is correct must be left to the decision of those who have a wider knowledge of the properties and structure of crystals than the present writer.

[688] James Prescott Joule. The first contribution of this physicist to our subject, namely the memoir of 1846 *On the Effects of Magnetism upon the Dimensions of Iron and Steel Bars*, has already been briefly referred to—see our Art 1333* and its foot-note. This memoir was published in the *Philosophical Magazine*, Vol. xxx pp 76–87, 225–241, and is reprinted in the *Scientific Papers*, Vol. i, pp 235–264. Joule commenced to experiment in 1841–2 (see *Sturgeon's Annals of Electricity*, Vol. 8, p 219), so that he was really the first investigator in this field—see our Art 1333*. He obtained the following results

(1) Magnetisation [[?] below a certain critical value] increases the length of a bar, but

(ii) It does not perceptibly increase its bulk owing to a lateral contraction.

(iii) The elongation is [perhaps approximately below the critical value] in the duplicate ratio of the magnetic intensity of the bar.

The bars for which Joule deduced these results were of annealed and unannealed iron and of steel.

(iv) When iron wires are submitted to longitudinal tension and are magnetised, the increase of tension diminishes the elongation due to magnetism and with more than a certain tension increase of magnetisation produces a shortening effect.

(v) When iron bars are subjected to pressure the amount of the pressure does not seem to sensibly affect the magnitude of the elongation due to a given magnetic intensity.

(vi) The shortening effect when a wire is under tension is very early proportional to the product of the magnetic intensity in the wire into the current traversing the coil. [Hardly warranted by Joule's own experiments and scarcely confirmed by later investigators.]

In a particular experiment with iron wire one foot long and a quarter of an inch in diameter the tension at which magnetisation would produce no elongation for the electric currents employed in the experiments was conjectured to be about 600 lbs. By this I take Joule to mean the *total* tension: see his p. 232. *Scientific Papers*, Vol. I., p. 254. With regard to the apparently diverse results (iii) and (vi), Joule remarks:

The law of the square of the magnetism will still indeed hold good where the iron is sufficiently below the point of saturation, on account of the magnetism being in that case nearly proportional to the intensity of the current. For the same reason, on examination of the previous tables, it will be found that the elongation is, below the point of saturation, very nearly proportional to the magnetism multiplied by the current. The necessity of changing the law arises from the fact that the elongation ceases to increase after the iron is fully saturated; whereas the shortening effect still continues to be augmented with the increase of the intensity of the current (pp. 232-3. *Scientific Papers*, p. 255).

(vii) Shortening effects in the case of iron wire are proportional *ceteris paribus* to the square root of the tension. [Scarcely proven.]

In the case of hardened steel wire, however, the shortening effects were found not to increase sensibly with increase of tension.

(viii) No magnetic influence on strain could be found in the case of copper wires.

These results of Joule's have been considerably modified (as indicated above) by more recent researches and new light has been thrown on the whole subject by Villari, Shelford Bidwell, Ewing and others in memoirs to be discussed later.

[689] The next paper of Joule's touching on our subject is entitled *On the Thermo-electricity of Ferruginous Metals, and on the Thermal Effects of stretching Solid Bodies* *Proceedings of the Royal Society*, Vol VIII, pp 355-6, 1857, *Scientific Papers*, pp 405-7 This paper records that experiments on the stretching of metals showed a decrease of temperature in the metal when the load was applied and an increase when it was removed The experiments were on iron wire, cast iron, copper and lead Joule writes

The thermal effects were in all these cases found to be almost identical with those deduced from Professor Thomson's¹ theoretical investigation, the particular formula applicable to the case in question being $H = \frac{t}{J} \times Pe$, where H is the heat absorbed in a wire one foot long, t the absolute temperature, J the mechanical equivalent of the thermal unit, P the weight applied, and e the coefficient of expansion per 1° (p 355)

The same results occurred with gutta-percha, but they were exactly reversed in the case of vulcanised india-rubber, which was heated by loading and cooled by unloading Sir William Thomson suggested that loaded vulcanised india-rubber would be found to be shortened when heated, a result Joule found in accordance with experiment as well as theory

[690] *On the Thermal Effects of the Longitudinal Compression of Solids* *Proc Royal Soc*, Vol VIII, pp 564-6, 1857, *Scientific Papers*, Vol I pp 407-8 In this paper Joule continues his experimental verifications of Thomson's thermo-elastic theory He finds that for metal pillars and cylinders of vulcanised india-rubber heat is evolved by compression and absorbed on removing compressive force His investigations lead him to determine how far the "force of elasticity in metals is impaired by heat," or what may be the effect of tensile stress on expansion by heat He makes experiments on a helical spiral of steel wire and on one of copper wire and he supposes such spirals, like J Thomson (see our Art 1382⁴-3³) to resist extension only by torsion He thus finds that for the steel wire the 'force of torsion is decreased 00041 by each degree of temperature' (C°), while the number for copper wire is 00047 Kupffer found for steel wire 000471 and for copper 000691 see our Art 754, where however, these results are given for a degree R°

[691.] *On some Thermo-dynamic Properties of Solids.* *Phil. Trans.*, 1859, Vol. CXLIX, pp. 91–131; *Scientific Papers*, pp. 413–73. This contains a detailed account of experiments similar to those referred to in the two previous memoirs (see our Arts. 689–90) bearing on the thermo-elastic relations of metals and india-rubber. Joule had found that a helical spring showed no sensible thermal changes when compressed, and he attributed this to the equal and opposite thermal effects produced in its compressed and extended portions. At the suggestion of Sir William Thomson, he undertook to investigate independently the “heat developed by longitudinal compression and that absorbed on the application of tensile force.”

[692.] The portion of the memoir which really concerns us begins with § 18 and is entitled: *Experiments on the Thermal Effects of Tension in Solids*. Joule made careful experiments to measure the thermal increase H in degrees centigrade due to the stress, and he compared his experimental results with the formula of Sir W. Thomson¹

$$H = \frac{t}{J} \frac{pe}{sw},$$

where t = temperature Centigrade from absolute zero,

J = mechanical equivalent of the thermal unit in foot-pounds,

p = total load in lbs. (negative of course for a tension),

e = longitudinal expansion per degree Centigrade.

s = specific heat, and w = mass in lbs. of a foot length of the bar.

As a measure of the coincidence of experiment and theory I think it well to cite the following results, noting that Joule took some of his constants from Dulong and Petit, Lavoisier and Laplace, etc., others he ascertained experimentally for his own specimens.

Values of H in degrees Centigrade.

	By Experiment.	Calculated.
Iron bar	{ - .115	- .11017
	{ - .124	- .1099
	{ - .1007	- .1069
Hard Steel	- .162	- .125
Cast Iron	{ - .1605	- .112
	{ - .1481	- .115
Copper	- .174	- .154
Lead	{ - .0531	- .0403
	{ - .0758	- .0550
Gutta-percha	{ - .0284	- .0306
	{ - .0524	- .0656

[693] Joule next turns to the curious thermo elastic phenomena presented by india-rubber §§ 33–58 (*Scientific Papers*, pp 429–440), which he discusses at considerable length. He refers to the discoveries of Gough see our footnote, Vol 1, p 386. Joule confirms Gough's conclusions, which might be deduced from Thomson's formula by supposing e negative. These conclusions are in accordance with those previously noted by Joule see our Art 690. Besides Gough's conclusions Joule deduces from his experiments the following results

(a) India rubber softened by warmth, may be exposed to 0° Fahr for an hour or more without losing its pliability, but a few days rest at a temperature considerably above the freezing point will cause it to become rigid

(b) A large amount of elastic after strain exists in india rubber

(c) Moderate stretching weights produce little heat or even a slight cooling effect, but after a certain weight is reached there is a rapid increase of heating effect

(d) When by keeping india-rubber at rest at a low temperature for some time it has become rigid, it ceases to be heated when stretched by a weight, and, on the contrary, a cooling effect takes place as in the metals and gutta percha

(e) For *vulcanised* india rubber results similar to (d) hold, but that the specific gravity is increased by stretching it, as Gough supposed (Vol 1 p 386 ftn (4)), appears to be exactly contrary to Joule's experience, § 45 (*Scientific Papers*, p 434)

(f) The slight cooling effect referred to in (d) produced by weak tensile forces disappears for vulcanised india rubber when the temperature of the thong is a few degrees higher than $7^{\circ} 8^{\circ} \text{C}$

(g) The effect of heat on a thong of india rubber under tension predicted by Thomson was experimentally measured §§ 50–58 (*Scientific Papers*, pp 433–40) and the numbers (p 438) agreed with theory perhaps as closely as could be expected with a material of this kind

(h) A rise of temperature removes from vulcanised india rubber set produced by earlier experiments at high tensions

(i) For vulcanised india rubber H (see our Art 692) = + 137 by experiment (corrected 'for elongation of rubber by use' to + 155), and + 114 by calculation

[694] Joule next turns his attention to *wood* which presents some remarkable thermo elastic properties and leads him to rather inconsistent results

The discrepancies arose apparently from considerable elastic after strain and from the effects of moisture on the wood in altering its elastic condition. Thus different hygrometric conditions could cause the wood under tension either to expand or contract, as the case might be, when its temperature was raised, and here again there were great differences

according as the wood was strained with or across the grain. Joule's general results are stated in § 75 (*Scientific Papers*, Vol. I., p. 450). Removal of set by heating and also elastic after-strain were observed in *whalebone* as well as wood §§ 84–5 (*Scientific Papers*, Vol. I., pp. 454–6).

[695.] The next portion of Joule's memoir (§§ 94–122, *Scientific Papers*, Vol. I., pp. 459–71) is devoted to the *Thermal Effects of Longitudinal Compression on Solids*. Here again Joule compares the heat evolved in degrees Centigrade with that calculated by Thomson's formula, and he finds the following *mean* results, where we omit those for vulcanised india-rubber and wood, the apparent agreement in the case of wood cut across the grain disappearing if the individual results are analysed :

Values of H in degrees Centigrade.

Thermal Effect from	Experiment.	Theory.
Wrought Iron	•115	•108
Cast Iron	•118	•107
Copper	•146	•124
Lead	•087	•079
Glass	•017	•011

Evidently the experimental results are somewhat in *excess* of the theoretical. Joule attributes this discrepancy to "experimental error due to the incorrectness of the various coefficients which make up the theoretical results" (§ 120). He also considers that elastic after-strain would introduce a small error into the thermo-elastic formula, but that this is too small to be capable of measurement in his experiments (§ 121).

[696.] The last paragraphs of the memoir (§§ 122–6, *Scientific Papers*, Vol. I., pp. 471–3) contain an experimental verification of a principle of Thomson's namely that :

"a spring be such that a slight elevation of temperature weakens it, and the full strength is recovered again with the primitive temperature, work done against that spring by bending or working in whatever way must cause a cooling effect.

Now Joule had found a diminution in the slide-modulus of steel of $\cdot 00041$ per degree Centigrade (§ 120 of the memoir, or see our Art. 690), hence the effect of compressing or stretching a helical steel spring ought to be to cool it slightly. By taking the mean of a hundred experiments on compression and then of a hundred

on extension Joule was able to measure this slight cooling effect. He found it 00306, theoretically it should have been 00403. The three-thousandth part of one degree Centigrade as measured by Joule is rather a small quantity to draw definite conclusions from, but he found in these numbers sufficient evidence of the truth of the theory and concludes his memoir with the words

Thus even in the above delicate case is the formula of Professor Thomson completely verified. The mathematical investigation of the thermo elastic qualities of metals has enabled my illustrious friend to predict with certainty a whole class of highly interesting phenomena. To him especially do we owe the important advance which has been recently made to a new era in the history of science, when the famous philosophical system of Bacon will be to a great extent superseded, and when, instead of arriving at discovery by induction from experiment, we shall obtain our largest accessions of new facts by reasoning deductively from fundamental principles (§ 126, *Scientific Papers*, Vol. I p. 472).

[697] One or two other memoirs of Joule's may be just referred to here, although falling into a later period.

(a) *On a Method of Testing the Strength of Steam Boilers*. *Memoirs of the Literary and Philosophical Society of Manchester*, 3rd Series, Vol. I pp. 175 and 233, 1861. This contains nothing with regard to the strength of the materials of the boilers tested.

(b) *On a new Magnetic Dip Circle*. A memoir of this title was published in the *Manchester Proceedings*, Vol. VIII 1869, p. 171, and when it was republished in the *Scientific Papers*, Vol. I p. 575, Joule added (pp. 579-583) some account of experiments on the strength of silk and spider filaments made in 1870. These experiments show the large influence of elastic after strain, and further prove that silk and spider filaments, like caoutchouc, when under tension, become shorter if the temperature be raised. The effect of moisture tends to obscure both after strain and temperature effects. Numerous experimental measurements are given.

(c) *On the Alleged Action of Cold in rendering Iron and Steel brittle*. *Manchester Proceedings*, Vol. X pp. 91-4, 1871, *Scientific Papers*, Vol. I pp. 607-610. *Further Observations on the Strength of Garden Nails* will be found on pp. 127-8 and 131-2 of the same volume of the *Proceedings*, or on pp. 610-13 of the *Scientific Papers*.

Joule brings evidence against the hypothesis that cold renders iron and steel brittle from (1) Experiments on iron and steel wires, part of which were in contact with a freezing mixture and part at about 50° F. The wires broke *outside* the freezing mixture. These were pure tensile experiments. (ii) Flexure experiments on steel drawing needles. The average strength of the metal at 12° F. was found to be slightly greater

than at 55° F. (iii) Impact experiments on warm and cold cast-iron garden nails, broken by the blunt edge of a steel chisel falling upon the middle of the nail terminally supported. These experiments were not in favour of the hypothesis that frost makes cast-iron brittle.

[698.] C. Matteucci: *Sur la rotation de la lumière polarisée, sur l'influence du magnétisme et sur les phénomènes diamagnétiques en général. Annales de Chimie*, T. XXVIII, pp. 493–9, Paris, 1850.

A heavy glass prism (presented to the author by Faraday) placed in a strong electro-magnetic field rotated the plane of polarised light. Matteucci records somewhat vaguely in this note the effect produced on this power of rotation by compressing the glass. He finds that:

(i) Before compression the rotations to the right or to the left according to the sense of the current are the same for the same intensity of current. After compression the one rotation is much greater than the other; the one being twice to thrice the other.

(ii) The greater rotation is always that which is produced by the passage of the current which acts in the same sense as the compression¹.

(iii) The maximum rotation of the compressed glass is sometimes greater, sometimes less than that which occurs when the glass is not compressed; when the rotation produced by the compression is very much greater than that which the electro-magnet produces in the uncompressed glass, then the maximum rotation due to the action of the electro-magnet on the compressed glass is equal to or greater than the maximum rotation produced by the electro-magnet in the uncompressed glass; the maximum rotation produced by the electro-magnet in the compressed glass is equal to or greater than that produced by the compression; in this case the maximum rotation is equal to or less than that produced upon the uncompressed glass.

(iv) Other glasses such as flint and crown exhibit the like phenomena. But the electro-magnetic field produces no sensible rotatory action on pieces of crown glass subjected only to slight compression.

Matteucci holds that this last result will explain to some extent why crystals do not exhibit rotatory power in the magnetic field. The electro-magnet further produced no rotatory power in compressed laminae of quartz and annealed glass: see Wertheim's results cited in our Arts. 786 and 797 (*d*).

(v) When the compression was removed the glass resumed its previous magnetic rotatory power.

(vi) There was a sensible although hardly measurable interval between the instant of closing the circuit and the instant at which the

¹ The 'rotation' due to the compression alone seems to have been measured by the angle through which the Nicol's prism of a bi-quartz analyser had to be turned in order that the two halves of the image should have the same colour.

maximum rotation was attained This interval was greater when the glass was compressed than when it was uncompressed

[699] Matteucci further records some experiments in which he placed vibrating square plates of glass, brass and iron between the poles of an electro magnet He found that the Chladni figures or system of nodal lines were the same whether the current was passing or not, whence he argues that very different groups of atoms (*groupes d'atomes*) must be affected by the action of magnetism and by the influence of acoustic vibrations (p 499)

[700] C Matteucci Some account of a memoir by this physicist entitled *Sur l'influence de la chaleur, de la compression, sur les phénomènes diamagnétiques* will be found on pp 740-4 of the *Comptes rendus*, T XXXVI, Paris, 1853 The only part of the account which concerns us is entitled *Compression du bismuth* and occurs on p 742 Matteucci writes

J'ai trouvé qu'une aiguille prismatique de bismuth, comprimée dans le sens de son axe, se dirige toujours équatorialement, quelle que soit la face qui est suspendue horizontalement, son pouvoir diamagnétique est considérablement augmenté par la compression Si l'aiguille de bismuth a été comprimée perpendiculairement à son axe, elle se dirige dans la ligne des pôles quand les faces comprimées sont verticales, et dans la ligne équatoriale si les faces comprimées sont horizontales Cette propriété persiste après avoir chauffé l'aiguille de bismuth jusqu'à une température peu inférieure à la fusion du métal

[701] C Matteucci *Sur fenomeni elettro-magnetici sviluppati dalla torsione Il nuovo Cimento*, Tomo VII pp 66-97, Pisa, 1858 *Annales de Chimie*, T LIII pp 385-417, Paris, 1858, *Comptes rendus*, T XLVI pp 1021-4, Paris, 1858

Parte I of this memoir is entitled *Di un nuovo caso d'induzione elettro-magnetica* (pp 67-81) Matteucci begins by describing his apparatus and mode of experimenting Briefly an iron rod supported perpendicular to the magnetic meridian was placed in circuit with a galvanometer and to this rod any amount of torsion in either sense could be given Round the rod was placed a coil of three or four turns of wire, through which a current could be sent in either direction and this served to magnetise the rod

When a current from two to four Grove elements was sent round the coil magnetising a bar of half-hard iron (*ferro semiduro*), then at the moment when it was started a small deflection of

$\frac{1}{4}$ to $\frac{1}{2}$ a scale division was exhibited by the galvanometer needle of the secondary circuit. But the result was quite different when a sudden torsion was given to the bar:

Perchè non vi sia difficoltà alcuna a concepire il risultato dell'esperienza principale, supporremo che per l'azione della spirale magnetizzante si formi un polo sud (o attratto dal polo nord della terra) in quella estremità della verga che è volta verso l'est, e un polo nord all'estremità opposta, che è quella fissata nel centro della ruota. Supporremo finalmente che l'osservatore che deve torcere la verga magnetizzata guardi la ruota. Nel momento in cui è applicata alla verga una certa torsione elastica che può essere di 5 fino a 20, o 25 gradi secondo la qualità del ferro, in modo che lo zero della ruota giri alla sinistra dell'osservatore, l'ago del galvanometro è spinto a 10 o 20 o 30 gradi o più, indicando una corrente diretta nella verga dall'estremità sud all'estremità nord. L'ago torna subito allo zero o al suo punto d'equilibrio e se allora si fa cessare bruscamente la torsione, l'ago indica una nuova corrente in senso contrario della prima. Ripetendo la stessa torsione in senso contrario, cioè verso la destra dell'osservatore, si ha di nuovo una corrente della stessa intensità di quella ottenuta colla torsione a sinistra, ma diretta in senso contrario cioè dal nord al sud nella verga. Anche in questo caso la detorsione sviluppa una corrente che è in senso contrario della corrente prodotta dalla torsione corrispondente (pp. 68-9).

Reversing the magnetising current, we have secondary currents in the reversed sense. The phenomena repeat themselves so long as the bar is subjected only to elastic torsion. Like all induced currents, the secondary currents vary in intensity with the time in which a given torsion is produced.

Matteucci develops in this earlier part of his memoir (p. 70) the theory (rejected by Wiedemann) that the iron bar may be looked upon as a bundle of conducting fibres which are converted into spirals by the torsion (see our Art. 713), and he supposes that the magnetising coil has greater induction on this bundle of spirals than on the bundle of fibres parallel to its axis.

Matteucci further notices that when he first twists the bar and then closes the primary circuit he likewise obtains an induced current, and that its magnitude is more constant for the same torsion than that obtained by reversing the order of proceeding. Opening the primary circuit¹ when the bar is twisted gives a less induced current, however, than the process of magnetising, and Matteucci attributes this to the residual magnetism (p. 71). After the primary circuit has been opened and closed several times, the bar reaches a definite permanent magnetisation and the induced currents at closing and opening become the same (p. 75). Experiments were also made on steel rods with a greater or less degree of hardness; the phenomena were the same in

¹ Termed by Matteucci the *demagnetisation*.

general character as for the iron rods, but the induced currents were much less in magnitude

[702] On pp 76–7 we have various experimental results connecting the induced current with the length, diameter and angle of torsion of the rod, on the latter page are also some statements with regard to the influence of torsional set or ‘tort’ Matteucci found that for rods of hard and half hard iron of 4 m in length and of diameters of 4 mm and upwards the current was proportional to the angle of torsion, and he further concluded that set had not the power of developing a current, see his p 77, to be compared with Wiedemann’s results in our Arts 713–4 Matteucci found that the induced currents due to twisting did not increase in proportion to the strength of the primary current¹, but began to diminish after this reached a certain intensity (cf Wiedemann in our Art 714) Further conclusions as to the difference in magnitude of the currents induced, according as untwisting was followed by the opening of the primary circuit or the reverse order was adopted, are given on pp 79–81, but the results are not stated with the clearness and precision of Wiedemann’s see our Art 714 Indeed the memoir suffers from the want of a general statement of results, and the *leggi determinate* to which Matteucci refers on p 81, have to be drawn from a rather confused mass of experimental statements

[703] *Parte II* of the memoir is entitled *Delle variazioni nello stato magnetico di una verga di ferro prodotte dalla torsione* (pp 82–8)

Matteucci opens this *Parte* with an historical résumé of his own² and Wertheim’s earlier investigations (see our Arts 812 and 811, 813 *et seq*) Wertheim had not obtained for rods of cast steel any diminution of the magnetisation by elastic torsion (see our Art 814 (ix)), but Matteucci asserts (p 83) that he has found small variations of the magnetisation with torsion in a variety of cast-steel bars He sums up the conclusions to be drawn from the scarcely sufficient experiments recorded in this part as follows

1° La torsione elastica di una verga magnetizzata a saturazione determina una diminuzione nella sua forza magnetica, la quale persiste per tutto il tempo in cui la torsione dura, colla detorsione la forza magnetica è ristabilita come prima

2° Dalle relazioni che esistono fra le variazioni determinate dalla torsione e detorsione nella forza magnetica di una verga e le correnti indotte nella spirale esterna, è dimostrato che quelle variazioni sono la cagione delle correnti stesse (pp 87–8)

See Wiedemann’s results cited in our Art 714

¹ Matteucci says magnetisation of the rod which he erroneously takes to be proportional to the strength of the primary current

Comptes rendus T xxiv p 307

[704.] *Parte III.* (pp. 88–97) of the memoir is entitled: *Spiegazione dei fenomeni descritti*. This portion of the memoir, after a remark that the phenomena of induction described in the preceding parts can only be produced in iron and some other magnetic bodies, proceeds to develop a second ‘bundle of fibres’ theory, namely: that each fibre is a separate iron rod and that these rods after being converted into magnets are then twisted by the torsion round the current in the direction of the axis of the bundle. This theory is supported by rather vague reasoning which does not seem to meet the objections which Wiedemann has raised against it: see our Art. 713.

On the whole Matteucci, while doubtless the first to discover many points relating to the influence of stress upon magnetism, had not that power of marshalling his experimental facts and clearly stating the conclusions to be drawn from them which is characteristic of both his French and German rivals in the same field. The memoirs of Wertheim and Wiedemann are models of physical research, but we must confess to finding Matteucci’s letter-press, never broken by a symbol or a formula and only occasionally relieved by a thin scattering of experimental numbers, wearisome reading.

[705.] In a footnote on pp. 95–7 of the memoir Matteucci records some earlier results as to the effect of stretching three magnetised iron wires of 1·5 mm. diameter. A wire was placed along the common axis of two spiral coils, one in circuit with a galvanometer, and the other used for magnetising; on the stretching or unstretching of the wire when magnetised an induced current was observed in the galvanometer. Matteucci measured by means of a certain astatic system, described in the second part of the memoir, the changes in the magnetisation of the wire due to the stretch, and he found induced currents corresponding to the changes in magnetisation. After demagnetisation (? opening the magnetising circuit) the currents obtained by stretching or unstretching the iron wire were much stronger than when the magnetising current was flowing. These phenomena were most marked in annealed iron wire, but the induced currents were in the *opposite sense* to those in the case of hard iron wire. Thus stretching appeared to diminish the magnetisation of annealed and increase that of hard iron wire. If the current in the magnetising coil were however broken, a stretch indicated an increase of magnetisation for annealed in the same way as for hard iron wire.

When an iron wire magnetised by a surrounding coil was put in circuit with a galvanometer, no trace of a current along the wire was observed at the moment when it was stretched or unstretched.

These results become more intelligible in the light of the later researches of Villari, Ewing and others.

[706.] G. Wiedemann: *Ueber die Torsion, die Biegung und den Magnetismus*. *Verhandlungen der naturforschenden Gesellschaft in Basel*, Vol. II., Basel, 1860, S. 168–247.

This important paper was reproduced in a rather fragmentary manner in various volumes of *Poggendorff's Annalen*

The following scheme shows the corresponding pages and will enable the reader to whom only the *Annalen* are accessible to identify our quotations

<i>Verhandlungen</i>		<i>Poggendorff</i>
S 169-172	= Bd cvi, 1859	S 161-164, (α)
S 172-184	= Bd cvi, 1859	S 174-183, (α)
S 184-193	= Bd cvii, 1859	S 439-448, (β)
S 193-196 and S 201-7	= Bd c, 1857	S 235-244, (γ)
S 197-201	= Bd cvi, 1859	S 170-174, (α)
S 207-223	= Bd ciii, 1858	S 563-577, (δ)
S 223-227	= Bd cvi, 1859	S 164-168, (α)
S 227-247	= Bd cvi, 1859	S 183-201, (α)

We shall cite the pages of the *Annalen* by the Greek letters

[707] Wiedemann commences his memoir with the following account of its object

Eine Reihe von Beobachtungen hatte mich vermuthen lassen, dass die durch mechanische Mittel hervorgebrachten Aenderungen der Gestalt der Körper nach ganz ähnlichen Gesetzen von den dieselben bedingenden Kräften abhängen, wie die Magnetisirung der magnetischen Metalle von den dieselbe bewirkenden magnetisirenden Kräften. Ich habe deshalb die Gesetze der Torsion und Biegung der Körper einerseits ebenso wie die der Magnetisirung des Eisens und Stahles andererseits in dieser Beziehung einer neuen Untersuchung unterworfen, deren Resultate ich im Folgenden mitzutheilen miß erlaube (S 169)

[708] The first section of the memoir is entitled *Torsion*, and occupies S 169-84. The section opens with an account of the apparatus employed (S 169-72, α , S 161-4), and then Wiedemann continues

Drahte von verschiedenem Stoffe wurden mit Hülfe dieses Apparates durch aufsteigende Gewichte L tordirt, welche stets so lange wirkten, bis der Draht eine constante Torsion angenommen hatte. Die dieser Belastung L entsprechende temporäre Torsion L des Drahtes wurde an der Kreistheilung abgelesen. Nach dem Heben der drehenden Gewichte wurde wiederum einige Zeit gewartet, bis die zurückbleibende permanente Torsion T_0 mittelst der Spiegelablesung bestimmt wurde. Nach der Torsion des Drahtes wurde er allmählig durch entgegengesetzt drehende Gewichte detordirt, wieder tordirt u. s. f. Dabei wurde sorgfältigst jede Erschütterung des Apparates vermieden (S 172-3, α , S 174)

This passage enables us without describing Wiedemann's apparatus to grasp his method of procedure. The intervals which

elapsed between the experiments served to remove as far as possible elastic after-strain. Wiedemann's experiments were upon annealed iron and brass wires; the numerical results of his experiments are given on S. 174-7 (α , S. 175-7) and they are in part represented graphically in Fig. 3 of his Plate I. His general conclusions for torsion including certain temperature effects, which are based on less careful experimental methods (*mit manchen Fehlerquellen behafteten Versuche*, S. 183), are given on S. 178-84 (α , S. 177-83). I do not cite them here, as we shall return to a general statement of conclusions for torsion and magnetism when considering the sixth section of the memoir.

[709.] The second section of the memoir is entitled: *Biegung*, and occupies S. 184-93 (β , S. 439-48). It shows that results similar to those holding for torsion hold for flexure also. Wiedemann's apparatus is described on S. 184-5 (β , S. 439-40). His experiments were made on annealed brass rods built-in at one end and bent in a horizontal plane. The numerical details are given on S. 187-9 (β , S. 442-4) and the general conclusions on S. 189-91 (β , S. 444-6). These are of such great interest and anticipate so much of Bauschinger's later work that we cite them here:

(i) If a rod previously unbent be bent by a series of increasing loads, the elastic flexures which the rod exhibits while subjected to these loads increase more rapidly than the loads.

(ii) After removal of the loads the rod exhibits flexural sets or *bents*¹; these begin with the smallest loads and increase in a far more rapid ratio than the corresponding loads.

(iii) If a bent rod have its bent removed (*entbogen*) by the application of reversed loads, then the bent decreases somewhat more slowly than the loads increase. To produce complete unbending a considerably smaller load is necessary than that which produced bending.

(iv) If the rod after the first bending and unbending is repeatedly bent and unbent, then the bents do not increase so much more rapidly than the loads as is the case in the first bending; on the contrary they become more and more nearly proportional to the loads, being greater for small loads than in the first case. The bent due to the maximum load decreases gradually to a definite limit after repeated loadings. On the other hand the load necessary for unbending the rod increases with

¹ Isaac Walton uses this word of a fishing rod, Wilkins of a bow and Richard Hooker for the set of 'an obstinate heart.'

repeated loading and unloading—the load which removed the first bent now leaving a residual bent

Thus in one set of experiments with Wiedemann's units a bending load of 240 produced a bent of 89, and an unbending load of 211 left a bent of only 1, but after repeated operations the same bending and unbending loads produced a bent of only 44.8 and left a bent of 24.4

(v) If a rod has been so often bent and unbent that the same bending load always produces the same bent, then when the rod is left to rest for awhile, it returns a little towards its primitive condition

This result was only based on one experiment. Indeed in these experiments on flexure upon only one occasion was 15 hours left between two series, the other series being carried on continuously and therefore their results were probably somewhat affected by after-strain see S 188 (β, S 443) of the memoir

(vi) It is obvious that if a definite load $-L$ deprives a rod of bent, neither this load nor any less load repeated in the same direction as $-L$ will give the rod a bent in the direction opposite to that of the first bent. But the load $+L$ on the contrary will produce a greater or less bent of the rod

(vii) If a rod, which possesses a bent B (which may be $=0$) be brought to another bent B' by a load L , and then by a load $-L'$ opposed to L be brought to a bent B'' which lies between B and B' , then to bring the rod again to the bent B' the load L will be again needful

(viii) If a rod be shaken while subjected to a bending load, this increases the elastic flexure, if it be shaken after the removal of the load, this decreases the bent. If a rod be bent and then deprived of bent by reversed load, shaking produces anew a bent in the sense of the initial bent

These results are at least qualitatively the same as for torsion. The temperature effect is not so great in the case of flexure as in that of torsion see our Art 754

[710] The practical value of these results has only been fully brought out by the more elaborate experiments of Bauschinger on larger masses of material, but Wiedemann certainly draws from his more limited range of experiments conclusions which to some extent anticipate those of the careful Munich technical elastician see also our Arts 749 and 767. These are given on S 191–3 of the memoir (β, S 447–8) for both torsion and flexure

Wiedemann remarks that it depends merely on the sensibility of our apparatus whether we are able or not to measure the set of the smallest loads (see our Art 1296*)

Demnach ist der Begriff der sogenannten I $+$ $+$ $-$ wie man ihn gewöhnlich faßt, durchaus ein nur für die Praxis willkürlich eingeführter, in sofern man dieselbe da ansetzt, wo eben für bestimmte Beobachtungsmethoden die permanenten Gestaltveränderungen der Körper sichtbar werden (S 192, β, S 447)

Thus if a body be bent to set and afterwards deprived of bent, or tortured¹ to set and afterwards deprived of tort, and this process be repeated, then on the bending or torting by any less load there will always be a sensible set, which becomes more nearly proportional to the load as the process is more often repeated. There is here then no limit of elasticity. Thus although we return to a state of no torsion or flexure, that is, of no *apparent* strain, the elastic condition of the material has quite changed in character. What we term the 'state of ease' has, for one sense of loading, been reduced to a vanishingly small range. On the other hand if a set has been produced by a load L , no load less than L in the same sense will produce any set. Thus, as we have frequently noted, L marks the elastic limit or state of ease. To obtain a state of ease, which starts from the position of no apparent strain and embraces a load L_1 , we must proceed as follows:

First apply a load L_2 in the opposite sense to L_1 and then a load L_3 in the same sense as L_1 which just undoes the bent or tort produced by L_2 , thus L_1 by (vii) will not produce any set provided we have taken L_2 so great that L_3 is greater than L_1 .

The suggestiveness of these results will be still more apparent as we come in the course of our *History* to further experimental investigations bearing on the state of ease.

[711.] Section III. of Wiedemann's memoir is entitled: *Magnetisirung von Eisen und Stahl* (S. 193–210; γ , S. 235–244 and δ , S. 563–6). This deals with the problems of temporary and residual magnetism and the effect of temperature on magnetism. The results obtained are very similar to those obtained for elastic strain and set in the previous sections of the memoir, but to discuss them here would lead us beyond our limits: see our Art. 714.

[712.] Section IV. is entitled: *Einfluss der Torsion auf den Magnetismus der Stahlstäbe* (S. 210–16; δ , S. 566–71). This problem had already been considered by Wertheim (see our Arts. 811–18), and Wiedemann commences by quoting Wertheim's results as to the magnetic equilibrium produced by repeated torsions in iron and steel bars: see our Art. 814. Wiedemann confirms and extends Wertheim's conclusions, measuring the changes in magnetisation by direct magnetometric means and not as Wertheim by induced currents in a coil surrounding the rod.

The only result of this section which is not cited in the general results of the sixth section is iv. (S. 216; but v. in δ , S. 571), and this accordingly may be noted here:

¹ I use the noun *tort* for torsional set and the verbs *to tort* and *to detort* for the processes of twisting and untwisting when it seems advisable to emphasise the tort part of the strain produced.

If by torsion more magnetism be withdrawn from a steel bar than could be withdrawn by repeated changes of temperature within definite limits (in the experiments 0° to 100°C), then any loss of magnetism produced by a rise of temperature within those limits is restored when the bar is again cooled to the previous temperature

[713] Section v of the memoir is entitled *Einfluss der Magnetisirung auf die Torsion der Eisen- und Stahldrahte* (S 217–27, δ , S 571–7, and α , S 164–8) The influence of magnetism in reducing torsional set or tort is here noted and measured Iron wires which have no tort do not appear to be twisted by magnetism As most of the results of this section are restated in the following section, we shall not specially cite them now, they deserve, however, careful attention from those interested in the mutual relations of magnetism and set¹ Wiedemann gives cogent reasons for rejecting Matteucci's hypothesis that an iron wire may be looked upon as a bundle of parallel fibres, which are converted by torsion into spirals and which magnetisation by producing mutual repulsion again straightens see our Art 704 He also rejects the hypothesis that the phenomena observed can be due to the heat produced in the wire by magnetisation (S 222–3, δ , S 576–7)

At the conclusion of the section the author promises in a future paper to deal with the influence of bending on magnetism, but at the same time he notes the great difficulties which stand in the way of experimental investigation (S 227)

[714] The sixth and final section of the memoir is entitled *Vergleichung der Resultate und Versuch einer Theorie* (S 227–47, α , S 183–201) We first find a comparison of the properties of magnetism and torsion which, although pressed rather far, contains a good deal of matter novel at the time I reproduce it here

Torsion

1 The temporary torsions of a wire twisted for the first time by increasing loads increase more rapidly than these loads

2 The torsional sets or torts of the wire increase still more rapidly

Magnetism

1 The temporary magnetisations of a bar magnetised for the first time by increasing galvanic currents increase more rapidly than the intensity of those currents

2 The permanent magnetisations of the bar increase still more rapidly

¹ On S 227 Wiedemann gives in grammes weight a measure of the detorting force of magnetism in a special case (α , S 167–8)

3. To completely detort the wire a much less load is required than to tort it.

4. By repeated tortings and detortings the torts of the wire approach nearer and nearer proportionality with the corresponding loads. The torts are greater than at the first torting.

5. By repeated application of the same torting and detorting loads L and $-L'$ the maximum of tort reached by the torting sinks and the minimum reached by the detorting rises to a certain definite limit.

6. The wire, if torted beyond the limits of the repeated tortings and detortings, conducts itself as if torted for the first time.

7. A torted wire, detorted by the load $-L$, cannot by repetition of this load be torted in a sense opposite to that of the initial torting. The load $+L$ torts it, however, in the first sense.

8. If a wire having the tort A be brought by the load b to the torsion B , and afterwards be brought to any other torsion C , which lies between A and B , then to obtain the torsion B again we have only to apply the same load b . Here A can be zero, and B greater or less than A .

3. To completely demagnetise the bar a much weaker current is required than to magnetise it.

4. By repeated magnetisations and demagnetisations of a bar, the permanent magnetisations approach nearer and nearer proportionality with the intensity of the magnetising currents. The magnetisations are greater than at the first magnetising.

5. By repeated application of the same magnetising and demagnetising currents J and $-J'$ the maximum of magnetisation reached by the magnetising sinks and the minimum reached by the demagnetising rises to a certain definite limit.

6. The bar, if magnetised beyond the limits of the repeated magnetisations and demagnetisations, conducts itself as if magnetised for the first time.

7. A magnetised bar, which is demagnetised by a current of intensity $-J$ cannot by repetition of this current be magnetised in a sense opposite to that of the initial magnetisation. The current $+J$ magnetises it, however, in the first sense.

8. If a bar having permanent magnetism A be brought by the current b to the magnetisation B and afterwards be brought to any other magnetisation C , which lies between A and B , then to obtain the magnetisation B again we have only to apply the same current b . Here A can be zero, and B greater or less than A ¹.

¹ Important qualifications of the above statements as to magnetisation, especially of 1-4, will be found on S. 192-200 (α , S. 172-3). Wiedemann apparently omits them in this *résumé* as he wishes only to emphasise the correspondences between torsion and magnetisation. These statements are thus very far from representing accurately the complete results of his purely magnetic experiments.

9 Shaking (*Erschütterung*) during the application of a twisting load increases the torsion of a wire

10 The tort of a wire after release of the load is lessened by shaking

11 A torted and then partially detorted bar loses part of its tort by shaking or gains tort afresh according to the magnitude of the detorting

12 Tort in an iron wire decreases owing to its magnetisation, but in a ratio decreasing with increasing magnetisation

13 Repeated magnetisations in the same sense scarcely continue to decrease sensibly the tort of a wire. A magnetisation in the opposite sense, however, produces afresh a large decrease of the tort

14 If a wire by repeated magnetisation in opposite senses is so far detorted as is possible by the given range of magnetisation, then by magnetisation in one sense the wire shows a maximum and by magnetisation in the opposite sense a minimum of tort

15 A torted wire which has been slightly detorted loses by magnetisation much less of its tort than one which has only been torted. If the wire be further detorted, it exhibits at first by slight magnetisation an increase of tort, this by increasing magnetisation rises to a maximum and then decreases. The more the wire has been detorted the greater

9 Shaking during the application of a magnetising current increases the magnetisation of a bar

10 The residual magnetisation in a bar after cessation of the current is lessened by shaking

11 A magnetised and then partially demagnetised bar loses still more of its magnetisation by shaking or gains magnetism afresh according to the magnitude of the demagnetisation

12 Residual magnetisation in a steel bar decreases owing to torsion, but in a ratio decreasing with increasing torsion

13 Repeated torsions in the same sense scarcely continue to decrease sensibly the residual magnetisation of a steel bar. A torsion in the opposite sense, however, produces afresh a large decrease of the magnetisation

14 If a bar by repeated torsion and detorsion is so far demagnetised as is possible by the given range of torsion, then by torsion in one sense it shows a maximum, by torsion in the opposite sense a minimum of residual magnetisation

15 A magnetised bar which has been slightly demagnetised loses by torsion much less of its magnetism than one which has only been magnetised. If the bar be further demagnetised, it exhibits at first by slight torsion an increase of its magnetisation, this by increasing torsion rises to a maximum and then decreases. The more the bar has been demagnet

must be the magnetisation in order to reach this maximum. If the wire has been very much detorted, then its tort increases even on the application of very great magnetisation.

ised the greater must be the torsion in order to reach this maximum. If the bar has been very much demagnetised, then its magnetisation increases even on the application of very great torsions.

16. If a wire be magnetised while subject to the twisting load, then its torsion increases for slight and decreases again for greater magnetisations.

16. If a steel bar be twisted while under the influence of a magnetising current, its magnetisation increases for slight but decreases again for greater torsions.

17. A wire torted at the ordinary temperature loses tort by heating and regains a part of its loss on cooling. The changes increase with increasing tort.

After repeated changes of temperature the wire reaches a stable condition in which a definite tort corresponds to each temperature, decreasing as the temperature rises.

17. A bar magnetised at the ordinary temperature loses residual magnetisation by heating and regains a part of its loss on cooling. The changes are proportional to the magnetisation. After repeated changes of temperature the bar reaches a stable condition in which a definite residual magnetisation corresponds to each temperature, decreasing as the temperature rises.

18. A wire torted at the ordinary temperature and then partly detorted, loses by heating so much the less of its tort the more it has been detorted. Its tort on cooling is less than before if the detorting has been slight, it is greater if the detorting has been large.

18. A bar magnetised at the ordinary temperature, and then partly demagnetised loses by heating so much the less of its residual magnetisation the more it has been demagnetised. Its magnetisation on cooling is less than before if the demagnetisation has been slight, it is greater if the demagnetisation has been large.

19. A wire torted at a higher temperature loses tort on cooling. On a second warming it loses still further and only by the second cooling regains a part of its loss. If the wire is shaken before the first cooling, it gains at once in tort.

19. A bar magnetised at a higher temperature loses residual magnetisation on cooling. On a second warming it loses still further and only by the second cooling regains a part of its loss. If the bar is shaken before the first cooling, it gains at once in magnetisation.

A conception of the advance made by Wiedemann may be formed by comparing the above statements with those of Matteucci and Wertheim, the most important previous investigators in this field see our Arts 701-5 and 811-8 especially comparing 12 and 13 above with (u), (vi) and (vii) of Arts 813-4

It will be seen that the laws of torsional set (*tort*)—which is what Wiedemann refers to when he speaks generally of a wire being “torted” in the above analysis—are similar to those of flexural set (*bent*), and their investigation constitutes a wide field for research which is only in the present decade being thoroughly explored

[715] On the basis of these analogies Wiedemann attempts a *mechanical* as distinguished from a *hydromechanical* or *aetheral* explanation of magnetisation (S 233-47, a, S 189-201) Luke W Weber, he supposes the ultimate magnetic element to be a polar molecule, and the axes of these molecules to be initially turned in all conceivable directions He then attempts by general descriptive reasoning to account for the above relations and analogies between magnetism and strain As a type of the general reasoning I quote the following paragraph

Erschütterungen setzen die Theilchen der Körper in Bewegung, die Reibung der Ruhe zwischen ihnen wird gewissermassen in eine Reibung der Bewegung verwandelt Daher werden in allen Fällen die Theilchen mehr den gerade auf sie wirkenden Kräften folgen können, und es müssen Erschütterungen eine Zunahme der temporären, eine Abnahme der permanenten Torsionen und Magnetisirungen bewirken (S 239, a, S 193)

The perusal of this type of descriptive (as distinguished from quantitative) reasoning leaves the mind almost as unsatisfied after as before, and Wiedemann himself freely acknowledges that his theoretical considerations do not fully explain all the observed phenomena (S 247, a, S 201) They do not, however, reduce in the least the value of the experimental part of this important memoir

[716] Resal *Recherches sur les effets mécaniques produits dans les corps par la chaleur Comptes rendus*, T LI, pp 449-50, Paris, 1860

This is an abstract from a memoir presented to the Academy The author supposes a body which is submitted to a uniform surface pressure to be heated The heat expended is then divisible into two portions, one of which does work against the uniform pressure, the other does internal work (*travail que l'on peut considérer comme le résultat du développement ou de l'introduction dans le système matériel de nouvelles forces moléculaires essentiellement repulsives*, p 450) The object of the memoir is the discovery of an expression for the latter work in the case of homogeneous bodies

Resal gives the following expression for it in solids :

$$T = \frac{wE\alpha^2}{3\pi c},$$

where α = coefficient of linear dilatation,

E = stretch-modulus,

w = specific weight,

c = specific heat.

No proof is given of this formula, nor do I understand how it is deduced.

[717.] Hermann Vogel: *Ueber die Abhängigkeit des Elasticitätsmoduls vom Atomgewicht. Annalen der Physik*, Bd. CXL, S. 229—239, Leipzig, 1869.

This is an endeavour to find a relation between the stretch-modulus and the coefficient of thermal expansion, but neither the theoretical reasoning nor the numerical results are satisfactory.

Let α be the coefficient of linear thermal expansion, c the specific heat and w the specific weight of a prismatic metal rod of unit length, unit cross-section and unit (?absolute) temperature. The quantity of heat of a volume of water equal to that of the rod being unity, then the amount of heat in the metal rod equals cw . This amount of heat produces an extension in length equal to α , and therefore unit quantity of heat produces an extension equal to $\alpha/(cw)$.

Vogel then continues :

Derselbe Stab erleidet durch eine, in der Richtung der Länge wirkende, dehnende, der Gewichtseinheit gleiche Kraft eine Ausdehnung, die man den *Dehnungsquotienten* nennt.

Ist nun die Arbeit, welche die Wärmeeinheit zu leisten vermag, eine constante Grösse, so werden die Ausdehnungen, welche verschiedene Metalle durch die Wärmeeinheit erfahren, in demselben Verhältnisse zu einander stehen, wie ihre Dehnungsquotienten (S. 230).

Vogel denotes by *Dehnungsquotient* the reciprocal of our stretch-modulus; and the first paragraph is intelligible, but I do not understand the second, for the amount of heat communicated not only dilates the body but also raises its temperature, and even if there were no heat expended in raising the temperature, the extensions which different metals receive from unit quantity of heat ought to be as the reciprocals of their dilatation-moduli rather than as those of their stretch-moduli. These two sets of ratios will not necessarily be equal unless we presuppose uni-constant isotropy.

[718.] It is possible of course if the amount of heat used in raising temperature be proportional to the total amount of heat applied to a

body that we may have, on the unit constant hypothesis, a relation of the form

$$\frac{E}{a} = \frac{E'}{a'} \frac{cw}{c'w'},$$

$$\text{or,} \quad \frac{Ea}{cw} = \text{a constant} \quad (1)$$

Hence it is worth while noting what numerical results Vogel gives. He finds for the metals the mean value of $Ea/(cw) = 2.44$, exactly agreeing with its value for silver. The minimum is 1.85 for lead and the maximum 3.18 for zinc. Below zinc stands iron with 2.79, and above lead are platinum with 2.01 and gold with 2.10. Thus the presumed constant has a rather wide range, which may be due to error in the theory, to the fact that the quantities were not determined from the same specimens of metal, or to the need of replacing the stretch-modulus by the dilatation modulus.

[719] According to Dulong and Petit and Regnault, if A be the atomic weight,

$$Ac = \text{a constant}$$

Hence, it must follow that

$$\frac{EaA}{w} = \text{a constant} \quad (11)$$

Or, the product of the stretch modulus, the coefficient of thermal expansion, the atomic weight and the reciprocal of the specific weight is a constant.

The exactitude of (11) seems even less than that of (1). The constant is 6.03 for lead, rising to 10.22 for zinc, the mean value being 7.716, which is not very different from that for tin (7.69). Vogel remarks of these results

In Anbetracht des Umstandes, dass alle in der Formel EaA/w enthaltenen Werthe, A ausgenommen, innerhalb gewisser Grenzen schwanken und noch dazu von verschiedenen Beobachtern an verschiedenen Metallstücken bestimmt worden sind, ist eine solche Uebereinstimmung immerhin merkwürdig genug (S. 233).

[720] Vogel then draws attention to a result of Masson's referred to in our Art. 1184*, 7, namely that the product of the reciprocal of the stretch modulus (*coefficient d'élasticité*) and the atomic weight or a multiple of the atomic weight is a constant. This would only be true according to Vogel's theory on the assumption that the ratios of the values of aE^2/w for the metals were as whole numbers. As a matter of fact they are nearly as 30 : 15 : 5 : 3 for iron, copper, silver and tin (S. 235). Vogel draws as easy corollaries from his formula the following statements

(1) If the values of a/w are in a very simple ratio to each other, then the product of the stretch modulus and the atomic weight or a multiple of it is constant.

For example, in the case of copper and silver, the values of α/w are very nearly equal, and we have $E\alpha = 397391$ for copper, and $= 409482$ for silver.

(ii) If for different metals $E\alpha$ is constant, then their specific volumes (or the values of A/w) are equal.

For example, in the case of iron and copper, $A/w = 3.6$, while the values of $E\alpha$ are $.2458$ and $.2157$ respectively.

Natürlich kann hier nicht von absoluter, sondern nur von annähernder Uebereinstimmung der Werthe von A/w und von $E\alpha$ die Rede seyn (S. 236).

[721.] Vogel in conclusion refers to Wertheim's result (see our Art. 1299*) that $E\left(\frac{A}{w}\right)^{\frac{7}{3}}$ is approximately constant for metals. Vogel

combines this with (ii) and finds: $\alpha \propto \left(\frac{A}{w}\right)^{\frac{7}{3}}$. He shows that for silver, iron and cadmium there is some approach to this law (S. 238).

He does not refer to Person's results, which are in some respects akin to his own: see our Art. 1388*.

While Vogel's theory is wanting in accuracy, and he himself admits that his formulae must not be pressed too far, still the numerical results of his paper are sufficient to show that careful experimental investigation in this field might lead to the discovery of results of great value, and for this reason the paper has been more fully referred to here than at first sight it appears to deserve.

GROUP B.

Kupffer's Memoirs with Zöppritz's theoretical Discussion of Kupffer's Results.

[722.] In 1849 the Russian government established a Central Physical Observatory in St Petersburg and appointed A. T. Kupffer as Director. According to the rules the Director had to furnish a yearly report on the experiments conducted in the Observatory as well as on other matters to the Minister of Finances. Thus arose the *Compte rendu annuel* of the *Observatoire physique central*. In these *Comptes rendus* for the years 1850 to 1861 will be found accounts of the researches in elasticity carried on by Kupffer. In 1860 he published the first volume of a great work entitled: *Recherches expérimentales sur l'élasticité des métaux faites à l'observatoire physique central de Russie*, Tome 1, St

Petersburg, 1860 This first volume is devoted to the experimental study of flexure and the transverse vibrations of elastic laminae with a view to the discovery of the elastic properties of metals A second volume was to be devoted especially to metals prepared in Russia and a third to torsion and torsional oscillations Further Kupffer promised to consider the resistance of metals strained beyond their elastic limit and also up to rupture Only the first volume of this important work was ever published, experiments partly covering the ground of this volume, and partly that of the proposed succeeding volumes, will be found in the above mentioned *Comptes rendus* up to 1861 see also our Art 1389* After this date they ceased and Kupffer died in 1865 Separate memoirs by Kupffer belonging to the period 1850-60 are also considered in our Arts 745-57 His researches are among the most elaborate and careful that have ever been made on the elasticity of metals We shall commence our consideration of them by noting points in the *Comptes rendus* not embraced in the volume of 1860

[723] *Compte rendu annuel* Année 1850 (St Petersburg, 1851) Pp 1-11 are occupied with a description of the apparatus recently erected and of the experiments made on the elasticity of metals at the new observatory The torsional experiments referred to are chiefly those of the memoir of 1848 see our Art 1389* The experiments on flexure are the earliest of the series described in the work of 1860, namely the determination of the stretch modulus by the transverse oscillations of a clamped free rod One or two points may be noted

(a) Kupffer as a rule uses in his experiments the symbol δ (sometimes δ') for the extension of a rod of unit length and unit radius (circular cross section) under the traction of unit force On p 9 of the *Compte rendu* for 1850 he gives a formula 'ou δ designe le coefficient d'élasticité du métal' On p 19 of the *Recherches expérimentales* he writes 'on designe par $1/\delta'$ ce que l'on appelle ordinairement le coefficient d'élasticité' Here δ or $\delta' = 1/(\pi E)$, where E is the stretch modulus Elsewhere in the *Recherches* he uses δ for $\pi\delta'$ and terms it the *dilatation élastique* (pp xv and xxi) On p 299 of the *Recherches* he says let $\beta = \text{l'accroissement du coefficient de dilatation élastique}$, and then uses a formula involving β and δ in such fashion that he evidently means δ to be the *coefficient de dilatation élastique* His experiments really go to show that the stretch modulus (and presumably the slide modulus) *decreases* with increase of the temperature, or that δ increases with increase of temperature If this be so, he must in the 11-11 of the memoir of 1848 cited in our Art 1395* mean by *coefficient*

d'élasticité the quantity δ , although both in that memoir and in the *Recherches* he defines this coefficient as either $1/\delta$ or $1/\delta'$. This really follows from the results in our Arts. 1392* and 1396*. Hence in the remarks following the citation in our Art. 1395* the words 'slide-modulus increases' and 'is probably increased' should be replaced by 'slide-modulus decreases' and 'is probably decreased' respectively. This confusion in terms is not confined to the *coefficient d'élasticité*; it is occasionally difficult to understand what Kupffer means by *la force élastique du métal*, a term which he freely uses in summing up his results.

In the present notice of his experiments (p. 4) he refers in the following words to Wertheim's results on the relation of temperature to the elastic moduli (see our Arts. 1298* and 1301*, 5°):

Ces mêmes expériences [i.e. those on torsion of 1848] m'ont fait voir que les changements de température exercent une influence sensible sur la force élastique des fils métalliques, qui augmente, lorsque la température diminue, et réciproquement. Les expériences de M. Wertheim.....avaient déjà signalé cette influence pour de grands intervalles de température; mes expériences étaient assez rigoureuses pour la préciser pour les différences de température de 10 à 15° R. M. Wertheim est arrivé à des résultats fort différents des miens, et la loi qu'il a trouvée n'est pas aussi simple que celle que je viens d'énoncer; mais comme nos valeurs ont été obtenues par des méthodes d'observation très différentes, elles ne sont pas exactement comparables. Cette question a encore besoin d'être traitée à fond, et le sera assurément, puisque la Société Royale des Sciences de Göttingue en a fait une question de prix pour l'année 1852.

[724.] (b) A second point worth noting is a suggestion, made I believe for the first time, to determine the mechanical equivalent of heat from the force necessary to produce a given stretch. It is contained in the following words:

Nous avons vu dans ce qui précède qu'on peut déterminer, avec une très grande précision, la dilatation qu'un fil éprouve par l'action d'un poids; évaluer ensuite la dilatation de ce même fil par la chaleur, n'est-ce pas évaluer en poids la force mécanique de la chaleur? (p. 5).

The reasoning, however, by which Kupffer deduces the mechanical equivalent of heat seems to me very doubtful, and the agreement of his value for it with Joule's must I think be looked upon as a happy coincidence.

The same numerical results as are here given are repeated in a paper in the *Bulletin*, but the reasoning there is somewhat different: see our Art. 745.

In the first place Kupffer makes an appeal to the theorem, due to Poisson, that the same traction applied to the terminal sections of a bar produces double the stretch that it would do if applied all over the surface. This is easily proved on the uni-constant hypothesis, but I fail to see that it is properly applicable to the present problem, where it would seem we ought to deal with equal quantities of work spent in these

two forms of strain rather than with equal tractions Kupffer then continues

Un cylindre, dont la longueur et le rayon sont égaux à l'unité, est allongé de cette même unité (c'est à dire d'un pouce), par un poids $p=1/\delta$, où δ désigne l'allongement que ce même cylindre éprouve par la traction de l'unité de poids (c'est à dire d'une livre), on peut donc évaluer la force élastique du cylindre, en disant qu'elle élève le poids p à la hauteur d'un pouce. En échauffant ce même cylindre de 0 à 80° R, il s'allonge de la quantité α , d'après l'hypothèse que nous avons adoptée plus haut, il s'allongerait de la quantité 2α , si l'effet de la chaleur n'avait lieu que dans une seule direction comme la traction, la quantité de chaleur, qui produit cet allongement est égal à wmd/d' , où w est la quantité de chaleur, qu'il faut pour élever de 0 à 80° R la température d'un cylindre d'eau, dont la hauteur et le rayon sont égaux à l'unité, m la chaleur spécifique et d' la densité du corps élastique, et où d' est la densité de l'eau* nous aurons donc l'expression $wmd/(2\alpha d')$ pour la quantité de chaleur, qui produirait un allongement d'un pouce, ou, comme les causes doivent être égales, lorsque les effets sont égaux, nous aurons évidemment $p=wmd/(2\alpha d')$. Mais nous avons aussi $p=1/\delta$ (p. 6).

* J'appelle densité le poids de l'unité de volume ou d'un pouce cube

Hence Kupffer reaches as his final equation

$$1/\delta = wmd/(2\alpha d'),$$

and by substituting the numerical values of the quantities involved, he finds a magnitude for w agreeing closely with Joule's

[725] But Kupffer obtains this result by a compensation of errors. In the first place the elastic work corresponding to p and unit extension ought to be $\frac{1}{2}p$ and not p . And further it is not evident that 'the effects are equal' (*les effets sont égaux*), for in the case of a pure elastic strain we have the body at temperature 0, say, but in the application of heat we have the same strain *together* with the body at a temperature of 80° R. Suppose H the quantity of heat given to the body and let it be held at the strain produced by this amount of heat and cooled down to temperature 0, and in doing so let H' be the amount of heat communicated to the refrigerator, and h the amount of heat the body would give off in being strained at constant temperature zero up to the same expansion, then the heat equivalent to the mechanical strain would seem to be $H - H' + h$ and not H as Kupffer assumes. There is, I think, no reason for assuming $H' - h$ indefinitely small as compared with H , indeed Kupffer's result seems to indicate (since he has dropped the $\frac{1}{2}$) that $H' - h = \frac{1}{2}H$ approximately in his case, otherwise his errors would not compensate each other as they appear to do¹.

¹ Kupffer's results are quoted without any apparent questioning in some modern works e.g. G. Helm, *Die Lehre von der Energie*, S. 91 just as they were cited in the *Philosophical Magazine Poggendorff's Annalen* and other journals without demur in 1852. In the *Fortschritte der Physik* for 1852, S. 373-7 Helmholtz remarks that the argument of the famous St Petersburg physicist is too brief to be open to intelligent criticism and he shows that Kupffer's formula is not identical with any of the known equations of Thermodynamics. He does not however, distinctly state that it cannot be true. Compare Vogel's paper discussed in our Aits 717-21.

[726.] (c) The last point to be noted in the present paper is the experimental discovery of after-strain in metals. Both Seebeck and Clausius had suggested its existence (see our Arts. 1402* and 474), but no physicist had distinctly seen and measured its effect, so far as I am aware, before Kupffer.

The following sentences give his conclusions :

(i) La flexion qu'une verge encastrée par une extrémité et libre de l'autre éprouve par une charge quelconque, suspendue à son extrémité libre, augmente avec le temps, et ne s'arrête qu'après un temps plus ou moins long, quelquefois après plusieurs jours seulement.

(ii) Lorsqu'une verge est restée fléchie pendant quelque temps, ce n'est qu'après un intervalle de temps plus ou moins long, qu'elle revient exactement à sa première position.

(iii) Une verge fléchie par un poids, pendant un instant seulement, revient tout de suite et exactement à sa première position, aussitôt que le poids a été ôté, mais cela n'a lieu que jusqu'à une certaine limite ; lorsque le poids dépasse cette limite, la verge ne revient plus tout de suite à sa première position ; elle n'y revient qu'après longtemps ou pas du tout (p. 11).

The last statement shows the possibility of *set* combined with after-strain arising from instantaneous loading.

[727.] *Compte rendu annuel*. Année 1851 (St Petersburg, 1852). Pp. 1-11 give an account of experiments to determine the elastic constants of iron and brass by different methods. Kupffer finds that for brass pure traction and flexure experiments give practically the same value for the stretch-modulus, but that this value differs considerably from the value deduced on the uni-constant hypothesis from the slide-modulus as determined by the method of torsional vibrations. Nor is the ratio of the slide- to the stretch-modulus the same for brass and for iron wire. This would be an argument against uni-constancy, if we could assume Kupffer's wires to have been isotropic (pp. 1-5). Kupffer next refers to the various effects which strain, annealing etc. have on the stretch-modulus, as obtained by the method of transverse vibrations of a bar (pp. 5-7), and then he deals with the influence of the resistance of the air on torsional vibrations (pp. 7-10). These matters will be more fully dealt with in our discussion of Kupffer's great work of 1860.

[728.] *Compte rendu annuel*. Année 1852 (St Petersburg, 1853). Pp. 1-19 furnish a further account of flexure experiments to determine the stretch modulus. The experiments were made partly by oscillatory, partly by statical methods. $1/\delta' = 1/(\pi\delta)$ is defined as *le coefficient d'élasticité du métal*¹ (p. 6). With regard to experiments by these

¹ δ and δ' exactly change meanings in the *Comptes rendus* and the *Recherches* ! compare pp. 19 and 133 of the latter work with p. 9 of the *Compte rendu* for 1850 or p. 6 of that for 1852 ; i.e. $\delta = \pi\delta' = 1/E$ in the *Recherches*, but $\delta' = \pi\delta = 1/E$ in the memoir of 1848 and the *Comptes rendus*.

different methods Kupffer finds (pp 13 and 19) in Russian measure the following results for $1/E$

Material	Statcal Method	Oscillatory Method
Soft Steel Lamina, No 5	$10^{-13} \times 296,020$	$10^{-13} \times 297,952$
Soft Cast Steel, No 6	$10^{-13} \times 301,055$	$10^{-13} \times 300,623$
Platinum Lamina	$10^{-13} \times 358,600$	$10^{-13} \times 358,438$
Brass Rod	$10^{-13} \times 592,913$	—
Iron Rod, No 3	$10^{-13} \times 329,270$	$10^{-13} \times 322,363$ (<i>Recherches</i> , p 283)

So far as this table goes we see that with the exception of the first steel lamina, δ is greater and therefore the stretch-modulus E is less when calculated by the statical method. The differences are small except in the case of iron. The exception in the case of one kind of steel agrees with the difference found by Kennedy and Wullner (see fn p 702 of our Vol I, where obviously the conclusion should say 'in favour of' and not 'opposed to' Wertheim's result). The numbers given for the steel lamina No 6 and for platinum in the *Recherches* vary a good deal (see pp 219–229, and 264–5) and therefore are perhaps not very exact. If E_s be the static and E_k the kinetic stretch modulus we have

For platinum, $E_k/E_s = 1.00045$,

For iron, $E_k/E_s = 1.0214$

These ratios are less than those obtained by Weber and Wertheim (see our Arts 705* and 1403*, Weber's numbers give for iron 1.072, for platinum 1.21 and for copper 1.09). Results like these differ, however, so enormously from those calculated by Sir W Thomson (Article *Elasticity* in the *Encyclopaedia Britannica*, § 76, *Thermodynamic Table II*, or *Mathematical and Physical Papers*, Vol III, p 71) and also among themselves, that but little faith can be placed in them. In fact they depend in Kupffer's case on the last three figures of his values, but an examination of the individual experiments shows that these three figures vary very greatly from one experiment to another. Kupffer gives no value of δ for the brass rod in the *Compte rendu*, but the values he gives for such rods in the *Recherches* (pp 111–21) make $E_k/E_s < 1$. Hence Kupffer's results will not allow us to assert that the kinetic method always gives larger stretch modulus than the static, and that the differences are too great to be explained solely by thermal action. Even if we could allow for influence of after strain (see our Arts 1402* and 474) the extreme difficulty of determining the modulus accurately to six places of figures would render any evaluation of the ratio of specific heats by Kupffer's process impossible.

Kupffer himself attributes the difference between the values of the modulus as obtained by the two methods to the fact that in the case of

transverse oscillations the rods oscillate elliptically and never in a plane, and he holds that this tends to diminish slightly the duration of the oscillations (ftn. p. 19). He does not demonstrate this, and I do not see why it should be true: see as to other difficulties our Art. 821 and footnote.

[729.] *Compte rendu annuel.* Année 1853 (St Petersburg, 1854). The continuation of experiments on the determination of the stretch-modulus by static and kinetic methods is described on pp. 1-7. Kupffer notes that the static flexural method gives results more in accordance with themselves than the kinetic (on voit encore ici, que les valeurs de δ' , obtenues par la flexion, sont d'une exactitude bien supérieure à celle, qu'on peut obtenir par des oscillations transversales, p. 4). A series of experiments on the static flexure of cast-iron is described on pp. 6-7. Kupffer remarks that flexural set always occurs with this kind of iron, and that when this is subtracted from the total flexure due to the load the deflections are still not proportional to the loads, but increase more rapidly than the loads. Thus for two bars (i) and (ii) of specific gravities 7.124 and 7.130 respectively we have

$$(i) \quad \begin{cases} \delta' = 10^{-13} \times 622,724 \text{ for a total load of 1 lb.} \\ = \dots \times 636,762 \dots\dots\dots 1.125 \text{ lbs.} \\ = \dots \times 653,590 \dots\dots\dots 1.375 \text{ lbs.} \end{cases}$$

For this bar $\delta' = 10^{-13} \times 559,288$ from transverse oscillations.

$$(ii) \quad \begin{cases} \delta' = 10^{-13} \times 589,100 \text{ for a total load of 1 lb.} \\ = \dots \times 601,650 \dots\dots\dots 2 \text{ lbs.} \\ = \dots \times 620,860 \dots\dots\dots 3 \text{ lbs.} \\ = \dots \times 636,980 \dots\dots\dots 4 \text{ lbs.} \end{cases}$$

For this bar $\delta' = 10^{-13} \times 564,137$ from transverse oscillations¹. These and similar results are in general conformity with Hodgkinson's experiments: see our Arts. 969* and 1411*, and conclusively show the want of exact meaning in the term stretch-modulus for the case of cast-iron.

[730.] In this year Kupffer also began a series of experiments on the dilatation by heat of the same metal bars as he had been experimenting on elastically. The observations were made by taking each bar as a pendulum, the bob being so attached to the bar that the distance of its centre of gravity from the axis of oscillation depended only on the length of the bar. The results of experiments on two brass bars only are given. These bars were taken from the same casting but one had been vigorously hammered. The coefficients of linear expansion were measured for an increment of 1° between 25° R. and 30° R. We have:

	Coefficient.
Cast brass	.000,025,727.
Hammered brass	.000,024,980.

¹ This number is incorrectly given in the *Compte rendu*: see the *Recherches*, p. 87.

Thus the ratio = 1 030 1 about. The ratio of the specific gravities was 1 1 035, or the coefficients of expansion were nearly inversely proportional to the specific gravities

[731] The *Compte rendu* for this year also contains a scheme for an extensive series of experiments on the entire elastic life of materials prepared in Russia. This scheme is perhaps the most complete ever drawn up for a detailed investigation of the cohesive and elastic properties of metals. The commission proposed in it would have achieved on a more catholic and more scientific (physical as distinct from empirico-technical) basis for many metals what the English commission did for iron only see our Art 1406*. Such experiments as Kupffer made in this direction would have occupied the second volume of his *Recherches*, what they were we can only gather from subsequent numbers of the *Comptes rendus*. The programme is drawn up with a view to the industrial use of metals, and I only regret that our space does not permit of its reproduction here. Elastic properties, as well as those of set and rupture, are taken into full consideration, further the influence of the various processes of manufacture, of working, of temperature-effect, of impulsive and long continued stress on one and all of these properties are dealt with. As a scheme for further physico-technical researches in elasticity, or for a treatise on the subject, Kupffer's programme would still, with a few modifications in the light of more recent discoveries, be of very great value. It occupies pp 11–14 of the *Compte rendu annuel*

[732] *Compte rendu annuel* Année 1854 (St Petersburg, 1855) The account of elastical researches occupies pp 1–28. It commences with some further remarks on flexural measurements chiefly directed to investigate the effect of 'working' on the metals. Kupffer concludes that "l'élasticité des métaux est considérablement augmentée par le travail qu'ils subissent dans le laminage, l'écrouissage et en passant par la filière" (p 3). By an augmentation of the elasticity is to be understood a smaller value of δ or a greater value of the stretch modulus

[733] The major portion of this report is occupied with experiments on torsion (pp 4–28). These were made with an apparatus similar to, but far more exact than that used for the experiments described in the memoir of 1848 see our Art 1389*. An account of this apparatus will be found in the *Compte rendu* for 1850 and it is repeated here (pp 4–5). The apparatus involves an oscillatory method of experiment, but one used by Kupffer with extreme accuracy and careful determination of all the possible sources of disturbance. The real slide-modulus μ is to be obtained from Kupffer's δ by the relation $1/\delta = \pi\mu$ see our Art 1390*. Kupffer's μ (p 6) is *not* our slide modulus, but $-\frac{1}{2}\pi\mu$, i.e. it is the moment of the force necessary to turn through unit angle a cylinder of unit radius and unit length

[734.] Kupffer confirms his former result (see our Art. 1391*) as to the law connecting the duration of the oscillations with the amplitudes. He finds that a/P_s (in the notation of our article referred to), now written ψ , depends largely on the nature of the material and the working it has been subjected to. This quantity ψ is termed by Kupffer the *coefficient of fluidity*. Kupffer's 'fluidity' of metals is a property corresponding to Sir W. Thomson's 'viscosity' (see our Chapter devoted to that physicist), and as it appears to be the first real consideration of the matter, I quote p. 15 of Kupffer's remarks :

ψ a une valeur constante pour chaque fil, mais varie considérablement d'un fil à l'autre, comme le prouvent non seulement les expériences que je viens d'exposer et qui se rapportent au fer et à l'acier, mais aussi toutes les observations qui vont suivre.

Les observations précédentes donnent

pour le fil de fer $\psi = \cdot 000616$,

pour le fil d'acier $\psi = \cdot 0003736$.

C'est-à-dire la valeur de ψ est 17 fois plus grande pour le fer, que pour l'acier.

De là il suit que l'accroissement, que la durée des oscillations éprouve lorsque les amplitudes augmentent, ne peut être un effet de la résistance de l'air, ni une conséquence de la loi générale de l'élasticité, quelle qu'elle soit d'ailleurs (que l'élasticité soit proportionnelle aux accroissements de la distance entre les molécules, ou qu'elle suive une autre loi relativement à ces distances); cela doit être une propriété inhérente aux corps élastiques, qui varie d'un métal à l'autre, qui varie même pour le même métal, selon le travail qu'il a subi.

J'ai fait voir, par des expériences rapportées dans mon Compte rendu de l'année 1851, que l'amplitude des oscillations diminue aussi bien dans le vide, que dans l'air, cette diminution ne peut donc pas être non plus un effet de la résistance de l'air, cette résistance la fait seulement diminuer plus rapidement. La position d'équilibre, à laquelle il faut rapporter toutes les forces, qui font osciller un fil métallique, se déplace continuellement et toujours dans le sens des oscillations; de sorte que cette position d'équilibre oscille avec le fil même autour d'une position moyenne, qui est celle du fil complètement revenu au repos. Il paraît que les molécules des corps solides possèdent la propriété non seulement de s'écarter les unes des autres, en produisant une résistance proportionnelle aux écarts, mais aussi de glisser les unes sur les autres, sans produire aucun effort. Cette propriété est possédée à un haut degré par les fluides; je la nommerais donc volontiers la fluidité des corps solides; le coefficient ψ pourrait être appelé coefficient de fluidité; la malléabilité des métaux paraît en dépendre, et peut être aussi leur dureté; des expériences ultérieures nous apprendront jusqu'où va cette analogie.

Le coefficient de fluidité peut varier beaucoup dans le même métal, deux autres fils de fer de $\cdot 04801$ et de $\cdot 08099$ de rayon ont donné $\psi = \cdot 000393$ et $\psi = \cdot 000494$. Pour un fil de cuivre jaune de $\cdot 09518$ de rayon, il a été trouvé égal à $\cdot 000284$, pour un autre, dont le rayon était égal à $\cdot 0807$ on a eu $\psi = \cdot 000930$. Mais il varie surtout d'un métal à l'autre: on a.

pour le platine $\psi = 0001376$,

pour l'argent $\psi = \cdot 0003650$,

pour l'or $\psi = \cdot 000300$.

Here we have a very clear description of the action of viscosity in metals, a property which has much exercised physicists upon its frequent rediscoveries since Kupffer's investigations of 1848-1854

[735] But Kupffer's torsion experiments led him to consider several other points connected with torsional vibrations which have been largely dealt with in recent years. Thus

(i) On pp 16-23 he shows how the resistance of the air may be taken into account and eliminated

(ii) On p 23 he refers to the reduction of the observations to a constant temperature see our Arts. 1392* and 1396*

(iii) On pp 23-28 he discusses what effect the traction of a wire has on its torsional resistance. This is important as it is necessary to allow for the weight of the vibrator

Kupffer had in the *Compte rendu* for 1851 given the following result, where M and M' are respectively the torsional rigidities of the wire¹ without and with a traction which produces a stretch s in the wire

$$M' = M(1 - 3s)$$

Kupffer remarks that Neumann of Königsberg (the great *Franz*) had sent him the result

$$M' = M(1 - \epsilon s),$$

where ϵ can vary between the limits 1 and 3, as the result of a mathematical investigation in which it is not assumed that the elastic coefficients are altered or the proportionality of stress and strain abrogated. The investigation is not given, but it is easy to replace it. Let η be the stretch squeeze ratio, and let the wire be of length l and radius r , then we have for the torsional rigidity without traction

$$M = \mu \frac{\pi r^4}{2l},$$

and with traction

$$M' = \frac{\mu \pi r^4 (1 - \eta s)^4}{2l(1 + s)} = M \{1 - (1 + 4\eta)s\}$$

Now η can take all values from 0 to $\frac{1}{2}$ for bi constant isotropy see our Art 169 (d). Hence Neumann's statement follows. That Kupffer's experiments gave $1 + 4\eta = 3$ or $\eta = \frac{1}{2}$ for his wires, brass and steel, I attribute, not to the fact that those wires had bi constant isotropy approaching its limit, but to their being really anisotropic.

[736] A result also due to Franz Neumann and recorded by Kupffer in a note on p 24 deserves notice. He says that Neumann had shown by fixing small mirrors to a rectangular bar under flexure

¹ Torsional rigidity of a wire is a convenient term for the torsional moment per unit angle of torsion

that a cross-section perpendicular to the axis is no longer a rectangle but a *trapezium*¹. This had been previously shown by E. Clark for set (see our Art. 1485*), and it is a physical confirmation of Saint-Venant's theory so well exhibited in his plaster-models of flexure: see our Arts. 92 and 95, and also the *Leçons de Navier*, p. 34.

Kupffer further notices that Neumann had experimentally demonstrated that the volume of a wire increases under traction up to the elastic limit, but that if it is stretched beyond this limit, the volume remains constant, i.e. that set is unaccompanied by change in volume. According to Kupffer, Neumann had also shown experimentally that the value of the stretch-squeeze modulus is not constant (e.g. $\frac{1}{4}$ according to Poisson, or $\frac{1}{3}$ according to Wertheim) but varies with the nature of the metal. Kupffer does not state what was the method used in Neumann's experiments (*expériences également ingénieuses et précises*).

[737.] *Compte rendu annuel*. Année 1855 (St Petersburg, 1856). This report deals with the influence of heat on the elasticity of metals. This as we have seen (Art. 723) was the subject of a prize offered by the Royal Society of Göttingen. It was awarded to Kupffer in November, 1855.

He divides his researches under two heads:

(i) Influence of an increase of temperature on elasticity, lasting only while this temperature is maintained.

(ii) Changes produced by an increase of temperature on elasticity after the thermal influence has ceased. Of these he writes:

On verra dans le cours de ces recherches, que ces deux actions de la chaleur sur les corps élastiques sont très différentes, elles peuvent même être opposées; lorsque la température d'un corps élastique augmente, son élasticité diminue toujours; mais lorsque l'action de la chaleur cesse et lorsque le corps élastique est revenu à sa température initiale, son élasticité ne revient pas toujours à la même valeur, mais elle a souvent changé considérablement; tantôt on la trouve augmentée, tantôt on la trouve diminuée (p. 2).

Kupffer points out that the elasticity of metals can be easily in-

¹ Turning to our Art. 95 we obtain for the tangent of the angle ψ through which a small mirror would be turned if fixed at the middle of a vertical side of a cantilever at a distance ζ from the loaded end

$$\tan \psi = \eta_1 \frac{P \zeta b}{E \omega \kappa^2} \dots \dots \dots (1).$$

If a small mirror were fixed to the middle of the top of the beam at the same distance, it would be turned through an angle ψ_1 , given by

$$\tan \psi_1 = \frac{P \zeta c}{E \omega \kappa^2}, \text{ approximately } \dots \dots (11).$$

Hence $\tan \psi = \eta_1 \frac{b}{c} \tan \psi_1$, and we have what appears to be a practical optical method of determining the stretch-squeeze ratio η_1 . It might also be found by substituting directly the value of E in (i).

vestigated in three different ways and the effects of heat on all these ought to be considered These are

Statistical Traction—Longitudinal Vibrations,

Statistical Flexure—Transverse Vibrations,

Statistical Torsion—Torsional Vibrations

[738] He points out how the investigations in these directions are affected by secondary elastic properties, more particularly by elastic after strain He now attributes to this property the augmentation of the duration of the oscillations, which he had found in torsional oscillations to vary as the square root of the amplitude see our Art 1391* In other words he supposes elastic after strain to be the origin of the property he has termed *fluidity*, or of our more modern *viscosity* Sir W Thomson seems to think also that the viscosity may be due wholly or partially to elastic after strain see our ftn p 390, Vol 1

[739] Returning to the formula of our Arts 1391* and 734, or

$$P_0 = P_s (1 - \psi \sqrt{s}),$$

we note that Kupffer now states that he has found more accurately how ψ varies with the size of his wire If r be the radius of the wire, l its length and ν a constant coefficient which depends on the elastic properties of the material, then

$$P_s = P_0 \left(1 + \nu r \sqrt{\frac{s}{l}} \right)$$

Kupffer terms ν the “true coefficient of fluidity or ductility” We may perhaps term it the “after strain (or viscosity) coefficient for torsional vibrations” see our Art 751 (d)

[740] The rest of the memoir is occupied with details taken from the great memoir on thermo elasticity see our Arts 748–57 If the temperature be raised from t to t' and the stretch and slide moduli change from E, μ to E', μ' respectively, then Kupffer gives the values of β_r and β_τ for various metals, where

$$E' = E \{1 - \beta_r (t' - t)\},$$

$$\mu' = \mu \{1 - \beta_\tau (t' - t)\}$$

These values are determined by transverse and torsional vibrations¹

¹ Kupffer neither here nor in his memoir clearly states whether he has attempted to eliminate the effect of heat in lengthening his wire and so affecting the torsional vibrations If he has not then by our Art 735 (m) the torsional moment is altered and thus the slide modulus will appear to be altered The alteration would be given by a formula of the form $\mu' = \mu (1 - \epsilon s)$ where s is the thermal stretch $= \alpha (t' - t)$, α being the coefficient of linear thermal dilatation Now for brass Kupffer has found (see our Art 730) $\alpha = 0.00025727$ and $\epsilon = 3$ nearly, hence $\mu' = \mu \{1 - 0.00077181(t' - t)\}$, but β_τ for the like brass = 0.006982 Thus the purely lengthening effect of change of temperature on the wire would only account for about $1/9$ of the change in μ

It should be noted that β_r here is twice the β of our Art. 1396*. The results are considered at length in our Arts. 752–4. We merely note now that the values of β_r are given for higher ranges of temperature than in the memoir of 1848: see our Arts. 1392* and 1396*. The effect also on ν of changes in temperature are noted as in the memoir above referred to.

[741.] *Compte rendu annuel*. Année 1856 (St Petersburg, 1857). Pp. 57–66 give an account of the elastical researches carried out during the year in the *Observatoire physique central*. One or two points may be noted:

(a) Three laminae were formed from the same piece of cast brass, the first remained as originally cast, the second was vigorously rolled (*fortement laminé*) and the third vigorously hammered (*fortement martelé*). It was found that their *stretch-moduli were nearly in the ratio of the squares of their densities*. The same result was very nearly true for specimens of English and Swedish wrought-iron (compare Art. 759 (e)).

On voit par ce qui précède, combien l'influence du martelage et du laminage sur l'élasticité des métaux est grande (p. 58).

The result is important if only approximate.

Kupffer regards (pp. 59–62) from a very insufficient theoretical standpoint the effect of a stretch produced by heat or load on the value of the elastic constants as obtained by experiment. He seems to have considerable difficulties with Neumann's formula (see our Art. 735 (iii)), largely due, I think, to his assumption that wires possess isotropy. He wants (p. 62) to reject the formula

$$M' = M(1 - \epsilon s)$$

as an explanation of the effect of traction on torsion when he finds values of ϵ greater than 3, although this would in fact not necessarily indicate anything more than anisotropy: see our Art. 308 (b).

He gives the results of some experiments on the value of ϵ when successive set-stretches are given to a wire under torsion; ϵ begins by being as great as 6 and diminishes to about 3·4 as the sets are continued.

(c) The report concludes with the results of a number of Kupffer's experiments giving the elastic moduli in kilogramme-millimetre units: see our Art. 772.

[742.] *Compte rendu annuel*. Année 1857 (St Petersburg, 1858). This contains:

(a) Values of the stretch-moduli for various kinds of Russian steel and comparison with the values for English steel (pp. 55–6).

(b) Proposals to measure the value of gravitation at different points of the earth by the difference in the periods of transverse vibration of an elastic rod clamped vertically and with a weight attached to its upper or free extremity (pp 60–1)

[743] *Compte rendu annuel* Année 1858 (St Petersburg, 1860) A few results for the stretch-modulus of copper, steel, aluminium and tin are given in French measure (p 51)

Compte rendu annuel Année 1859 (St Petersburg, 1861) This contains nothing concerning elasticity but a notice of the completion of the printing of the first volume of the *Recherches* (p 41)

Compte rendu annuel Année 1861 (St Petersburg, 1862) On pp 45–48 numerical values are given of the inverse of the stretch-moduli and of the specific gravities of various metals, principally different kinds of Russian and Austrian iron and steel

The *Comptes rendus* for the years 1862–4 give promises of further experiments on elasticity,—promises destined never to be fulfilled

[744] We now turn to the memoirs Kupffer published during this decade and note first two shorter ones which are printed in the *Bulletin*. We shall then pass to the long memoir on thermo elasticity and conclude with an analysis of the *Recherches*

[745] A F Kupffer *Bemerkungen über das mechanische Aequivalent der Wärme Bulletin de la Classe physico-mathématique de l'Académie Impériale des Sciences*, T x, cols 193–7 St Petersburg, 1852 A reprint of this paper will be found in the *Annalen der Physik*, Bd 86, S 310–14, 1853 Suppose a cylinder of unit length and unit radius to receive extension δ under unit tractive load, and further when it is raised from freezing to boiling point of water let its extension be a Then if m be the specific heat of the metal and S its specific gravity, it will take mS times the heat to raise the metal cylinder from 0° to 100° that it takes to raise a cylinder of water of the same radius and height through the same range of temperature

Let c be the latter quantity in mechanical units, then we have cmS for the work done Kupffer now continues

Da nun die Ausdehnungen, die ein Diath erleidet, den angewandten Kriften proportional sind, so sieht man gleich, dass die Werthe von a und δ uns eine Vergleichung der ausdehnenden Kraft der Wärme mit der dehrenden Krift eines Gewichts darbieten, oder mit andern Worten, dass jene Werthe uns ein Mittel an die Hand geben, das

mechanische Aequivalent der Wärme zu bestimmen. Man muss hier nicht vergessen, dass die Wärme gleichmässig nach allen Seiten wirkt, wie ein Druck: nun hat aber Poisson gezeigt, dass ein Gewicht welches einen Drath um δ ausdehnt, als nach allen Seiten gleichmässiger Druck angewandt, eine lineäre Ausdehnung von $\frac{1}{2}\delta$ hervorbringen würde. Wir haben also $2a/\delta$ als das Verhältniss der mechanischen Wirkung der bezeichneten Wärmemenge zur mechanischen Wirkung eines Pfundes anzusehen. Um dieses Verhältniss in Zahlen auszudrücken, darf man nur für irgend eine Substanz die elastische Constante, den specifischen Wärmestoff und das specifische Gewicht, so wie auch ihre Ausdehnung durch die Wärme kennen (Col. 194).

Kupffer then gives the equation :

$$cmS = 2a/\delta,$$

and calculates c in Russian units for the results he has found for iron, brass, platinum and silver wires. The mean value of these results he reduces to English and French units and finds

$$J = 9921 \text{ inch-pounds for } 1^\circ \text{ F.,}$$

$$= 453 \text{ kilogrammètres for } 1^\circ \text{ C.}$$

[746.] I do not follow Kupffer's reasoning. Putting aside the fact that he assumes the wires to possess uni-constant isotropy, he seems to me on this occasion to equate a quantity of heat or energy to a *force*. I have already alluded to the difficulties I feel with regard to Kupffer's method of treating this problem in Art. 725, and his argument here seems to me, although somewhat different, no clearer than that in the *Compte rendu annuel*.

[747.] A. F. Kupffer: *Untersuchungen über die Flexion elastischer Metallstäbe*. *Bulletin de la Classe physico-mathématique de l'Académie Impériale des Sciences*, T. XII., cols. 161–7. St Petersburg, 1854.

This contains matter which reappears in Kupffer's great work, notably the erroneous formulæ for flexion: see our Arts. 760–2.

Ibid. T. XIV., cols. 273–84, and cols. 289–99. *Einfluss der Temperatur auf die Elasticität der festen Körper*. This contains matter which reappears in the memoir of 1852–7 (see our Arts. 748–57) and partially in the *Compte rendu annuel* (see our Art. 740) and the *Recherches* (see our Arts. 770–1), so that we need not discuss it further here.

[748] A T Kupffer *Ueber den Einfluss der Wärme auf die elastische Kraft der festen Körper und ins besondere der Metalle Mémoires de l'Académie de St Pétersbourg, Sixieme Série, Sciences mathématiques, physiques et naturelles*, T VIII, *Première Partie Sciences mathématiques et physiques*, T VI, pp 397—494 (separate pagination 1—98), St Petersburg, 1857 This memoir, written in German, received the prize of the Royal Society of Gottingen in 1855 see our Art 723 It was apparently read before the St Petersburg Academy on December 3, 1852

It commences with a *Vorwort* describing its scope, of which the first paragraph may be cited here

Die nachstehende Abhandlung ist aus einer grosseren Arbeit über Elasticität entnommen, die noch nicht beendet ist, und die zu ihrer Zeit wird bekannt gemacht werden Ich habe einstweilen in der Einleitung einige allgemeine und noch nicht bekannte Thatsachen aus der grosseren Schrift mittheilen zu müssen geglaubt, um den Leser zu zeigen, wie man die Elasticitätscoefficienten derselben Metalle sehr genau bestimmen könne, und bestimmt hat, für welche in dieser Schrift der Einfluss der Temperatur auf diese Coefficienten bestimmt worden ist Indem ich durch Versuche erwies, dass der Einfluss der Temperatur bei Torsionsschwingungen ein anderer sein kann als bei Transversalschwingungen, war es interessant nachzuweisen, dass auch der Elasticitätscoefficient für die Torsionsschwingungen ein anderer ist, als für die Transversalschwingungen Diese Mittheilungen führten zur Erwähnung des Coefficienten ν , den ich den Flüssigkeitscoefficienten genannt habe, und von dem meines Wissens vor mir noch nicht die Rede war, oder dessen Werth wenigstens vor mir noch nicht genau bestimmt worden ist (S 399)

Thus Kupffer's discovery of viscosity and after-strain in metals dates at least from 1852 The *coefficient of fluidity* certainly appeared implicitly in the memoir of 1848 (see our Art 1391*), but I do not think Kupffer had at that date clearly separated its effect from that due to the resistance of the air

[749] The *Vorwort* goes on to state that all the experiments on temperature have been made by vibrational as distinguished from statical methods, in this case by means of transverse and torsional oscillations

Ich habe auch Versuche über den Einfluss der Temperatur auf das statische Moment der Elasticität gemacht, aber sie sind vollständig misslungen bei fortdauernder Erwärmung war die bleibende Aenderung des Flexions oder des Torsionswinkels so stark, dass die vorübergehende, mit der Erhöhung der Temperatur eintretende, und mit deren

Verminderung sich wieder vermindernde, ganz darin verschwand; die elastische Nachwirkung brachte noch mehr Verwirrung in die Resultate (S. 399).

The full complexity of elastic problems was fully appreciated by Kupffer and he foreshadows in the following words the direction of much of the research taken later by Bauschinger:

Ich sah daraus, dass um die Einwirkungen der Wärme auf das statische Moment der Elasticität zu finden, man vor allen Dingen ein Mittel haben müsste, die Einwirkung derselben Wärme auf die Verückung der Gränzen der Elasticität und auf die Nachwirkung von ihrer Einwirkung auf die Elasticität selbst zu trennen; um ein solches Mittel zu finden, werden noch viele Arbeiten über die Gränze der Elasticität und über die Nachwirkung erforderlich sein, so dass die Lösung dieses Problems mir noch sehr ins Unbestimmte hinaus gerückt zu sein scheint. Man hat aber erst angefangen die Gesetze der Elasticität in ihrem ganzen Umfange zu studiren; bei jedem Schritte stösst man in diesen Untersuchungen auf neue Eigenschaften der elastischen Körper; je weiter man vorgeht, desto mehr Verwicklung. Bei solchen Umständen ist wohl in diesem Augenblick keine völlig abgeschlossene Arbeit über irgend eine Eigenschaft der elastischen Körper möglich (S. 400).

Notwithstanding our great increase in knowledge, the same words may almost be used of the science of elasticity to-day. The fact is that to grasp thoroughly the bearing and mutual relations of the secondary elastic properties we must know what is the real kinship between the various branches of physics when viewed from the standpoint of the molecule—and this is very far from being understood even forty years after Kupffer wrote.

[750.] The next portion of the memoir, termed *Einleitung*, occupies S. 401–427. It contains details of the methods of experiment and of the formulae adopted¹. Several points here deserve notice:

(a) On S. 404–7 we have the details of the first scientific experiments on the elastic after-strain of *metals*², the existence of

¹ Kupffer, S. 402, defines the stress that can be called into play in a body by external pressure its 'elasticity.' This is another instance of his tendency to rather vague definition to which I have previously referred: see our Arts. 723 (a), 728 and footnote.

² Between Weber and Kupffer a few experiments on after-strain were made by R. Kohlrausch, and are referred to by him in an article on an electrometer in *Poggendorffs Annalen*, Bd. 72, 1847: see S. 393–6. His remarks amount to little more than the assertions that he has confirmed Weber's discovery of after-strain in silk threads, and finds that it is manifested also in the torsion of glass threads. He makes, further, some not very conclusive statements (S. 396–8) on the influence which rise of temperature has upon the torsional elasticity of silk threads, and upon the effect which boiling them in soapy water has on their elastic after-strain.

which had been doubted even by Wertheim and Saint-Venant see our Arts 819 (noting Art 803) and 197 The experiments were made on the flexure of a cylindrical bar of steel and the continual decrease of the deflections for a period of several days after the removal of the load was clearly marked The influence of elastic after-strain on the reduction of the amplitude and period of torsional vibrations *in vacuo* is also referred to on S 407-8

Die allmähliche Abnahme der Schwingungsweiten (selbst im luftleeren Raum) lässt sich sehr gut durch die Nachwirkung erklären, weshalb auch schon Weber vorausgesehen hat, dass die Schwingungsweiten elastischer Körper in luftleerem Raum allmählich abnehmen wurden, wie ich später durch Versuche bewiesen habe Die Nachwirkung bringt hier dieselbe Wirkung hervor, wie die Friction beim Widerstande der Luft, und besteht wohl auch in Nichts anderem, als in einem mit Friction verbundenem Gleitschen der Theile über einander nur ist nicht zu übersehen, dass die Friction der Theilchen unter einander nicht zu erklären im Stande ist, warum der Stab oder der Draht, nach Aufhebung der ablenkenden Kraft, wieder zu seinem ursprünglichen Gleichgewichtszustande zurückkehrt, diese Erscheinung setzt offenbar eine gewisse Kraft voraus, welche jeden festen Körper, selbst wenn er durch Aenderung seiner Form in andere Gleichgewichtsbedingungen versetzt worden ist, dennoch immer wieder in längerer oder kürzerer Zeit zu seiner ursprünglichen Form (oder zu seiner ursprünglichen Gleichgewichtsbedingung) zurückführt, wenn die Abweichung von der ursprünglichen Gleichgewichtslage nicht gar zu gross gewesen ist (S 407-8)

This passage seems to me to mark off the real distinction between after-strain and any frictional action between the parts of a body, and I think destroys the force of the comparison of a solid body's elastic after-strain with fluid action It is a strong reason for not allowing elastic after-strain to be masked under the term 'viscosity' see the footnote p 390 of our Vol I

(b) Kupffer shows that elastic after-strain is not proportional to the load and that accordingly the vibrations are not truly isochronous (see his S 407-8) He further adds that working temperature etc have all great influence on the elastic after-strain as well as on the elastic fore-strain (S 409)

[751] (c) The next portion of the *Einleitung* is termed *Transversalschwingungen elastischer Stäbe*, and occupies S 409-419 This contains the formula for transverse vibrations, which I shall have occasion again to refer to when dealing with the *Recherches* It must be looked upon, I suppose, as an empirical formula, to be justified by its agreement with the data of Kupffer's experiments, but I cannot see that

theory at all justifies its form: see our Arts. 763-6. I shall return to this point more fully later. A series of experiments intended to show the good results obtainable from this theoretically questionable formula are given in this part of the *Einleitung*.

(d) The remainder of the *Einleitung* (S. 419-27) is occupied with the formulae for torsional vibrations. The method is that due to Gauss and presents some variations on that of the memoir of 1848, notably the equation $P_s = P_0 \left(1 + \nu r \sqrt{\frac{s}{l}} \right)$ is used for the reduction of the periods: see our Art. 739.

Some interesting experiments as to the exactness of this formula are given on S. 423-426. Kupffer finds that for

$$\begin{array}{ll} \text{copper} & \left\{ \begin{array}{l} \text{unannealed, } \nu = .04302 \text{ (to } .04828), \\ \text{annealed, } \nu = .2365 \text{ (to } .2450), \end{array} \right. \\ \text{steel} & \nu = .007122. \end{array}$$

He shows that the coefficient ν of elastic after-strain is capable of immensely modifying the value of the elastic-modulus as determined by the method of torsional vibrations (S. 427). It should, however, be noted that the discrepancy he finds between the values of $\delta = 1/(\pi E)$ as found by transversal and torsional vibrations for copper wire need not be solely due to the influence of elastic after-strain. Kupffer's δ as obtained from torsional vibrations is $= 2/(5\mu\pi)$ and from transverse vibrations $= 1/(\pi E)$, but any want of *uni-constant isotropy* in the copper wire would not allow of our assuming $E = 5\mu/2$ or these values of δ to be equal. On the other hand the fact that steel wire with a very small ν (see above) gave for δ almost the same values when determined by torsional and by transverse vibrations may only point to a nearer approach to uni-constant isotropy in that material.

[752.] The next portion of the memoir is entitled: *Einfluss der Temperatur auf die elastische Kraft der festen Körper*. Kupffer divides the effects of heat into two main groups:

(i) Change of elasticity during the time the temperature is raised, the elasticity returning to its old state when the temperature is lowered to its first value.

(ii) Change of elasticity remaining after the heating has ceased, and the old temperature has been restored.

The first series of investigations as to (i) was upon the transverse vibrations of a rod clamped at one end so as to be vertical, the free end being loaded with weights of different magnitudes. If E_t be the stretch-modulus at temperature t , we have according to Kupffer

$$E_{t'} = E_t \{ 1 - \beta_f (t' - t) \},$$

where $t' > t$ and β_f is a constant. Kohlrausch takes the effect of temperature to be represented by an expression involving also the square

of $(t' - t)$ so that the factor is then of the form $\{1 - \beta(t' - t) - \gamma(t' - t)^2\}$. In most cases γ is very small, but if $t' - t$ be large the term in $(t' - t)^2$ might be sensible. Kupffer's first series of experiments were only made for the difference between external and internal winter temperatures—amounting to from 13 to 25 degrees Réaumur. The values of β_f were obtained from what I have spoken of as the questionable formula for transverse vibrations (see our Art 751 (c)), but as the stretch modulus probably appears as a factor of the correct formula—at least to a close degree of approximation,—serious error would hardly be introduced by the use of the formula

Kupffer neglects the effect of heat in expanding the rods, remarking that the changes of temperature only altered their dimensions insensibly see, however, the ftn. on our p 509. At the same time he notes that the least change in the distance from the point of clamping to the centre of gravity of the vibrating load would have made an important alteration in the period of oscillation (S 430 and ftn.) He does not seem to have noted that the dimensions of the rod would also have been slightly different in the positions when the weight and the clamped end were respectively uppermost. Both these causes might somewhat effect the values of β_f he gives for the different metals. They are reproduced in the Table I below from his S 451. S 431-51 are occupied with numerical details of the observations

I

Values of β_f for one degree Réaumur found from changes of temperature lying between -15°R and 15°R , the changes being not much more than 20° ,

$$E_t = E_t \{1 - \beta_f(t' - t)\}, \quad t' > t$$

Metal	β_f	β'_f
Silver	000563 (mean)	_____
Brass (hammered)	000471 (mean)	000478 (mean)
„ (cast)	000533 (mean)	000533 (mean)
Brass (rolled ¹) (1st kind)	000536	_____
„ „ (2nd kind)	000476	000500
Platinum	000201 (mean)	_____
Plate Glass	000125 (mean)	_____
Cast Iron (soft)	001795 (mean)	00188 ($\beta_f = 001618$ for same specimen)
Steel (soft, rolled)	000348 (mean)	_____
English Forged Steel (1st kind)	000320	_____
„ „ „ (2nd kind)	000256	_____
Steel (soft, cast)	000242 (mean)	_____
Swedish Wrought Iron	000456	000381
Rolled Iron Bar (1st kind)	000442	_____
„ „ „ (2nd kind)	000463	000488
English Wrought Iron	000376	_____
Rolled Iron Plate (across fibre) ²	000353	_____
„ „ „ (along fibre)	000425	_____
Copper	000260	000598 (but elasticity had been permanently altered)
Zinc (rolled)	000644	_____
Lead (rolled)	003035	_____
Gold	000394	_____

[753.] In the third column of the above Table I. I have placed the mean β'_τ of some of the results of Kupffer's experiments included in the following section of his memoir (S. 551–63) entitled: *Einfluss der Temperatur auf die Elasticität der Metalle bei höhern Temperaturen.* (i) *Bei Transversalschwingungen.* The change in temperature here was a rise from about 14° R. to 79° R. In all cases except those of Swedish wrought-iron where there appears to be a reduction, and of cast-brass where there is no sensible change β'_τ appears to be $> \beta_\tau$; in the former case the experiments do not seem to have been made on the same specimens, so that not much stress can be laid on the result. We see therefore that the introduction of Kohlrausch's term $\gamma(t' - t)^2$ with a *positive* value of γ would be in accordance with Kupffer's results.

[754.] Our author next ((ii) *Bei Torsionsschwingungen*) determines the effect of a like *large* change in temperature on the slide-modulus. Assuming in his memoir uni-constant isotropy Kupffer speaks of this effect as an alteration in the stretch-modulus. Without this assumption, however, we may gather the following results from S. 464–8 of his work:

II.

Values of β'_τ for one degree Réaumur found for changes of temperatures between 15° R. and 79° R., the changes being about 65° , where $\mu'_t = \mu_t \{1 - \beta_\tau(t' - t)\}$, $t' > t$.

Metal.	β'_τ
Copper	•0008634
Best Viennese Pianoforte Wire (Steel)	•0005885
Very soft Brass Wire	•0006982
Very hard Brass Wire	unannealed •0004258
	annealed •0004861

Thus, so far as we can compare the materials of these wires with those of the bars in the previous article, we see that β'_τ for copper and steel is greater than β'_τ , or that the slide-modulus for these metals diminishes with the rise of temperature more rapidly than the stretch-modulus. Kupffer's result for copper differs widely from that of Kohlrausch, but supposing Kohlrausch's brass wire to have been of the sort that Kupffer terms very hard, then they agree fairly closely for this metal.

[755.] The next section of the memoir is entitled. *Beobachtungen über den Einfluss vorübergehender Temperaturerhöhungen auf die Elasticität der Metallstäbe.* It occupies S. 469–492.

Da die Wärme den Aggregatzustand des gehämmerten, oder gewalzten, oder gehärteten Metalls bleibend ändert, so ist zu vermuthen, dass der Elasticitätscoefficient sich ebenfalls durch vorübergehende Temperaturänderung bleibend ändert (S. 469).

The experiments were made by means of the transverse vibrations of rods exactly as in the method referred to in our Art. 752. The change in temperature was produced by heating the rods with a Berzelius' spirit lamp, sometimes to incandescence. The stretch-modulus

[756] Kupffer concludes his memoir by an investigation of the effect of heat on elastic after-strain (*Einfluss der Temperatur auf die elastische Nachwirkung* S 492-4) We have already seen that Kupffer attributes to elastic after strain a considerable portion of the reduction of the amplitudes of torsional oscillations Hence if the wire be subjected to any thermal process the effect of this on its after strain property will be shown by the difference, if any, in the number of oscillations made between the same amplitudes before and after the thermal process—the resistance of the air being the same in both cases Thus the change in the after strain coefficient, if not its absolute value in either case, could be ascertained without the need of experimenting *in vacuo* Details of the experiments on the various metals in the case of both elasticity (see the previous article) and after strain are given in the memoir, we summarise them in the following Table

III

Temperature Effect on Metals

Metal.	Cyclic Effect of rise of Temperature.		Permanent Effect after a heating nearly or quite to incandescence.	
	Coefficient of after strain ν	Stretch & Slide-Moduli E & μ .	Coefficient of after strain ν	Stretch Modulus E
Silver	increases	diminish	increased (if almost to incandescence)	diminished (if almost to incandescence)
Brass	do	do	increased (if to softening)	increased (if to softening)
			diminished (even if to incandescence)	increased with slight heating and then diminished
Copper	do	do	increased (if to incandescence)	diminished (if to incandescence)
			diminished (if not to incandescence)	increased (if not to incandescence)
Zinc	do	do	slightly diminished (if heated till covered with a coating of oxide)	much increased (if heated till covered with a coating of oxide)
Platinum	do	do	diminished (if heated short of or up to incandescence)	increased (if heated short of or up to incandescence)
Cast Iron	do (considerably even at temperatures low as that of boiling water)	do	No experiments	No experiments
Steel	do	do	diminished (if tempered very hard after annealing)	increased (if tempered very hard after annealing)
			increased (if soft and heated up to incandescence)	increased (if soft, and heated up to incandescence)
Wrought Iron	do	do	No experiments	No experiments
Gold	do	do	much increased	diminished

The general law thus seems to be that processes which increase the coefficient of after-strain or 'viscosity' decrease the elastic-constants and *vice-versâ*, but there are exceptions to this rule.

Kupffer speaks simply of the 'elasticity' as being increased or diminished. I have put stretch- or slide-modulus according as his method was that of transverse or torsional vibrations, in order that there may be no assumption that even in questions of thermal influence these necessarily exhibit the same tendencies.

[757.] In conclusion we may remark that this memoir of Kupffer's is of very considerable value although we cannot feel thoroughly satisfied with his use of the experimental method of transverse vibrations, and could have wished a more complete investigation of β_f and β_r for a greater variety of temperatures. Still to have demonstrated the existence of after-strain in metals and indicated its changes with temperature is no small service, while the absolute measurements of the thermal coefficients are at least valuable for comparison.

[758.] A. T. Kupffer: *Recherches expérimentales sur l'élasticité des métaux faites à l'observatoire physique central de Russie*. Tome I. folio, (all published), pp. i-xxxii and 1-430, with nine plates. St Petersburg, 1860.

This work contains some of the most carefully made experiments on the stretch-moduli of different metals and the effect of temperature upon them, which we have to record in this period. The experiments seem to have been conducted with extreme accuracy;—unfortunately the formulæ used by Kupffer do not appear equally accurate, and it may be questioned whether very useful labour might not still be spent in revising Kupffer's numbers with the aid of a more accurate elastic theory.

The preface to the work explains its scope and the contents of the projected remaining volumes: see our Art. 722. It also states the relation between Russian, English and French measures¹. It occupies pp. i-ix.

[759.] The *Introduction* occupies pp. xi-xxx. One or two brief remarks may be made here.

¹ A Russian foot = an English foot; a Russian inch = an English inch = 2.540 centimetres. A Russian pound = .9 English pounds nearly = 409.512 grammes (or 1 kilogramme = 2.442 Russian pounds).

For comparison of specific gravities we may note: a cubic inch of water at the normal temperature $13\frac{1}{2}^{\circ}$ R. ($=62^{\circ}$ F.) and *in vacuo* weighs very nearly .01 Russian pounds.

(a) On p. xii Kupffer remarks that the formula of Euler for the transverse vibrations of a rod clamped at one end and loaded at the other does not give accurate results. He seems to think the formula theoretically correct, but this is not the fact. It is only an approximation which neglects the inertia of the rod.

(b) The author insists upon the importance of a national institution for experiments on the resistance of materials. This importance is no less to-day than in 1860,—greater also in a manufacturing country like England than in Russia.

Je crois, qu'un établissement spécial, consacré à des expériences sur la résistance des matériaux entre et hors des limites de l'élasticité, où l'on pourra mettre à l'épreuve les productions métalliques de toutes les usines du pays, avant et à mesure qu'elles sont livrées au commerce, ne présenterait pas seulement des données certaines pour la rectification des devis de construction, mais contribuerait aussi puissamment au perfectionnement des méthodes de fabrication, puisque chaque fabricant désirera que ses productions fussent notées le plus haut possible. Rien n'entrave les perfectionnements dans la fabrication des métaux, comme l'incertitude où le gouvernement ou le public se trouvent relativement à leur qualité, et si, à cause de cette incertitude, ils sont toujours taxés de la même manière, qu'ils soient bons ou mauvais. L'élévation des prix, que la confiance publique accorde à certaines usines anciennes et connues, n'a pas d'autre source que l'épreuve du temps, qui pourrait être considérablement abrégée par des expériences préliminaires (p. xiii).

(c) The doubtful formulæ for flexure and transverse vibrations to which I have referred in Arts 747 and 751, and to which I shall return in Arts 760–6, are given on pp. xv–xvii and pp. xx–xxiv.

(d) On p. xviii Kupffer cites experiments confirming Hodgkinson's result—namely that the stretch modulus of cast-iron decreases rapidly with the load. Of this he remarks:

La rapidité, avec laquelle la dilatation élastique de la fonte augmente avec la charge, me semble prouver, que nous n'avons pas ici affaire à une autre loi des dilatations et des compressions, mais à une autre propriété des corps élastiques que quelques métaux seulement possèdent et qui cache la véritable loi (p. xix).

He promises to return to this matter in a later volume, but we have no later trace of it, I think, in his published work. (See our Arts 729 and 767, however.)

(e) Remarks on the relation of the stretch modulus to the density are given on p. xxvii. In the case of brass Kupffer shows that, after working different specimens of the same piece, the moduli were as the cubes of the densities (compare Art 741 (a)). Our hope, however, of finding any general law connecting modulus and density is even to-day very small. He further notes the effect of working in producing a difference in the stretch modulus for different directions (p. xxviii).

[760.] The first portion of the text of Kupffer's work deals with the preliminary experiments and the theory of the statical deflection of bars. It occupies pp. 1-44. He remarks (p. 2) that he had noticed the fact of the distortion of the contour of the cross-sections by flexure. This had already been observed experimentally by Clark for set (see our Art. 1485*) and theoretically by Saint-Venant for elastic strain (see our Art. 170). Thus a rectangular contour becomes a trapezium with slightly curved sides: see our Art. 736.

Kupffer then turns to the formula for flexure which he states as follows for the case of a horizontal cantilever:

$$\left. \begin{aligned} 1/E &= \frac{1}{4} \frac{dab^3}{l^3 L (\frac{3}{8}p + p')}, \text{ for a rectangular section,} \\ 1/E &= \frac{3}{4} \frac{d\pi r^4}{l^3 L (\frac{3}{8}p + p')}, \text{ for a circular section,} \end{aligned} \right\} \dots\dots(i).$$

$$d = \frac{2}{3}L \tan \phi, \text{ for both, } \dots\dots\dots(ii),$$

where: d is the total deflection of the free end,

ϕ is the angle the tangent at the free end makes with the horizontal,

l is the length of the bar,

L is the horizontal distance of the free end from the built-in end after flexure,

p' is the load at the free end,

p is the weight of the bar,

a is the horizontal, b the vertical side of the rectangular cross-section, r the radius of the circular cross-section.

(See pp. xvi, xvii, 11, 19, 45, 50 etc.)

The angle ϕ can be measured by the angle between the reflected and incident rays of light on a small mirror attached to the free end of the bar, and thus the stretch-modulus E can be determined. This Kupffer did with very great caution and accuracy.

The formulae above occur frequently in his works on elasticity, and we have now to ask how far they are as accurate as his measurements really require.

[761.] Neglecting slide we have on the Bernoulli-Eulerian hypothesis

$$E\omega\kappa^2/\rho = p' (L - x) + \frac{p}{l} \int_x^L \frac{ds}{dx'} (x' - x) dx' \dots\dots(iii),$$

where x is the horizontal distance of the element ds of the central axis of the rod from the built-in end, ρ the radius of curvature at ds and $E\omega\kappa^2$ the flexural rigidity of the bar: see our Art. 79.

First suppose the deflections so small that we may neglect $(dy/dx)^2$ or put $1/\rho = d^2y/dx^2$ and $ds = dx$. Then we easily find

$$E\omega\kappa^2 \tan \phi = \frac{l^2}{2} \left(p' + \frac{p}{3} \right),$$

and

$$E\omega\kappa^2 d = \frac{l^3}{3} \left(p' + \frac{3p}{8} \right)$$

Hence

$$d = \frac{2l}{3} \tan \phi \frac{1}{1 - \frac{p}{24p' + 9p}} \quad (1v)$$

Thus we see that Kupffer's formula (u) cited above is not true even for small flexures unless $\frac{p}{24p' + 9p}$ be very small

In several of the experiments p' and p were about the same order of magnitude, so that the values of d derived from this formula would have an error of 2 or 3 per cent. Further it is to be noted that Kupffer replaces l by L , and that many of his rods were so flexible that L could differ from l very considerably without the elastic limit being passed. Suppose then the difference between l and L to be so considerable that we must take it into account. Then we ought to solve the equation (iii) above to at least a second approximation, but this leads to very complex results. To test the accuracy of Kupffer's formulae however, it is sufficient to take the case when $p = 0$. We then find, if χL^2 or $p' L^2 / (E\omega\kappa^2)$ be a small quantity, that to a second approximation

$$\left. \begin{aligned} d/L &= \frac{1}{3}\chi L^2 + \frac{1}{3^{\frac{1}{5}}}(\chi L^2)^{\frac{1}{5}} \\ l/L &= 1 + \frac{1}{1^{\frac{1}{5}}}(\chi L^2)^{\frac{1}{5}} \\ \tan \phi &= \frac{1}{2}\chi L^2 + \frac{1}{1^{\frac{1}{8}}}(\chi L^2)^{\frac{1}{8}} \end{aligned} \right\} \quad (v)$$

$$\text{Hence} \quad d = \frac{2}{3}L \tan \phi \left\{ 1 - \frac{11}{2^{\frac{1}{8}} 80} (\chi L^2)^{\frac{1}{8}} \right\} \quad (vi)$$

We thus see that Kupffer's formula neglects the term in $(\chi L^2)^{\frac{1}{5}}$, but this is just the order of the difference between l and L . Thus his results would have been as satisfactory, if he had always taken l for L . But in some of his observations the difference between l and L is so considerable¹ that he does not feel able to neglect it, *in these cases therefore his numerical results are still liable to the same order of error as if he had replaced L by l in his formulae*

Further the deflection due to slide is of the order $\frac{\kappa}{l^2}$, and if we include terms of the order $\left(\frac{p l}{E\omega\kappa} \right)^2$, we cannot neglect slide unless $(\kappa/l)^2$ is small as compared with $p/E\omega$. For these reasons I do not think Kupffer's values of E are necessarily so accurate as his attempted distinction between l and L would lead us to believe.

¹ For example $l = 28.003$, $L = 27.685$ (pp. 17-18), $l = 13.9607$, $L = 13.7985$ (pp. 39-40).

[762.] A value to a second degree of approximation of the stretch-modulus obtained from flexure is given by Saint-Venant in his *Leçons de Navier*, p. 84, footnote. He supposes however, that p is distributed uniformly along L and not along l ; further in his equation, p. 82 (at the top of the footnote), I do not see why the second term on the right, which he admits is only approximate, is really admissible to the degree of approximation required. It is equivalent in our case to replacing the integral on the right of equation (iii) by $\frac{1}{2}(L-x)^2/\cos \phi$. I have not succeeded in solving equation (iii) to a second approximation.

If $p = 0$, we easily find from (v)

$$\chi L^2 = 2 \tan \phi - \tan^3 \phi,$$

but
$$L^2 = l^2 \left\{ 1 - \frac{2}{15} (\chi L^2)^2 \right\} = l^2 \left\{ 1 - \frac{8}{15} \tan^2 \phi \right\}.$$

Hence
$$\chi = \frac{1}{l^2} 2 \tan \phi \left\{ 1 + \frac{1}{30} \tan^2 \phi \right\},$$

or
$$\frac{1}{E} = \frac{\kappa^2}{l^2} \frac{\omega}{p'} 2 \tan \phi \left\{ 1 + \frac{1}{30} \tan^2 \phi \right\}.$$

For a circular section :

$$\frac{1}{E\pi} = \frac{r^4}{2l^2 p'} \tan \phi \left\{ 1 + \frac{1}{30} \tan^2 \phi \right\}.$$

Kupffer uses :

$$\frac{1}{E\pi} = \frac{r^4}{2lLp'} \tan \phi,$$

which really
$$= \frac{r^4}{2l^2 p'} \tan \phi \left\{ 1 + \frac{8}{30} \tan^2 \phi \right\}.$$

He further replaces $\tan \phi$ by $\phi \tan l'$. In most cases I do not think that the term with $\tan^2 \phi$ really affects his results, but the distinction between L and l ought not then to have been preserved.

Kupffer's own deduction of the result $d = \frac{2}{3} L \tan \phi$ is absolutely erroneous; he assumes the form of the elastic line to be a semi-cubical parabola, which is of course quite inadmissible (p. 11).

[763.] We next turn to the formula which Kupffer has adopted for the transverse vibrations of a loaded elastic rod clamped at one end. This formula has been largely used in his researches. It will be found discussed in his volume on pp. xix-xxv and pp. 126-135. Kupffer's experiments were made in the following manner. A bar, of which the weight of the vibrating part was p , was loaded with a weight p' at one end; the other end was then firmly clamped and the bar set vibrating about a vertical position, first with the weight p'

uppermost, and secondly with the clamped end uppermost, t_1 and t , the periods of the complete oscillations in these two positions, were then observed

Kupffer gives the following empirical formula for E , the stretch modulus, in the case of a rectangular bar of cross-section $a \times b$, oscillating parallel to the side b

$$E = \frac{9}{2} \frac{I g}{a b^3} \frac{t_1^2 + t^2}{t_1^2 - t^2} \sqrt{\frac{\lambda}{\sigma}} \quad (1),$$

where

I = total moment of inertia of bar and load about the clamped end

λ = length of a simple pendulum having the same period as the pendulum which would be formed by the bar of weight p and the load p' supposed rigid and capable of freely oscillating about an axis through the clamped end

$\sigma = \frac{1}{2} \frac{t_1^2 t^2}{t_1^2 - t^2} \frac{g}{\pi^2}$, or, according to Kupffer, σ is the length of a simple pendulum, which would have the same period as the bar "si le barreau n'avait point d'élasticité, et si la pesanteur agissait seule" (p 133). By this Kupffer means that the 'elasticity of the bar is supposed zero,' but I do not grasp the exact bearing of this. Practically he calculates the value of σ from t_1 and t as given above

[764] Let us examine a little more closely into the formula for a vibrating rod. The complete period T of the fundamental note of a 'clamped free' bar is given by

$$T^2 = \frac{4\pi^2 l^3 p}{a b^3 E g} \frac{12}{m^4},$$

where m is the least root of

$$\cos m \cosh m + 1 = 0$$

See our Art 49* or the footnote Vol 1 p 50

Seebeck, in the memoir referred to in our Art 471 (see our p 140), finds $m = 1.875104$, hence we have

$$m^4 = 12.3624$$

Thus if found from the fundamental note

$$E = \frac{4\pi^2 l^3 p}{a b^3 T^2 g} \times 970688 \quad (11)$$

Now Kupffer says (p xx and p 134) that, if a free clamped bar oscillates very rapidly, so that the influence of gravity is inappreciable whatever be the position of the bar, then Euler has given the following formula for its stretch modulus

$$E = \frac{4\pi^2 l^3 p}{a b^3 T^2 g} \quad (111)$$

Formula (ii) would, of course, be a close approximation if a horizontal bar were oscillating in a horizontal plane and its weight p produced no vertical deflection worth taking into account. For example a short bar in which a was considerably greater than b .

Kupffer cites (iii) indeed as due to Euler but I do not know to what memoir of Euler's he is referring. He supposes it to hold in cases in which (ii) is really true. It is therefore not surprising that he found formula (iii) in small agreement with observation.

[765.] But the point to be noticed is that even with an unloaded bar, Kupffer found the action of gravity was sensible and different according as the bar was placed vertically with the free end upwards or downwards, in other words gravity produced different effects upon the periods in the two cases. Thus for an unloaded brass bar $t_1/2 = .31625$ seconds and $t/2 = .28200$ seconds (p. 135).

We cannot therefore apply formula (ii) still less (iii) to this case. We are bound to take gravity into account. Indeed Kupffer's bars must have been so flexible that they vibrated with something of a pendulous nature about the clamped end. He measured the transverse vibrations not by the note but by the eye :

Une lame, qui est assez longue et assez mince, pour que ses oscillations transversales soient appréciables à la vue, oscille plus lentement, lorsque son extrémité libre est en haut que lorsqu'elle est en bas, la formule d'Euler n'est donc plus applicable directement (p. xx).

Kupffer modifies the formula (iii) and deduces from it (p. xxi) :

$$E = \frac{9}{2} \frac{I g}{a b^3} \frac{t_1^2 + t^2}{t_1^2 - t^2} \dots\dots\dots (iv),$$

but I am unable to accept his reasoning. This formula still not giving results in accordance with experiment, he proceeded to further modify it and found that it would give values agreeing among themselves and with those obtained from flexure experiments if the right hand side were multiplied by $\sqrt{\lambda/\sigma}$. I cannot find any formula in the least agreeing with Kupffer's by attempting to solve the problem by the assumption of a form for the normal-function. Indeed, as Lord Rayleigh has pointed out for a similar case—where, however, gravity and the inertia of the bar are neglected—there seems to be not one but two principal periods : see *The Theory of Sound*, Vol. I. § 183. This formula must therefore be treated as a purely empirical formula, and I find it accordingly difficult to draw any comparison between the values of the stretch-moduli as found from the statical and from the vibrational methods. On the other hand for comparative values of E , as for the same bar affected only by temperature, possibly (i) may give good results. Kupffer in this case works with the formula :

$$\frac{E}{E'} = \frac{t_1^2 + t^2}{t_1^2 - t^2} \cdot \frac{t_1'^2 - t'^2}{t_1'^2 + t'^2} \dots\dots\dots (v),$$

supposing the part $\frac{9}{2} \frac{I_g}{ab^3} \sqrt{\frac{\lambda}{\sigma}}$ of (1) to be but slightly influenced by temperature

[766] The problem of a vertical rod clamped at one end and loaded with a weight at the other was first attempted by Ménabréa in the memoir referred to in our Art 551 (g). He did not, however, form and solve the equation for the notes, and the equations which give rise to the transcendental equation for the notes do not look promising (especially when as in Kupffer's case the weight of the rod and the load are not very different). One thing appears clear, I think, from Ménabréa's results, that there would be two different series of notes, nor does there seem any reason why both of these should not have been present in Kupffer's experiments, nor for the terms involving the fundamental note of one series being negligible as compared with those involving that of the other. Kupffer observed the time of, say, a thousand transits of a mark on his rod across the mid-thread of his telescope, dividing the time by the number (1000) of vibrations, he considered the result to be the time t_1 or t (as the case might be) of an oscillation of the rod, and substituted in the formula given above. There thus seems to me considerable doubt as to what period t_1 or t really denotes, and till the theory of this vibrating motion is fully worked out, it does not seem possible to derive all the profit from Kupffer's experiments that their accurate methods of observation would justify. We shall see later (Arts 774 *et seq.*) that Zoppritz also has not surmounted the difficulties which arise in dealing analytically with this case.

[767] The details of the first series of experiments on the statical flexure of bars of rectangular cross-section are given on pp 51–109. Such bars Kupffer terms *laminae* (*lames*), while those of circular cross-section, details of experiments on which he gives on pp 109–125, he terms rods (*verges*). The former set of experiments contains most interesting evidence as to after-strain in cast-iron see pp 83–4, 88–9, and to its imperfect elasticity (see our Art 729 and Vol 1, p 891, Note D) that is, the apparent decrease of its stretch-modulus with increase of the load (p 87). This appears still more markedly if we can accept the value of the stretch-modulus given by Kupffer from transverse vibrations as that for vanishingly small loads.

The values Kupffer gives for $\delta (= 1/E)$ as obtained by statical and vibratory methods do not show that E is invariably greater or less when measured by the one or by the other method, but this does not seem to me very conclusive as those values are obtained

from formulae which I cannot recognise as sufficiently exact for this purpose.

Kupffer notes on p. 125 that the original limits of elasticity (state of ease) can be altered by repeated alternating stress (extension of state of ease: see our Vol. I. pp. 886–8 and Arts. 709, 749). The flexure experiments were made on various kinds of steel, cast and wrought iron, brass and platinum.

[768.] On pp. 135–268 we have details of experiments on the transverse vibrations of bars of rectangular cross-section, and on pp. 268–94 on those of bars of circular cross-section. The value of E is found to depend to some extent on the length of the vibrating portion of the bar. This divergence Kupffer thinks is due rather to the variation of E along the bar than to the effect of the resistance of the air acting on different lengths. It seems to me it may also be partially due to defects in Kupffer's empirical formula: see his pp. 153, 172 etc.

The experiments cover most of the principal metals: brass, steel, iron, silver, gold, platinum, zinc bars and brass, copper and steel wires.

[769.] Pp. 294–7 are entitled: *Oscillations transversales des lames horizontales, dont une extrémité est encastrée*, and would, if more extensive, have been most valuable for comparison and investigation of Kupffer's empirical formula for the vertical vibrating rod. We have here a case to which existing theory ought directly to apply. Unluckily Kupffer only gives the details of a few experiments on a steel bar, and substitutes the results in an empirical formula instead of the theoretical one.

He adopts the following formulae:

For the transverse vibrations of a bar in a horizontal plane,

(i) loaded at the free end:

$$E = \frac{9}{2} \frac{4\pi^2}{ab^3} \frac{Il'}{T_1^2} \sqrt{\frac{\sigma}{\lambda}} \dots \dots \dots \text{(vi)},$$

(ii) without load:

$$E = \frac{4\pi^2}{gab^3} \frac{p\ell^3}{T_1^2} \sqrt{\frac{\sigma}{\lambda}} \dots \dots \dots \text{(vii)},$$

where: T_1 = duration of the oscillations (= twice Kupffer's T_1),

p = weight of vibrating part of rod,

ℓ = distance of centroid of load from clamped end,

and the remainder of the notation is the same as in our Art 763. If we supposed p/p' very small, we might obtain a formula suitable for case (1) by supposing the bar to take at each instant the statical form corresponding to the actual deflection at l' . We then find

$$E = 4 \frac{4\pi^2 Il'}{ab^3 T_1^2} \quad (\text{viii})$$

On the other hand Equation (vii) ought to be the same as Equation (ii) of our Art 764. Thus we ought to find at least approximately that with load $\sqrt{\sigma/\lambda} = 8889$, and without load $\sqrt{\sigma/\lambda} = 9707$. From the values given on p. 296 I find with load $\sqrt{\sigma/\lambda} = 9410$ (in a case, however, for which p/p' is not very small), and without load $\sqrt{\sigma/\lambda} = 9908$. I do not clearly understand what the physical meanings of σ and λ are supposed to be (neither in the latter case equals $\frac{2}{3}l$), and the above results show that their values when substituted do not give any close relation between Kupffer's empirical formulae and our (viii) or (ii) above. We cannot delay longer over the matter now, but there seems to be sufficient ground for suggesting that Kupffer's experiments and formulae require cautious dealing with. See Zoppritz's investigations referred to in our Arts 774–84.

[770] The remainder of Kupffer's work is devoted to the influence of heat on the elasticity of metals. A great part of this is reproduced from the memoir of 1852—see our Art 748, and thus does not require further discussion here. As the measurements are chiefly based on Equation (v) of our Art 765, by putting $E_t/E_i = 1 - \beta_f(\tau' - \tau)$ where $\tau' - \tau$ is the rise of temperature and β_f the thermal constant required, I do not think there is the same difficulty about the trustworthiness of the results as in the case of absolute measurements.

P. 299 gives the formula, pp. 300–2 describe the apparatus and method of experimenting, pp. 302–341 give the details of the experiments on various metals the results of which have already been tabulated in our Art 752. These pages indicate how the value of β_f differs for ordinary and for high temperatures, and according as the metal has been cast, hammered or rolled.

[771] Pp. 341–373 deal with the influence of a past change in temperature on the elasticity. These experiments have already been considered in our discussion of the memoir of 1852—see our Art 755. The remarks in the memoir on after strain are omitted in the *Recherches* as they would have fallen under the head of *Torsion*, the topic of the projected third volume of the work.

Pp. 377–425 are entitled *Additions*, and are occupied with the details of experiments on the determination of E for steel and copper bars by the method of transverse vibrations. The experiments on steel were made with a view of determining $\sqrt{\lambda/\sigma}$, especially when the bar being vertical the load at the free end was such that it buckled in the position of equilibrium.

On p. 425 Kupffer finds that for a soft and for a rolled copper bar without load $\sqrt{\lambda/\sigma} = 1.02200$ and 1.02625 respectively. These give $\sqrt{\sigma/\lambda} = .978,47$ and $.974,42$, the theoretical value, if the bar were horizontal, being $.970697$ (see Art. 764 above). Hence I am inclined to think that if Kupffer had placed his bars horizontally and allowed them to oscillate horizontally without any load at the free end, he would have obtained better results and these in good accordance with a well established theoretical formula.

[772.] Kupffer prefixes to his work (pp. xxxi–ii) a table of the quantity $\delta (= 1/E)$, or in his units the number of millimetres which a bar of one metre length and one square millimetre cross-section would be extended by a load of one kilogramme. The density of each material is also tabulated, but there is no obvious relation between the density of a substance and its δ . Indeed it is not always the denser specimen of a metal which has the least δ , although this is generally true.

As Kupffer's work is not accessible to all and his numbers are not to be found cited in the ordinary text-books of elasticity, I give in Table IV. on p. 531 certain of his results for metal bars in which I have taken mean values for the different specimens whenever the number is followed by (*m*), and have added some of the results for brass, iron, steel and copper *wires*.

The numbers in brackets with the letter Z. attached to them I have calculated from Zöppritz's discussion of Kupffer's experiments. Zöppritz obtains his results from a *more accurate* theory, but they are deduced from a very small range of Kupffer's measurements and so are more liable to the influence of error in the individual experiment or to fault in the individual specimen.

It should be noted that Wertheim's value of the stretch-modulus for gold is considerably larger (by $\frac{1}{3}$) than Kupffer's and consequently his value of δ smaller. Wertheim finds $\delta = .115,674$ to $.112,971$. But the effect of annealing was to send δ up to $.179,051$, so that the form of treatment or working appears to alter the modulus of gold very greatly. See the memoir referred to in our Art. 1292*.

[773.] A useful *résumé* of the various memoirs on elasticity by both Kupffer and Wertheim will be found in the *Bibliothèque universelle de Genève: Archives des sciences physiques et naturelles*, T. 25, pp. 40–58, Genève, 1854. Tables of the numerical results of both investigators are likewise given.

IV

Metal	$\delta = 1/E$ (For units see Art 772)	Density
Brass, Cast	{ 112,365 (m) (109,806, Z (m))	8 2648 (m)
„ Rolled	{ 090,016 (m) (093 572, Z)	8 5047 (m)
„ Hammered	{ 088,400 (m) (088 285, Z)	8 5538 (m)
Iron, Wrought (English)	{ 048 892 (m) (049,848, Z)	7 6957 (m)
„ „ (Swedish)	{ 046 929 (m) (047,553, Z)	7 8114 (m)
„ Rolled in bars	{ 049 937 (m)	7 6449 (m)
„ Plate (in direction of fibre)	{ 056,732 (051,951, Z)	7 6763
„ (perpendicular to direction of fibre)	{ 052,225 (047 366, Z)	7 6775
Steel, Soft, Rolled	{ 046,938 (047,558, Z)	7 835
„ „ Cast	{ 047,114 (m) (047,906, Z)	7 838 (m)
„ Wrought (English)	{ 047 432 (m)	7 8335 (m)
„ Remscheid	{ 047,069 (m) (047,393, Z)	7 8321 (m)
Tin (English)	{ 19,673	7 263
Aluminium	{ 13,940	2 739
Copper, Vigorously rolled	{ 078,213 (079,076, Z)	8 907
„ Soft (‘passé au rouge’)	{ 077,093 (077 961, Z)	8 930
Iron Cast	{ 088 490 (m) (088,755 Z)	7 1272 (m)
Platinum	{ 056,467	21 122
Silver	{ 126,632 (128 650, Z)	10 494
Gold	{ 132 832 (134,916, Z)	19 264
Zinc, Rolled (Belgian)	{ 099,815 (103,456, Z)	7 1517
Wires { Brass (diameter 4 mm)	{ 090 602 (m) (096,386, Z)	8 4150 (m)
„ { Iron („ 5 5 mm)	{ 051 384 050 782	7 9326 7 6620
„ { Steel („ 3 5 mm)	{ 019,525 (051,878, Z)	7 7572
„ { Copper („ 4 mm)	{ 065 017	8 9241
„ { „ („ 5 5 mm)	{ 066 937	8 9427

It deserves to be noted how little the working alters the stretch modulus of steel Zoppitz's results are chiefly based on isolated experiments and specimens

[774] Three memoirs of K Zoppritz bearing on Kupffer's investigations will be best considered in this place although they belong to a somewhat later date The first is a *Habilitations*

Dissertation, published in Tübingen, 1865, and entitled: *Theorie der Querschwingungen eines elastischen, am Ende belasteten Stabes*. Its purpose is explained in the following words of the *Einleitung*:

Die vorliegende Arbeit wurde veranlasst durch das Erscheinen von Kupffers *Recherches expérimentales*.....; und mir von meinem hochverehrten Lehrer, Herrn Professor Neumann in Königsberg empfohlen mit dem Wunsche, dass es mir gelingen möge, durch eine strenge, auf die Principien der Elasticitätslehre basirte Theorie diese Versuche in der Ausdehnung für die Wissenschaft zu verwerthen, wie es dem für ihre Anstellung gebrauchten Aufwand an Zeit, Mitteln und Mühe entsprechend sei (S. 1).

After reference to the labours of Euler, D. Bernoulli, Poisson and Seebeck, the *Einleitung* draws attention to an erroneous theory of the vibrations of a loaded, weightless rod given by Lippich (*Poggendorffs Annalen*, Bd. 117, S. 161, 1862). It then points out the difficulty of solving generally the differential equation for the vibrations of a heavy loaded rod, especially for the case when the weights of the rod and load are, as in Kupffer's investigations, not very different, and finally gives a *résumé* of the contents of the paper.

[775.] The first section (S. 3–8) is entitled: *Ableitung der Differentialgleichungen für die Bewegung eines schweren, am Ende belasteten Stabes*. As in Kupffer's experiments the rod is supposed vertical, clamped at one end, and loaded at the other or free end.

Zöppritz adopts the method of Lagrange (*Statique, Sect. V. Art. 42*) and deduces by a not very luminous or satisfactory process the general equation. We can obtain Zöppritz's form at once, if ω be the cross-section of the rod, by writing equations (i) of our Art. 780 in the form:

$$E\omega\kappa^2 \frac{d^4 y}{dx^4} - \frac{d}{dx} \left(\frac{dy}{dx} \int_x^l \Delta\omega X dx \right) - \Delta\omega Y = 0.$$

Here,
$$\int_x^l \Delta\omega X dx = \pm \left(m \frac{l-x}{l} + M \right) g,$$

$$\Delta\omega Y \equiv -\Delta\omega \frac{d^2 y}{dt^2},$$

where $m (= \Delta\omega l)$ and M are the masses of the rod and load respectively. Hence

$$E\omega\kappa^2 \frac{d^4 y}{dx^4} \mp (m + M) g \frac{d^2 y}{dx^2} \pm \frac{mg}{l} \frac{d}{dx} \left(x \frac{dy}{dx} \right) + \Delta\omega \frac{d^2 y}{dt^2} = 0.$$

Zoppritz writes
$$\frac{E\kappa}{\Delta} = b^2, \quad \frac{Mg}{\omega\Delta} = 2a^2,$$

whence we find

$$b^2 \frac{d^4 y}{dx^4} + (2a^2 + gl) \frac{d^2 y}{dx^2} \pm g \frac{d}{dx} \left(x \frac{dy}{dx} \right) + \frac{d^2 y}{dt^2} = 0 \quad (1)$$

The upper sign corresponds to the free end downwards, the lower to it upwards¹

For terminal conditions we have

$$\left. \begin{array}{l} \text{at } x = 0, \quad y = 0, \quad dy/dx = 0, \\ \\ \text{at } x = l, \quad \left\{ \begin{array}{l} d^2 y/dx^2 = 0, \\ M \frac{d^2 y}{dt^2} = \mp Mg \frac{dy}{dx} + E\omega\kappa^2 \frac{d^3 y}{dx^3}, \\ \text{or } \frac{2a^2}{g} \frac{d^2 y}{dt^2} = \mp 2a^2 \frac{dy}{dx} + b^2 \frac{d^3 y}{dx^3} \end{array} \right\} \end{array} \right\} \quad (11)$$

[776] If we neglect the terms involving g explicitly in equation (1), equations (11) remaining the same, we have the case of a loaded weightless rod. This case is discussed in the second section of the memoir (S 9-16), while the case of a heavy unloaded rod is discussed in the second memoir (see our Arts 780-1)

Zoppritz, taking the *upper sign*, solves (1) for the former case by assuming

$$y = \sum X_n (C_n \cos m_n t + D_n \sin m_n t),$$

where X_n is of the form

$$C_1 \cosh ax + C_2 \sinh ax + C_3 \cos a'x + C_4 \sin a'x,$$

$$\text{and} \quad \left. \begin{array}{l} \alpha = \pm \frac{1}{b} \sqrt{a^2 + \sqrt{a^4 + b^2 m_n^2}}, \\ \\ \alpha' = \pm \frac{1}{b} \sqrt{-a^2 + \sqrt{a^4 + b^2 m_n^2}} \end{array} \right\} \quad (111)$$

To determine m_n he obtains the transcendental equation (S 12)

$$0 - \frac{gb}{l} m_n + \cosh al \left\{ \frac{g}{a} (2a^4 + b^2 m_n^2) \cos a'l - 2\gamma ab m_n \sin al \right\} \\ + \sinh al \{ 2\gamma a' m_n b \cos al + gb m_n \sin a'l \} \quad (112),$$

where $\gamma = \sqrt{a^4 + b^2 m_n^2}$

The *last* root of this equation would give the periodic time observed by Kupffu, for rods whose weight is insensible as compared with the load. The above case corresponds to the clamped end uppermost and

¹ It will be noted that Zoppritz neglects the influence of the rotatory inertia of the rod which would introduce the term $-\kappa \frac{d^4 y}{dt^2 dx}$ into (1)

the load undermost. For load uppermost we must change the signs of g and a^2 in (iii) and (iv). Zöppritz makes no attempt to solve (iv) for any of the large range of numerical examples given in Kupffer's *Recherches*.

[777.] The second section concludes by demonstrating that if

$$y = X_n \{C_n \cos m_n t + D_n \sin m_n t\}$$

be a solution of the general equation (i) of a loaded heavy rod, then

$$\int_0^l X_n X_{n'} dx + \frac{2a^2}{g} (X_n X_{n'})_{x=l} = 0,$$

if n be not equal to n' .

Zöppritz indicates how this enables us to determine the arbitrary constants of the solution in terms of the initial conditions.

[778.] The third and final section of the memoir is entitled: *Angenäherte Anwendung auf den schweren Stab* (S. 17–24). There are some interesting points in it, but the reasoning seems occasionally questionable.

Suppose a rod of weight w to have the weight W attached to one end; further suppose the rod to remain straight and rigid while the effect of its flexural rigidity is replaced by a restorative couple $\epsilon l \phi$, when the rod is inclined at an angle ϕ to the vertical position, l being the length of the rod. Then the equation of small oscillations would be

$$\frac{Wl^2 + \frac{1}{3}wl^2}{g} \frac{d^2\phi}{dt^2} = -\epsilon l \phi \mp (Wl + \frac{1}{2}wl) \phi,$$

the negative sign corresponding to the fixed end uppermost. Hence if $T = 2\pi/m$ be the periodic time we have:

$$\begin{aligned} m^2 &= \frac{4\pi^2}{T^2} = \frac{g}{l} \frac{\epsilon \pm (W + \frac{1}{2}w)}{W + \frac{1}{3}w}, \\ &= g \frac{\epsilon l \pm (S + S'')}{J + J'} \dots\dots\dots (v), \end{aligned}$$

where S and S'' are the first and J and J' the second moments of the *weights* of load and rod about the point of support¹.

To compare this very questionable result, which suggested Kupffer's formula, with what really takes place, Zöppritz returns to equation (i) and assumes the principal vibration to be of the form

$$y = X \cos (mt + a),$$

¹ Zöppritz has dropped an l as factor of his ϵ in either his equation (62) or

so that by substitution we have, taking the upper sign,

$$b \frac{d^4 X}{dx^4} - (2a'' + gl) \frac{d^2 X}{dx^2} + g \frac{d}{dx} \left(x \frac{dX}{dx} \right) - m'' X = 0$$

Integrate from 0 to x , and we find

$$b^2 \frac{d^3 X}{dx^3} - \frac{dX}{dx} \{2a^2 + g(l-x)\} - m'' \int_0^x X dx = C$$

To determine the constant C put $x=l$, and use equation (u), we thus have

$$C = -m'' \left(\frac{2a^2}{g} X_l + \int_0^l X dx \right)$$

Substitute this value of C and integrate again between the limits 0 and l , then remembering (u) and integrating where necessary by parts, we have

$$b \left(\frac{d^3 X}{dx^3} \right)_0 + X_l 2a^2 + g \int_0^l X dx = m'' \left\{ \int_0^l x X dx + \frac{2a}{g} l X_l \right\}$$

Whence substituting the values of a'' and b'' and putting

$$1/R_0 = \left(\frac{d^2 X}{dx^2} \right)_0$$

$$\text{we have} \quad m^2 = g \frac{\left(\frac{E\omega\kappa^2 l}{f_l R_0} + Wl + w \int_0^l \frac{f}{f_l} dx \right)}{Wl + w \int_0^l \frac{x f}{f_l} dx} \quad (vi),$$

where $1/R_0$ is the maximum curvature at the clamped end, f_l the maximum deflection at the free end, and f the deflection at the distance x when the rod takes the maximum deflection at the free end

Comparing (v) and (vi) we see that they will be identical, if we take

$$\epsilon = \frac{E\omega\kappa^2}{f_l R_0}, \quad S' = w \int_0^l \frac{f}{f_l} dx, \quad J' = w \int_0^l \frac{x f}{f_l} dx$$

Obviously f can never be greater than $x f_l / l$ or the maximum values of

$$\int_0^l \frac{f}{f_l} dx \quad \text{and} \quad \int_0^l \frac{x f}{f_l} dx$$

are

$$l/2 \quad \text{and} \quad l/3 \quad \text{respectively}$$

I cannot, however, agree with Zoppritz's arguments on S. 20, that to a close approximation we may suppose these quantities equal to their maximum values. I think a far closer approximation would be obtained by giving them their values for the statical relationship of f to f_l . I have not worked out the ratio of f to f_l for the general statical case, but it can be found in terms of Bessel's functions in the manner indicated

in the footnote to Vol. i. p. 46. If we suppose W only to act,—certainly a more reasonable hypothesis than supposing the bar to remain straight,—we find :

$$\int_0^l \frac{f}{f_i} dx = .3634l \text{ and } \int_0^l \frac{xf}{f_i} dx = .2687l^2$$

instead of $.5l$ and $.3l^2$ which Zöppritz adopts.

An approximation to the value of R_0 might also be made from statical considerations, but while results for dynamical deflections based on such considerations are generally fairly approximate, those for curvature are often very erroneous : see our Art. 371 (iii).

Zöppritz himself suggests (S. 21) putting for R_0 the value calculated in the second part of his paper, but this would involve the solution of (iv) for every experiment and an appalling amount of labour for the reduction of any series of observations. For a rod with the free end uppermost we must change R_0 to R'_0 , f to f' , and alter the signs of W and w in the numerator of (vi).

[779.] For the case of an unloaded rod, if $2\pi/m$ and $2\pi/m'$ be the periods when the free end is undermost and uppermost respectively :

$$m^2 = g \frac{\frac{E\omega\kappa^2 l}{R_0} + w \int_0^l f dx}{w \int_0^l xf dx},$$

$$m'^2 = g \frac{\frac{E\omega\kappa^2 l}{R'_0} - w \int_0^l f' dx}{w \int_0^l xf' dx}.$$

Suppose $2\pi/m_0$ the period when the rod is weightless, then since this must be the same whichever way the rod is placed we have

$$m_0^2 = \frac{gE\omega\kappa^2 l}{R_0} \bigg/ \left(w \int_0^l xf dx \right) = \frac{gE\omega\kappa^2 l}{R'_0} \bigg/ \left(w \int_0^l xf' dx \right),$$

or,

$$m^2 = m_0^2 + g \frac{\int_0^l f dx}{\int_0^l xf dx},$$

$$m'^2 = m_0^2 - g \frac{\int_0^l f' dx}{\int_0^l xf' dx}.$$

Zöppritz, who seems to me to have treated R_0 and R'_0 as *absolute constants independent of w* , then puts (S. 22)

$$m^2 + m'^2 = 2m_0^2 \quad (.....)$$

In this he supposes the second members on the right hand of the expressions for m'' and m'^2 to be equal, i.e. he does not distinguish between f and f' , but assumes without comment that they can be taken equal.

For the gravest note of a weightless free-clamped rod we have

$$E = \frac{wl^3}{\omega k^2 g} \frac{m_0^2}{(1.875,104)^4},$$

(see our Art 764 or Lord Rayleigh's *Theory of Sound*, Vol 1 pp 207 and 224)

Whence for a rod of rectangular section $a \times b$,

$$E = \frac{wl^3}{1.0302ab^3g} m_0^2 \quad (\text{viii})$$

Equations (vii) and (viii), if T and T' be the times of half oscillations (i.e. $T = \pi/m$, $T' = \pi/m'$) give

$$E = \frac{w}{g} \frac{l^3}{ab^3} \frac{\pi^2}{1.0302} \frac{1}{2} \left(\frac{1}{T^2} + \frac{1}{T'^2} \right) \quad (\text{ix})$$

This agrees with the result of Zoppritz's third memoir (see our Art 783, Equation (xi)), but in the present paper (S 20) he has the number 1.019 instead of 1.0302 in the denominator.

He concludes by calculating E for one series of experiments made by Kupffer on an iron bar. Owing to the numerical error just referred to, the results cannot be very accurate.

The exactness with which this approximate theory gives the fairly accurate formula (ix) is, considering the assumptions, somewhat surprising and suggests the use of like methods in similar cases.

[780] The second of Zoppritz's memoirs is entitled *Theorie der Querschwingungen schwerer Stäbe*, and occupies S 139-56 of Bd 128 of *Poggendorffs Annalen*, Leipzig, 1866. Zoppritz first forms the equations for the equilibrium of a thin prismatic rod of uniform cross section and density built-in at one end and acted upon by any body-forces in such wise that the flexure takes place in one plane.

The equation for the deflection y at distance x from the built-in end is easily found to be

$$\frac{E\kappa}{\Delta} \frac{d^4 y}{dx^4} - \frac{d}{dx} \int_x^l \Lambda dx + X \frac{dy}{dx} - Y = 0 \quad (1),$$

where X and Y are the body forces per unit mass in the plane of flexure parallel to the axis and perpendicular to it respectively, while l is the length and Δ the density of the rod. Further,

$$\left. \begin{array}{l} \text{when } x = 0, \\ \text{when } x = l, \end{array} \right\} \begin{array}{l} y = 0, \quad dy/dx = 0, \\ dy/dx = 0, \quad d^2 y/dx^2 = 0 \end{array} \quad (11)$$

Zoppritz now takes the special case of $X = \pm g$, $Y = -d^2 y/dt^2$, or that a rod is vibrating transversely in a vertical plane under its own

weight. X will be $+g$ or $-g$ according as the fixed or free end of the rod is uppermost. The equation (i) now becomes :

$$\frac{E\kappa^2}{\Delta} \frac{d^4 y}{dx^4} + \frac{d^2 y}{dt^2} + g \frac{d}{dx} \left\{ (l-x) \frac{dy}{dx} \right\} = 0 \dots\dots\dots(\text{iii}).$$

The solution of (iii), subject to (ii), will therefore correspond to Kupffer's experimental determination of the period of oscillation of a heavy vertical rod built-in at one end.

[781.] Zöppritz writes (iii) in the form :

$$\frac{d^4 y}{dx^4} + \frac{1}{b^2} \frac{d^2 y}{dt^2} = p \frac{d}{dx} \left\{ \left(1 - \frac{x}{l} \right) \frac{dy}{dx} \right\} \dots\dots\dots(\text{iv}),$$

where $p = \pm \Delta l g / E \kappa^2$ and $b^2 = E \kappa^2 / \Delta$.

Now Zöppritz remarks that p , or as I think he should say $p l^2$, is a very small quantity owing to the magnitude of E as compared with $\Delta l g$, and hence it will generally be legitimate to neglect its square (i.e. if l^2/κ^2 is small as compared with $E/\Delta l g$). He assumes y to be of the form :

$$y = \Sigma (u_m + p v_m) \cos (m t + a) \dots\dots\dots(\text{v}),$$

where $\frac{d^4 u_m}{dx^4} - \frac{m^2}{b^2} u_m = 0$, or u_m is the type of term given by the Euler-Poisson solution for the vibrations of a weightless rod. Neglecting p^2 , v_m will be given by the equation (S. 146) :

$$\frac{d^4 v_m}{dx^4} - \frac{m^2}{b^2} v_m = \frac{d}{dx} \left\{ \left(1 - \frac{x}{l} \right) \frac{du}{dx} \right\} \dots\dots\dots(\text{vi}).$$

Equation (vi) is then solved subject to the conditions (ii). This is followed by a rather long algebraic investigation of the equation for the notes. If $\lambda = l \sqrt{m/b}$, Zöppritz finds (S. 153) :

$$0 = 1 + \cosh \lambda \cos \lambda + \frac{p l^2}{8 \lambda^2} [\lambda^2 (\cosh \lambda \sin \lambda + \sinh \lambda \cos \lambda) - 2 \lambda \sinh \lambda \sin \lambda + 4 (\cosh \lambda \sin \lambda - \sinh \lambda \cos \lambda)] \dots\dots(\text{vii}),$$

a result which I have not verified. If we put $p = 0$, the equation reduces to Euler's form

$$1 + \cosh \lambda_0 \cos \lambda_0 = 0, \quad (\text{see our Art. 49}^*)$$

the root of which corresponding to the fundamental tone is $\lambda_0 = 1.875104$.

Assuming $\lambda = \lambda_0 + p \chi$, χ is found to be given by

$$\chi = \frac{l^2}{\lambda_0^3} \times .39342,$$

$$\text{or} \quad \lambda = \lambda_0 \pm .39342 \frac{g l^3}{b^2 \lambda_0^3} \dots\dots\dots(\text{viii}).$$

See S. 148-56 of the memoir¹.

¹ In the equations of lines 9 and 10 on S. 156 read l^2 for l^3 .

[782] The third memoir of Zoppritz is entitled *Berechnung von Kupffers Beobachtungen über die Elasticität schwerer Metallstäbe*, and is published in *Poggendorffs Annalen*, Bd 129, S 219–237 Leipzig, 1866. It directly applies the result (viii) of our preceding article to Kupffer's numbers. This result, however, only covers a very limited range of Kupffer's work, for his most important experiments were made with heavy rods having weights attached to their free extremity. Zoppritz does indeed indicate how this latter problem might be treated and describes the stages of the theory so far as he has worked it out (S 221).

Diese Arbeit ist indessen eine wegen der algebraischen Rechnung ausserst muhselige und zeitraubende und die Endform der Gleichung so complicirt, dass ich mich bis jetzt noch nicht zu einer Berechnung der Kupffer'schen Beobachtungen danach habe entschliessen können und somit der grösste Theil dieses ausgezeichneten Materials noch unvollkommen benutzt liegen bleibt¹.

Zoppritz also concludes, although on different grounds (S 220), that Kupffer's formula which we have criticised in our Arts 763–5 is inadmissible.

[783] Let T be the time of a half oscillation, then $T = \pi/m$, whence, since $\lambda = l \sqrt{m/b}$, we have, neglecting $p\chi$, from (viii) of Art 781,

$$\frac{l^4}{b} \frac{\pi^2}{T^2} = \lambda_0^4 \left\{ 1 \pm 4\nu \frac{gl^3}{b\lambda_0^4} \right\} \quad (1x),$$

where $\nu = 39342$

Whence to the same degree of approximation

$$b = \frac{L\kappa}{\Delta} = \frac{l^4}{\lambda_0^4} \left\{ \frac{\pi}{T^2} \mp 4\nu \frac{g}{l} \right\},$$

or,

$$E = \frac{w}{g} \frac{l^3}{\omega\kappa} \frac{1}{\lambda_0^4} \left\{ \frac{\pi}{T^2} \mp 4\nu \frac{g}{l} \right\} \quad (x),$$

where w is the weight of the rod.

Thus (x) gives the stretch modulus when the period T of a half oscillation is known. If T' be the half period when the free end is downwards, T'' when the free end is upwards, we have,

$$E = \frac{w}{g} \frac{l^3}{\omega\kappa} \frac{\pi}{2\lambda_0^4} \left\{ \frac{1}{T'^2} + \frac{1}{T''^2} \right\} \quad (x1)$$

¹ Elsewhere he refers to the invaluable material which, owing to the want of a strict theory, has not yet been used in a manner corresponding to what the

By subtracting the two values of E we have

$$\pi^2 \left(\frac{1}{T'^2} - \frac{1}{T^2} \right) = 8\nu \frac{g}{l}.$$

Let σ be the length of the simple pendulum equivalent to the rod when oscillating about an extremity supposed pivotted; then $\sigma = \frac{2}{3}l$, or

$$\sigma = \frac{16}{3} \nu \frac{T^2 T'^2}{T'^2 - T^2} \frac{g}{\pi^2} \dots\dots\dots (\text{xii}).$$

Remembering that in the notation of our Art. 763, $t_1 = 2T'$ and $t = 2T$, we see that, there being no terminal load, Kupffer puts for his σ

$$\sigma = \frac{2T^2 T'^2}{T'^2 - T^2} \frac{g}{\pi^2},$$

or he omits the factor $\frac{8}{3}\nu = 1.04912$ in his estimation of the values of σ .

For the case of a rod of rectangular section ($a \times b$) we have $\omega\kappa^2 = ab^3/12$, and with the rest of the notation as in our equation (i), Art. 763, we find from (xi) by the aid of (xii):

$$E = \frac{9}{2} \frac{I g}{ab^3} \frac{t_1^2 + t^2}{t_1^2 - t^2} \times \frac{32\nu}{\lambda_0^4} \dots\dots\dots (\text{xiii}).$$

The factor $32\nu/\lambda_0^4 = \frac{1.04912}{1.03020} = 1.01837$, and instead of this Kupffer

has $\sqrt{\lambda/\sigma}$ where λ is the symbol defined in our Art. 763. Kupffer obtains values of $\sqrt{\lambda/\sigma}$ such as 1.02016, 1.02581, 1.02399 etc. (see his pp. 136, 148, 156 etc.) when the bars are unloaded. Thus his E will be slightly too large and his δ too small. Kupffer works, I think, for the unloaded beams from a formula like equation (i) of our Art. 763 and not from one of the type of (ix) in our Art. 779 with the number 1.0302 replaced by $\sqrt{\lambda/\sigma}$ as Zöppritz (S. 237) seems to imagine. Hence the amount of his error is measured by the ratio of $\sqrt{\lambda/\sigma}$ to 1.01837 and not to 1.0302 as Zöppritz states. Further Kupffer endeavours to allow for the effect of certain parts of his apparatus in his value of $\sqrt{\lambda/\sigma}$ (see his value of λ , p. 134, which contains i'), which Zöppritz's theory of course does not include. Thus the error in his formula is not so large as might be imagined, and his results agree very closely with those calculated by Zöppritz (S. 223—33) for the case of *unloaded* bars. In many cases the difference is within the limits of experimental error. But this is not the case when we compare Kupffer's values of the stretch-modulus for rods carrying a load with the results calculated by Zöppritz for unloaded rods; i.e. it is, as we have indicated in Art. 771, in the case of the loaded rod that Kupffer's formula is inadmissible. Zöppritz sums up his results as follows:

Kupffers Werthe für δ sind fast durchweg kleiner als die meinigen. Bei den Messingstaben 1, 2, 4, 5, 8 betragen die Abweichungen nur $\frac{1}{140}$ bis $\frac{1}{70}$ des ganzen Werthes und steigen bei No. 6 auf $\frac{1}{15}$ negativ. Bei Stahl ist die Abweichung nur höchst unbedeutend negativ, ebenso bei den meisten Eisen-

staben Bei den Eisenblechstreifen 1 und 2 sind aber Kupffer's Werthe um ein volles Zehntel zu gross Bedeutendere Abweichungen zeigen auch Gold $\frac{1}{80}$, Zink $\frac{1}{30}$, und Remscheid Stahl No 17 ebenfalls $\frac{1}{30}$ Die Werthe, welche Kupffer aus den Versuchen *ohne* angehangtes Gewicht berechnet hat, kommen den meinigen im Allgemeinen viel naher, manche fallen innerhalb der Fehlergränzen mit ihnen zusammen, leider aber hat Kupffer gerade diese Beobachtungen verworfen, weil ihm die Resultate zu schlecht mit den übrigen, bei angehangtem Gewicht angestellten, übereinstimmten (S 234)

[784] Zoppritz notes four misprints of Kupffer's on the latter's pp 270—2 and corrects them (S 229) Further on S 233 he gives the value in French measure of those few of Kupffer's experimental results which allow at present of calculation by accurate theory He compares them with the numbers obtained by Wertheim and other earlier experimentalists These results on S 233 may be said to represent all of Kupffer's work which has probably a numerical exactness equivalent to the excellency of his experimental methods We have tabulated them in a somewhat different form alongside Kupffer's results on our p 531 They are the numbers in brackets with the letter Z attached

Zoppritz's three memoirs certainly throw a great deal of light on the degree of accuracy in the results obtained by Kupffer from empirical formulae of a doubtful character They form also an interesting chapter in the theory of vibrating rods

GROUP C

*Wertheim's Later Memoirs*¹

[785] Wertheim and Breguet *Experiences sur la vitesse du son dans le fer* (Extrait) *Comptes rendus*, T 32, pp 293—4 Paris, 1851 This paper gives some account of experiments by the authors on the velocity of sound in the iron wire used for telegraphing between Paris and Versailles Biot had found the velocity of sound in cast iron to be 105 times that in air, although the theoretical value of the velocity deduced from the stretch-modulus was 122 times that of air After describing their method of making the experiments, the authors continue

Ces expériences ont donné en moyenne une vitesse de 3485 mètres par seconde, tandis que 2 mètres du même fil de fer tendus sur le sonomètre longitudinal rendent un son de 2317 vibrations, d'où l'on déduit une vitesse de 4634 mètres

La vitesse linéaire, d'après l'expérience directe dans le fer, est donc

¹ For Wertheim's earlier researches see our Arts 1292*—1351*

de beaucoup inférieure, et à la vitesse théorique, et à celle que l'on déduit du procédé de Chladni ; la différence est dans le même sens et plus grande encore que celle qui résulte de l'expérience de M. Biot sur la fonte.

[786.] G. Wertheim : *Mémoire sur la polarisation chromatique produite par le verre comprimé. Comptes rendus*, T. 32, pp. 289–292. Paris, 1851. This is an abstract of a memoir which contained the details of certain experiments made with the aid of apparatus described in a sealed packet ; this packet had been opened and read by the President on February 3 of the same year (see *Comptes rendus*, T. 32, pp. 144–5. Paris, 1851).

The object of the investigations described in the memoir was to ascertain whether the very different doubly-refracting powers of glass or crystals of different materials are really inherent in their substance, or are due to different states of initial stress (*tensions moléculaires*) in different crystals.

En d'autres termes : si, dans différents corps homogènes et dans les mêmes directions, on pouvait produire des compressions et des dilatations égales, ces corps acquerraient-ils le même pouvoir biréfringent ou auraient-ils des pouvoirs divers ? (p. 290.)

Experimented on crown, plate and flint glass, all substances, specific gravities and very different stretch-moduli. He varied with different weights till he produced the same difference of refraction between the two rays, which he rather unfortunately terms 'ordinary and extraordinary' rays. Suppose this to be obtained in any case by a vertical squeeze s , then the horizontal stretch $= \eta s$, where η is the stretch-squeeze ratio. Then Wertheim found that the ratio $(1 + \eta s)/(1 - s)$ was the same for the various kinds of glass. He terms this the *rapport des deux densités linéaires*, and he puts $\eta = 1/3$ on his own hypothesis: see our Art. 1319*. I do not know quite why he should thus define it, but it is interesting to know that it is the same for all kinds of glass. Since η is taken by Wertheim a constant, it is the same thing as saying that it requires the same squeeze to produce the same doubly-refracting power in all kinds of glass, which is one way in which Wertheim himself states his result. Since $s = T/E$, the measurement of the load T required to produce a given doubly-refracting power gives a means of ascertaining the stretch-modulus of the glass.

Wertheim points out in the conclusion of the paper that the magnetic rotation of the plane of polarisation is the more feeble the greater the mechanical strain: see our Arts. 698, (iv) and 797, (d).

[787.] *Rapport sur divers Mémoires de M. Wertheim*, by Regnault, Duhamel, Despretz and Cauchy (rapporteur). *Comptes*

rendus, T 32, pp 326-330 Paris, 1851 The Commission appears to have dealt with those memoirs of Wertheim which supported his hypothesis that $\eta = 1/3$, see our Arts 1319*-26* and 1339*-51* They sum up briefly the experimental arguments he has given for $\eta = 1/3$, but remark that this value is impossible on the ordinary (i.e. rari-constant) theory of elasticity But that theory is based on the supposition that each molecule may be reduced to a point

Si l'on suppose, au contraire, chaque molécule composée de plusieurs atomes, alors, suivant la remarque faite par l'un de nous, dès l'année 1839 (comparez our Art 681*), les coefficients compris dans les équations des mouvements vibratoires cesseront d'être des quantités constantes, et deviendront, par exemple, si le corps est un cristal, des fonctions périodiques des coordonnées Or, en développant ces fonctions et les inconnues elles mêmes, suivant les puissances ascendantes et descendantes des fonctions les plus simples de cette espèce, représentées par des exponentielles trigonométriques convenablement choisies, on obtiendra des équations nouvelles desquelles on deduira, par élimination, celles qui détermineront les valeurs moyennes des inconnues D'ailleurs les équations définitives, trouvées de cette manière, seront encore des équations linéaires et à coefficients constants, qui ne pourront devenir isotropes et homogènes, sans reprendre la forme obtenue dans la première hypothèse Mais le rapport entre les deux coefficients ($\lambda + \mu$, μ) que renfermeront alors les équations dont il s'agit ne deviendra pas nécessairement égal à 2, quand les pressions intérieures s'évanouiront, et l'on verra par suite disparaître l'objection proposée (p 329)

Cauchy thus sees clearly what Wertheim never appears to have done, namely that the latter's theory is incompatible with the uni-constancy of the early elasticians Cauchy attempts a reconciliation by means of his suggestion of 1839 The objections to this hypothesis have been considered by Saint-Venant see our Art 192, (d)

The Commissioners speak highly of Wertheim's memoirs and recommend their insertion in the *Recueil des savants étrangers*

[788] G Wertheim *Note sur la double refraction artificiellement produite dans des cristaux du système régulier Comptes rendus*, T 33, pp 576-9 Paris, 1851

Wertheim holds that the optic axes of these crystals under pressure do not coincide with their elastic axes, but make with them an angle which changes when the same force is applied in different directions to the body His reasoning is founded on the

statement that it is impossible to suppose the 'coefficient of elasticity' to be different in different directions in these crystals. It would contradict Neumann's statements, which, however, had been already corrected by Neumann himself as well as by Ångström: see our Arts. 788*-93* and 683-7. Wertheim's arguments are based on experiments on alum, which he says ought to have its elasticity equal in all directions.

[789.] G. Wertheim: *Deuxième Note sur la double réfraction artificiellement produite dans des cristaux du système régulier. Comptes rendus*, T. 35, pp. 276-8. Paris, 1852. This *Note* gives a series of results similar to those referred to in the previous article. We may note the following points:

(a) Crystals of cubic form act under external force like homogeneous bodies, the same force in *any direction* perpendicular to two faces of the crystal produces the same difference of phase between the 'ordinary and extraordinary' rays.

(b) For rock-salt and fluor-spar the difference of phase in the two rays is the same when the compression is the same as Wertheim found for the different kinds of glass (see our Art. 786), i.e. they have the same specific doubly-refracting power as glass.

(c) Alum which crystallises, Wertheim says, in *cubo-octaèdre* does not act like a body optically homogeneous, "although its elasticity is equal in all directions." Under pressure the elastic and optic axes do not coincide.

This is a restatement of the conclusion in our Art. 788. Various results as to the effect of pressure on other forms of crystals of the regular system are given. Wertheim sums up these results with the following statement, which seems somewhat doubtful in so far as it definitely asserts that the elasticity of a body is independent of the various changes of form (? sets) which the body has previously undergone:

Tous ces phénomènes: l'inégale compressibilité optique, aussi bien que la rotation de l'ellipsoïde optique, paraissent avoir leur origine dans les effets permanents produits par les tensions ou pressions qui ont lieu pendant l'acte de la cristallisation; on sait que l'élasticité mécanique ou moléculaire est indépendante des changements de forme que le corps a subis antérieurement; mais l'élasticité optique en conserve pour ainsi dire l'empreinte (n. 278)

[790] G Wertheim *Note sur des courants d'induction produits par la torsion du fer Comptes rendus*, T 35, pp 702-4 Paris, 1852 The contents of this *Note* are stated among many others in our discussion of the second part of the great memoir on *Torsion* see our Art 813

[791] G Wertheim *Mémoire et thèse sur la relation entre la composition chimique et l'élasticité des minéraux Conclusions Cosmos* T IV, pp 518-20 Paris, 1854

This paper gives the results of a memoir by Wertheim which I do not think was ever published

Wertheim considers the elasticity of a metal to be independent of its manufacture and to depend only on its density, chemical constitution, and crystalline form The coefficient of elasticity increases with the density, but more rapidly, a slight chemical change has a great influence on the elasticity On passing from the amorphous to the crystalline stage a body changes its density, and it has yet to be determined how far crystallisation *directly* affects elasticity (the densities of graphite and diamond¹ are as 1 2, their elasticities, if graphite is like other carbons, are as 1 20) A body which can crystallise in two different forms with the same density (e g pyrites) and composition can have different elasticities in the two forms When bodies enter into chemical combination each retains its own elasticity, which is not destroyed by the action of the chemical forces, but only modified by the elasticities of the other bodies in the combination (Wertheim appears to have arranged bodies in tables according to their chief constituent, e g iron, nickel or manganese, but I do not know that these tables were ever published) The following conclusion seems of sufficient importance to be cited at length

D'après ce qui précède, on pourrait être tenté de calculer l'élasticité d'un corps composé en prenant la moyenne entre les élasticités des corps composants, et en attribuant au corps gazeux ou liquides une élasticité hypothétique qu'ils auraient à l'état solide, par un procédé analogue à celui dont on s'est servi pour le calcul des densités et des points de fusion En effet, les sulfures et les arsénures se prêtent assez bien à ce mode de calcul, mais il est complètement en défaut pour les oxydes, l'oxyde magnétique est doué d'une élasticité inférieure à celle du fer métallique, tandis que les sesqui oxydes de fer ont une élasticité supérieure à celle-ci Il faudrait donc, d'après le premier, attribuer à l'oxygène solide une élasticité inférieure à celle du fer, et d'après le second, lui en attribuer une supérieure (p 519)

When two bodies of "analogous composition" or "which belong to the same type" are compared, the elasticity is always the greatest for that in which the molecules are closest (*les plus rapprochées*), but this relation does not hold for bodies of entirely different composition For these on the contrary the elasticity and molecular distance diminish

¹ The *Encyclopædie der Naturwissenschaft Handbuch der Physik* Bd I S 155 gives the ratio of the mean density of graphite to the density of diamond as

as they become more complex" (p. 520). The memoir concludes by suggesting the need for new hypotheses as to the grouping of molecules and as to molecular weight; such hypotheses, however, could only be verified by a wider range of experiments than, Wertheim states, he had at that time undertaken. He promises to complete his researches in this direction.

[792.] G. Wertheim: *Mémoire sur la double réfraction temporairement produite dans les corps isotropes, et sur la relation entre l'élasticité mécanique et l'élasticité optique. Annales de chimie et de physique*, T. XL., pp. 156–221. Paris, 1854. This memoir is translated into English in the *Philosophical Magazine*, Vol. VIII., pp. 241–61 and 342–57. London, 1854. It is an attempt to investigate the relation between stretch and traction and the question of the equality of the stretch- and squeeze-moduli by means of photo-elasticity. There are references in the memoir to the researches of Brewster, Neumann and Maxwell: see our Vol. I. p. 640 Arts. 1185*, and 1556*. I do not think, however, that Wertheim has sufficiently expressed his indebtedness to these authors.

[793.] The memoir commences with twelve pages entitled *Historique* (pp. 156–168). Here it is pointed out that the theory of elasticity assumes: (i) the proportionality of stress and strain; (ii) the equality of the stretch- and squeeze-moduli. There are, however, various experimental investigations, which throw doubt on the truth of these assumptions, notably those of Hodgkinson (see our Arts. 234*, 1411*–12*). Wertheim remarks on the great difficulty of making direct experiments on compression. For sensible squeezes we require a long bar of material, and this will certainly buckle unless supported at the sides. But if supported at the sides the disturbing action of friction is introduced. This disturbing action Vicat had met with in his experiments on the compressibility of lead (see his memoir of 1833 referred to in our Art. 724*). Wertheim also attributes the large values of the squeeze-modulus for wrought-iron obtained by Pictet (see his memoir of 1816 referred to in our Art. 876*) to the same cause. The difficulties attending experiments on compression have hindered the undertaking of any important series of *direct* experiments except those of Hodgkinson. These Wertheim discusses at very considerable length on pp. 159–166. He takes Hodgkinson's results and, assuming the equality of the stretch-

the purely elastic stretches and squeezes the values of the stretch- and squeeze-moduli for forged and cast-iron. He obtains the following results

(i) Removing the set, the proportionality of stretch and traction for wrought-iron holds almost up to rupture

(ii) Removing the set, the stretch increases more rapidly than the traction for cast iron. (Wertheim holds that this result may be due to defects almost unavoidable in the method of experiment)

(iii) Removing the set, then for eight series of experiments on cast-iron the squeezes diminish with the pressures in three series, in one series they increase, and in four there is a sensible proportionality. Two of the last series of experiments are for a mixture of cast-irons (Leeswood and Glengarnock)¹. Wertheim considers that Hodgkinson's experiments are very far from giving any conclusive answer as to the legitimacy of the assumptions made in the usual theory. He proposes therefore to investigate them afresh by the aid of photo-elastic measurements. For the theory of photo elasticity he claims (p. 168) some precedence for Fresnel over Neumann. He refers to a memoir of Fresnel's written in 1819 and only published in 1846, five years after Neumann's (see *Annales de Chimie*, 3^e serie, T. xvii). Fresnel's paper in no wise detracts from the transcendent merits of Neumann's great memoir. That memoir was based upon Brewster's experimental researches, and the discovery of double refraction by pressure is the real contribution to be attributed to Fresnel. The statement of the fundamental equations of photo elasticity and their application to the wide range of phenomena observed by Brewster is undoubtedly due to Neumann.

[794] Pp. 169-185 describe Wertheim's apparatus, which is constructed with his usual ingenuity, not the least valuable part is the differential arrangement described on pp. 181-2 for use when the loads are small. It lies beyond the scope of our *History* to do more than refer to accounts of physical apparatus. Suffice it to say that Wertheim shows that the difference of the equivalent paths of the two rays is approximately proportional to the loads, and by means of a very complete table on p. 180 he is enabled to measure the loads by a scale

¹ These results assume of course that we may suppose the set not to affect the stretch and squeeze moduli: they are not based on experiments in which the bars have been previously reduced to a state of ease embracing the maximum load. Supposing squeeze set to be produced by lateral stretch, we should not expect the squeeze modulus to be so sensibly affected by set as the stretch modulus until the pressure was 4 to 6 times as great as the traction (i.e. granted $\eta = \frac{1}{2}$ to $\frac{1}{3}$).

Thus the compression load of about 350 cwt which limits the compression experiments ought not to be compared, so far as equality of the stretch and squeeze moduli is concerned, with a load of more than about 70 cwts in the traction experiments. It will then be found that the difference between the stretch and

of colours of the two images. He thus carries out exactly what Brewster had proposed in the *Chromatic Teinometer*: see our Art. 698* and ftm., Vol. I. p. 640. The reader will easily understand how this colour scale of stress can be applied to the problems stated in the previous article.

[795.] Taking Neumann's theory (see our Art. 1191*, Eqn. (iv)) we see that air thickness answering to the colour measured in Newton's scale is proportional to the stretch (or squeeze) in the case of a prism under pure positive (or negative) traction. According to Wertheim's experiments it is proportional to the load; we have thus a method of ascertaining whether stress is here proportional to strain, and if so whether the constant of proportionality is the same for both positive and negative stress. Wertheim's own theory and his comparison of its results with those deduced from Neumann's seem to me somewhat obscure. Thus he says:

"Let O be the velocity of light in the air; O_o and O_e the ordinary and extraordinary velocities in the substance¹, which possesses for the time double refraction" (p. 199).

Then if h , l , b be the height, length and breadth of the prism subjected to a *total* traction P in the sense h , these dimensions become

$$h(1+s), \quad l(1-\frac{1}{3}s), \quad b(1-\frac{1}{3}s),$$

where s is the stretch produced by P . Wertheim puts this down without stating that he is assuming that $\lambda = 2\mu$ and consequently $\eta = 1/3$, his own particular theory of the inter-constant relation for isotropy. He

states: "The two rays have to traverse the distance $l(1-\frac{1}{3}s)$; exactly the difference of their equivalent air-paths d , after ^{have} the prism is proportional to $l(1-\frac{1}{3}s) (O/O_o - O/O_e)$ and to dilatation s , we have then:

$$d = sl(1-\frac{1}{3}s) (O/O_o - O/O_e) \dots\dots\dots(i).$$

Assuming s^2 negligible, and stress proportional to strain, or,

$$s = P/(Elb),$$

we find:

$$d = \frac{P}{Elb} (O/O_o - O/O_e) \dots\dots\dots(ii).$$

Now: " O/O_o and O/O_e are the two indices of refraction I_o and I_e ; and for $d = \pm 1$ and $b = 1$, we have $P = C$, and accordingly,

$$I_e = I_o \mp E/C \dots\dots\dots(iii),$$

where it is necessary to take the negative sign for positive traction and the positive sign for negative traction."

I do not understand Equation (i). I should have thought that if

¹ Wertheim following the analogy of natural double refraction speaks of 'ordinary and extraordinary' rays. Homogeneous plane polarised light, being incident normal to the face $h \times b$ of the prism, will be decomposed into two rays, one with vibrations parallel to h , the other with vibrations parallel to b . These rays travel with velocities differing from each other and from the velocity of light in the unstrained prism. Neither ray has thus a special claim to be termed 'ordinary.'

O_o and O_e were the ray velocities the value of d must, for small s , be $l(O/O_o - O/O_e)$, which agrees with Neumann's value in our Art 1191*, if we remember that his δ is not the length of the equivalent air path, but the thickness of air for the corresponding colour of the Newtonian scale. Further, since Wertheim makes $O/O_o - O/O_e$ or $I_o - I_e$, a constant in Equation (iii) depending on the elastic nature of his material, he can hardly mean O_o and O_e to be the *velocities* of the two rays. They are really the velocities divided by the stretch. Comparing Wertheim's Equation (i) above with Neumann's (iv) of our Art 1191*, we see that

$$\frac{p-q}{V^2} (1+\eta) = \frac{1}{O_o} - \frac{1}{O_e},$$

or, that the constant $I_o - I_e$, which Wertheim terms "the true measure of the double refraction,"

$$= \frac{p-q}{V} (1+\eta) \times r$$

in terms of the photo elastic constants p and q of Neumann, where r is the refractive index and V the velocity of light in the unstrained material. Taking $r = O/V$ and assuming it = 1.543 for plate glass, Neumann's values for p/V and q/V (see Art 1193*) give $I_o - I_e = 158$ according to my calculations and with unconstant isotropy. Wertheim gives 157 for its theoretical value for $\eta = \frac{1}{2}$, and, 168 for $\eta = 1/3$. His experimental determination gives 191. The difference is considerable, but in both Neumann's and Wertheim's results all the elastic and optic constants were not determined for the same kind, still less for the same piece of glass.

It may be noted that Wertheim terms the constant C above (Equation (iii)) the "*coefficient d'elasticite optique*." Thus C is proportional to the inverse of what Maxwell terms the "optical effect" see our Arts 1543*, 1544*, and 1556*. Wertheim's name seems well chosen, as we have from Equation (ii), $d = P/(Cb)$, an equation analogous to $s = P/(Ebl)$, thus C is the load corresponding in a prism of unit breadth to unit difference of equivalent air paths (p. 196).

[796] Wertheim's first three experimental results verify the relation $d = P/(Cb)$, where C depends on the material and not on the size of the prism taken (Experimental Laws, 1° - 3°, pp. 189-90). A fifth law stated on p. 197 is that the difference (d) of the equivalent air paths of the two rays is independent of the wave length, thus the dispersion accompanying the double refraction is insensible.

Wertheim's fourth experimental law is the answer to the problems he stated at the commencement of his memoir. According to Neumann's theory d is proportional to the stretch s and

by Wertheim's experiments d is given as a function of P . Hence if d be plotted up to P , the curve ought to be a straight line if P be proportional to s , or if stress be proportional to strain. Further this line ought to pass through the origin without change of slope if the stretch- and squeeze-moduli are equal. The following is Wertheim's conclusion:

Double refraction or the difference of the equivalent air-paths of the two rays is proportional to the mechanical stretch or squeeze, but these are not rigorously proportional to the tractions. In taking the tractions for abscissae and the stretches and squeezes for ordinates, a curve is obtained for the pressures concave to the axis of abscissae, and another for the tensions convex to the same axis; these curves straighten themselves as the stresses increase till they coincide with one and the same straight line which corresponds to the elastic modulus usually adopted for both stretch and squeeze (p. 191).

What Wertheim's experiments go to show is a want of proportionality between d and P . He gives (pp. 192-3) reasons for supposing that s and d are proportional, hence it follows that s and P are not. It must be remembered that Wertheim has been plotting up his curves starting with initially very small loadings quite within the elastic limit, and that it is not till these small loadings are passed that the exact proportionality of stress and strain appears to commence. In other words the slopes of the tangents to the stress-strain curves at the origin are not what we are to understand by the statical moduli. Are we to take then the slope of one or other tangent at the origin as the modulus obtained by vibrational methods, or are we to suppose no proportionality between very small stresses and strains? This latter view is opposed to the isochronism of sound vibrations. Of course in experiments involving delicate measurements of this kind, it is always possible to raise a suspicion as to the accuracy of the results. Here is what Wertheim himself says of his results:

Les résultats que nous venons d'obtenir ne sont d'aucune importance pour la pratique des constructions; ces différences sont trop petites pour être prises en considération lorsqu'il s'agit de l'emploi des matériaux, et nos expériences prouvent que l'on peut continuer en toute sûreté de se servir d'un même coefficient d'élasticité pour calculer les effets des tractions et des compressions. Mais ces résultats acquièrent une grande importance lorsqu'on les considère au point de vue de la théorie des forces moléculaires ou de celle des oscillations mécaniques et des vibrations sonores; je crois qu'ils fourniront la solution d'un certain nombre de questions qui sont restées en suspens, et sur lesquelles je me propose de revenir dans une autre occasion (pp. 196-7).

[797] Some other points in the memoir deserve notice

(a) The "double-refractive power" (=in Wertheim's notation $I_o - I_e$) depends in some undiscovered way on the other elastic and optical properties of the bodies. According to Wertheim it is not the same for all substances (he finds on p 202 values from 2182 for crown glass to 0875 for 'Flint Faraday' and 0641 for 'alum inactif'), neither does it stand in any simple relation to the density, nor is it a function of the refractive index only

We note that Neumann's value of the "double refractive power" contains $(1 + \eta)$ and r^2 as factors, if it be written in the form

$$\frac{p-q}{O} (1 + \eta) r^2,$$

and hence throws us back on the determination of p and q as functions of the elastic and optic constants (pp 204-5)

(b) Wertheim holds that there is no relation between the two kinds—natural and artificial—of double refraction. To convince oneself of this, he says, it is only requisite to consider the forces which it is necessary to apply to an isotropic body in order to produce for equal thickness the same double refraction which arises from the passage of a ray across a plate of doubly refracting crystal cut parallel to the axis. For example he takes Iceland spar and ordinary crown glass, for which he says "the differences of the two indices of refraction are the same". Now I have already referred to his obscurity about the quantities O_o and O_e and indicated that his I_o and I_e are not the true refractive indices. It seems to me that $s(I_o - I_e)$ is the real difference of the refractive indices for the strained material. Does he then mean that this or that the "double refractive power" $I_o - I_e$ for crown glass is equal to the difference of the indices for Iceland spar? If he does mean, as he says, the difference of the indices, then the force required to make the crown glass refract as the Iceland spar is $P = Ps$, or P would be the pressure required to produce the necessary strain in the glass for the given difference of indices. On the other hand if he means that the "double refractive power" of crown glass is equal to the difference of the indices of Iceland spar, then we have $P = E$, as he says, or a pressure is required a thousand times greater than would crush the glass (p 204)

This apparent confusion leads me to doubt the accuracy of the values given for I in the table p 202. E/C is presumably found from the experiments and equals $I_o - I_e$ in Wertheim's notation, but why is $I_o - I_e$ the refractive index for the isotropic material? Since it is $s(I_o - I_e)$ which is the difference of the refractive indices of the 'ordinary and extraordinary' rays, this appears a perfectly arbitrary assumption.

(c) In a footnote on p 206 Wertheim objects to Maxwell's having referred (in the memoir of 1850) to his hypothesis that $\lambda = 2\mu$, while citing *only* his experiments on calcareous evidence for it, and neglecting all the other experimental evidence in favour of it. He also not

unreasonably objects to Maxwell's taking cork and jelly as types of isotropic homogeneous bodies, but Maxwell has not been the only offender in this respect.

(d) Wertheim considers what rotatory effect magnetic force has on the plane of polarisation when an isotropic body in the magnetic field is subjected to positive or negative traction. His experiments were on bodies which possess to a high degree the magnetic rotatory power when isotropic ('tels que les flints'). The result was always the same, a small stress rendered this power relatively feeble. The exact load at which it disappeared was not capable of accurate measurement, but, the light being homogeneous, all rotation had disappeared when the difference of the equivalent air-paths of the two rays had become equal to half the wave length of the light. Wertheim considers that for all natural or artificial doubly-refracting media the magnetic rotatory power is in inverse ratio to the doubly-refracting power,—when the one is most energetic the other is feeblest. Thus it is to be noted that purely mechanical forces can apparently annul the action of magnetism on the optical medium¹ (pp. 207–9).

(e) On pp. 209–216 Wertheim describes what he terms the *Dynamomètre Chromatique*. This is merely a variation of Brewster's *Chromatic Teinometer*: see our Art. 698*, Vol. i. p. 640, ftn. Brewster's Teinometer is based on flexural stress, Wertheim's on traction, but the idea is exactly the same in both. Wertheim, it is true, makes considerable practical application of his instrument, and describes accurately its structure and use, but he ought to have acknowledged the source from which he had taken his idea, as he elsewhere refers to the very of Brewster's in which an account of the *Teinometer* is given.

Wertheim, assuming the accuracy of his Teinometer, shows what very large errors may arise in the manometric measurements of pressure in a large hydraulic press (p. 215).

(f) He applies his Teinometer to ascertain the squeeze-modulus of diamond. Turning to Equation (ii) of Art. 795, we have

$$d = \frac{P}{Eb} (I_o - I_e).$$

Now d , b , and P can be measured, hence if we knew $I_o - I_e$ we should have E . Here I fail to follow Wertheim, he assumes $I_o - I_e$, instead of $s(I_o - I_e)$, as the difference of the refractive indices again. He puts $I_o = 2.470$, Brewster's value for unstrained diamond, and assumes for I_e a value equal to that of fluor-spar. Thus he obtains $E = 10,865$ kilos per sq. mm., or about the value for annealed copper—"et nullement en rapport avec sa grande dureté" (p. 217).

Pp. 217–21 contain a *résumé* of the results of this memoir,—a memoir which is undoubtedly of value, but which requires somewhat cautious and critical reading.

¹ Wertheim (p. 208) refers to experiments of Bertin and Matteucci in the same direction, but without giving the *loci* of their memoirs: see our Arts. 698, (iv) and 702.

[798] G Wertheim *Mémoire sur la torsion Comptes rendus*, T 40, pp 411-414, and *Mémoire sur les effets magnetiques de la torsion*, in the same volume, pp 1234-7 Paris, 1855 These contain extracts from the great memoir on Torsion see our Arts 799 *et seq*

[799] G Wertheim *Mémoire sur la Torsion Annales de chimie et de physique*, T 50 Première Partie (*Sur les effets mécaniques de la torsion*), pp 195-321 Seconde Partie (*Sur les effets magnétiques de la torsion*), pp 385-431 Paris, 1857 This paper was presented to the Academy on February 19, 1855

Wertheim exhibits here as in other work all his merits and demerits,—excellency and width of experimental investigation, ignorance or misapplication of theory, which leads him to misinterpret the results of some even of his own experiments

[800] The memoir, after a brief statement of the problem of torsion, opens with an account of the history of that subject (*Historique*, pp 196-202) Here reference is made to Coulomb (Art 119*) and Biot (Art 183*) for the theory of torsion, to Poisson, Cauchy, Lamé and Clapeyron for the general equations of elasticity, to Neumann, Stokes and Maxwell as arriving at the same results by different processes but as adding nothing essential, to Heim¹ and Segnitz (Art 481) as determining the shortening of a prism by torsion, to Savart (Art 333*), Duleau (Art 229*), Bevan (Art 378*), Giulio (Art 1218*) and Kupffer (Art 1389*) as experimentally verifying the laws of torsion, or as determining by its means the elastic constants, reference is made also to Saint-Venant, whose work Wertheim seems totally to have misunderstood, probably to a great extent through insufficient analytical knowledge The footnote on p 199 is neither just to the results which Saint-Venant had published before 1857, nor does it apparently grasp his position It is one thing to agree that a certain coefficient of correction is necessary, it is another to accept Wertheim's erroneous theory of torsion and his purely empirical relation between the coefficients of bi-constant isotropy ($\lambda = 2\mu$) in order to deduce that coefficient We cannot enter at length into

¹ Heim in the work referred to in our Art 906* deals (S 237-47) by a cumbersome analysis with the stretch in the 'fibres' of a prism due to torsion What is material on this point has been said in our Art 51

the details of this controversy which we have had occasion several times to refer to (see our Arts. 1339*-43*, 1628*-30*, and 191-2). It must suffice to state here that we hold Wertheim to have been in the wrong throughout, and occasionally, we fear, influenced by the dread that Saint-Venant's brilliant theoretical achievements would throw into the shade his own very valuable experimental researches. The lesson to be learnt from the controversy is the ever-recurring one, namely, the need that physicists should have a sound mathematical training, or, failing this, leave the theoretical interpretation of their results to the mathematician.

[801.] After a description (pp. 202-205) of the apparatus adopted for the experiments, Wertheim states the problems he proposes to deal with. They are the following :

(i) Whatever may be the magnitude of the *elastic* strain, are the angles of torsion still rigidly proportional to the moments of the torsional couples and to the lengths of the prisms to which torsion is applied?

(ii) What is the relation between torsional elastic strain and torsional set (*tort*)?

(iii) Is torsional elastic strain accompanied by change of volume, and if it be, what is the relation of that change to the torsional couple and to the shape of the prism?

(iv) How far is the accordance with experiment of the formulae of torsion modified by the aeolotropy of the material or by the shape of the prism?

(v) How far do the results of torsional experiments confirm Wertheim's theory that $\lambda = 2\mu$, or tend to demonstrate uni-constant isotropy, $\lambda = \mu$?

Wertheim's experiments were made on 65 prisms, partly on circular, partly on square, rectangular and elliptic bases, some being solid and some hollow. The materials were steel, iron, brass, glass, and in a few cases oak and deal.

In the experiments on torsion the terminal cross-sections of the prism were fixed at a constant distance from each other, *i.e.* the length of the prism could not change with the torsion (p. 202).

[802.] Wertheim takes the opportunity afforded by the hollow prisms to investigate in Regnault's manner the value of the stretch-slide ratio η . The hollow prism blocked at the ends is filled with fluid communicating with a capillary tube passing through one of the terminal blocks. The prism is then stretched with a given stretch s_1 . If the prism were isotropic the change in unit volume of the hollow ought to be $s_1(1 - 2\eta)$. This change in volume can be measured by the amount the fluid has advanced or receded in the capillary tube. There are consider-

able difficulties in making the experiment,—e.g. Wertheim found that the results depended to some extent on the diameter of his capillary tube (see pp 209–10 and the numerical tables) The results are given in a table on p 212 Wertheim puts $\eta = 1/3$ and thus takes the change in unit volume to be $1/3$ of the stretch The calculated results do not agree very closely with the observed, being greater for cylinders of brass and less for those of iron Rectangular prisms of brass give fairly good results At the same time $\eta = 1/3$ gives generally better results than could be obtained from $\eta = 1/4$ As Wertheim, however, admits that despite the annealing his prisms were *not isotropic*, there is no real reason why η should be equal to $1/4$ This want of isotropy Wertheim considers beyond the reach of the then existing theory, and an attempt he makes to deal with it on the basis of Cauchy's equations is not successful The difficulty was fully overcome in Saint-Venant's paper of 1860 *Sur les divers genres d'homogénéité* see our Arts 114–125 While probably the anisotropy accounts for the variety of the results, Wertheim also notices that the fluid itself may affect chemically the material of the tube or the cement which fastens its terminals (p 216)

Pp 216–221 are entitled *Sur les effets optiques produits par la torsion*, and mainly describe the difficulty of making the necessary experiments Wertheim concludes from experiments made on glass only that

Ces expériences prouvent qu'il s'agit seulement d'une double refraction ordinaire qui devient positive ou négative selon que la torsion a lieu vers la droite ou vers la gauche, on ne peut rien en conclure en ce qui concerne un corps parfaitement homogène, et elles ne peuvent servir ni à confirmer ni à infirmer les prévisions de l'analyse de M. Neumann (See our Art 1195 ')

[803] Pp 221–225 are entitled *Sur quelques faits généraux et indépendants de la forme de la section transversale* Wertheim commences by dividing the angle of torsion into two parts, ψ_1 the elastic part and ψ the set part He recognises the after strain discovered by Weber (*l'effet secondaire découvert par M. Weber, et qui est insensible dans l'allongement des métaux*) to be sensible in torsion experiments on metals, but he disregards it because

ses effets se confondent avec ceux des oscillations tournantes que la barre exécute autour de chaque position d'équilibre avant de revenir au repos (p 221)

As after strain can be observed for more than twenty minutes in steel wires, I am somewhat doubtful as to the exact meaning of the sentence cited

The following general conclusions are drawn by Wertheim

(a) There is no point at which set can be said to commence (thus Wertheim had not reduced his prisms to a state of ease)

(b) The set angle bears no obvious relation to the elastic angle It is not proportional to the length of the prism nor to the load couple, although of course it varies with these It begins to increase

at first very gradually, then more rapidly, and finally just before the bar breaks (ou se mette à *filer*) becomes incapable of determination. (This seems to point to the early stages of set being merely due to the 'working' of the individual specimen.)

(c) The angles which measure the elastic strain are not rigorously proportional to the load-couples applied.

Wertheim attributes this result to two causes: the first that stretch is not proportional to traction as shown by his paper of 1854 (see our Art. 796), whence, as he holds torsion involves a longitudinal traction, torsional stress ceases to be proportional to strain; and the second that as the torsion increases the cross-sections contract, and so the 'moment of resistance' of the prism decreases. (Both these causes seem to me quite insignificant except for very large strains, which of course do not fall within the ordinary theory of elasticity. The effect of the traction on the torsional couple is given in our Art. 735, (iii)).

(d) The angles of torsion are not rigorously proportional to the lengths of the prisms.

(e) The interior cavity of a hollow prism, whatever be its form, is diminished under the influence of torsion. This diminution is proportional to the length of the prism and to the square of the angle of torsion per unit length of prism.

For the case of hollow circular cylinders Wertheim gives the following formula for the diminution δV of the cavity V :

$$\delta V/V = -\tau^2 \alpha_1^2,$$

the angle of torsion per unit length of the prism and α_1 the radius of the hollow cylinder (p. 226). This gives results fairly in accordance with his experiments. He propounds a partial theory in Arts. 229-235, which I am not able to accept. It contains the conclusions cited below, which I think are erroneous:

Il se présente d'abord la question de savoir si, ainsi que nous le supposons, la diminution de volume que nous venons de trouver représente réellement celle qu'aurait éprouvée un cylindre solide de même matière que la paroi du tube, de dimensions telles, qu'il remplit toute la cavité intérieure de celui-ci, et qui aurait été soumis à la même torsion temporaire? L'affirmative ne me semble pas douteuse (p. 229).

We can test the result in the manner of our Art. 51. With the notation of that article the longitudinal squeeze of a solid cylinder of radius a is $\frac{\tau^2 a^2}{4}$ if the cylinder be allowed to shorten. The cylinder, however, in Wertheim's experiments was maintained at length l . Hence there would be a longitudinal tension corresponding to a stretch of $\frac{\tau^2 a^2}{4}$, or if η be the stretch-squeeze ratio its radius a would become $a \left(1 - \eta \frac{\tau^2 a^2}{4}\right)$ and therefore

$$V + \delta V = \pi a^2 l \left(1 - 2\eta \frac{\tau^2 a^2}{4} \right),$$

$$\begin{aligned} \text{or } \frac{\delta V}{V} &= -2\eta \frac{\tau^2 a^2}{4} \\ &= -\frac{\tau^2 a^2}{8} \text{ for uni constant isotropy,} \\ &= -\frac{\tau^2 a^2}{6} \text{ on Wertheim's hypothesis } (\lambda = 2\mu) \end{aligned} \quad (1),$$

On the other hand the longitudinal squeeze is not equal to $\frac{\tau^2 a_1^2}{4}$ for a hollow cylinder of inner radius a_1 . To ascertain its value ϵ (\equiv the η of the notation of our Art 51) we must put instead of the equation at the middle of our page 42

$$\int_{a_1}^{a_2} 2\pi r dr E \left(\frac{\tau^2 r^2}{2} - \epsilon \right) \sin P'PN = 0$$

$$\text{This gives us } \frac{\tau^2 (a_2^4 - a_1^4)}{8} = \epsilon \frac{a_2^2 - a_1^2}{2},$$

$$\text{or, } \epsilon = \frac{\tau^2 (a_2^2 + a_1^2)}{4},$$

that is the *double* of its previous value if a_2 be nearly equal to a_1 . Hence by the same reasoning as before the internal radius a_1 becomes

$$a_1 \left(1 - \eta \tau^2 \frac{a_2^2 + a_1^2}{4} \right)$$

Hence the new volume of the cavity

$$= V + \delta V = \pi a_1^2 l \left(1 - 2\eta \tau^2 \frac{a_2^2 + a_1^2}{4} \right),$$

$$\begin{aligned} \text{or, } \frac{\delta V}{V} &= -2\eta \tau^2 \frac{a_2^2 + a_1^2}{4} \\ &= -\frac{\tau^2}{8} (a_2^2 + a_1^2) \text{ for uni constant isotropy,} \\ &= -\frac{\tau^2}{6} (a_2^2 + a_1^2) \text{ on Wertheim's hypothesis} \end{aligned} \quad (11),$$

Thus (11) gives for the hollow cylinder a value at least double that for a solid cylinder of the radius of the hollow. Our theoretical investigation, however, gives a value for $\delta V/V$ for these cylinders only about a *third to a fourth* of that given by the formula which Wertheim holds established by experiment. I am unable to explain this discrepancy between the above theory and experiment. Possibly it arises from the difficulty in Wertheim's apparatus of the terminal sections contracting and hence in some way there may result a tendency to an inward buckling of the sides of the cylinder.

[804.] On pp. 235-7 we have a *résumé* of the results for hollow and solid circular cylinders. In comparing the experimental results with theory Wertheim takes $\eta = 1/3$, and it appears to agree better than $= 1/4$, but if we adopt bi-constant isotropy then there is no particular reason for taking $\eta = 1/4$, and if we suppose rari-constant anisotropy the same remark holds. In both cases we should choose a value of η best fitting with the experiments and varying from one material to another. Hence it is impossible to agree with Wertheim's statement :

Quant à l'exactitude de la constante que j'ai introduite dans la formule, nul doute ne peut subsister à cet égard ; tous les angles calculés seraient avec l'ancienne formule de $\frac{1}{18}$ plus petits, et il en résulterait entre le calcul et l'expérience un désaccord constant et de beaucoup supérieur à la limite des erreurs, désaccord qui, dans les torsions considérables, atteindrait souvent l'importance de plusieurs degrés (p. 237).

This statement is a fair enough argument against the uni-constancy of the material of Wertheim's prisms, but is of no value in favour of the general law that $\eta = 1/3$. He appears to consider that there is really a theoretical reason for this particular value, so that it has more claim on our attention than $\eta = .3$ say, while in fact it has a purely empirical basis : see our Arts. 1324*-6*.

[805.] Wertheim next passes to the torsion of prisms on elliptic bases. Here his method is very singular. He writes :

On obtient la formule pour la torsion de ces cylindres, en substituant dans la formule que M. Cauchy a trouvée pour les prismes rectangulaires, à la place du moment d'inertie du rectangle par rapport à l'axe, le moment polaire (p. 238).

It has a footnote to 'l'ellipse'—"Voyez les ouvrages de MM. Poisson, Lamé, Moseley et Weissbach."

Now Cauchy's formula for rectangular prisms is quite wrong (see our Arts. 661*, 684*, 25 and 29), and if it were correct it could not be applied in the manner suggested to elliptic prisms. But the wrong formula for rectangular prisms, erroneously assumed to hold for elliptic prisms, does give the true result for the latter as Saint-Venant had shown ten years before this memoir (see our Art. 1627*). Wertheim in this manner reaches Saint-Venant's formula for prisms of elliptic cross-section (see our Art. 18) without referring to its discoverer. The footnote can hardly serve to do more than mystify the reader. In our Art. 1623* it has been pointed out that Saint-Venant in 1847 separated the *gauchissement* into two elements, a distinction which he afterwards dropped. This distinction, however, made no change in the facts or formulae he deduced for torsion. Now Wertheim (taking however $\eta = 1/3$) finds a close agreement between what is really Saint-Venant's formula and the results of his own experiments. He writes :

Les résultats moyens des expériences s'accordent donc avec le calcul d'une manière satisfaisante même pour les cylindres 12 et 14 qui ont pour bases

des ellipses d'une forte excentricité, dans la théorie de M. de Saint-Venant cet accord prouverait que le premier gauchissement qui seul existerait dans des cylindres elliptiques, et dont l'influence sur le moment de résistance à la torsion n'a pas été déterminée par ce géomètre, serait complètement négligeable sous ce rapport (p. 239)

The only intelligible reading of this passage would seem to be that Wertheim had a different theory from Saint-Venant for elliptic prisms and that the theory of the latter was demonstrated by the experiments to be erroneous. These conclusions would be the exact opposite of the truth. Saint-Venant's reply to "cette observation de l'honorable et consciencieux expérimentateur" is polite but complete (see the *Leçons de Navier*, pp. 629-31, and our Art. 191)

[806] The next section of Wertheim's memoir is entitled *Sur la torsion des prismes homogènes à base rectangulaire*, and occupies pp. 239-53

Before entering on the matter of this section we must remind the reader that Saint Venant had in 1847 given the true theory for rectangular prisms (see our Art. 1626*) and shown wherein Cauchy's theory was erroneous. Further that in 1854 Cauchy had acknowledged the justice of Saint-Venant's criticism (see our Art. 684*). Wertheim's memoir was read in 1855 but not published till two years later, after, indeed, the appearance of Saint Venant's great memoir on *Torsion*, which was printed in a volume of the *Mémoires des savants étrangers* dated 1855. Hence it seems unaccountable that Wertheim should without comment adopt Cauchy's formula as the theoretical view of the subject, and apply to it a numerical coefficient of correction which depends in an unknown manner on the ratio of the sides of the rectangular base.

Wertheim commences by comparing the experiments of Duleau and Savart on rectangular prisms with Cauchy's formula and deducing a coefficient of correction. This is close to its value as given by Saint Venant's theory see our Arts. 31, 34 and 191.

The next point dealt with is the diminution of volume of the interior of a hollow rectangular prism or tube under torsion. Wertheim gives the formula,

$$\delta V/V = - \frac{(a_1^2 + b_1^2)^4}{16 (a_1 b_1)^5} \tau^2,$$

where $2a_1$, $2b_1$ are the sides of the hollow and τ the angle of torsion per unit length of the prism. But he remarks

il n'est pas impossible que la théorie après de nouveaux progrès conduise à une formule différente de celle-ci, et qui ne s'accorde pas moins bien avec les expériences (p. 243)

This seems possible as there is a mistake somewhere in this

empirical formula, for the left-hand side is a numerical quantity, but the right-hand side is an *area*. Possibly Wertheim intended to write in the denominator $16 (a_1 b_1)^3$.

If we go back to Art. 51 and *assume* the shortening of the 'fibre' at any point of the hollow rectangle to be still $\frac{1}{2} \tau^2 r^2 - \epsilon$, where r is the distance of the fibre from the axis of the prism, we easily find $\epsilon = \frac{1}{2} \tau^2 \kappa^2$, where κ^2 is the swing-radius of the section about the axis of the prism. In the case of a hollow rectangle with lengths of inner sides $2a_1, 2b_1$, of outer sides $2a_2, 2b_2$, and uniform thickness we easily find :

$$\kappa^2 = \frac{1}{3} (a_2^2 + b_2^2 + 2a_1 b_1).$$

Whence with the same reasoning as before :

$$\delta V/V = -2\eta \frac{a_2^2 + b_2^2 + 2a_1 b_1}{3} \frac{\tau^2}{2}.$$

If the prism be very thin we have :

$$\begin{aligned} \delta V/V &= -\frac{1}{12} (a_1 + b_1)^2 \tau^2 \text{ for uni-constant isotropy,} \\ &= -\frac{1}{9} (a_1 + b_1)^2 \tau^2 \text{ on Wertheim's hypothesis.} \end{aligned}$$

For the case of a square section ($a_1 = b_1$) these give only about one *third to a half* of Wertheim's results, thus differing almost as much as in the case of a hollow circular cylinder (see our Art. 803, (e)).

If we were to multiply the above results by $(1 + 2\eta)/2\eta$, or by 3 or 2.5 according to the hypothesis adopted, they would then agree fairly well with Wertheim's experiments. But this amounts to supposing that Wertheim's terminal conditions were of such a nature that there was for a *thin* prism a reduction of sectional dimensions given by $\frac{1}{2}(1 + 2\eta)$. Thus according to Wertheim if the torsional couple be so large that it would produce, when the ends of the prism were not fixed, a sensible longitudinal squeeze, then, if the ends be fixed, there will be a diminution of the linear dimensions of any internal cavity of about $(1 + 2\eta) \times$ this squeeze.

[807.] So far as Wertheim's own experiments on solid prisms of rectangular cross-section go, the 'coefficient of correction' was very nearly that required by Saint-Venant's theory,—the errors were such as were not unlikely to occur in material which was hardly isotropic and in torsions carried in many cases beyond the limit of linear elasticity. See Saint-Venant's *Leçons de Navier*, pp. 622–629.

The formula for the torsion of hollow rectangular tubes given on p. 250 is of course wrong : see our Art. 49.

[808] *Sur la torsion des corps non-homogènes* is the title of the section of the memoir which occupies pp 253–258 Wertheim supposed that for sheet iron and wood there are three rectangular axes of elasticity, but his struggles to reach a theoretical formula for this case were not successful The true formulae for prisms of elliptic and rectangular cross sections are given in our Arts 46–7 Wertheim obtains by a series of inadmissible hypotheses a formula for a rectangular prism which corresponds to some extent with Saint Venant's for an elliptic prism He applies it, not very satisfactorily, to his experiments on wood

One point in this section deserves to be noticed, namely that for hollow cylinders of sheet-iron there was an *increase* instead of a decrease of internal capacity produced by torsion (p 254) This cannot be explained by the formula (ii) of our Art 803 (e) unless we put η negative, which is, however, impossible Wertheim's own formula is equally inapplicable

[809] The following section (pp 258–269) deals with the torsional vibrations of homogeneous bodies So far as the theory of this section goes it is partly erroneous (e.g. for rectangular prisms) and partly hypothetical It was a retrograde step to publish it after Saint Venant's memoir of 1849 see our Arts 1628–30* Saint-Venant shows in the *Leçons de Navier* (see pp 635–645, especially p 643) that Wertheim's experimental observations are in complete accord with the formula

$$\frac{n}{n'} = \sqrt{\frac{E}{\mu} \frac{\omega \kappa}{v}}$$

given in our Art 1630* Wertheim introduces as before a 'coefficient of correction' for the bars of rectangular section

In a footnote (pp 264–6) he corrects a slip of Cauchy's in his *Exercices*, T. IV, p 62 This slip is also noted by Saint Venant in a footnote to p 641 of his edition of the *Leçons de Navier* It is not of importance, however, as the corrected formula is itself wrong

There is only one remark in this section which it seems interesting to quote Possibly the influence which produced the effect observed was after strain

Je profiterai de cette occasion pour faire remarquer que cette dépendance mutuelle entre l'intensité du son et son élévation n'a pas seulement lieu pour les vibrations tournantes, c'est au contraire un fait général dont on a pu faire abstraction pour faciliter les calculs, mais dont il faudra tenir compte actuellement Les sons des corps solides montent en s'éteignant, tandis que ceux des liquides et des gaz baissent à mesure qu'ils s'affaiblissent En ce qui concerne les corps solides, ces inégalités proviennent évidemment de ce que l'allongement qu'ils éprouvent par l'effet d'une faible traction n'est ni rigoureusement égal à la compression produite par cette même force lorsqu'elle agit comme pression, ni rigoureusement proportionnel à cette force (on this point Wertheim refers to the memoir discussed in our Art 792) Maintenant, lorsque l'on se sert de vibrations longitudinales pour déterminer le coefficient d'élasticité, on trouve nécessairement une valeur plus ou moins élevée selon

ue l'on considère comme le vrai son fondamental de la barre ou du fil un son plus ou moins faible. Ordinairement on n'emploie à cet effet que les sons les plus faibles, parce que ce sont en même temps les plus purs, et qu'on les reproduit plus facilement avec le sonomètre, la sirène, ou avec l'instrument quelconque qui sert à la détermination du nombre de vibrations. On comprend donc qu'en opérant ainsi, on obtiendra toujours un coefficient d'élasticité trop élevé, et que cette différence ne disparaîtrait que si l'on pouvait, pour ces déterminations, se servir de sons tellement intenses, que leurs amplitudes fussent égales aux allongements et aux compressions considérables, que l'on emploie pour la détermination directe de ce même coefficient (pp. 59-60).

The inequality of the elastic constants as found by statical and vibrational methods has, indeed, been disputed: see our Arts. 767 and 24. But if the pitch of the fundamental note really depends as Wertheim asserts on the intensity of the disturbance, it must necessarily follow. If this assertion were true then the argument of tones in favour of the linearity of the stress-strain relations from the tautochronism of sound vibrations falls to the ground: see our Arts. 928* and 299. The matter would be clearer if the effects of after-strain which Wertheim holds "se confondent avec ceux des scissions tournantes" could be eliminated in all cases of vibrations.

[810.] We now pass to the section of the memoir entitled: *Sur la rupture des corps homogènes produite par la torsion* (pp. 269-80). Wertheim distinguishes two kinds of rupture, which he considers characteristic respectively of hard and soft bodies (*des corps roides* et *des corps mous*). In the first class rupture occurs by slide, in the second by stretch of the fibres converted into helices. As hard bodies he takes glass, tempered steel and sealing wax; as soft certain sorts of iron (*fer doux*), cast-steel and brass, the second metal forming the transition from one class to the other. The distinction does not seem to me very real or necessary. I imagine that sealing wax might be made to show very great change in form before rupture if a small twisting force were applied to it for a very long time. Our figure reproduces the



rupture-surface according to Wertheim for cylinders of sealing wax or of glass of small diameter. As he remarks, this surface certainly merits, were it feasible, analytical treatment.

To the *hard* bodies Wertheim applies a theory of strength deduced from the hypothesis that elasticity lasts up to rupture. But when applying this theory he always supposes rupture to occur in the 'outermost fibre.' The theory of elasticity, however, only makes the strain greatest in this fibre in the case of a right circular cylinder. In

addition Wertheim puts $\mu = \frac{2}{3}E$, a result which flows from his hypothesis that $\lambda = 2\mu$. He gives, even admitting this assumption, a totally wrong expression for the strength of a rectangular prism (p 275)

For soft bodies Wertheim believes rupture to take place by the stretch of the extreme fibres when they become helical. He appeals for the case of a right circular cylinder to Weisbach's *Mechanik*, and gives for the stretch in a surface fibre $\frac{\tau^2 a^2}{2}$. With the notation of

our Art 51, it is $\frac{\tau^2 a^2}{2} - \eta = \frac{\tau^2 a^2}{4}$, and this must be less than T/E , where T is the rupture traction. This gives for the safe angle of torsion

$$\tau a < 2\sqrt{T/E}$$

Now if S be the shear at which rupture would take place by pure slide we have $\tau a < S/\mu$. Hence in order that rupture should take place by longitudinal stretch we must have

$$2\sqrt{T/E} < S/\mu,$$

$$\text{or } \frac{S}{\mu} > 4 \frac{T}{S} \frac{\mu}{E}$$

Now according to Wertheim's hypothesis $E = \frac{8}{3}\mu$, and as a rule T and S are not very different (see our Vol. I p 877), hence we must have S/μ something like $3/2$, which seems quite absurd as S is at most $1/500$ part of μ . Wertheim's whole treatment, however, of rupture is very unsatisfactory. He applies the proportionality of stress and strain, which does not extend beyond the fail limit (see our Arts 5 (e) and 169 (g)), and although he uses this elastic theory he places his fail points in the surface fibres of his prism farthest from instead of nearest to the axis. The only grain of satisfaction to be found in these pages is the confirmation of Saint-Venant's theory to be found in the following words

Le fer fibreux se rompt par l'allongement des fibres extrêmes, longtemps avant la rupture on y remarque souvent des fentes profondes et parallèles à l'axe, surtout vers le milieu des petites faces des prismes (p 278)

See our Arts 23, 30, etc

Wertheim states that for practical construction it is worth noting that a torsional set in soft iron increases the resistance to torsional elastic strain (p 280)

The *Première Partie* of the memoir concludes with a summary of results on pp 280–6 and with tables of the experimental measurements—possibly the most valuable portion of the whole paper—on pp 288–321

[811] The second part of the memoir is entitled *Sur les effets de la torsion* (pp 385–431)

We have already referred to other experiments of Wertheim

himself and to those of de la Rive, Joule, Matteucci, Wiedemann &c. on the relations between magnetism and stress. Wertheim in this memoir proposes to deal with the influence of shearing rather torsional stress on the magnetic properties of a body. He commences with some account of the early researches on the influence of mechanical action on magnetism. Gilbert was apparently the first to observe that the regular or irregular vibrations of a bar of iron affect its state of magnetisation or the rate at which it develops magnetisation. Gay-Lussac was among the first to analyse these effects, while Réaumur¹ offered an explanation of them which would hardly be considered satisfactory to-day. Scoresby² added to previous knowledge by showing that the same mechanical actions which cause an iron bar to acquire magnetism when parallel to the direction of magnetic force, produce a loss when the bar is perpendicular thereto; further that repeated blows cause a highly tempered and strongly magnetised bar of steel to lose a large part of its magnetisation whatever may be its position relative to the magnetic poles of the earth. Baden-

¹ *Mémoires de l'Académie Royale des Sciences, Paris, 1723* (Edition Amsterdam, 1800). *Expériences qui montrent avec quelle facilité le fer & l'acier s'aimantent, sans toucher l'aimant*, pp. 116-149. See also the *Histoire*, pp. 7-8. Réaumur describes the effect of hammering in magnetising a bar: Après le premier coup de marteau, cette vertu est encore faible; on l'augmente si on applique une seconde fois la pointe de l'outil sur un morceau de Fer, & qu'on frappe sur l'autre bout une seconde fois. Cette opération simple, répétée un nombre de fois, ajoutera toujours à la nouvelle force attractive; mais il y a un terme par de-là lequel on n'obtient plus rien. Cette opération, la vertu de l'outil n'y gagneroit plus rien (p. 119). This is probably the first scientific notice of the effect of impulsive stress on magnetism.

² William Scoresby: *Transactions of the Royal Society of Edinburgh*, Vol. ix. pp. 243-58, 1823, gives an account of the influence of impulsive stress (hammering) on the production of magnetism in iron and steel bars. A résumé of his results is given in the *Edinburgh Philosophical Journal*, Vol. iv., 1821, pp. 361-2. We extract the following:

4. A bar of soft iron, held in any position, except in the plane of the magnetic equator, may be rendered magnetical by a blow with a hammer or other hard substance; in such cases, the magnetism of position seems fixed in it, so as to give it a permanent polarity.

5. An iron bar with permanent polarity, when placed anywhere in the plane of the magnetic equator, may be deprived of its magnetism by a blow.

6. Iron is rendered magnetical if scoured or filed, bent or twisted, when in the position of the magnetic axis, or near this position; the upper end becoming a south pole and the lower end a north pole; but the magnetism is destroyed by the same means, if the bar be held in the plane of the magnetic equator.

9. A bar-magnet, if hammered when in a vertical position, or in the position of the magnetic axis, has its power increased, if the south pole be upward, and loses some of its magnetism if the north end be upward.

10. A bar of soft steel, without magnetic virtue, has its magnetism of position fixed in it, by hammering it when in a vertical position; and loses its magnetism when being struck when in the plane of the magnetic equator.

Powell¹ following Scoresby was apparently the first to deal with the effect of torsion on the magnetisation of an iron bar placed in the magnetic meridian but inclined at different angles. He also showed that a straight bar magnetised and then bent loses a great part of its magnetisation. De Haldat² observed that sound vibrations have less effect than irregular impulses in destroying magnetisation, but according to Wertheim his views on the influence of torsion are incorrect. A memoir by E. Becquerel of which the title, Wertheim says³, will be found in the *Comptes rendus*, February 9, 1845, had not yet been published when Wertheim wrote, but Wertheim was able to state briefly one of Becquerel's conclusions

Un fil de fer doux est chargé d'un poids à son extrémité inférieure, et une partie de ce fil vertical est placée au centre d'une spirale dont le circuit comprend un galvanomètre, on observe un courant de même sens pour toutes les torsions, que celles ci aient été effectuées dextrorsum ou sinistrorsum, et un courant de sens oppose pour toutes les détorsions quel que soit leur sens (p. 387)

[812] Finally Wertheim cites a note of Matteucci to Arago⁴. This ought to have been noticed in connection with our Arts 1333*-36*. It gives an earlier date to several of Matteucci's results published in the memoir of 1858 see our Art 701. In it Matteucci arrives at the following conclusions

(i) A bar of soft iron or steel being magnetised by the passage round it of a spiral current, the first torsions of the bar increase the strength of the magnetisation

(ii) This effect is independent of the sense in which the torsion is applied, i.e. whether it is in the same or the opposite direction to the current

(iii) When the current has ceased the same torsions tend to decrease the magnetism, and this whether they are applied immediately after the cessation of the current or several days after

(iv) If the same mechanical stresses be applied at short intervals successively they cease to have the same magnitude of effect

Le magnétisme acquis par les mêmes actions de torsion, données successivement soit dans un sens, soit dans le sens oppose, soit alternativement, va toujours en diminuant, si l'on continue toujours, on voit apparaître les signes du magnétisme qui se détruit qui sont remplacés par des signes du magnétisme qui s'accroît, et tous ces faits oscillent dans les mêmes limites (p. 388)

¹ Thomson's *Annals of Philosophy* Vol. III, 1822, pp. 92-5
Annales de Chimie, T. XIII, 1829, pp. 39-43

² I cannot find even the title of this memoir in the *Comptes rendus* for 1845. The memoir in T. XV (pp. 1708-11), contains nothing material to the present point and was read on June 9

⁴ *Comptes rendus* T. XXIV, 1847 p. 301

(v) When the current has ceased the same repeated actions rapidly destroy the magnetism.

[813.] Wertheim in a note communicated to the Academy in 1852¹ printed in the *Comptes rendus*, T. xxxv. p. 702, had announced results not in perfect accord with Matteucci's and he repeats the contents of this note in the present memoir. They are as follows :

(i) In so far as a bar of iron has not attained a state of magnetic equilibrium torsions and detorsions¹ act upon it as all other mechanical disturbances, i.e. they tend to facilitate its magnetisation when under the influence of a current or terrestrial magnetism, and they tend to facilitate its demagnetisation when it is under no such influence.

(ii) In both cases as soon as magnetic equilibrium is established, whether the bar be or be not under the influence of magnetic induction, elastic torsion, whatever be its sense, produces partial demagnetisation, while elastic detorsion restores the primitive magnetisation.

(iii) When an iron bar or a bundle of iron wires under the action of a current or terrestrial magnetism receives a large torsional set, in all elastic torsion or detorsion which is applied to it in the sense of the torsional set produces a partial magnetisation, and all elastic torsion or detorsion in the opposite sense produces a demagnetisation (389) : see our Art. 815, (xiv) and (xv).

[814.] Wertheim in the memoir under consideration discusses experiments which confirm the results of the previous article. He gives in addition certain amplifications and corrections of the same. Among the latter we may note :

(iv) The purely mechanical actions of torsion and detorsion are in themselves insufficient to magnetise iron (p. 401). This result, as Wertheim remarks, is initially probable.

(v) The torsion of a bar under magnetic influence enables it to receive a much greater permanent magnetisation than it would otherwise be capable of (p. 401).

(vi) When the bar has taken all the temporary and permanent magnetisation of which it is capable under the action of the given external magnetising force, then torsion diminishes, and the corresponding detorsion restores its magnetisation (p. 401).

This is only an ampler statement of (ii).

(vii) When the external magnetising influence is removed torsion and detorsion (as other mechanical disturbances) rapidly destroy the temporary magnetism, but they continue indefinitely to exercise in-

¹ *détorsion*, by which I presume Wertheim means a release from a state of torsion, not a *negative* torsion, but his language is obscure.

fluence on the permanent magnetism, i.e. the latter is diminished by the torsions and restored by the detorsions (p 401)

This is an amplification of (ii) and it is important to notice that Wertheim now makes a distinction between a *temporary* and a *permanent* magnetisation

(viii) The effect of torsion is generally greater than the opposite effect of detorsion (p 401)

This may possibly have been only apparent, i.e. due to Wertheim's mode of experimenting

(ix) Whatever may be the magnetic state of the bar, provided it be one of equilibrium, the effects of the torsions are proportional to the angles of torsion, but the magnitude of these effects appears to depend more on the magnitude of the permanent than on that of the temporary magnetisation (pp 401-2)

Wertheim follows up these results (pp 402-4) by some remarks on the different effects produced by torsion on different materials, e.g. soft iron, hard iron and untempered cast steel (see our Art 703)

(x) The effects of torsion diminish with the elapse of time as the iron loses a part of its magnetisation. There appeared however to be a limit to this diminution as iron bars of any quality gave perceptible magnetic results when twisted six months after their magnetisation (p 407)

(xi) Je dois faire remarquer ici une anomalie que j'ai observée plusieurs fois et qui me semble tout à fait inexplicable. Elle consiste en ce que les fers durs donnent souvent, immédiatement après l'interruption du courant, des déviations plus fortes qu'ils n'en avaient fournies tant que le courant passait, dans ces cas la diminution ne se fait sentir qu'après quelque temps (p 407)

The 'deviations' referred to are those of a galvanometer, connected with a coil round the bar, and were caused by the induced currents whereby Wertheim measured the changes in magnetisation of the bar. The further current, which he himself mentions in (xi), is that which produced the magnetising force on the bar.

(xii) Wertheim was unable to obtain any sensible results in the case of torsion applied to diamagnetic bodies (p 407)

[815] The next points to which Wertheim turns are of considerable interest. Suppose the torsional set to be zero or negligible, then suppose any elastic torsional strain given to the bar and let it be magnetised in the strained state. Will the magnetisation be a maximum in this state, in the state of zero strain, or in any other state? Wertheim found that

(xiii) The maximum of magnetisation always coincides with the position of zero strain (p 409)

He next turned to the problem of torsional set. Set he found exercised no influence, if it preceded magnetisation. But supposing the set was applied during the time the bar was under the influence of magnetising force, what would be the position of maximum magneti-

tion; would it coincide with the position in which the bar would have no elastic torsional strain? The angle between the positions of zero torsional couple and maximum magnetisation is termed the *angle de rotation du maximum*. Wertheim found that for harder sorts of iron (*fer dur, ou même demi-dur*) very large torsional sets were not necessary in order that this angle of rotation should be sensible; on the other hand it was very difficult to obtain sensible measurements when soft iron bars and not wires were used. A table of numerical results is given on p. 413. We may note:

(xiv) The angle of rotation is less than the elastic limit to torsional strain measured from the new position of zero elastic strain, and is in the direction of the torsional set.

(xv) Torsional strains when less than this angle of rotation produce increasing magnetisation, when greater than this angle decreasing magnetisation, which becomes less than the magnetisation at zero strain for double the angle of rotation (pp. 411–12).

It will be noted that (xiv) and (xv) sensibly modify (iii) of Wertheim's *Note* of 1852: see our Art. 813. The latter statement is only true provided the torsions do not exceed double the angle of rotation.

[816.] Wertheim now turns to the last of his experimental investigations. A bar having been given an elastic torsional strain while under the influence of the magnetising force, what will be the character of its magnetism when the magnetising force is suddenly removed? He found that:

(xvi) For all qualities of iron the effect of removing the magnetising force (stopping the current in the coil) while there is an elastic torsional strain is to rotate the position of maximum magnetisation in the direction of the temporary strain, but the angle of rotation is always less than the angle of this torsional strain (p. 414).

The phenomena of (xiv), (xv) are especially marked in hard iron, those of (xvi) in soft iron. Some additional information will be found on pp. 414 and 419, while pp. 415–8 are occupied with tables of the experimental results.

[817.] On pp. 419–428 Wertheim discusses how far the phenomena he has described can be accounted for by any known theory of magnetism. His results, as might be supposed, are negative. Thirty years later we have hardly reached a really valid theory of the relation between strain and magnetism, although we see more exactly their physical relations. The two-fluid theory, the *force coercitive* of Coulomb, or even the hypothesis of Matteucci—that the magnetic effect of strain is a secondary effect of its change of volume—give Wertheim no aid. It is curious that Wertheim takes refuge in a wave theory of the ether. We may not be able to follow his somewhat vague reasoning, but it is not without interest to note that he holds that magnetisation as a polarisation—or a bringing into concordance—of pre-existing discordant

ether-vibrations surrounding the molecules, is a hypothesis far better fitted than those before cited to account for magnetic phenomena

The memoir concludes with some rather general remarks on the effect of earth-strain (produced by other celestial bodies, change of temperature, earthquakes etc) on terrestrial magnetism, and on possible methods of correcting compass deviations in iron ships

[818] Historically the importance of this memoir of Wertheim's seems considerable. He noticed a number of novel phenomena, although he did not see the necessary limitations to some of his statements—in particular he did not discover the existence of a 'critical twist,' except in so far as this is implied by (xiv)–(xvi) for the cases of *previous* torsional set under magnetisation or of elastic torsional strain with sudden cessation of the magnetising force. Wertheim's results must therefore be read with due regard to more recent researches: see the references to *Magnetisation under Stress* in the Index to this Volume, also Wiedemann, *Lehre von der Elektrizität*, III S 692, and J J Thomson, *Applications of Dynamics to Physics*, pp 59–62

[819] Wertheim *Mémoire sur la compressibilité cubique de quelques corps solides et homogènes* *Comptes rendus*, T LI pp 969–974 Paris, 1860 (Translated in the *Philosophical Magazine*, Vol XXI, pp 447–451 London, 1861)

Wertheim refers to his memoir of 1848 (see our Art 1319*) and to the value $1/3$ which he there proposes for the stretch-squeeze ratio η , and which he holds has been confirmed by subsequent experiments. He remarks that several distinguished mathematicians, without doubting the accuracy of his experiments, have yet endeavoured to bring them into unison with the results of uni-constant isotropy by the aid of *hypothèses très diverses, mais malheureusement aussi très arbitraires* (p 970). Wertheim refers in the first place to Clausius: see our Art 1400*. Clausius did not deny the homogeneity of Wertheim's materials, but, as we have noticed, supposed like Seebeck (Art 474) that elastic after-strain had affected his results. Wertheim rejoins that no one has yet observed after-strain in metals or glass. This statement was absolutely incorrect even in 1860: see our Arts 726, 748 and 756.

Wertheim next remarks that he does not assert that $\eta = 1/3$ holds for all metals, but only for those upon which he has

perimented. This, I think, is not in complete accordance with his earlier statements, but it allows him to maintain that he is not in disagreement with Lamé and Maxwell, nor even with Clapeyron's results for vulcanised caoutchouc: see our Arts. 63*-4*, 1537* (and footnote) and 610.

He next proceeds to criticise Saint-Venant's hypothesis of isotropy, or rather of varied distributions of elastic homogeneity (see our Arts. 114, *et seq.*), in language which suffices to prove that he has not understood it.

Finally Kirchhoff's memoir of 1859 (see Section II. of our Chapter XII.) with its direct determination of η for brass and tempered steel is discussed. Wertheim holds that Kirchhoff's apparatus and his mode of experimenting were likely to produce error (*sont autant de circonstances fâcheuses*: p. 973).

He takes comfort in the fact that the mean of the values given by Kirchhoff for η (.294 for tempered steel and .387 for brass) is not very far from $1/3$. He will not affirm that $\eta = 1/3$ for steel, but he holds that Kirchhoff's experiments do not demonstrate its improbability. Putting aside Clapeyron's experiments on caoutchouc, Wertheim sees no fact that has yet been deduced to show that η varies from body to body. He promises to present shortly a memoir to the Academy on this subject.

[820.] The last mentioned memoir (*Expériences sur la torsion?*) has never, so far as I know, been published. Scarcely a month (January 19, 1861) after the presentation of the memoir discussed in the last article Wertheim in a fit of melancholy committed suicide by throwing himself from the tower of the cathedral at Tours. A bibliography of Wertheim's papers and some criticism of his methods by Verdet will be found in *'Institut*, T. xxix., pp. 197-201, 205-9 and 213-6. Paris, 1861.

GROUP D.

*Memoirs on the Vibrations of Elastic Bodies*¹.

[821.] A. Baudrimont: *Recherches expérimentales sur l'élasticité des corps hétérophones*. *Annales de chimie et de physique*, [xxxii., pp. 288-304. Paris, 1851.

¹ See also Arts 433-9, 471-4, 510, 534, 539-41, 546-8, 550-9, 583, 612-7, 680-2, 722-86 *passim*, and 809 of this Chapter.

Baudrimont uses the word *isophone* to denote a body, the elasticity of which is the same in all directions, or an isotropic body, *hétérophone* he applies to aeolotropic bodies, but especially to bodies having axes or planes of elastic symmetry. The object of this paper is to present a preliminary investigation of the notes given by rods vibrating laterally. Baudrimont's ultimate object, however, is to calculate the stretch-moduli in different directions of an aeolotropic material by means of the notes given by the lateral vibrations of rods so cut from the material that their axes are in the given directions.

It is first needful to ascertain how far, what Baudrimont terms Euler's formula, is accurate for such rods. This formula gives for the frequency f

$$f = n^2 \frac{\kappa}{l^2} \sqrt{\frac{E}{\rho}} \quad (1),$$

where n is a mere numeric depending on the graveness of the note, E is the stretch modulus in the direction of the length l of the rod, ρ the density of the material and κ the swing-radius of the cross section about an axis through its centroid perpendicular to the plane of vibration (see Lord Rayleigh's *Theory of Sound*, Vol. I § 171). Thus for the gravest note of a given material the frequency varies directly as the swing-radius and inversely as the square of the length.

Equation (1) is obtained theoretically (a) by supposing the cross sections to remain plane after bending and perpendicular to the axis of the rod, (b) by assuming the rod not to diverge much from absolute straightness, and (c) by concentrating the inertia of each cross section at its centroid.

Baudrimont by a series of experiments on ice, metal, quartz, and wooden bars, believes that he has demonstrated that the laws which hold for isotropic and aeolotropic bodies are the same, but that the frequency of the notes is not inversely as the square of the length of the rod.

Lord Rayleigh has given a correction for the rotatory inertia of the cross-section (*Theory of Sound*, Vol. I § 186), but assuming Baudrimont's experimental results to be true¹, this correction is very far from accounting for the divergence between Euler's formula and physical fact, even when the ratio of length to diameter is as great as 30, 40, or even 50. The correction is in the right direction but not nearly large enough. It is obvious that we must for sound vibrations accept the assumption (b). Hence if we are to trust Baudrimont's results, the formula obtained from the Bernoulli-Eulerian theory for the notes of rods is very inaccurate so long as the ratio of length to diameter of a

¹ I suspect some large source of error which might possibly have arisen in clamping the rods. See the remarks on the difficulty of determining the stretch modulus by lateral vibration in a memoir by Wertheim in the *Annales de chimie et de physique*, T. XL, p. 201. Paris, 1804.

rod is less than 30 to 40. The complete theory, which ought to be deduced from the general equations of elasticity, would like Saint-Venant's theory of the flexure of beams take account of slide; it would be interesting to ascertain the order of the modification such a theory would introduce into the expression for the frequency: see for the case of *longitudinal* vibrations Chree, *Quarterly Journal of Mathematics*, Vol. xxi., p. 287. If we accept Baudrimont's results it is obvious that the stretch-modulus as calculated from Euler's formula for lateral vibrations must diverge very considerably from that obtained by pure tractional loading, except when the length of the rod is immensely greater than its diameter. Such rods it would be difficult to procure in many of the aeolotropic bodies (crystalline materials for example) whose elasticity Baudrimont proposes to investigate by the method of transverse vibrations.

[822.] Montigny: *Procédé pour rendre perceptibles et pour compter les vibrations d'une tige élastique. Bulletins de l'Académie Royale...de Belgique*, T. XIX. 1^{re} Partie, pp. 227-50. Bruxelles, 1852.

This is an extension of a method suggested by Antoine (*Annales de chimie et de physique*, T. XXVII. pp. 191-209. Paris, 1849) of rendering sonorous vibrations visible by combining a motion of translation with that of vibration. Montigny used the following arrangement to render visible the vibrations of a rod :

Si l'extrémité de la tige autour de laquelle les vibrations doivent s'effectuer, est fixée perpendiculairement à un axe de rotation, si, lors de sa révolution rapide, l'extrémité libre éprouve un choc contre un obstacle fixe, les vibrations transversales de la tige, excitées de cette manière dans le plan de sa révolution, la rendent visible sur toute sa longueur dans des positions rayonnant du centre, et qui se trouvent également espacées (p. 228).

After some general reasoning as to what it is the eye really sees in this combination of motions Montigny concludes that :

Il résulte de là que l'œil ne perçoit la tige qu'à chaque vibration double, et que nous devons prendre pour le nombre des vibrations simples, effectuées dans un temps donné, le double des images de la tige vues pendant le même intervalle de temps (p. 229).

The rotation round the axis is so arranged that after a complete revolution the rod returns to visibility at the same position as before; this can always be obtained by quickening or slackening its spin. Hence if t be the time of a revolution and n the number of images of the rod seen, the number of vibrations of the rod will be $2n$ and their period $t/2n$. The positions of visibility arise where the

velocity due to the spin is almost equal and opposite to the velocity of an element of the rod due to lateral vibration. It seems to me that Montigny is using the word vibration for what we in England term the *half* oscillation and that with our terminology we should have the period of oscillation equal to t/n

Montigny applies his method to verifying some of the well-known theoretical laws of the vibration of rods. His experiments confirming theory are thus opposed to the results obtained by Baudrimont and cited in our Art 821. This difference between his own and Baudrimont's results our author discusses at some length (pp 241-7), and the inference certainly is that there was some large source of error in Baudrimont's experiments. The memoir concludes by noting how the new method may be rendered available for technical purposes, for example, in finding the stretch-moduli in the case of iron and wood¹

[823] A. Masson *Sur la corrélation des propriétés physiques des corps* *Annales de chimie et de physique*, T LIII, pp 257-93 Paris, 1858. This memoir was presented to the Academy, March 2, 1857. It is only the first chapter of the *Première Partie* (*Vitesse du son dans les corps*) with which we are concerned. Masson after some slight discussion of the relation between the stretch-modulus, the coefficient of thermal expansion, the specific heat of a material and the mechanical equivalent of heat,—which is based upon Kupffer's erroneous hypothesis (see our Arts 724-5 and 745),—proceeds to describe the experiments by which he has measured the velocity of sound in metals (pp 260-4)

As he had previously found that the velocity of sound deduced from the longitudinal vibrations of a metal rod increased with the

¹ While referring to memoirs dealing with methods of rendering vibrations visible I may note the following paper which escaped record in its proper place in our first volume

E F August *Ueber einige isochrone Schwingungen elastischer Federn* *Zwei Abhandlungen physikalischen und mathematischen Inhalts* Berlin 1829. This was published in the *Program des Colnischen Real Gymnasii*. It contains some account of simple school experiments for proving Taylor's laws for vibrating strings (here represented apparently by fine brass wire spirals) with no more complex apparatus than the stand of an Atwood's machine. The effect of isochronous vibrations is rendered visible by the oscillating of the machine violently for one length only of the spring under a given load. The paper concludes (S 4-10) with a rather clumsy demonstration of the formula for the period of vibration of a weight suspended by such a spring and with some experimental confirmation of its accuracy.

length of the rod, the diameter remaining constant, he replaced the rod by a wire of very small diameter: see our Art. 821. He took wires as a rule of 1·5 metres length and of diameters from ·1 to ·9 mm. The wires were placed horizontally and kept stretched, one end being passed over a pulley and attached to a weight. The vibrations were measured by the aid of a sonometer, and in all the experiments the periods of a great number of harmonics as well as that of the fundamental vibration were measured on each wire.

[824.] The densities for a number of metals are tabulated on p. 263, and the corresponding velocities of sound are given on p. 264. These velocities were found for gold, brass, copper, silver, platinum, iron, zinc, lead, tin, aluminium, cadmium, palladium, steel, cobalt and nickel. Direct experiments were also made on some of these metals to find their stretch-moduli. Masson gives the following among other results on p. 264:

Stretch-modulus in kilogrammes per sq. millimetre.

	From Sound Experiments.	From Traction Experiments.
Gold	8247	6794
Brass	9783	9446
Silver	7421	7080
Platinum	16932	15924
Iron	19993	18571

These are in general agreement with Wertheim's results except the case of iron: see our Art. 1297* and compare with Art. 728.

[825.] (a) A. Terquem: *Note sur les vibrations longitudinales des verges prismatiques*. *Comptes rendus*, T. XLVI. pp. 775–8. Paris, 1858.

(b) Same author and title. *Comptes rendus*, T. XLVI. pp. 75–8. Paris, 1858.

(c) *Idem*: *Étude des vibrations longitudinales des verges prismatiques libres aux deux extrémités*. *Annales de chimie et de physique*, T. LVII. pp. 129–190. Paris, 1859.

(d) J. Lissajous: *Note sur les vibrations transversales des lames élastiques*. *Comptes rendus*, T. XLVI. pp. 846–8. Paris, 1858.

(e) J Bourget et Félix Bernard *Sur les vibrations des membranes carrées Premier Mémoire Annales de chimie et de physique*, T LX pp 449-479 Paris, 1860

These five memoirs deal with the nodes of vibrating bars and the nodal lines of square membranes, and so belong more particularly to the theory of sound¹ They contain, however, references to the elastical researches of Wertheim, Savart, Germain, Poisson, Lamé etc, while (a) and (b) ought to have had a reference to Seebeck see our Arts 471-5 The papers (a), (b) and (c) have special application to the case in which a rod is able to vibrate longitudinally and transversely with the same tones and to the

¹ I may take this opportunity of referring to a memoir on the nodal lines of plates which escaped my attention in the first volume

It is by Giovanni Paradisi and entitled *Ricerche sopra la vibrazione delle lamine elastiche Mem dell' Accad delle Scienze di Bologna*, T 1 P 2, pp 393-431 Bologna, 1806

The memoir is among the earliest which followed the publication of Chladni's researches The author made experiments on plates of rectangular (including square) and equilateral form the material of the plates being glass, brass, silver, tin, wood (walnut and maple) and bone The material was observed to influence the note but not the nodal lines The author found that the nodal lines (*le curve polvifere*) and the centres of vibration (*centri di vibrazione*) were such that the point of support of the plate might be anywhere on a nodal line and the point of disturbance (*punto del suono, il centro primario*) at any other of the centres of vibration (*centri secondari di vibrazione*) without any change in the system of nodal lines By the centres of vibration 'primary and secondary' Paradisi appears to denote the points of maximum vibration corresponding to the loops in the vibrations of a rod or string Paradisi asserts that with the same point of support and the same centre of disturbance plates can be made to vibrate with one two or more different tones, according to the manner in which the vibrations are excited and that each such tone has a different system of nodal lines (pp 416-9),

Dallo stesso triangolo sospeso nel centro e suonato alla metà della base in S, secondo che si preme più o meno l'arco, ricaviamo un tuono diverso talvolta un tuono acuto talvolta un medio e talvolta un grave Questi tre tuoni i quali sono i soli che possono ricavarsi dal punto S dispongono la polvere in tre diverse maniere (p 417)

He supposes that the nodal lines must be due to one or other of two causes (1) that they are the locus of points at which the plate is at rest (2) that they are the locus of points at which, although the points themselves are in motion the forces on the grains of powder are in equilibrium (p 397) He chooses the latter alternative notwithstanding his experimental demonstration that the nodal system remains unchanged if the points of the vice which supports the plate be moved along a nodal line His arguments in favour of this alternative are far from convincing and his comparison of the nodal lines and centres of disturbance in plates with wave motion in strings and water is unsatisfactory (pp 399-401, 404-5) His diagrams showing the manner in which the lines of powder are gradually formed in experiment are however interesting

Finally his attempt to form on his hypothesis a differential equation connecting the nodal lines with the centres of vibration may be dismissed as absolutely fruitless It is based upon the assumption that the *unknown* force on any grain of powder upon a nodal line is along the tangent to that nodal line which would cause the powder to move along the nodal line and not remain at rest there (pp 429-31)

resulting nodes. Lissajous confirms Terquem's conclusions by a very different experimental method. The excitement of transversal tones by longitudinal vibrations had been already noted by Savart¹: see our Art. 350*. Bourget and Bernard give interesting figures of the nodal lines of square membranes.

The title of another acoustic paper by Terquem bearing on a kindred subject but belonging to the next decade may be cited here:

(f) *Note sur la co-existence des vibrations transversales et tournantes dans les verges rectangulaires. Comptes rendus*, T. LV. pp. 283-4. Paris, 1862.

[826.] J. Lissajous: *Mémoire sur l'étude optique des mouvements vibratoires. Annales de chimie et de physique*, T. LI. pp. 147-231. Paris, 1857. This classical memoir deserves at least a reference here. By means of the image of a bright point reflected from a small mirror attached to a vibrating elastic body, the image being given a translatory or oscillatory motion perpendicular to the direction of the vibration produced in it by the vibrating body, we obtain an optical representation of the vibrations of the body. Lissajous shows how vibrations may be analysed, and vibrations in the same or perpendicular directions optically compounded. His methods are as important for the investigation of the vibrations of large masses of elastic material as for the ordinary purposes of acoustics.

[827.] F. P. Le Roux: *Sur les phénomènes de chaleur qui accompagnent, dans certaines circonstances, le mouvement vibratoire des corps. Comptes rendus*, T. L. pp. 656-7. Paris, 1860.

This note draws attention to the fact that if a vibrating rod of wood, ivory, steel etc. be clamped at a point which is not a node of the free vibrations, this point rapidly rises in temperature. Various experiments are described by which this rise in temperature can be easily rendered sensible.

Le Roux concludes that when any vibratory motion is damped, the kinetic energy of the vibrations will be converted into heat in the neighbourhood of the parts damped.

¹ The subject is briefly referred to by Lord Rayleigh: *Theory of Sound*, Vol. I. § 158.

GROUP E

Elastic After-Strain in Organic Tissues

[828] E Weber *Muskelbewegung*, S 1-122, Zweite Abtheilung, Bd III of R Wagner's *Handwörterbuch der Physiologie* Braunschweig, 1846 This article contains a considerable number of experiments on the elasticity of muscle (S 70-99) and some attempt to explain their elastic action (S 100-117) The treatment, however, is rather physiological than physical The general results of the writer as to the elasticity of muscle are given in S 121-2, and we cite the following

27 Die Thatigkeit des Muskels besteht namlich nicht nur in einer Aenderung seiner (naturlichen) Form, die sich verkürzt, sondern auch in einer Aenderung seiner Elasticitat, die sich vermindert.

28 Weil die Elasticitat des Muskels sich beim Uebergange zur Thatigkeit beträchtlich vermindert, übt ein Muskel durch seine Verkürzung eine weit geringere Kraft aus, als er ausüben würde, wenn seine Elasticitat unverändert dieselbe wie im unthatigen Zustande bliebe

29 Die Elasticitat des thatigen Muskels ist sehr veranderlich, sie vermindert sich bei Fortsetzung der Thatigkeit immer weiter Diese fortschreitende Abnahme der Elasticitat bei fortgesetzter Thatigkeit ist die Ursache der Erscheinungen der Ermüdung und der grossen Kraflosigkeit, welche die Muskeln während derselben zeigen

Weber also points out that the elasticity is more imperfect in dead than living muscle, and that there is a great difference in the general elastic properties of the two conditions

[829] W Wundt *Ueber die Elasticitat feuchter organischer Gewebe* *Archiv für Anatomie, Physiologie und wissenschaftliche Medizin* Jahrgang 1857, S 298-308 Berlin, 1857


After referring to the experiments of Wertheim and E Weber (see our Arts 1315* and 828) Wundt remarks that these experiments leave us without any simple conception of the stretch-modulus in the case of moist organic tissues, and that we are thrown back on an empirical stress-strain diagram At the same time he takes exception to Wertheim's experimental methods, chiefly on the grounds that they were made too long after the

death of the tissue-bearing individual, and that sufficient regard was not paid to the time-element, which is so important a factor in the elastic after-strain of such tissues.

Wundt's objects in this paper are to measure: (i) the ultimate extensions by given loads, and (ii) the temporary extensions in given intervals of time.

[830.] On S. 301-3 Wundt describes his apparatus, especially his means for keeping the tissue moist. As to his results he concludes that *the ultimate extensions are proportional to the loads*, but he comes to no definite conclusions as to after-strain (*die vorliegende Untersuchung hat zu keinem für die Kenntniss der elastischen Nachwirkung bemerkenswerthen Resultat geführt*, S. 303).

The following diagram clearly indicates the results of experiments on a frog's muscle of 2.79 mm. length; *AB* is the stretch-traction curve for ultimate extensions, where two abscissa-divisions represent 1 gramme and



the ultimate extension for 1 gramme = .272 mm. The three heavy line ordinates *a*, *b*, *c*, respectively .272 mm., .254 mm. and .242 mm. long, are projected on *CB* and, one abscissa-division measuring 10 minutes, the after-strain curves for these three loadings are given to the right of *CB*, so that after each increase of load we see the extension gradually increasing up to linear elasticity. Wundt points out that the line *AB* is within the limits of experimental error straight, and his after-strain curves are distinctly of interest. He concludes also that the limits within which this proportionality of traction and final stretch holds are wider the fresher is the tissue and the less it has been previously loaded. The following are the stretch-moduli in grammes per sq. millimetre, the loads being from 1 to 10 grammes and the temperature 10° to 15° C.: Artery 72.6; muscle 273.4; nerve 1090.5; sinew 1669.3.

The experiments were made on artery (calf), muscle (ox and frog), nerve (calf), tendon (calf), but Wundt only gives details of some few of them (S. 307-8).

[831] A W Volkmann *Ueber die Elasticität der organischen Gewebe Archiv für Anatomie, Physiologie u s w, herausgegeben von C B Reichert und E du Bois-Reymond, Bd I S 293-313* Leipzig, 1859

W Wundt *Ueber die Elasticität der organischen Gewebe Zeitschrift für rationelle Medizin von Henle und Pfeufer, Bd VIII, S 267-279* Leipzig, 1860

These papers relate to a controversy of considerable interest upon the exact form taken by the stress-strain relation for organic tissues. We have already referred in our first volume to Wertheim's researches (see our Art 1315*), but his chief results may be cited here in order that the reader may understand the point in dispute between Volkmann and Wundt. They are as follows:

(i) Wertheim recognised after-strain to exist in human tissues. He found it to vary with their dryness but to be only a very small proportion of the total strain when the latter was measured in the first few minutes after loading.

(ii) He represented the immediate stress strain (stretch traction) relation by an equation of the form

$$s_x^0 = a\widehat{xx}^2 + b_{22}$$

If a be positive as Wertheim found it, the stretch traction relation is thus hyperbolic¹. Set was excluded from the measurement of strain (see our Arts 1315*-18*).

These experiments of Wertheim are in agreement with those of E Weber, who also found that the stretch-traction relation for muscles was not linear: see our Art 828.

[832] As we have seen W Wundt published in 1857 a paper (see our Art 829), in which he asserted that if regard were only paid to elastic after strain, it would be found that the stress was proportional to the strain for organic tissues.

It is at this point that Volkmann took up the matter, and made an attempt to measure elastic fore strain by itself (see Vol I p 882). He adopted an ingenious method of tracing by a *Kymographion* the longitudinal vibrations of a muscle or artery suspended vertically and suddenly loaded but without any impact. The load then oscillated about the mean position which was that of statical equilibrium. This mean position altered with the time the weight was left oscillating owing to elastic after-strain. The mean positions are those of maximum speed in the oscillating weight, and they correspond to the points of inflexion on the diagram of the oscillations which is drawn on the revolving cylinder of the kymographion. The first point of inflexion ought to give the elastic fore strain. Unluckily Volkmann found that

¹ The hyperbolic form of this curve is really confirmed by the researches of C S Roy: see the *Journal of Physiology*, Vol III pp 125-59, corrected Vol IV pp 227-8. Cambridge 1880 and 1888.

the points of inflexion were not easily determined with great accuracy, as slight errors in the motion of the cylinder or of the tracing pen influenced their position. Under these circumstances he gave up the idea of measuring the first mean position, and contented himself in each series of experiments by measuring all the strains at the *same* small interval of time after the instant of loading.

In eight series of experiments he compares his observed stretches with those given by Wertheim's relation in (ii) above. The result is a very close agreement. Volkmann finds for silk thread, for human hair, for an artery, for a nerve (*nervus vagus* of man) that a is positive; on the other hand for muscle it is negative, or the stretch-traction relation is *elliptic*. Permanent set appears to have been sensible only in the final experiments of any series. In the last series of experiments (S. 307) Volkmann subtracted the set before applying Wertheim's formula and again found it to hold. He thus considers that formula to be proved for elastic fore-strain, i.e. for primary strain within the elastic limits.

I may note that Volkmann seems to think this stretch-traction relation something peculiar to organic bodies, distinguishing them from inorganic bodies. But as we have seen (see our Vol. i. p. 891) that the stretch-strain relation within the elastic limits for certain metals is not linear—whatever else it may be,—it is not necessary on this account to suppose that an absolute distinction must exist between the elasticity of organic and of inorganic substances.

[833.] The remainder of the paper is a criticism of Wundt's experiments, chiefly based on the ground that the time-element had not been taken into account, and that accordingly the strain measured by him was neither fore- nor after-strain. Further Volkmann holds that Wundt's experiments cover such a small range of loads, that for that range the stress-strain curve might approximately be taken as straight. An attempt to show that some of Wundt's experiments contradict his own hypothesis is, I think, fairly met in Wundt's reply.

[834.] In Wundt's reply, the title of which I have given in Art. 831, he does not I think do justice to the care with which the experiments of Wertheim and Volkmann appear to have been conducted. Against E. Weber's and Wertheim's results Wundt cites their want of caution in drying the tissues, in noting the influence of set, the effect of physical change (as *rigor mortis*), and above all the existence of after-strain, which he asserts was left out of consideration. Now it seems to me that Wertheim does reckon with all these factors and especially refers to the latter: see our Art. 1317*. Wundt suggests also that the weights applied were such as to change the elastic modulus of the body, i.e. its elastic constitution.

He defends his own limited range of loads on the ground that only for such loads as he applied do set and elastic after-strain cease to be so considerable that elastic fore-strain can be easily measured. (We

may note here that Wundt seems to consider that want of proportionality between stress and strain would certainly mark organic substances sharply off from inorganic substances!) He objects to Volkmann's method of getting rid of after strain by making his measurements of stretch at a constant interval after loading. He remarks that the empirical formula given by W. Weber for after strain involves a constant itself depending on the load (the c of our Art 714*) He complains also that Volkmann gives no evidence that he has proved the unaltered condition of the elasticity of his material after each experiment by allowing it to return to its original condition as to load. This, he holds, is especially necessary to free successive experiments from the after strain of previous ones.

I do not think these objections of Wundt have really great force, because Volkmann's observations were made while the elastic after-strain was an exceedingly small quantity, and because his notice of the existence of set shows that he must have examined whether his tissues returned to their original lengths. A further and supposed conclusive argument of Wundt's against Volkmann, namely, that the elliptic nature of the stress strain relation would prove that by increase of load the muscle would ultimately be shortened instead of extended, is simply absurd. What the formula really denotes is the elliptic form of the relation *within the limits of elasticity*. Had Wundt examined the values of the constants given by Volkmann he would have found that the extension would have become enormous—far beyond the limits of rupture—before the stretch began to decrease with the load.

[835] On S 274—6 Wundt compares the accuracy for tissues of Hooke's law as deduced from his own experiments, with its accuracy as deduced from Wertheim's. But it is no argument to assert that because the former experiments give results less divergent from Hooke's law than the latter do, therefore this law must hold for the latter as well as the former. The fact is that Hooke's law may hold for neither within the range of loads applied.

On S 277 we are treated to a proof—by means of Taylor's Theorem (11)—that stress *must* be proportional to strain for all bodies whatever within certain limits of strain. see our Arts 928* and 299.

Having deduced from Taylor's theorem that the stress strain relation to a second approximation *must* be of the form

$$\widehat{xx} = A s_x + B s_x^2,$$

Wundt, by squaring and some absolutely illegitimate process of neglecting the cube in preference to the fourth power, deduces that

$$\widehat{xx} = A (s_x) + B (s_x^2)'$$

This he naively remarks is an equation of the hyperbolic form of Wertheim and Volkmann, whose results he then attributes to the fact that the strains considered by them exceed those for which the first term of Taylor's series suffices. It is perhaps needless to remark that Wundt, if a good physiologist, is but a poor mathematician and physicist.

GROUP F.

Hardness and Elasticity.

[836.] We now reach a number of memoirs dealing with the hardness of materials, a subject intimately related to their elasticity and strength. It will perhaps not be out of place here to refer briefly to the earlier history of the subject. I owe my references chiefly to M. F. Hugueny's *Recherches expérimentales sur la Dureté des Corps*¹ and to the memoir of Grailich and Pekárek², but I have in every case consulted the original authorities for myself, and I have often amplified the notices of these writers when the original papers were not accessible to them or had escaped them.

(a) Apparently the first writer to make any reference to the scientific measure of hardness and the variation of hardness with *direction* is Huyghens. In his *Traité de la Lumière* (Leyden, 1690) after suggesting a grouping of flat spheroidal molecules as suited to explain the optical phenomena of Iceland spar he continues (pp. 95-6) :

Tout cecy prouve donc que la composition du cristal est telle que nous avons dit. A quoy j'ajoute encore cette expérience ; que si on passe un cousteau en raclant sur quelqu'une de ces surfaces naturelles, & que ce soit en descendant de l'angle obtus équilateral, c'est-à-dire de la pointe de la pyramide, on le trouve fort dur ; mais en raclant du sens contraire on l'entame aisément. Ce qui s'ensuit manifestement de la situation des petits spheroides ; sur lesquels, dans la premiere manière, le cousteau glisse ; mais dans l'autre il les prend par dessous, à peu près comme les écailles d'un poisson.

(b) Musschenbroek concludes his *Physicæ Experimentales et Geometricæ Dissertationes* (Leyden, 1729) with a chapter entitled : *Tentamen de corporum Duritiâ* (pp. 668-672), that portion of his work (*Introductio ad Cohærentiam corporum firmorum*) to which we have referred in our Art. 28* 8. His method, of which he speaks very diffidently, was to count the number of the blows of a mass swung like the bob of a pendulum which are required in order to drive a chisel through a slab of definite thickness of the given material. He supposes that the number of blows divided by the specific gravity of the material may be taken as a measure of its hardness. He tested in this way the hardness of a great number of specimens of wood and of some of the

¹ This work will be dealt with under the year 1865.

² See our Arts. 842-4.

more usual metals. He gives the following ascending order of hardness for metals: lead, tin, copper, Dutch silver of small value, gold, brass, Swedish iron. Obviously Musschenbroek's definition of hardness would involve absolute strength rather than set.

(c) Torbern Bergman writes in 1780 that testing gems by their hardness is usual. The following passage is taken from his *Opuscula Physica et Chemica*, Vol II, p 104, Upsaliae, 1780 (*De Terra Gemmarum*, pp 72-117) *English Translation*, Vol II *Physical and Chemical Essays*. London, 1784 (Of the Earth of Gems, pp 107-8)

The species of gems is used to be determined by the hardness, and by that quality particularly, together with the clearness, has their goodness been estimated. The spinellus is particularly worthy of observation, which is not only powdered by the sapphire, but even by the topaz, as also the crysolith, which is broken down by the mountain crystal¹, the hardness of which seems rather to be owing to the degree of exsiccation than the proportion of ingredients. The analysis of spinellus, of crysolith, and other varieties, will sometimes illustrate the true connection, otherwise, after the diamond, the first degree of hardness belongs to the ruby, the second to sapphire, third to topaz, next to which comes the genuine hyacinth, and fourth the emerald.

(d) A G Werner in 1774 in his treatise on mineralogy gave a first scale of hardness. This was somewhat extended by R J Haüy in his *Trate de Minéralogie*, Paris, 1801.

In Tome I (p 221) Haüy defines hardness in a vague way, and gives (pp 268-71) in four groups the substances (i) which scratch quartz, (ii) which scratch glass, (iii) which scratch calcspar and (iv) which do not scratch the latter substance. In these lists he confines himself to substances usually termed *stones*. On p 348 of Tome III Haüy gives the following list of the usual metals in order of hardness: lead, tin, gold, silver, copper, platinum, iron or steel. Perhaps the only importance of Haüy's work for the theory of hardness lies in the fact that he appears to have first suggested the 'mutual scratchability' of substances as a measure of their relative hardness.

Ultimately Mohs' modification of Haüy's scale was adopted by mineralogists. In his *Grundriss der Mineralogie*, 1822, Bd I S 374 he gives the following order: (i) Talc, (ii) Gypsum, (iii) Calcspar, (iv) Fluor spar, (v) Apatite, (vi) Adularia, (vii) Rock Crystal (Rhombohedral Quartz), (viii) Prismatic Topaz, (ix) Sapphire, (x) Diamond. In this scale each member was able to scratch all preceding members. Mohs gave numbers to these classes and placed other bodies with decimal places between these numbers by testing the relative hardness of two nearly equally hard bodies by their resistance to a file and the comparative noise. In 1836 Breithaupt attempted to introduce a scale of hardness of 12 classes, but it does not appear to have met with any wide acceptance.

¹ The Latin version has *crystallo montana*. I suppose *rock crystal*. See also p 113 of the *Opuscula* for a further remark on the hardness of diamond.

(e) The conception of relative hardness based upon the power of one body to scratch a second is evidently very unscientific. Huyghens had shown a century earlier that the hardness of a body varies with direction, and its power to scratch varies also with the nature of the edge and face. The latter fact was well brought out by a memoir of Wollaston entitled: *On the Cutting Diamond*, *Phil. Trans.* 1816, pp. 265-9. This memoir draws a distinction between *cutting* and *scratching*, which has been unfortunately lost sight of by later writers on hardness. Wollaston shows that the diamond irregularly tears the surface unless its natural edge, which is the intersection of two curved surfaces and thus a curved line, be so held that a tangent to it lies in the plane face of the material to be cut and is also the direction of motion of the diamond. The curved surfaces must also be held as nearly as possible equally inclined to the plane face. By paying attention to similar principles Wollaston succeeded in getting sapphire, ruby and rock crystal to cut glass for a short time with a clean fissure. It required a fissure of only $\frac{1}{200}$ of an inch deep to produce a perfect fracture.

Further evidence in the same direction is given by C. Babbage in his work *On the Economy of Machinery and Manufactures* (London, 1832). After some remarks (p. 9) to the same effect as Wollaston's on the proper position for working the diamond he continues:

An experienced workman, on whose judgment I can rely, informed me that he had seen a diamond ground with diamond powder on a cast-iron mill for three hours without its being at all worn, but that, changing its direction with reference to the grinding surface, the same edge was ground down (p. 10).

(f) L. Pansner in a pamphlet published in St Petersburg in 1813 seems to have been the first to adopt the plan of testing minerals, not by scratching them upon each other but by means of a series of diamond and metal points. Later in a memoir entitled: *Systematische Anordnung der Mineralien in Klassen nach ihrer Härte, und Ordnungen nach ihrer specifischen Schwere*, published in both Russian and German in the *Mémoires de la Société Impériale des Naturalistes*, T. v., pp. 179-243, Moscow, 1817, we find him classifying minerals as follows: (a) *Adamanti-Charattomena* (scratchable by a diamond, but not by a steel graver); (b) *Chalybi-Charattomena* (by a steel but not by a copper graver); (c) *Chalco-Charattomena* (by a copper but not by a lead graver); (d) *Molybdo-Charattomena* (by a lead graver); (e) *Acharattomena* (those whose hardness cannot be tested by scratching). These classes formed by relative hardness are again subdivided according as the specific gravity of the mineral is less than 1, less than 2 etc., into (0) *Natantia*, (1) *Hydrobarea*, (2) *Di-hydrobarea*, (3) *Tri-hydrobarea* etc., etc. Pp. 183-202 (erroneously paged 173) are occupied with a table of several hundred minerals thus classified, with the specific gravities to four places of decimals. The remainder of the memoir does not relate to hardness but to a classification of inorganic substances by other physical characteristics.

Pansner was followed by Krutsch who also states that he had used

metal needles to scratch bodies in his *Mineralogischen Fingerzeug*, Dresden, 1820, but I have been unable to find a copy of this work

(g) The first experimentalist to obtain results of value from this method was Frankenheim in his *De crystallorum cohaesione Dissertatio Inauguralis*, Biatislaviae, 1829 Of this work I have been unable to procure a copy Its contents are, however, embodied and extended in the same author's later book *Die Lehre von der Cohasion*, Breslau, 1835 see our Arts 821* and 825* Frankenheim's results were obtained by scratching with the metal needle held in the hand and judging relative hardness by the pressure and pull necessary to produce a scratch He applied this method to test the relative hardness of crystalline surfaces in different directions It cannot be said that such a method is capable of really great scientific accuracy, but we shall have occasion later to compare some of Frankenheim's results with those of other experimentalists

(h) About 1822 Barnes of Cornwall had noted that a circular plate of soft iron if revolving with very great rapidity is capable of cutting the hardest steel springs and files His experiments were repeated by Perkins in London, and accounts of them were published in most of the physical and technical journals Further experiments were made by Darier and Colladon in 1824 (*Bibliothèque universelle des Sciences et Arts*, T xxv pp 283-89, Geneva, 1824, or Schweigger's *Jahrbuch der Chemie u. Physik*, Bd XIII S 340-6 Halle, 1825,) and these physicists showed that when the iron disc moved with a circumferential speed of less than 34 ft per second it was easily torn by hardened steel, but that with a speed of 35 ft 1 in. per second the iron began to affect the steel, till at 70 ft per second only small fragments of iron were thrown off, although the steel was violently attacked (pp 265-6) They further showed that the effect was not produced by the softening of the steel during the process, nor, at any rate initially, by the particles of steel which cling later to the iron disc and increase the effect They attributed the result to the influence in some way of the impact, and supposed it to depend, not on the cohesion of the iron, but on each particle of the iron acting for itself Chalcedony was slightly attacked and quartz was torn by the rotating iron disc (p 287) A disc made of copper mixed with one fifth tin produced no effect on steel, and a copper disc was itself attacked by steel even at a circumferential speed of 200 ft per second (p 288)

In Silliman's *American Journal of Science*, Vol x p 127, and p 397, 1826, will be found further facts with regard to the above phenomenon in letters to Silliman from T Kendall and I Doolittle (see also Schweigger's *Jahrbuch der Chemie und Physik*, Bd XVII S 77-81, 1826) The former points out that when the iron cuts the steel, it is the latter which gets hot, but that when it fails to do so, the iron takes even a blue colour from the heat He considers that the steel is in the process heated up to that particular heat ('black heat') at which it is easily fragile, which it is not at a less or greater heat

He thus holds that the results are associated with a particular temperature, and attributes to the inability of copper to produce this temperature in steel its failure when rapidly rotated to cut the latter metal. I. Doolittle notes that although he could cut steel with a rotating iron plate, he found it quite impossible to cut perfectly gray and soft cast-iron.

I have cited the above results to show that in measuring relative hardness the velocity with which the graver moves is in itself of importance; hence the report referred to by Darier and Colladon that the Chinese cut diamonds with iron may not after all be so entirely mythical.

(i) Seebeck in a school program of 1833 (*Ueber Härteprüfung an Krystallen,—Prüfungsprogramme des Berliner Real-Gymnasiums*), of which I have been unable to procure a copy, invented a more scientific instrument for measuring hardness. He placed a loaded needle or scriber on the crystal and measured the hardness in any direction by the least weight which would just cause the needle to scratch the crystal when the latter was drawn under the point by the hand. Seebeck writes of this method:

Bei der hier angeordneten Bestimmungsmethode ist es nur der Druck der Spitze gegen die Fläche welcher gemessen wird; etwas anders würde es sein, wenn bei constantem Drucke die zum Verschieben nöthige Kraft gemessen würde; auch hier würde man wohl, wenigstens bei einem ziemlich starken Drucke zwischen den verschiedenen Richtungen des Krystalls, Unterschiede finden, andere zwar als die vorigen, aber mit ihnen zusammenhängende. Bei der Prüfung mit der Hand (Frankenheim) werden sich beide Wirkungen durch das Gefühl ziemlich vermischen, wenn man auch vorzüglich auf den gegen die Fläche ausgeübten Druck achtet.

Franz, as we shall see later (Art. 837), experimented much in Seebeck's manner except that he used a conical point, instead of a needle, and did not draw the crystal by hand.

The 'Sklerometer' of Grailich and Pekárek (see our Art. 842) is a more complete form of Seebeck's instrument.

Seebeck did not make very much use of his machine, but he confirmed with it Huyghens' statement (see our Art. 836 (a)) and made some experiments on calcspar, gypsum and rock salt. In the case of the first substance Seebeck's results differ from those of Frankenheim (*Die Lehre von der Cohäsion*, S. 335) and Franz: see our Art. 839.

(j) It will be seen that Seebeck did a good deal to advance the scientific conception of hardness, and to produce an instrument which could measure those differences in the hardness of crystals which had been first noted by Frankenheim, namely: (i) hardness in different senses of the same direction, (ii) hardness in different directions of the same face, (iii) hardness in different faces of the same crystal.

But none of the various ideas of hardness held by these writers clearly distinguish: (i) between set and rupture, (ii) between shearing, tensile and compressive actions. Yet it seems very clear that relative

hardness may be different according as the instrument applied merely produces set or actually tears the material that is according to the manner in which it produces an effect, whether for example by indent or by scratch. The reader will find it well to bear in mind this obscurity in reading our *résumés* of later memoirs on the subject

(k) To the researches of Ångström on the hardness of gypsum and feldspar and to those of Wade on the hardness of metals, we have referred in other parts of this chapter see our Arts 685 and 1040—3

The following ten articles are devoted to some account of the researches on hardness due to the decade 1850—60

[837] R Franz *Ueber die Harte der Mineralen und ein neues Verfahren dieselbe zu messen* Poggendorff's *Annalen*, Bd 80, S 37—55 Leipzig, 1850

Franz defines the hardness of a mineral as follows

Mir scheint nämlich die Harte eines Minerals diejenige Kraft desselben zu seyn, welche seine Theilchen zusammenhaltend, dem Körper, der diese zusammenhängenden Theilchen trennen will, Widerstand leistet [So far this might stand as a definition of cohesion] Sie ist also diejenige Kraft des Minerals, welche das Eindringen eines Körpers in das Mineral verhindert, und zugleich der Fortbewegung einer in die Oberfläche eingedruckten Spitze sich entgegenstellt Das Maass dieser Widerstandskraft ist nun aber offenbar der Druck, welcher angewandt werden muss, um den Körper zum Eindringen in das Mineral zu bringen (S 37)

It seems to me that this manner of determining hardness may really measure two different kinds of resistance, viz the resistance to entry and the resistance to tearing after entry Franz assumed that in measuring these resistances he was measuring one and the same property—hardness¹

[838] Seebeck in 1833 had already drawn attention to these different methods of measuring hardness, viz by (1) the least load on a scribe drawn normal to the surface of a mineral which will produce a scratch, (11) the least load parallel to the surface which will draw a scribe which has already entered the mineral across the surface Franz's apparatus differed little from Seebeck's, except that he has two separate instruments for measuring the resistances (1) and (11), and in (1) the mineral mounted in a car is drawn

¹ A criticism of Franz's methods on rather different grounds will be found on pp 39 and 48 of Hugueny's *Recherches expérimentales sur la Dureté des Corps*, Paris, 1865

its bed by a winch and not pulled with the hand: see our §. 836 (i). Franz used the first method to determine considerable differences of hardness and the second for slight differences, which as occur for example in the relative hardness in different sections of the same crystalline surface. He used for scribes a steel cone of 54° vertical angle and a diamond crystal. The steel was sharpened daily before experimenting till it was just sharp enough to scratch under a given load a standard bit of gypsum.

[839.] We may note the following results:

Talc. No variation of the hardness with different directions was found (S. 40).

Gypsum. The hardness in the plane of most perfect cleavage was estimated. The maximum hardness was found in a direction making an angle of about 20° with the shorter diagonal of the rhombus and approximating to the second direction of cleavage; the minimum hardness in a direction about perpendicular to this (S. 41-3). Ångström rejects Franz's results as untrustworthy. See our Art. 685.

Iceland Spar. On the rhombohedral surface the greatest hardness was found in the shorter diagonal when the scribe moved in the direction from the obtuse to the acute angle of the rhombohedron. The minimum hardness was in the same direction but in the reversed sense. In the direction of the greater diagonal both senses gave the same value. Frankenheim, according to Franz, found the greatest hardness in the greater diagonal, the least in the same direction as Franz. Franz demonstrated Frankenheim's supposed error by causing the scribe to describe circles on the face; when it went round clockwise the deepest furrow was made exactly at the points where there was scarcely a trace of a furrow when it went round counter-clockwise *vice versa*. He refers for Frankenheim's error to S. 337 of the work discussed in our Arts. 821* and 825*. On reference to this page, it will be found that Frankenheim says nothing about the directions of the least and greatest hardness in the rhombohedral surface, but that on S. 5, where he does, he writes:

Am grössten ist die Härte parallel der kurzen Diagonale, wenn man nach scharfen Ecke zieht.....Die Härte auf der langen Diagonale steht zwischen der Härte auf beiden Richtungen der kurzen Diagonale, allein dem Maximum näher, als dem Minimum.

In a footnote Frankenheim even corrects an error of Seebeck's who found the minimum hardness in the direction of the longer diagonal. Franz's 'correction' of Frankenheim's 'error' is thus rather gratuitous. Think he could not have carefully read Frankenheim's work. What the latter indeed says about the hardness in the longer diagonal being nearer to maximum than the minimum is confirmed neither by Franz nor by

Graulich and Pekárek (see our Art 844) Franz returns to the real error of Seebeck and the imaginary error of Frankenheim on S 53—5 In fig 4 on Plate II he gives a curve of hardness for the rhombohedral surface of Iceland spar I believe he was the first to make use of these curves of hardness, in which *radu-vectores* measure the hardness in a given direction, the credit of them has been recently attributed to Exner

Fluor Spar The least differences in hardness are found in the octahedral surface In the cubic surface, the greatest hardness is in the diagonal, the least in lines parallel to the sides of the cube (S 45)

[840] Various rather scanty results are given for the hardness in certain planes and in a few directions of *Apatite*, *Felspar*, *Quartz*, *Topaz*, *Sapphire* and *Syenite* (in this case somewhat more complete, with a curve of hardness, Fig 5 on Plate II) From all these results Franz draws the following conclusions (S 49—51)

(i) The directions of the greatest and least hardness in the same crystalline surface are intimately associated with the directions of cleavage

(ii) The direction which is the softest in planes which cut the planes of cleavage is that which is perpendicular to the direction of cleavage, the hardest direction in the crystal is that which is parallel to the planes of cleavage

(iii) If the surface of the crystal is cut by two directions of cleavage, then in this surface the hardest direction approaches the direction of easiest cleavage

(iv) Of the different surfaces of the same crystal, that one is the hardest which is intersected by the plane of most perfect cleavage

(v) If the direction of an easy cleavage is not perpendicular to the surface of investigation, then the hardness is greatest when the acute angle between the surface and the plane of easy cleavage points in the direction opposed to that of the motion of the scribe, it is least in the opposite direction (Compare with these the almost identical results of Frankenheim on S 337—8 of his work above cited) On S 51—3 Franz gives details of the mean hardness of a considerable number of minerals

[841] A Kenngott *Ueber ein bestimmtes Verhältniss zwischen dem Atomgewichte, der Harte und dem specifischen Gewichte isomorpher Minerale Jahrbuch der k k geologischen Reichsanstalt Jahrgang III, Vierteljahr¹ IV, S 104—116 Wien, 1852*

This memoir does not state particulars as to the manner in

¹ Each Vierteljahr has a separate pagination

hich the hardness of the various substances discussed has been determined. The author supposes his atoms to be liquid and herical; he states that they can or must be treated as liquid if they are to group themselves into molecules and as such into crystals (S. 104). As to the numerical results given in the memoir, I am unable to express any opinion as to their value, but the conclusions which the author draws from his chemical data appear to be summed up in the following paragraph which occurs S. 114-5, and which I content myself with citing:

Wenn die hier vorgeführten Beispiele zeigen, dass bei isomorphen Species, welche homolog zusammengesetzt sind, ein bestimmtes Verhältniss zwischen dem Atomgewicht, dem Atom- oder Molecül-Volumen, dem specifischen Gewichte und der Härte vorhanden ist, so dass mit dem relativen specifischen Gewichte in geradem, oder dem Atomvolumen umgekehrtem Verhältnisse die Härte steigt und fällt, und bei diesen gleich ist, während die Krystallgestalten wegen der übereinstimmenden Gruppierung übereinstimmend sind, weil die gleichgeordneten Atome der einen die Masse in einem dichteren Zustande enthalten, die Atome der anderen, so zeigen sie auch gleichzeitig, dass auf diese Differenzen der Härte und des relativen specifischen Gewichtes die Stellung in der elektrochemischen Reihe oder das elektrochemische Verhältniss der verbundenen Atome ohne Einfluss ist. Aus diesem Grunde habe ich die Atome in der elektrochemischen Reihenfolge rangestellt, darunter die Verbindungen der ersten Ordnung und in denselben die höheren, wo es dergleichen gibt, und es wird daraus ersichtlich, dass nicht durch den stärkeren elektrochemischen Gegensatz eine grössere Härte und das grössere relative specifische Gewicht hervorgerufen sind.

[842.] J. Grailich und F. Pekárek: *Das Sklerometer, ein Apparat zur genaueren Messung der Härte der Krystalle. Sitzungsberichte der k. Akademie der Wissenschaften. Bd. XIII., math. Naturwiss. Classe, S. 410-36. Wien, 1854.*

This memoir opens with an interesting historical account of the various modes of classifying or measuring hardness (S. 410-21). The authors note how unscientific was the earlier use of the word 'hard' by palaeontologists and mineralogists, and then record the searches of some of the writers to whom we have referred in our art. 836.

[843.] Grailich and Pekárek describe on S. 421-3 the principles of their own *sklerometer* ($\sigma\kappa\lambda\eta\rho\delta\varsigma$ = hard). It is essentially

given of the relative hardness of metals and alloys, *cast-iron* stands at the top¹. I do not understand the reference to the "half-hour" in the method of experimenting, nor how the load could be so regulated as to drive the steel point into the disc just 3·5 mm. in half-an-hour.

The method differs from that of the continental experimentalists and approaches more nearly that of Wade (see our Art. 1040), but it is open to the same objection as the methods of Seebeck and Franz, i.e. that a steel point driven 3·5 mm. deep would sometimes produce set and sometimes rupture.

[846.] Clarinval: *Expériences sur les marteaux pilons à Ames et ressorts et sur la dureté des corps. Annales des mines.* t. XVII., pp. 87–106. Paris, 1860. This paper gives an account of a *marteau pilon* invented in 1848 by Schmerber and its application in ascertaining the relative hardness of various substances. Clarinval finds that, the hardness of lead being taken as unity, tin has a hardness of about 4, and very hard iron heated to the temperature usual in forging from 1·4 to 2·5, the increase depending on the cooling of the metal during the series of experiments (pp. 98–102). He compares these results with those obtained by F. C. Calvert and R. Johnson in the *Manchester Memoirs* of 1848 (see our Art. 845), who with unity for lead give 1·7 for tin. Clarinval attributes this divergence to want of chemical purity in his own specimen. At the same time he remarks that he much prefers his own method of experimenting for practical purposes (p. 106).

GROUP G.

Memoirs on Elasticity, Cohesion, Cleavage etc.

[847.] Volpicelli: *Cosmos*, T. I. pp. 214–15. Paris, 1852. We find here a note attributing to this writer *une méthode qui nous semble nouvelle, pour la détermination des coefficients d'élasticité*. The coefficients in question are the so-called coefficients of restitution in the

¹ Staffordshire cold blast cast-iron being taken as 1000, we have: steel 958 (?), wrought-iron 948, platinum 375, copper 301, aluminium 271, silver 208, zinc 183, gold 167, cadmium 108, bismuth 52, tin 27 and lead 16. Probably these are not very trustworthy results as absolute numbers.

theory of impact of elastic bodies, or the kinetic coefficients of elasticity in Newton's theory. The 'new' method is the one used by Newton and described by him in the *Principia* see footnote to p 26 of our Vol 1

[848] J T Silbermann *Memoire sur la mesure de la variation de longueur des lames ou regles soumises à l'action de leur propre poids, pour servir de correctif aux mesures linéaires Comptes rendus*, T xxxviii, pp 825-8 Paris, 1854 This memoir remarks on the effect of the weight of a standard scale of length in elongating it when it is supported vertically by one terminal and not placed horizontally see also our Art 1247* It gives the detail of some experiments to ascertain this elongation for certain bars used as scales of measurement

[849] Ch Brame *Sur la structure des corps solides Comptes rendus*, T xxxv, pp 666-9 Paris, 1852 This letter to M Babinet discusses the cleavages of various substances and is not directly concerned with our subject

[850] A Laugel *Du Clivage des roches Comptes rendus*, T xl, pp 182-5 Paris, 1855, with a *Supplément* on pp 978-80

This memoir, of which only a *résumé* is given, was an attempt to extend the methods of Lamé and Resal see our Arts 561-70 The author apparently starts from Lamé's ellipsoid of elasticity and supposes that at each point of the earth's surface one principal plane of the ellipsoid will be horizontal He then states a number of propositions which he says he has demonstrated with regard to the planes of cleavage It is not evident how he has obtained them from the ellipsoid of elasticity or how, if found, they would necessarily be true, for I see no reason for associating cleavage with a stress rather than a strain surface see our Arts 1367* and 567 (b) Numerical measurements of the inclinations of the planes of cleavage in various localities are given and are compared with what are termed 'calculated values,' but the method by which the latter have been obtained is not explained The *Supplément* contains further results professing also to be based on the ellipsoid of elasticity bearing on rupture and the general elevation of mountain chains by eruption, but it is difficult to understand, from the vague description given of the memoir, whether the statements made have any real basis in the theory of elasticity

[851] P Boileau *Note sur l'élasticité du caoutchouc vulcanisé Comptes rendus*, T xlii, pp 933-7 Paris, 1856

The author made experiments on 'springs' composed of alternate plates of iron and annular discs of vulcanised caoutchouc He found that the squeeze of such a 'spring' was very far from being proportional to the load The increments of squeeze for increments of charge amounting to 2 kilogram per sq centimetre are tabulated, and it will be

und that they reach a maximum for a load of about 4·7 kilog. per square centimetre, and then decrease, far less rapidly, however, than they have increased. The writer neglects apparently the squeeze of the iron plates as compared with that of the caoutchouc. There are various other irregularities in the way in which the increments of squeeze alter. Thus after a load of 11·5 kilog. they become very small indeed, and after set has begun they appear to have alternate periods of slow and rapid alteration up to rupture. The author attributes these complicated phenomena to the peculiar molecular structure of caoutchouc and to its thermal characteristics. He notices also elastic after-strain in the springs. Finally he proposes 14 kilog. per sq. centimetre for static and 10 for impulsive or repeated loading as the proper limit for caoutchouc of good quality.

There is a paper on the strength of ice in the *Moniteur*, No. 2417, Paris, 1860, but I have been unable to find a Paris periodical.

[853.] W. Fairbairn and Thomas Tate: *On the Resistance of Glass Globes and Cylinders to Collapse from external pressure; and on the Tensile and Compressive Strength of various kinds of glass*. *Phil. Trans.*, pp. 213–247. London, 1859. The paper was received May 3 and read May 12, 1859.

[854.] This is a memoir which in some senses is characteristically British. Its authors display little theoretical knowledge and small acquaintance with the works of previous writers or investigators, but at the same time they present us with a number of useful experimental results, which would have been of very much greater value had the researches been directed by any regard to theory. There is no reference to the experiments of Ørsted, Colladon and Sturm, Regnault or Wertheim, nor to the theories of Poisson or Lamé: see our Arts. 686*–91*, 1310–11*, 1327*, 1357* and 535*, 1358*. It is true that the results of the mathematical theory of elasticity will only apply approximately, if they apply at all, to absolute strength; still a comparison of Saint-Venant's results (see our Art. 119) with those of this memoir would be of value, even if we did not adopt an empirical stress-strain relation at rupture such as that suggested in our Art. 178. The words 'hard,' 'rigid,' 'homogeneous' are used in a rather vague manner in the memoir and without precise definition.

[855] I cite the following experimental results (pp 216 and 221)

Glass	Tenacity per sq inch in lbs	Crushing load per sq inch in lbs
Flint	2286—2540 ¹	27,582
Green	2896	31,876
Crown	2546	31,003

Not much weight can be laid on the very few tenacity experiments. The glass was in cylindrical bars and the flint-glass annealed, the increase of tenacity, however, with the diminution of section points to a skin change of elasticity or to a cylindrical distribution of homogeneity. In the case of crushing, fracture occurred frequently with a load of only $\frac{2}{3}$ that of the crushing load. We have in the fracture surfaces a strong argument in favour of rupture by transverse stretch see our Aits 169 (c) and 321 (b). The authors write

The specimens were crushed almost to powder from the violence of the concussion, when they gave way, it however appeared that the fractures occurred in vertical planes, splitting up the specimen in all directions. This characteristic mode of disintegration has been noticed before, especially with vitrified brick and indurated limestone. The experiments following on cubes of glass which were exposed to view during the crushing process, illustrated this subject further. cracks were noticed to form some time before the specimen finally gave way, then these rapidly increased in number, splitting the glass into innumerable irregular prisms of the same height as the cube, finally these bent or broke, and the pressure, no longer bedded on a firm surface, destroyed the specimen (p 221)

[856] For cut glass cubes the following results were obtained

Glass	Crushing load per sq inch
Flint	13,130
Green	20,206
Crown	21,867

In these cut glass cubes (sides about 1") the skin effect was probably quite lost or reduced to a minimum, so that we find the crushing load of such cubes is to that of the glass cylinders on the average only as 1 : 1.6. *Supposing we might assume* the fracture load to have been $\frac{2}{3}$ of the crushing load, we should have for green glass rupture occurring by transverse stretch under a load of 13,471 lbs, but rupture by longi

¹ Area of section in the first case 255 and in the second 196 sq inches

dinal stretch takes place at 2896 (or probably a little less, if skinfect were allowed for)—the ratio of these numbers is about 4·6 : 1, somewhat different from the 4 : 1 of the theoretical limiting loads *r elastic* stretch and squeeze.

In some *General Observations* on these crushing experiments (pp. 13–4) the authors refer to Coulomb's theory of compressive strength; they are apparently unaware of its erroneous character: see our *rtts.* 120* and 169 (c).

[857.] Section III. of the memoir (pp. 224–231) is devoted the 'resistance of glass globes and cylinders to internal pressure.' There were only 17 experiments, 14 on spherical, 1 on cylindrical and 2 on ellipsoidal vessels. Section IV. (pp. 231–240) deals with external pressure. Here 11 experiments were made on glass spheres and 12 on glass cylinders. It is obvious that such a very narrow range of experiments (4 vessels of the last set were not captured) cannot be considered as a very satisfactory basis for the purely empirical formulae given in Section V. as a deduction from the experimental results (pp. 241–247).

[858.] These empirical formulae are the following :

External Pressure.

P = external pressure at rupture in lbs. per sq. inch.

d = diameter of the sphere or cylinder, l = length of the cylinder.

τ = thickness of the glass.

p = pressure P reduced to unity of thickness taken to be $\tau = \cdot 01$ inch.

Then if $C, C', a, a', \beta, \beta'$ be constants the authors *assume* we can represent P by :

$$\left. \begin{aligned} P &= \frac{C\tau^a}{d^\beta} \text{ for spheres,} \\ P &= \frac{C'\tau^a}{d^{\beta'}l^a} \text{ for cylinders,} \end{aligned} \right\} a \text{ being the same for both.}$$

They conclude that

(a) For spheres :

$$P = 28,300,000 \times \tau^{14}/d^{34}.$$

This formula, however, gives calculated results varying in some cases from the experimental by $\pm 1/4$ of their value, and does not therefore seem to me worthy of much credit (p. 243).

(b) For cylinders

$$P = 740,000 \times r^4/dl$$

This formula gives values of P differing in some cases by $+1/3$ to $-1/7$ from their experimental values and is not deserving of more confidence than the previous one

[859] The authors next deal with internal pressure, and adopt, as *experimentally* proved for vessels of glass, the formula

$$P = \frac{\omega T}{A},$$

where P = bursting pressure, T = the tenacity of the material, ω = the area of a longitudinal cross section of the material, that is, the area of the rupture surface, and A = the area bounded by a longitudinal section of the vessel

From the experiments in Section III the authors find in lbs per sq inch

$$\begin{aligned} T &= 4200, \text{ for flint glass,} \\ &= 4800, \text{ for green glass,} \\ &= 6000, \text{ for crown glass} \end{aligned}$$

Thus the mean tenacity = 5000 or nearly *twice its value* as given by direct tractive experiment see our Art 855 The authors remark

The tenacity of glass in the form of thin plates is about twice that of glass in the form of bars (p 246) This difference is no doubt mainly due to the fact that thin plates of this material generally possess a higher tenacity than stout bars, which, under the most favourable circumstances, may be but imperfectly annealed (pp 216-7)

[860] The memoir in its concluding paragraph assumes that the *mean* ratio of the tensile and compressive strengths of glass is equal to the mean ratio of the tensile and crushing strengths or as 1 118 nearly It seems to me that we ought to take fracture rather than crushing to powder as the limit of compressive strength, in which case the results for the flexural strength of glass bars deduced on p 247 from formulae and not from experiment would be much modified

It should be noted that Saint-Venant's theory for cylinders and spheres of thickness small as compared with the radius does not lead to formulae for safe loading of the type given in the preceding articles for bursting pressures see our Arts 120 and 124

GROUP H.

Minor Notices chiefly of Memoirs on Molecular Structure.

[861.] J. Szabó: *Einfluss der mechanischen Kraft auf den Molecular-Zustand der Körper. Haidingers Berichte über die Mittheilungen von Freunden der Naturwissenschaften in Wien.* Bd. VII., 1849, S. 164–73. Wien, 1851. This paper brings a good deal of rather discursive evidence to show that bodies of the same chemical constitution can exist in more than one physical condition, and that the application of such mechanical processes as scratching, vibrating, changing the temperature etc., suffices to throw the body from one condition into the other. The author cites for example black and red cinnabar and wrought iron in the fibrous and crystalline conditions. The paper is not of any permanent value, and is a collection of old rather than of novel facts.

[862.] O. L. Erdmann: *Ueber eine merkwürdige Structurveränderung leihtaltigen Zinnes. Berichte über die Verhandl. der k. sächsischen Gesellschaft der Wissenschaften. Mathematisch-physische Classe, Jahrgang 1851, S. 5–8. Leipzig, 1851.*

At the repair of an organ said to date from the 17th century in the *Schlosskirche* at Zeitz, the pipes were found to be strangely crystallised in certain places, *die ohne Ordnung, jedoch ziemlich gleichmässig vertheilt standen und von verschiedener Grösse, von der eines Silberroschens bis zu der eines Thalers waren.* The crystallised parts were extremely brittle, the rest of the metal ductile. Analysis showed the constitution of both parts to be chemically the same, so that the difference was in mechanical structure. Erdmann attributed this change of structure to the vibrations which the pipes had undergone, but hazarded no conjecture as to the manner in which the crystallisation was distributed.

Jedenfalls dürfte aber die mitgetheilte Beobachtung nicht ohne Interesse in Bezug auf das von einigen Technikern noch immer bezweifelte Krystallinischwerden von eisernen Achsen, Radreifen u. s. w. sein, wenn dieselben, wie beim Eisenbahnbetriebe, fortwährenden Erschütterungen ausgesetzt sind (S. 8).

[863.] D'Estocquois: *Note sur l'attraction moléculaire. Comptes-rendus*, T. 34, p. 475. Paris, 1852. This note merely refers to a paper which the author had submitted to the Academy. He states that he has proved that, if the molecules of a liquid all attract or all repel each other according to some inverse power of the distance, then they cannot retain the liquid condition "*à moins que cette puissance ne soit le carré.*" No further reference is given to the mode in which this singular result has been deduced, beyond the statement that it depends on the equation of continuity.

[864] Sir David Brewster *On the Production of Crystalline Structure in Crystallised Powders by Compression and Traction* *Edinburgh Royal Society, Proceedings*, Vol III, 1853, pp 178–180 Edinburgh, 1857 Evidence is given in this paper of the effect of compression on powders and of traction on 'soft-solids' in producing doubly refracting properties

[865] I have given a reference to several memoirs by Séguin in Art 1371* The molecular theory expounded in them formed the subject of a quarto volume of 55 pages and two plates published in 1855 at Paris It is entitled *Considérations sur les causes de la Cohésion, envisagées comme une des conséquences de l'attraction Newtonnienne et résultats qui s'en déduisent pour expliquer les phénomènes de la Nature*

The author in his preface speaks somewhat sorrowfully of the neglect which his memoirs read before the *Institut* have met with, and also somewhat slightly of the advantages of mathematical analysis His present work, he tells us, aims at providing a basis for the discussion *in the future* of molecular action

Tout le monde sait, que chaque question scientifique a son heure et son moment, qu'il ne depend pas de la volonté d'un seul homme de faire avancer ou retarder Cette heure et ce moment viendront, je l'espère, et alors ma cosmogonie se trouvera forcément à l'ordre du jour

Séguin's cosmogony is based on the elements of bodies, here termed molecules, of small volume and infinitely great density This theory was gained from a conversation with Herschel in 1811 It supposes the density to increase inversely as the volume of the molecules which are taken to be spherical By arranging these molecules in files and supposing them to obey the Newtonian law of gravitation, he endeavours to explain some of the features of cohesion, i.e. to obtain from the Newtonian law a sufficiently great cohesive force The whole of his calculations are of a most crude, insufficient and often obscure kind I must confess that I am in many places unable to follow his reasoning The density of the molecule has to be immensely greater than the density of the earth (pp 8–9), this might be intelligible, but as he puts the molecules of a bar of iron in contact, it seems to me that he makes a bar of iron of a different order of density to the earth Perhaps this difficulty may be got over by a right interpretation of the following words

Si l'on considère la vaste échelle sur laquelle Dieu a tout créé, tout fait, tout ordonné et le témoignage de nos sens, tout comme notre raison, doivent être, en pareille mesure, complètement émines comme tendant à l'infini et restreindre nos idées dans la sphère de nos conceptions qui sont si éloignées de l'intelligence des œuvres du Créateur (p 20)

Further Séguin tells us that in the beginning matter created by

God consisted of infinitely small, infinitely dense molecules uniformly distributed through space. Then :

au *fiat lux* la matière reçut de Dieu la faculté de s'attirer en raison directe des masses et inverse du carré des distances, et je considère que cette attribution, que la matière inerte a reçue de Dieu, constitue pour elle une espèce de vie matérielle (p. 41).

The *fiat lux* of the Jewish cosmogonist has received many interpretations, but scarcely any so grotesque as this of the French physicist and member of the *Institut* !

The reader will probably agree with the view expressed in our first volume (Arts. 163*-72*, 752*-8*) that the Newtonian law is insufficient to account for the phenomena of cohesion. What might be said for Herschel's idea, does not, however, seem to me to have been said in an intelligible fashion by Séguin¹. I feel, indeed, reluctantly compelled to class him with Eisenbach and Père Mazière. From the *Polytechnische Bibliothek* 1887, No. 9, S. 133, I see that a reprint of Séguin's work has just appeared in Lyons. I venture to doubt whether 'son heure et son moment' has even yet arrived.

[866.] R. P. Bancalari: *Sur les forces moléculaires*. *Cosmos*, VIII., pp. 501-3. Paris, 1856. Bancalari appears to have published a memoir in the preceding year in which he is said to have established the remarkable proposition that: *the resultant of the molecular forces in a body is directly proportional to the increments or decrements of inter-molecular distance and inversely proportional to the cubes of the same distances*. The methods by which the law of gravitation and Hooke's law are deduced from this proposition seem to me very unsatisfactory, and have not encouraged me to examine the original memoir for more particulars than *Cosmos* provides.

[867.] J. Zaborowski: *De triplici in materia cohaerendi statu. Disquisitio physica*. Posaniae, 1856. This is a quite worthless metaphysical dissertation which asserts that cohesion, treated as either negative or positive, is really adhesion and depends on the absolute continuity of matter. The author appears quite ignorant of the enormous advances which had been made in physical science between the time of Bacon and the middle of the nineteenth century, and the sole interest of his pages lies in their demonstration of the possibility of atavism in science.

¹ The theory of Herschel has been dealt with by Sir William Thomson in a paper published in the *Proceedings of the Royal Society of Edinburgh*, Vol. IV., pp. 604-6, 1862, and reprinted in the *Popular Lectures and Addresses*, Vol. I., pp. 59-63. London, 1889. Sir William, of course, is suggestive and clear, but his conclusion that :

It is satisfactory to find that, so far as cohesion is concerned, no other force than that of gravitation need be assumed,
seems to me far too optimistic.

[868] C S Cornelius *Ueber die Bildung der Materie aus ihren einfachen Elementen Oder Das Problem der Materie nach ihren chemischen und physikalischen Beziehungen mit Rücksicht auf die sogenannten Imponderabillen* Leipzig, 1856

This tract of xi + 64 pages professes to explain chemical, cohesive and gravitational forces by a new atomic theory. The method of procedure, although making frequent appeals to physical and chemical facts, is so metaphysical that I have not been able to perform the *gewisse Denkooperationen, die ihren Grund mehr oder weniger im Thatsächlichen haben*, which would have allowed me to reach the principles on which the author bases the sensible properties of matter. I am the more disappointed in this as the author assures us that his investigation is *in ihren Art vollständig*, and it appears not only to explain gravitation and elasticity but to remove in general any difficulty about the mutual action between body and soul. It would appear that the author arrives on S 18 at precisely Bosovich's definition of an atom, although he associates it with the names of Ampère, Cauchy, Séguin, Moigno and Faraday, together with a metaphysician or two. After this I can only follow an occasional passage here and there. It seems that a true element of matter must be *ein völlig intensives Eins*, but a contradiction arises from the fact that *ein sich selbst gleiches substantielles Eins* cannot influence its kith and kin. *Da jedes dem anderen hinsichtlich der Qualität völlig gleich ist, so kann keinem etwas von dem anderen widerfahren* (S 20). However by a *dauernder Act innerer Thätigkeit* an element can produce motion in the unlike. Hence arises a vibratory motion of a sphere of ether all round an atom. At this point we are rather abruptly introduced to mass and pressure, shown how action at a distance takes place, and given a demonstration of the law of gravitation. Strangely enough an atom treated as a pulsating ether squirt *does* go a considerable way to explain chemical and cohesive forces. Perhaps some scientist who is capable of performing the required *Denkooperationen, die ihren Grund mehr oder weniger im Thatsächlichen haben* will be able to say whether the author has any inkling of this. If so metaphysicians have a royal road to truth quite out of the ken of the ordinary scientist.

[869] Vogel *Zur Theorie der Glashäutchen* *Eidmanns Journal für praktische Chemie*, Bd 77, S 481-2 Leipzig, 1859. The writer of this note placed 'Ponce Rupert's drops' (*larmes butaniques*) in hydrofluoric acid so that the outer coat including the major part of the tail of the drop was dissolved away in 48 hours. The drop did not break up, and no effect was produced by breaking away the fragment left of the tail. A slight blow of the hammer, however, caused the drop to burst. The author concluded that the outer surface of the drop was not that which preserved the inner material in a state of great strain, or its removal would have brought about the bursting of the drop.

[870] A. Bouche *Recherches sur l'attraction moléculaire* *Mémoires de la Société Académique de Maine et Loire*, T VI, pp 229-333

ngers, 1859. T. VIII., pp. 133–144. Angers, 1860. T. x., pp. 181–49. Angers, 1861.

This is an elaborate attempt to explain the phenomena of gravitation, cohesion and chemical affinity by means of the law of intermolecular attractive force R ,

$$R = \frac{f}{d^2} \left(1 - \frac{a}{d} \right) \dots\dots\dots (i),$$

here d is the distance of two molecules, a is a very small constant distance and f another constant.

Bouché obtains this law by simply combining Newton's law of gravitation with Mariotte's law that the pressure of a gas varies as its density, while the density of a gaseous mass must vary inversely as the cube of the intermolecular distance. He proposes in the first paper to apply this law to distances less than interplanetary and greater than gaseous intermolecular distances.

[871.] Bouché works out at very considerable length the results which flow from accepting this law in the cases of planetary action, of the pressure of gases &c., but there is nothing very conclusive in these results, or that could not in general terms have been almost foreseen from the nature of the formula itself. The second part of the memoir consists of rather indefinite philosophical reasoning. In the third paper (p. 223) in *Tome x.*, Bouché makes a a function of the temperature and obtains an expression for the pressure p of the form :

$$p = f \left\{ \frac{A}{d^2} - \frac{Ba(1 + K\theta)}{d^3} \right\},$$

here A , B , K are additional constants and θ is the temperature. Of this formula he now writes :

Nous regarderons cette formule comme vraie dans toute l'étendue des intervalles planétaire et gazeux, et pour les valeurs de θ aussi grandes qu'on veut (p. 223).

There is again much indefinite discussion, and we conclude the memoir with the feeling of having made no real progress in understanding how far such a law as (i) will carry us in explaining intermolecular action. The same form of force has been discussed by Saint-Venant and Berthot: see our Art. 408.

[872.] J. G. Macvicar, D.D.: *An adaptation of the Philosophy of Newton, Leibnitz and Boscovich to the Atomic Theory.* *Proceedings of the Philosophical Society of Glasgow*, Vol. iv., pp. 32–80. Glasgow, 1860. This paper deals with atomic and molecular phenomena from the metaphysical standpoint. The remarks on elasticity (pp. 55–6) are unintelligible to me, and some critics might term them nonsense.

SECTION III

Technical Researches

GROUP A

Treatises and Text-books dealing with the Strength of Materials from the Technical Standpoint

[873] THE decade with which we are dealing is marked by the publication of many works treating of the strength of materials and the theory of structures. I cannot hope to have formed even an approximately complete list of works of this character, but it is probable that those I have considered in the following articles are very fair representatives of their class and suffice to indicate the progress of technical research and applied elasticity.

[874] A work by G. F. Warr entitled *Dynamics, Equilibrium of Structures and the Strength of Materials* was published in London in 1851. There is an interesting chapter, now of course quite out of date, on bridge structure (pp. 117–232), and one on the strength of materials (pp. 232–282), which contributes, however, nothing of value to the history of our subject.

[875] C. L. Moll and F. Reuleaux *Die Festigkeit der Materialien, namentlich des Guss und Schmiedeeisens (Besonderer Abdruck aus der Construktionslehre für den Maschinenbau)*, Braunschweig, 1853, 72 pages. This work is a synopsis of formulae rather than a treatise. It emphasises, however, an important principle, which has too often been forgotten by technical writers, namely that the rupture strength of a material is not a true guide to its use in construction. The authors adopt what they term a *Coefficient der stabilen Festigkeit* as a measure of the stress permissible in a material. This coefficient is based upon the *elastic limit*, but we are not told how the elastic limit is to be determined, while we know that within a certain range, it can safely be extended without injuring the material. For cast iron they take the elastic limit in compression double its magnitude in extension (7.5 kilogs per sq. millimetre), and they suggest that upon this result the best practical section for a cast iron beam ought to be based, and not upon Hodgkinson's results as to rupture strength. See our Arts. 243*–4*, 176 and 951.

We may note that the authors appear to have had no conception of shear or slide. They take (§ 65) the *Drehungsmodell* (*sic*!) always of the stretch modulus without any mention of anisotropy or multi-constancy. Further their views on torsion and the resulting formulae

are completely erroneous (S. 12-13 and the footnote (!)); and, notwithstanding their assumption of uni-constancy, they treat all elastic bodies as built-up of 'fibres' (S. 2). Lastly they give copious values for the moments of inertia of various cross-sections. I have not tested all these, but some of them are certainly wrong and others inconsistent with the results given by later writers (e.g. XVIII. S. 23).

[876.] In the year 1853 was published the fifth volume of Morin's *Leçons de mécanique pratique*, the first volume of which had appeared in 1846. This fifth volume forms the first edition of the well-known *Résistance des matériaux*, a work which in several editions extending over a long course of years has had great influence as a book of reference for students of technical elasticity¹.

A note giving an account of this work by Morin himself, will be found in the *Comptes rendus*, Tome XXXVI., pp. 284-7. Paris, 1853. Morin states that his work is not intended as a complete treatise on the strength of materials; it is only the text of lectures delivered by him in the *Conservatoire des Arts et Métiers* during the years 1851-2. His object in the work has been to remove doubts which have arisen with regard to the ordinary theory of elasticity owing to its extension to problems lying outside its proper limits. Those limits, however, contain, he maintains, really all that is needful for most practical constructions: for it is not the *absolute* but the *elastic* strength of a material which ought to determine the proportions of any piece of it.

A second edition of Morin's *Résistance des matériaux* appeared in 1856, and a note by Morin on its presentation to the *Académie* will be found in the *Comptes rendus*, Tome XLIII., pp. 939-41. Paris, 1856. It is therein remarked that the additions made to the volume tend further to demonstrate the applicability of the ordinary theory to small strains. Thus by very careful measurements on the flexure of wooden, wrought-iron and cast-iron beams, Morin states, that he has demonstrated that the resistances to stretch and squeeze are "within the elastic limit" equal, *i.e.* that the stretch- and squeeze-moduli are initially equal: see, however, our Arts. 1411* and 793. The difficulty here is to grasp the exact meaning of the term "elastic limit." Morin uses in one place (p. 940) the phrase "*premières flexions et celles que l'on peut sans danger admettre dans les constructions*," but this seems equally vague.

¹ The third edition in two volumes appeared in 1862.

[877] We cannot analyse all the separate editions of Morin's work and must content ourselves therefore with some remarks on the first edition and a notice of additions in the last edition at a later stage of our history. A German translation of the first edition under the title *Die Widerstandsfähigkeit der Baumaterialien* will be found on S. 196–264, Jahrgang XVIII, and S. 194–343, Jahrgang XIX, of *Forsters Allgemeine Bauzeitung*, Wien 1853 and 1854. The first part of this concludes with a bibliography of earlier works on elasticity and the strength of material having special reference to technical researches, most of the work referred to will be found quite sufficiently dealt with in our first volume.

[878] The *Première Partie* of Morin's work is entitled *Extension*, and occupies pp. 1–60. This section is very characteristic of his methods. While G. H. Love (see our Arts. 894–90) exaggerates the discrepancies between theory and practice and would reduce elasticity to an empirical science, Morin on the other hand seems to me to disguise the real difficulties which occur, and so to some extent his book tends to check that development of theory which invariably follows when any discordance with experience is clearly recognised. He endeavours to reconcile the insufficient theory of Navier and Poncelet with the experimental conclusions of Hodgkinson, Fairbairn and others.

Thus he assumes (i) that for every given material the limits of elasticity are absolute and not relative to the working, (ii) that perfect elasticity necessarily ceases with the proportionality of stress and strain (pp. 2–3), (iii) that the limit of safe stress for practical purposes is this elastic limit (pp. 3 and 7). On p. 48 we have a table of absolute limits of elasticity and the corresponding safe stresses for a great variety of materials. Now to-day we are certain that the limit of elasticity is relative to the working and the previous loading of the individual specimen, and further does not necessarily connote proportionality of stress and strain (see our Vol. I Note D, p. 891 and Art. 796). Hence it is difficult to consider Morin's treatment of safe-loading as satisfactory. Indeed he himself remarks that further experiments on the elastic limits are needed and proposes to fall back on 1/10 of the rupture stress for wood, stones and cements and 1/6 of the rupture stress for

etals as the safe permanent stress. He gives tables of stresses thus calculated on pp. 54-6.

[879.] We may briefly note one or two other points in this first part.

(a) On pp. 5-17 the results of experiments by Bornet, Ardant and Hodgkinson for wrought- and cast-iron are given and stress-strain stretch-traction) curves are plotted out (Plate I.). These are very valuable and suggestive for the comparison of various types of hard and soft iron, and their relative technical advantages. Compare our Arts. 817*, 983*-4* and 1408* *et seq.*

(b) On pp. 17-28 various elementary theoretical and empirical formulae are given for cylindrical and spherical shells subjected to internal pressure. These are applied to numerical examples in the case of boilers and hydraulic presses. Notably it is shown that the presses used to raise the tubes of the Britannia bridge were dangerously weak (p. 25-7).

(c) We may note here the formula adopted at that date by the French Government for the thickness τ of boilers of plate iron of internal diameter d , subjected to N atmospheres of internal pressure:

$$\tau = .0018Nd + .003,$$

and τ being measured in metres.

Here .003 is a constant introduced to allow for the wear of the material, and the safe tractive stress for plate iron is taken to be 300,000 kilogs. per sq. metre. As the rupture traction of plate iron equals about 30,000,000 kilogs. per sq. metre, and according to Morin we ought to take 1/6 of this for safe loading, the formula leaves considerable margin of safety. We refer to this formula here as it occurs in many French and even in German books of this period: see, for example, our Art. 1126.

(d) On pp. 28-31 the experiments of Fairbairn and Clarke on plate iron are considered. Morin seems to hold that Fairbairn's results are generally correct for the better kind of plates, but this should be compared with our Arts. 1497* and 902. He then passes to Fairbairn's experiments on rivets and cites his result that absolute tractive and shearing strengths are practically equal: see our Arts. 1480* (ii) and 1499*-1500*. He compares it with that of Gouin et Cie¹, who found for iron rivets the tractive and shearing strengths about 4000 and 2000 kilogs. per sq. centimetre respectively, or very nearly in the ratio of 5/4, which is what the theory of uniconstant isotropy would give for the ratio of the corresponding *fail* limits in traction and shear: see our Arts. 5 (e), 185, and Vol. I., p. 877.

¹ The details of Gouin et Cie's experiments were given in the *Mémoires. de la société des ingénieurs civils*, Année 1852, pp. 155-7, Paris, 1852: see our Art. 1108.

(e) After a *résumé* of experiments on wood (see *Wood*, Index, Vol 1) Morin gives some details of experiments on the strength of iron cables by which it would appear that the French navy at that date had cables considerably stronger than those of the English navy (pp 42-7) I may note one point which seems to me suggestive. In the experiments of Captain Brown the absolute strength of the iron employed to make the links of the chain cables was about 40 kilograms per sq mm, but the strength of the chain cable was only 34 kilograms per sq mm or the ratio of the two = $\frac{5}{4}(1 - \frac{1}{17})$, or nearly $5\frac{1}{4}$. But this by the preceding paragraph is the ratio of the shearing to the tractive strength in wrought iron. Hence it appears to me that Brown's cables were possibly destroyed by shearing and not tensile stress see our Art 641

(f) On p 49 Morin, reasoning, however, only from Wertheim's experiments on *wires*, states that annealing does not effect the elasticity of iron and steel, but does that of copper, gold, platinum and silver. He suggests, however, that this would not hold true for larger masses of iron, as for example axles, kept at a moderately high temperature for a long period. He believes that such masses would change from a soft and fibrous to a crystalline condition, and he cites an experiment of his own, where moderate and continuous annealing during five months and twelve days produced this effect. Hence he concludes that it is not advisable to anneal axles and other large pieces of metal see our Arts 1295*, 1463*-4*, 891 (d), and 1070

(g) On pp 57-60 Poncelet's results for elastic and absolute resilience are reproduced (see our Arts 981*, 988*-92*) These resiliences are the areas of the corresponding parts of the stress strain curves. It does not, however, seem to me true that because the rupture resilience of soft iron is greater than that of hard iron, the former ought to be employed for bodies like iron cables, etc subjected to impulses. Repeated impulses with less resilience than the elastic resilience of a hard iron bar, but greater resilience than that of a soft iron bar, would leave the former undamaged but wear the latter out. It is only when the resilience of the impulse is likely to be greater than the elastic resilience of both hard and soft iron, that it is advantageous to use the latter. See on this point Cavalli's remarks cited in our Arts 1085-9

Further I must note that Morin's method of equating the kinetic energy of a falling body to the total resilience of a bar does not seem to me to give a true limit to the height from which the body may fall on the bar without destroying it. It has first to be shown that the kinetic energy of the falling body will not be absorbed by one element of the bar, but be distributed throughout its volume. This Morin has not attempted to do. The complete solution of any problem of resilience is one of great complexity see our Arts 362-71, 401-7 and 410-14

[880.] The *Deuxième Partie* of the work is entitled: *Résistance des corps solides à la compression* and occupies pp. 61–123. We may note briefly one or two points:

(a) Pp. 61–76 deal with the resistance of wood. Morin compares the results obtained experimentally by Rondelet and Hodgkinson. Rondelet in his *Traité de l'art de bâtir* (see our Art. 696*) does not seem to have distinguished between rupture by pure compression and rupture by buckling. He gives a table of the following kind for wooden columns:

Ratio of height to least dimension of cross-section	1	12	24	36	48	60	72
Crushing Strengths	1	5/6	1/2	1/3	1/6	1/12	1/24

This is a purely empirical table and it would not be necessary to refer to it here, had not a recent writer apparently adopted these numbers for the crushing strengths of apparently all kinds of material¹. Obviously a different kind of strain appears the moment the block comes long enough to buckle, and these numbers are at best only approximately true for the particular type of wood upon which Rondelet was experimenting.

Hodgkinson on the other hand found for short blocks (height double the diameter) that the crushing load P was proportional to the area of cross-section, while for wooden struts (see our Art. 965*) of length l and rectangular cross-section $a \times b$ ($b < a$) he adopted a formula of the type $= Kab^3/l^2$, where K is a constant depending on the material. Morin adopts Hodgkinson's results in preference to Rondelet's and gives the following values for K , when a and b are measured in centimetres, and l in decimetres:

Strong oak: 2565.

Weak oak: 1800.

Red and strong white deal and resinous pine: 2142.

Weak white deal and yellow pine: 1600.

For safe loading $1/10$ of P may be taken (pp. 68 and 73).

Obviously $100K$ = crushing strength of a cube of the material of the centimetre side, or K equals crushing strength in kilogrammes per sq. decimetre of such cubical blocks. The numbers we have cited can only be treated as roughly approximate, for the crushing strength varies greatly with the degree of moisture, age, etc. of the wood: see our Arts. 1312*–4*.

¹ F. Auerbach in the *Handbuch der Physik* (Dritte Abtheilung of the *Encyclopædie der Naturwissenschaften*), Bd. 1., S. 312.

(b) Pp 76-89 give details of the experimental results of Rondelet, Clark and Vicat on the crushing strengths of stone, mortar, cement and brick see our Arts 696*, 1478* and 724*-30* Morin after citing at length Vicat's results on the compression of cylinders and spheres between parallel tangent planes, and the pyramidal or conical surface of rupture remarks

Les nombreuses observations que nous avons recueillies à Metz, M Probert et moi, sur la rupture des projectiles brisés par le choc, ont montré que dans ce cas la rupture se fait d'une manière analogue, avec cette différence que le point choqué est le plus ordinairement le sommet déprimé d'une pyramide à cinq faces quand la vitesse du choc n'est pas très considérable, et qu'aux grandes vitesses cette pyramide se change en un cône à génératrice curviligne, qui est presque toujours multiple ou formé de plusieurs autres cônes coniques, et dont l'axe diminue de longueur à mesure que la vitesse du choc augmente (p 81)

Supposing we assume that the rupture surfaces are practically in close agreement with the surfaces of maximum elastic stretch I think an explanation of these extremely interesting conical and pyramidal rupture surfaces, to which I have frequently had to refer (see our Arts 730*, 949*, 1414* and 1446*), might be deduced by Hertz's method of investigation (*Crelle's Journal*, Bd 92, 1882, S 156-71)

(c) Pp 90-100 deal with Hodgkinson's experiments on cast-iron see our Arts 1410*-5* Morin adopts a *mean* value for the squeeze modulus, which does not seem to me justified by Hodgkinson's results see our Art 1411* Pp 100-105 deal with wrought-iron and a comparison of its action under compression with that of cast iron Morin gives graphical representations of Hodgkinson's results Then follows a discussion of Hodgkinson's experiments on cast-iron pillars (see our Arts 954*-65*), which are represented by numerical tables (pp 108-9), more easy to work from than Hodgkinson's formulae, and also graphically by curves on Plates II figs 4 and 5, III figs 1 and 2 Pp 115-23 deal by approximate methods with the compression in arched ribs Here a circular rib is treated as a parabolic arch and supposed to be loaded uniformly per foot-run of the horizontal chord, although Morin (p 116) speaks of the load as being often in great part due to the weight of the arch Thus Morin really only deals with a part of the complete expression as worked out by Bresse see our Art 525 A table on pp 118-9 gives the compressive stress in a number of existing arches and viaducts in France on these assumptions

[881] The *Troisième Partie* on *Flexion* occupies pp 124-431, or embraces the bulk of the volume

(a) After some general remarks on the experiments of Duhamel du Monceaux, Dupin, Duleau, Hodgkinson, etc, which he holds tend to confirm the customary axioms of the Bernoulli Eulerian theory, Morin proceeds with a slight historical preface (pp 140-4) to develop

that theory in the usual manner. The usual problems are solved and the fail-limit or safe load for a beam is deduced from the formula for the bending moment (see our Art. 173).

$$M_0 = \frac{T_0 \omega \kappa^2}{h},$$

where T_0 is taken as a quantity to be determined by flexure experiments and not to be assumed from pure tensile results. Morin gives a table of its values for different materials on p. 169, but he does not note that it is part of the 'paradox in the theory of beams' that it varies from one form of section to another: see our Arts. 173 and 930. Besides the fact that in a great variety of special cases the deflection of simple beams is worked out, there is nothing calling for special notice in the whole of these pages (pp. 138–232).

(b) Morin next proceeds to apply these theoretical results to the experimental determinations of the elasticity and strength of wood made by Barlow (see our Art. 188*), and of cast-iron made by several English Engineers for the *Report of the Iron-Commissioners* (see our Art. 1406*). In the latter case Morin concludes that the flexure of cast-iron for all practical purposes obeys closely enough the laws of the Bernoulli-Eulerian theory (p. 268), but I hardly think the facts warrant this conclusion. He next deals with rolled and plate iron girders, considering especially a great variety of T and double-T beams (pp. 269–90). Next we have a long account of the theory and construction of tubular bridges in plate-iron, with details of Fairbairn's experiments (pp. 290–322): see our Arts. 1465* *et seq.* Then follow descriptions of a girder in plate-iron designed by Brunel, of the experiments of James and Galton on travelling loads, and remarks on the alteration of structure in axles by Marcoux¹ and Arnoux²: see our Arts. 1417* and 1463*–4*.

(c) The remaining portion of the *Troisième Partie*, namely pp. 354–431, is devoted to a discussion of roof trusses (*charpentes*) in wood and iron. The theory employed is analytical, and appeals only to the elementary principles of statics combined with the Bernoulli-Eulerian theory of beams. Morin cites Ardant's results (p. 361 etc.: see *Addenda* to our Vol. I., pp. 5–10), and gives formulae and tables which might possibly be still of service in the design of roof-trusses. The only articles which call for special notices are §§ 324–6, which deal with the first experiments ever made, I believe, to test the stresses calculated for the members of a frame. In these experiments Morin was assisted by Tresca and Kaulek. The tie rods to be tested

¹ Marcoux considered that axles were weakened by prolonged vibration, but that they did not change their structure from fibrous to crystalline (p. 350).

² Arnoux considered that axles were weakened by prolonged service and that there was a structural change (p. 353).

were replaced by chains containing dynamometers, and the chains were carefully screwed up to the original length of the replaced tie rod. The stresses measured by the dynamometers agreed with the results of calculation to a degree sufficiently accurate for practical purposes,—in all cases but one with less than 6 p.c. difference and often with considerably less (pp 396–400)

[882] The *Quatrieme Partie* is entitled *Torsion* and occupies pp 432–53. The statement on pp 432–3, that the absolute displacements are proportional to the distances of the displaced elements from the axis of the prism under torsion, is only true for prisms of circular cross section, and the application of Coulomb's theory to bars of rectangular cross-section (p 438) is of course incorrect. Some experiments on the resistance of cast-iron shafting to torsion made at Mulhausen and some others made by Carillion in Paris are cited on pp 444–51, but the theory given of rupture by torsion (p 448) seems to me obscure if not erroneous, and this portion of the work is not satisfactory.

Considering the date at which the work was published, it was extremely good of its kind, although Love's book is in many points of more practical service. It has in later editions progressed with the advance of technical elasticity and we shall have occasion to refer to it again.

[883] H. Tellkamp *Die Theorie der Hängebrücken mit besonderer Rücksicht auf deren Anwendung* Hannover, 1856. This is a useful *resumé* in 120 pages of the theory of suspension bridges from the practical side. Attention may be drawn to the *Sechstes Kapitel* entitled *Oscillationen der Hängebrücken*, S. 99–114, which develops various, not absolutely rigid, theories of impact. We may note especially § 49 (S. 107–12), which applies a theory of impact similar to that of Hodgkinson, Cox and Saint-Venant to the case of a weight falling on the centre of a suspension chain. This may be taken as an example of a theory, which if somewhat hypothetical still gives results probably accurate enough in practice—see our Arts 943*, 1434*, and compare with Arts 366–71.

[884] We are justified in asserting that the period with which we are dealing in this chapter marks a great improvement in the type of text-books for practical technologists and students. Notably in this respect we owe much to J. Weisbach, Moiré and J. M. Rankine. The first edition of Weisbach's *Ingenieur-Mechanik* appeared in 1846, the second in 1850, the third and fourth in 1856 and

1863 respectively. Polish, Swedish, Russian, English and American translations have appeared. E. B. Coxe's translation of the fourth edition (Trübner, 1877) is the form most accessible to English readers. Section IV. and the Appendix deal with a number of elastic problems and profess in the fourth edition to incorporate the then recent book of Lamé, Rankine and Bresse. An interesting sign of the progress of our science is the continual remodelling of these portions of the book in successive editions. While the work shows greater advance over the earlier text-books on the strength of materials and while some points of it might even be of service to-day, it must nevertheless be read with caution. In the English edition of 1877 we still find an unsatisfactory and even erroneous treatment of flexure, torsion and of the theory of struts, while the theory of combined stress exhibits the same errors as Weisbach's earlier memoir on that subject: see our Art. 1377*—8*. Further, contrary to Weisbach's opinion, Kupffer's experiments show that the stretch-modulus can be found with some degree of accuracy from transverse vibrations by means of the formula cited in § 5 of the *Appendix*. The book so far as our subject is concerned is entirely replaced on the theoretical side by Grashof's text-book; neither of them can, however, be considered satisfactory from the physico-technical side. An account of Weisbach's labours is given by Rühlmann: *Vorträge über Geschichte der technischen Mechanik*, 1885, S. 415—24.

Other German text-books of this period, to which I have found frequent reference in memoirs dealing with the strength of materials, are discussed in the three following articles.

[885.] G. Rebhann: *Theorie der Holz- und Eisen-Constructionen mit besonderer Rücksicht auf das Bauwesen*. Wien, 1856. This is a text-book of technical elasticity and bridge-construction containing xiv + 602 pages. It was probably a serviceable students' work at the time it was written but it embraces nothing, I think, of permanent or historical importance.

[886.] H. Scheffler: *Theorie der Gewölbe, Futtermauern und eisernen Brücken*. Braunschweig, 1857 (454 pages and XVIII. plates). So far as this work deals with masonry structures it may be considered to lie entirely outside our field as it does not appeal to any *elastic* principles, i.e. any relation between stress and strain. S. 375—454 deal with the *Theorie der eisernen Brücken*. They are, however, with a few exceptions, only of historical interest, and with a few cases of con-

tinuous beams. They present no particular grace of method and no originality of result, at least, so far as a cursory examination of this and a more thorough acquaintance with other writings of the same engineer allow me to judge.

[887] Fr Laissle and Ad Schubler *Der Bau der Bruckenträger mit wissenschaftlicher Begründung der gegebenen Regeln und mit besonderer Rücksicht auf die neuesten Ausführungen* Stuttgart, 1857

I have been unable to find a copy of a second edition of this work, but there appears to have been an edition or issue of a somewhat similar work by these authors published in 1869 and 1870, of which I have seen a French translation entitled *Calcul et Construction des ponts métalliques*, Bruxelles, (1871?). The later work is very much more extensive than that of 1857, involving about 600 pages in two volumes with numerous plates, while the former has only 156 pages and four plates.

[888] The authors in their preface state that the ordinary theory of beams due to Navier has not proved itself incorrect but rather incomplete, and that their object is to supplement rather than replace it—*wir haben hiebei streng den Gang der Wissenschaft beibehalten*. They refer especially to the work of Schwedler (see our Arts 1004-5) as having been of special service to them. They also mention the works of Rebhann and Scheffler (see our Arts 885-6) as having appeared while their work was in course of preparation.

[889] There is little deserving of note in the present day in the book. The statement on S 7 is of course erroneous, the moment of the tractions in the longitudinal fibres of a beam about the neutral axis, as well as the total shear in a cross section, were certainly not first introduced by Schwedler in 1851, although he may have been the first to use the symbols $\Sigma(Xy)$ and $\Sigma(Y)$ for them. Not was Schwedler, I think, the first to show that the slope of the bending moment curve is the total shear $\left\{ \text{i e in symbols } \frac{d\Sigma(Xy)}{dx} = \Sigma(Y) \right\}$, or that points of zero total shear are points of maximum bending moment, but our authors seem to think so on S 9.

The discussions on shearing stress and the resolution of stresses on S 18-25 are all old work, and the former only a rough approximation at best. The treatment of the buckling load of struts on S 25-7 follows Schwarz's work and is as obscure as the original see our Art 956. The general discussions on simple and continuous beams, and on plate and lattice girders are reproductions of the results published in various articles in the *Civilingenieur*, *Erbbaus Zeitschrift* and the journals of the German and the Austrian *Ingenieur Vereine* to which we have drawn elsewhere sufficient attention. The book denotes progress in Germany in the theory of bridges but it is in no way superior

to the works of Bresse, Morin or Love, published about the same time in France. It was favourably reviewed by Grashof in the *Zeitschrift des Vereins deutscher Ingenieure*, 1858, S. 312–21.

[890.] L. Molinos and C. Pronnier: *Traité théorique et pratique de la construction des ponts métalliques*, Paris, 1857. The text is in quarto and contains viii + 340 pages; there is also an atlas of plates in folio. This is an extremely well got-up work dealing with the practical side of bridge-structure. The early chapters, containing experimental details and theoretical investigations of flexure and bending moment in simple and continuous beams, are chiefly based on the researches of Hodgkinson, Fairbairn, the Iron-Commission, Clapeyron and Belanger. The practical labours of Stephenson, Brunel and Cowper, as well as the numerous English and French researches on riveting receive ample attention. Indeed the book presents the best historical picture of the state of bridge construction in 1857, both from the mechanical and theoretical sides, that I have come across. A number of cases of continuous beams will be found worked out with practical applications on pp. 253–78, and the comparative criticism of the various types of metal bridges with which the work closes might possibly be still of service. The book is certainly pleasant reading after the laboriously written and poorly printed treatises to which we have referred in the immediately preceding articles.

[891.] *The Useful Metals and their Alloys: Orr's Circle of the Industrial Arts*, London, 1857. This book is the joint production of J. Scoffern, W. Fairbairn, W. Truran and others. Chapters XII.–XXIII. deal with iron and steel and structures made from them, and present a fairly complete picture of the current knowledge with regard to them at that time. We may note a few points of the work:

(a) Chapter XII. entitled: *The strength and other properties of Cast Iron* (pp. 210–19) gives details of the various influences which alter the tenacity of cast-iron. Thus the tenacities of cast-iron prepared with cold and hot blast respectively are nearly as 1 : .8; remeltings increasing the density will increase the tensile strength 2 to 3 times; maintaining the iron in fusion, which has much the same influence, will also nearly double the tensile strength (p. 215); casting 'under a head,' rapidity of cooling, etc. which increase the density, produce increase of strength.

(b) Chapter XIII. (pp. 220–251) and Chapter XIV. (pp. 252–69) giving accounts of the preparation of wrought-iron and of 'Recently patented refining processes' (notably the Bessemer, 1856) can be still read with interest, especially by those who wish to understand how it is possible for the processes of working to produce such totally different physical characteristics as occur in the various types of iron.

(c) Chapter XV. is entitled: *Metals which alloy with iron* (pp.

270—309), it is devoted rather to their chemical constitution than to their elastic properties

(d) Chapter XVI is entitled *On wrought iron in large masses* (pp 310—33), and is principally occupied with the effect of various methods of working on the tenacity and ductility of wrought-iron intended for ordnance see our Arts 879 (f), and 1065—7 Chapter XIX deals with the subject of cast-iron for ordnance (pp 385—397)

(e) Chapters XVII (*Steel manufacture*) and XVIII (*Application of steel*), pp 334—84, discuss the processes of making steel (including the then recently introduced patent processes of Heath, Bessemer, Uchatius, etc) and especially treat of the varying physical characteristics due to difference of chemical constitution or to working

(f) Chapters XXI—XXIII deal with the application of cast- and wrought-iron to various types of structures Pp 410—33 form a practical treatise on the strength of various types of beams, pp 433—41 deal with iron floors and roofs with considerable detail as to strength and cost, pp 442—66 treat of girders and bridges for railways, etc with a *résumé* of the experiments of Fairbairn, Hodgkinson and others on tubular bridges as well as details of strength, pp 467—78 are occupied with the application of iron to shipbuilding, and give a *résumé* of Fairbairn's experiments on rivets and plates

It will be seen from this brief account of the contents that the book is calculated to give the reader a very fair knowledge of the condition of applied elasticity in 1857 Novelty in results is of course not to be expected in a work of this kind

[892] A work by E Roffiaen entitled *Traité théorique et pratique sur la résistance des matériaux*, 1858, might possibly contain some contribution to our subject from the technical side, but I have been unable to find a copy see however our Art 925

[893] J B Belanger *Théorie de la Résistance et de la Flexion plane des Solides* PARIS, 1858 The first edition of this book, a reprint of lectures at the *École centrale des Arts*, contains 104 pages The second issued in 1862 and somewhat augmented and modified contains xii + 148 pages My references will be to the pages of the second edition as the more accessible

Chapters I and II of the book deal with pure traction and torsion, the latter by the old erroneous theory, and offer nothing of note Chapters III to VI are occupied with the discussion of flexure on the Bernoulli-Eulerian hypothesis In the last of these Chapters various cases of continuous beams are worked out with some detail, and on p 67 Clapeyron's Theorem of the three moments is given for the case of uniform loading, the two spans having unequal flexural rigidity and the

supports not being on the same level. In the notation of our Art. 607 the theorem then takes the form

$$4 \frac{l_1}{\epsilon_1} M_1 + 8 \left(\frac{l_1}{\epsilon_1} + \frac{l_2}{\epsilon_2} \right) M_2 + 4 \frac{l_2}{\epsilon_2} M_3 = \frac{p_1 l_1^3}{\epsilon_1} + \frac{p_2 l_2^3}{\epsilon_2} - 24 \left(\frac{y_1 - y_2}{l_1} + \frac{y_2 - y_3}{l_2} \right),$$

where $\epsilon_1 = E_1 \omega_1 \kappa_1^2$ and $\epsilon_2 = E_2 \omega_2 \kappa_2^2$ are the flexural rigidities and y_1, y_2, y_3 the heights of the three points of support corresponding to the two spans.

Both simple and continuous beams are dealt with analytically, and their treatment presents no novelty of method. Very simple geometrical proofs based on Mohr's theorem might be given for most of the results stated in these pages.

Chapter VII. modifies the previously given theory of flexure by introducing Jouravski's treatment of slide (see our Art. 183 (a)). Chapter VIII. deals on the old lines with solids of equal resistance and Chapter IX. discusses struts without throwing any new light on that difficult subject. Chapter X. treats some simple cases of beams braced by tie-rods; Chapter XI. contains a very insufficient treatment of arched ribs, while the last Chapter XII. after an elementary treatment of the problem of the indefinitely thin right cylindrical shell, practically reproduces Bresse's treatment of a slightly elliptic flue: see our Art. 537.

It is somewhat remarkable that a book certainly not standing at the level of then existing knowledge should have reached a second edition; still more noteworthy that reference to it should be met with at the present day.

[894.] G. H. Love: *Des diverses Résistances et autres Propriétés de la Fonte, du Fer et de l'Acier et de l'emploi de ces métaux dans les constructions*, Paris, 1859. This work contains xxxi + 357 pages. It contributed largely in its day to a knowledge of the physical properties of cast-iron and steel, and forms the opposite pole in technical literature to Morin's book published in 1853. Morin attempted to show that the Bernoulli-Eulerian theory suffices in practical elasticity, Love tried to discredit it altogether. The mean of these views is probably nearer the truth; there are many phenomena of great practical importance, which cannot be explained by existing mathematical theories, while on the other hand these theories *used with proper limitations* are capable of being made of great service in directions not hitherto considered. To those who wish to ascertain the exact results of the technical experiments conducted in the preceding decade, Love's book will

[895] After a copious *Table des Matieres* (pp v-xxiii), the book opens with an *Introduction* (pp xxv-xxxi) in which the author refers to a first publication of his work in 1852¹, and explains why at that time he depended upon English experiments for so much of his data. In the present volume he takes due account of recent French work. He pays, however, a high compliment to Hodgkinson on pp xxvi-xxvii.

Aussi longtemps que l'emploi du fer fut restreint aux anciens usages, ou que l'industrie n'éprouva qu'un mouvement graduel et modéré, personne ne songea à constater l'insuffisance des anciennes données pratiques et à vérifier le plus ou moins d'exactitude des formules fournies par la Théorie. Mais à peine l'industrie des chemins de fer prenait-elle naissance en donnant une grande extension à l'emploi de la fonte, que M. Hodgkinson commença ses essais sur cet utile métal. Experimentateur consciencieux, il rejeta toute idée préconçue, comme celle de la *limite d'élasticité*, de nature à limiter le cadre de ses expériences, et, par suite, à donner des notions incomplètes ou inexactes sur les propriétés de la fonte. Il pensa, sans doute, dans sa probité scientifique, qu'il n'avait pas le droit de présenter des expériences tronquées comme celles que nous avaient léguées la plupart de ses prédécesseurs, pour venir en aide à la Théorie. Son but, plus sage, plus utile, était de faire connaître les propriétés du métal aussi complètement que possible, ce à quoi il ne pouvait arriver évidemment qu'en poussant, dans tous les cas, ses essais jusqu'à la rupture, au lieu de les arrêter, comme les autres expérimentateurs, en des points variant avec l'imagination ou la fantaisie particulière de chacun. Le résultat le plus saillant de ces essais faits sur une très grande échelle et jusques en ces derniers temps, fut un démenti donné à la *limite de l'élasticité*. M. Hodgkinson démontra, en effet, qu'il n'existait, pour la fonte, aucun point fixe où l'élasticité commençait à s'altérer, que cette altération se produisait sous les plus petites charges, pour le fer comme pour la fonte.

This paragraph expresses concisely Love's view and the nature of his attack on the theorists. If there be no limit of elasticity, there can be no truth in the ordinary theory, he argues, and thus elasticity becomes a purely empirical science.

[896] *Livre Premier* of the work is entitled *Du fer, de la fonte, et de l'acier soumis à des efforts de traction*, and its first chapter is devoted to the extension of these metals (pp 1-67). In this chapter (pp 2-3) Love states the general conclusions of the old theory, perhaps

¹ I suppose this to refer to the memoir *Résistance du fer et de la fonte basée principalement sur les recherches expérimentales les plus récentes faites en Angleterre* or possibly to a reprint of it. It was published in the *Mémoires de la Société des Ingénieurs civils*, Année 1851 pp 163-272. Paris, 1851.

a little too unfavourably, and then formulates the following propositions in opposition to them, propositions which give the key-note to his book (pp. 3-5) :

(i) La proportionnalité entre l'allongement et la charge n'existe pas *pour la fonte* d'une manière absolue, et pour *le fer doux* cette loi ne peut s'affirmer en général que pour les charges comprises entre zéro et la moitié de celle qui produirait la rupture instantanée.

Does Love here mean (a) that cast-iron cannot be reduced to a state of ease, or (b) that if it can be, there is not direct proportionality of stress and strain? Would a cast-iron tuning fork give no note?

(ii) Un allongement permanent se manifeste sous les plus petites charges, et le point où les allongements croissent beaucoup plus vite que ces charges est très variable, même dans les fers de même provenance. Par conséquent la limite d'élasticité, en tant qu'elle existe, n'a pas le caractère défini qu'on lui a attribué, et perd forcément toute importance aux yeux du praticien.

The state of ease would here again be an important factor.

(iii) Sous la même charge la fonte s'allonge beaucoup plus que le fer.

This is stated because certain engineers had held the reverse to be true¹; Love's statement would certainly follow for the state of ease from the greater value of the stretch-modulus of wrought-iron.

(iv) Les écarts considérables de résistance observés sur les échantillons de fer ou de fonte de même calibre, mais de provenances diverses, ne permettent en aucune façon de compter sur une *moyenne de résistance*. Il en résulte que lorsqu'on ne connaît pas la résistance particulière du métal dont on dispose, la prudence conseille d'adopter le taux minimum de résistance fourni par l'observation.

This is only an argument in favour of establishing testing laboratories independent of the manufacturers, possibly as government institutions.

(v) Le fer et la fonte, soustraits aux chocs ou aux vibrations, supportent indéfiniment les charges les plus voisines de celles capables de produire la *rupture instantanée*.

That this is highly questionable follows from the experiments of Wöhler and others: see our Arts. 991, 992 and 997, etc. Most ordnance makers and users would certainly be glad if it were true!

(vi) Les formules tirées de la théorie en vigueur ne peuvent être appliquées avec quelque sécurité qu'après avoir subi des transformations importantes.

The legitimate application depends entirely on the limits within which the formulae are applied and on various modifications which may be made in the definitions of the quantities involved.

¹ Love writes: L'opinion contraire s'est généralement accréditée chez les praticiens (cf. p. 9). He does not, however, cite examples.

[897] The major part of this first chapter is occupied with details of the experiments of Hodgkinson (see our Arts. 969*, 1411*-12*, 1449*, etc), of Bornet (see our Art 817*), of Vicat (see our Arts 721*-36*), of Leblanc (see our Art 936*), and of the more recent French experimenters on steel, Gouin and Lavalley, Jackson, Petin and Gaudet, and Tenbrinck, whose results appear to be published in Love's work for the first time

Love adopts Hodgkinson's formula for cast-iron see our Art 1411* He admits a proportionality of stress and strain for a first stage of the elastic life of wrought-iron and steel, and he gives a formula for iron wire or cable (pp 61-3) which is based upon the fact that such a wire only becomes straight under a definite load, the wire or cable itself always being manufactured under an initial traction This practically consists in adding to the stretch modulus the constant traction under which the cable was manufactured (see, however, our Art 241) It seems to me that this traction would form an indefinitely small part of the stretch modulus (i.e 300 to 1158240 in the example on p 62) and might well be neglected The real point, I think, to be noted is that no stretch traction relation would hold till the applied traction reached the constant traction under which the cable had been manufactured

[898] Noting the discordance between various observers' results on extension Love remarks

que, dans l'état actuel des choses, ce que l'on possède sur l'allongement des métaux usuels laisse énormément à désirer et que des renseignements plus précis seront difficiles à obtenir Tandis, qu'au contraire, les faits de rupture présentent une constance sur laquelle on peut se reposer avec sécurité, qu'ils ne peuvent, dans leur interprétation, laisser de prise à l'invention ou à l'imagination comme les allongements Car il est évident que si deux expérimentateurs peuvent différer sur la question de savoir si, à un moment donné, une barre a atteint, sous une certaine charge, son degré définitif d'allongement, il est impossible qu'ils ne tombent pas d'accord immédiatement sur un fait aussi tranché, aussi brutal que celui de rupture D'ailleurs les expériences sur la rupture étant les plus simples et plus faciles, tout fait une loi de fixer cette phase de la résistance des solides, comme le point de départ, la seule base de toute formule pratique de résistance (pp 58-59)

To the last sentence we can only put a very large query, but the first sentences express a very real and oft neglected experimental difficulty

[899] Chapter II (pp 68-93) of Love's work is devoted to the absolute strength of cast iron The author commences by citing Lord gold's extraordinary statements on the absolute strength of cast iron (*Practical Essay on the Strength of Cast iron*, p 252, Edn 4) due to the 'paradox in the theory (see our Arts 999* and 178), and then proceeds to analyse the early experiments of Mmard and Desormes and of Hodgkinson (see our Arts 940*, 966* and 1408*) These are followed

by details of experiments on French cast-iron, in most cases here published for the first time. Love repudiates any mean value for the absolute strength of cast-iron (p. 74), and considers that it must be determined *de novo* for each particular sort.

[900.] Chapter III. (pp. 94–135) deals with various cast-iron structures, as tubes, cylinders, hydraulic presses etc., in which Love supposes the principal stress to be tractive. Love gives an interesting *résumé* of the various empirical formulæ for cast-iron pipes. He objects to such formulæ on the ground that they do not allow sufficient play for the variation in strength of the metal employed, but concludes by adding a new formula of his own. Let τ be the thickness in centimetres of the pipe, N the number of atmospheres of internal pressure, T the absolute strength in kilogs. per sq. centimetre, D the diameter in centimetres; then Love puts (p. 102):

$$\tau = \frac{6ND}{2T} + \cdot 7.$$

Morin in his *Résistance des matériaux* puts:

$$\tau = \cdot 85 + \cdot 00238ND.$$

It might seem that Love's formula must be better than Morin's which takes no account of possible differences in the value of T , but as Love determines his constant term ($\cdot 7$) for a particular kind of iron from the Fourchambault foundry the advantage is not so obvious. His formula gives far less thicknesses in all cases than any of the other formulæ then in use, and thus certainly does not err on the side of safety: see the Table of comparative results p. 103. The reason of this divergence is that Love takes for his formula a less factor of safety (about 6), and allows less ($\cdot 7$ instead of $\cdot 85$ or even 1) for the wear and tear of the surfaces of the pipe.

Pp. 113–7 of this section of the work are devoted to tubes as used for the foundations (piers) of bridges.

For the cylinders of steam-engines Love retains the above formula, increasing, however, the constant term $\cdot 7$ to 1.5 centimetres, as he considers there is greater wear. He compares results calculated from this formula with those given by other formulæ (pp. 117–20).

[901.] The remainder of the chapter is devoted to the discussion of hydraulic presses.

Love adopts again the same formula as for pipes, only, having regard to the thicknesses with which we have to deal in such cases, he now neglects the constant $\cdot 7$. He cites also formulæ of Barlow and Redtenbacher (pp. 121–2). It is strange that these formulæ, based on no theory whatever, should have retained their places in the text-books so long after Lamé's investigations (see our Arts. 1013* and 1038*). Love discusses at some length the hydraulic presses used for raising

the tubes of the Britannia Bridge (see our Art 1474*) and the dimensions and presumed strength of various other presses in practical use (pp 123-37)

[902] Chapter IV (pp 138-87) is entitled *Résistance finale à la rupture par traction du fer et de l'acier*. It cites the experiments on bars of iron of Rondelet, Duleau, Martin, Brunel, Tenbrinck, etc (see our Arts 696*, 226*, 817*), and gives in a fairly concise form their results as to absolute strength, final stretch, stricture, temperature of the section of rupture and the nature of the rupture-surface (pp 138-50). The experiments of Séguin, Leblanc and Dufoui on iron wire (see our Arts 984*, 936* and 692*) are then discussed (pp 150-9). Love shows that if the absolute strength be plotted up to the area of the cross section we obtain a curve with several maxima of strength, which maxima themselves appear to lie on a regular curve. Such a curve would probably depend very much on the preparation of the wire, and Love himself is compelled to conclude that the tenacity of each special make of wire ought to be independently determined (p 157).

He then turns to iron plate and cites the experiments of Navier (see our Art 275*), Clark and of Lavalley, those of the latter being here published for the first time. Finally we have a brief reference to Fairbairn's results (see our Art 1497*). Love considers that these only show that iron plate can be prepared by special processes to be equally strong in and across the direction of the rolling¹, but they do not invalidate the conclusion of other experimenters that the absolute strength and the ultimate extension are considerably less perpendicular than parallel to the 'fibres'. After some few pages on the absolute strength of various special kinds of iron Love discusses the resistance of steel to traction (pp 176-87). He publishes for the first time experimental results due to Tenbrinck and Lavalley. The discussion is solely of practical value and has special reference to the kind of steel produced at that date.

[903] Chapter V (pp 188-212) is entitled *De la résistance à la rupture par traction de la tôle assemblée par des rivets et accessoirement de la résistance des rivets au cisaillement*. Love cites the experiments made for the tubular bridges (see our Arts 1480*-2*) on the proportion of riveting strength due to shearing strength and friction respectively, and considers the amount of confirmation Clark's results receive from experiments made for MM Gouin et Cie. Both sets of experiments go to show that the additional strength due to the friction produced on the cooling of the rivet is from 1200 to 1300 kilog per sq centimetre of the section of the rivet (p 191). On the other hand while Clark found the absolute shearing strength of rivet iron only 2/3 the absolute tractive strength, Lavalley determined it at 3/4

¹ Il suffisait paraît-il de croiser les mises du paquet au lieu de les placer dans le même sens (p 171).

Love adopts Clark's value; if we suppose uniconstant linear elasticity to hold up to rupture we should have the ratio equal to $4/5$: see our Vol. i., p. 877. The remainder of the chapter forms an interesting practical discussion on the various modes of riveting and the resulting theoretical and experimental strengths.

[904.] Chapter VI. (pp. 213–338) is entitled: *Application du fer et de l'acier sous leurs diverses formes aux appareils et constructions usités dans l'industrie*. This chapter consists entirely of practical applications, and the small amount of theory applied is often of a rather dubious character (e.g. pp. 214, 217 etc.). The topics dealt with are: riveted boilers (pp. 213–25), water pipes of plate iron (pp. 225–32), water reservoirs of plate iron (pp. 232–42), iron chain-cables (invented by Captain Brown¹ and first used by him on board the *Penelope*, 1811), the best form of link for chains and the few details known of their strength (pp. 242–75), and lastly the cables of iron wire and bar-iron for suspension bridges with a lengthy discussion of the various applications of such bridges, the strength of their various parts, their advantages and dangers (pp. 275–338)².

[905.] The final chapter (pp. 339–57) of Love's work is entitled: *De certaines résistances du fer et de la fonte se rapprochant plus particulièrement de la résistance à la rupture par traction*. This is devoted to such subjects as the strength of screws under a traction which does not turn them (pp. 340–3), so that rupture is produced by shearing off the thread, on punching (pp. 343–5), on the resistance of iron and steel to torsion (pp. 345–51), and on the strength of railway axles and their journals (pp. 351–7). Several of these matters are treated with greater detail and more exact theory in other works of this period: see our Arts. 966–7, 1043, 1049, 957–9 and 988–1003.

The work concludes with an appendix giving sheets prepared with blank columns for various details on the local preparation and strength of the different kinds of metals: these were to be filled in by experimenters and returned to the author.

In conclusion we may remark that the book was distinctly the best practical treatise on the strength of iron and steel produced in the years 1850–60, and that even to the present day it may be consulted on some points with advantage.

[906.] W. Fairbairn: *Useful Information for Engineers*. The first edition of the *First Series* appeared in 1855 and a fifth edition of this series in 1874, the first edition of the *Second Series* in 1860,

¹ For the history of chain cables: see *Transactions of the Institution of Naval Architects*, Vol. i., pp. 160–70. London, 1860.

² The first suspension bridge was built in America by James Finley at Jacob's Creek in the year 1796; the first in Great Britain was due to Samuel Brown and crossed the Tweed at Berwick, being built in the year 1819; and the first in France was due to Séguin aîné and dates from 1821.

and a second edition in 1867, the first edition of the *Third Series* in 1866. Our references will be in each case to the pages of the last edition mentioned. The work consists of reprints of Fairbairn's original researches, and of more popular articles and lectures by him. It has played a considerable part in developing a more rational scientific education for engineers.

[907] In the *First Series*, *Lecture II* deals in a popular manner with the strength of boilers (pp 28-53) and *Lectures VI* (pp 127-153) and *VII* (pp 154-7) have further details of the strength of the materials used in boiler construction. *Lecture X* is a popular account of the strength of the material used in non ship building. In the *Appendix* is a reprint of Fairbairn's Royal Society paper on the strength of wrought-iron plates see our Arts 1495*-1503*.

[908] The only other part of this *Series* which needs notice is the second portion of the *Appendix* entitled *Experimental Researches to determine the Strength of Locomotive Boilers, and the causes which lead to Explosion* (pp 321-40). This paper originally appeared in *The Civil Engineer and Architect's Journal*, Vol 17, 1854, pp 219-223. See also the *Mechanic's Magazine*, Vol 60, pp 393-5. A series of experiments was first made on the absolute strength of the fire box and exterior shell of a locomotive boiler (pp 325-8). This was followed by an attempt to find relations between the temperature of the steam, the time and the pressure in a boiler when the safety valve is screwed down and the fire kept going. It is shown that under these circumstances a boiler will burst in from about 20 to 40 minutes (pp 328-331). Fairbairn next deals with the strength of the flat surfaces or sides of a fire box and with the strength of the stays (pp 331-7). Two experiments were made in which two pair of parallel plates one of copper (5" thick) and the other of iron (375" thick) were stayed together with one stay to the 25" and one stay to the 16" respectively. Fairbairn says that the weakest part of the box was not in the copper but in the iron plates which gave way by stripping or tearing asunder the threads or screws in the part of the iron plate at the end of a stay. In the first experiment, however, the head of one of the stays was drawn through the copper plate. The pressures at which the fire boxes gave way were respectively 815 and 1625 lbs per square inch and thus immensely greater than what could be borne by any other part of the boiler. It is not easy to see theoretically why the strengths should be nearly as 1 : 2 in the two cases of one stay to the 25 and one stay to the 16 sq inches respectively.

The paper concludes with *Experiments to determine the Ultimate Strength of Iron and Copper Stays generally used in riveting the Flat Surfaces of Locomotive Boilers* (pp 338-40). Here iron and copper stays were screwed and riveted into iron and copper plates. Fairbairn concludes that

the iron stay and copper plate (not riveted) have little more than one-half the strength of those where both are of iron; that iron stays, screwed and riveted into iron plates, are to iron stays screwed and riveted into copper plates as 1000:856; and that copper stays, screwed and riveted into copper plates of the same dimensions, have only about one half the strength of those where both the stays and plates are of iron (p. 340).

Hence so far as regards strength iron is much superior to copper as a stay, but its inferior conducting powers and probably inferior durability have still to be taken into account.

[909.] In the *Second Series* we may note as popular lectures involving only elementary theorems in the strength of materials: *Lectures V. and VI.* (pp. 100–37) on the *Strength of Iron Ships*: see also *Transactions of the Institution of Naval Architects*, Vol. i., pp. 71–97, London, 1860. This is a subject on which Fairbairn had, as one of the earliest constructors of iron-vessels, a great right to be heard and these lectures are thus of considerable interest from the standpoint of the history of technical elasticity. *Lecture VII.* (pp. 138–56): *On Wrought Iron Tubular Cranes* with experiments on their deflection and set, and a theory of their strength by Tate, is also of interest: see our Art. 960. *Lecture VIII.* (pp. 157–73) returns to the old subject of boiler-strength, appealing, however, to the then recently published memoir on the strength of flues: see our Art. 980.

In the second part of this volume entitled: *Experimental Researches* we have reprints of the memoirs on cylindrical vessels of wrought-iron (see our Art. 980), on glass globes and cylinders (see our Arts. 853–6), on the tensile strength of wrought-iron at various temperatures (see our Art. 1115)¹, and on the resistance to compression of various kinds of stone (see our Art. 1182). On pp. 328–9 will be found some experiments on Irish Basalt or Whinstone to be added to the results of this memoir. The specimens of this stone “fractured by vertical fissures splitting up into thin prisms, wedge-shaped usually at one end.”

[910.] The *Third Series* contains the following papers dealing more or less closely with our subject: *Lecture VI.* (pp. 98–124) entitled: *Iron and its Appliances*, which returns again to the strength of boilers; a paper on the *Construction of Iron Roofs* (pp. 204–43), this gives details of the trusses of large iron roofs and the calculation of the stresses in their members; a paper *On the mechanical properties of the Atlantic Cable* (pp. 276–89), this is a reprint from the *Report of the British Association*, 1864, pp. 408–15, and gives details of the absolute strength, stretches and ultimate elongations of a great variety of cables as well as of their several parts, central core, covering wires and gutta percha sheath; finally a reprint (pp. 290–316) of Fairbairn’s Royal Society memoir of 1864 (*Phil. Trans.* pp. 311–25) on the effect of impact and repeated loading on wrought-iron girders. The experi-

¹ See also *The Artizan*, 1856, pp. 227–8, and *Dinglers Polytechnisches Journal*, Bd. 150. 1858. S. 105–8 and S. 288–95.

ments embraced in this paper had formed the subject of a communication to the British Association in 1860 (see our Art 1035) and various accounts of them had appeared in the technical journals¹ We defer our full analysis of the memoir and criticism of the methods of experiment until we come to deal with the technical memoirs of the decade 1860-70

[911] The titles of two other books by Fairbairn may be just noted here

(a) *On the Application of Cast and Wrought Iron to Building Purposes* London, 1854 The third edition has added to it a section on *Wrought Iron Bridges* A fourth edition appeared in 1870

(b) *Treatise on Iron Ship Building, its History and Progress, as comprised in a Series of Experimental Researches on the Laws of Strain, the Strengths, Forms and other Conditions of the Material, etc* London, 1865

[912] Another technical text-book, the contents and method of which are much like those of this decade is A Ritter's *Lehrbuch der technischen Mechanik* The first edition was published in 1865, and the third edition which I have used appeared at Hannover in 1874 The *Fünfter Abschnitt* entitled *Statik elastischer Körper* (S 479-563), and the *Sechster Abschnitt* (S 564-616) *Dynamik elastischer Körper*, belong to our subject The work in its third edition is still a fairly useful text-book for the engineering student The part on elasticity and the strength of materials contains one or two points, to which I may refer as interesting, and one or two grievous errors, against which the student should be warned

[913] Let us assume that it is legitimate to apply the Bernoulli-Eulerian theory of beams to a cantilever, which has a constant thickness (h) in the vertical plane of flexure, but in a horizontal plane perpendicular to the plane of flexure, is in the form of an isosceles triangle of base b and height l Then, if $1/\rho$ be the curvature at distance x from the free end of the cantilever under load P and $E\omega\kappa$ be the flexural rigidity, we have

$$\frac{E\omega\kappa}{\rho} - Fh \frac{2b}{l} \frac{h}{12\rho} = Pz,$$

$$\rho = \frac{Fh^2b}{12lP} \quad (1)$$

¹ E.g. *The Arts* in 1860 pp 219-21 and 1861 pp 228-31

Thus the cantilever has uniform curvature. Further if f be the terminal deflection, then f equals $l^3/(2\rho)$ very nearly, or

$$f = \frac{6l^3P}{Ebh^3} \dots\dots\dots(ii).$$

If S be the maximum traction to which the material ought to be subjected :


$$S = \frac{Eh}{2\rho} = \frac{6lP}{h^2b},$$

which gives for the minimum requisite breadth b at the built-in end :

$$b = \frac{6lP}{h^2S} \dots\dots\dots(iii).$$

Such formulae can at most be supposed to hold only when the triangular cantilever changes its cross-section very gradually, i.e. when b/l is very small.

Ritter now builds up a spring formed of several laminae by cutting



up the triangular cantilever and replacing the several parts as indicated in the accompanying figures. He thus gets the half of a laminated spring of the ordinary form, and one which has besides a very easy theory. He supposes the pointed end of each lamina to press on the lamina above with a force equal to P , the load at the end of the spring. The result is that the triangular part of each lamina supports as a cantilever a load P at its apex, which causes it to take the curvature given in (i), while the rectangular part of each lamina is acted upon by a couple $Pl/4$ which will also be found to give it the curvature determined by (i). Thus each lamina is bent in exactly the same way as if it were a part of the triangular cantilever discussed above, while the spring itself is a solid of equal resistance, whose deflection is given by (ii) and whose proper breadth can be determined by (iii). For this special case the result appears to agree with that of Phillips see Eqn (xxv) of our Art 496. Ritter does not, however, demonstrate clearly how and why the action of the apex of one lamina on the lamina above must equal P .

[914] On S 521-6, we have another added to the already numerous methods of calculating the maximum safe loading for a strut. Suppose the strut bent to a central deflection f , its ends being pivoted. Then if $\omega\kappa^2$ be as usual the moment of inertia of the cross section and h the diameter of the section in the plane of flexure, it is easy to see that the maximum compressive stress T due to a longitudinal load P is (see our Art 832*)

$$T = \frac{P}{\omega} \left(1 + \frac{fh}{2\kappa^2} \right)$$

Now, Ritter argues that f cannot be as great as it would be in the case of a circular flexure, when

$$f = l / (8\rho), \text{ nearly,}$$

if l be the length of the strut and $1/\rho$ its uniform curvature. But if δ be the stretch (or squeeze) due *solely to the bending* at the central section

$$\delta = h / (2\rho),$$

and thus the maximum of $fh = l\delta/4$, whence we find on this hypothesis

$$P = \frac{\omega T}{1 + \frac{\delta l}{8h}}$$

If T be the maximum safe compressive stress, this will give a minimum limit for the safe maximum load P , supposing the safety to be rendered doubtful by compression before extension. So far there is no ground for much criticism. But what is δ to be taken as? Ritter says it is to be put equal to *das Verhltniss, welches*
die mittlere Streckung des Querschnitts zum mittleren Querschnitt
der Stbte hat (S 521). That is, $\delta = \frac{1}{2} \frac{f}{h}$.

something greater than its real value which is solely due to the bending and therefore the tendency would be to err on the side of safety. Ritter would thus make $\delta = T/E$, where T is the maximum compressive stress, although he does not express himself in this manner. We thus obtain finally:

$$P < \frac{\omega T}{1 + \frac{1}{8} \frac{T^2}{E \kappa^2}} \dots\dots\dots (a).$$

This result agrees with that which I have obtained by a very different method in Eqn. (x). Art. 650, if it be remembered that C and p_0 of that article = T and $\pi^2 E \kappa^2 / l^2$ of this respectively.

Hence it seems extremely probable that (a) may be considered as a fairly efficient measure of the safe load for struts, although the process by which Ritter deduces it is extremely questionable.

The application on S. 528 to the case of an eccentric load upon a strut seems to me quite illegitimate.

[915.] (a) On S. 528–33 we have a wholly inadmissible theory of shear, which leads to the slide-modulus being always one-half of the stretch-modulus. This is applied to deduce an erroneous theory of torsion on S. 533–6.

(b) The following sections deal very fully with stresses in a great variety of roof trusses and bridge frames. These stresses are deduced by taking a section cutting three bars only, and by equating the moment of the stress in one bar about the intersection of the other two to the bending moment of the girder at the section. This valuable method, especially useful in testing graphical work, is now generally termed *Ritter's Method* (S. 537–55). The following pages (S. 555–63) deal with frame arches having a pin-joint, and therefore zero bending moment, at the crown. These important frames have been largely used in German engineering practice. For a still more complete discussion of the application of *Ritter's Method* to the stresses in various types of frames, we must refer the reader to his *Elementare Theorie und Berechnung eiserner Dach- und Brücken-Constructionen*, Hannover, 1862 (Second edition, 1873¹).

[916.] (a) In the *Sechster Abschnitt*, Ritter turns in the first place to problems of resilience. Thus he calculates in the usual elementary manner (S. 567) that the total longitudinal resilience of a bar = $\frac{1}{2}$ (volume) $\times T^2/E$, where T is the maximum traction allowable. But like most elementary writers he equates this result to the kinetic energy of the impulse-giving body, quite forgetting that it does not follow that such a body will communicate its kinetic energy to the whole bar uniformly and not expend it in producing strain in one part only. That it is not distributed *statically* in the case of either transverse

¹ An English translation by H. R. Senken appeared in 1870 (London: Spear).

or longitudinal impact is shown in our Arts 361-71 and 401-7, the same remark holds good for torsional impulse

(b) On S 567-8 there is a paragraph entitled *Einfluss Fehlstellen*, in which the author remarks

Es ergibt sich also das bemerkenswerthe Resultat dass die Widerstandsfähigkeit eines Körpers gegen mechanische Arbeit, oder gegen heftige Kräfte bewegter Massen, durch Verminderung der Materialmenge und durch Vergrössert werden kann

This paradox is easily accounted for by a flaw in Ritter's argument which it is surprising should have survived a third edition

(c) The erroneous theory of torsion and a consequently wrong expression for torsional resilience reappear on S 571-3 The theory of the torsional pendulum on S 573-5 is also incorrect

(d) *Capitel XXV* (S 575-608) involves little more than the usual theory of impact of particles and of uniplanar bodies The method by which the problem on S 589-91 is treated seems to be very doubtful indeed Ritter endeavours to ascertain what the velocity of a cylindrical shot must be in order that the shot may penetrate a non plate of a given thickness, and he obtains a solution by equating the kinetic energy of the shot to the product of the maximum transverse shearing resistance of the hole punched in the plate into the semi length of the shot It seems to me that a better result would have been obtained by equating the kinetic energy of the shot to the work done in punching, or to

$$\frac{S}{2\mu} \pi \pi d,$$

where S is the absolute shearing strength, d the diameter of the shot, τ the thickness of the plate and μ the slide modulus This of course supposes elasticity to hold up to rupture, which is an approximation for some sorts of steel only Ritter supposes the work done by total shear ($S\tau\pi d$) in flattening the shot to be the total shear into semi length of the shot, but I do not understand this, nor his method of deducing Equation (823)

(e) *Capitel XXVI* (S 608-16) deals in an elementary fashion but not always correctly, with the stresses produced in elastic bodies owing to the relative accelerations of their parts For example, a thin ring of radius a and uniform density ρ be rotating with speed ω about an axis perpendicular to its plane it is easy to show that maximum stress $= \rho(a\omega)^2$ (S 613), but when Ritter attempts to apply a similar theory to a rotating circular disc he goes hopelessly wrong for he assumes the stress uniform across the whole length of a drum There are other parts of this chapter which seem to me very doubtful

[917.] A third edition of Rühlmann's *Grundzüge der Mechanik* was published at Leipzig in 1860, but I have not examined this work, as the number of technical text-books is too great to be examined individually. So far as my experience goes they rarely contain any novelty in the domain of elasticity—beyond an occasional theoretical heresy.

GROUP B.

Memoirs dealing with the Application of the Theory of Elasticity to special Technical Problems.

[918.] F. Fink: *Versuche über die Tragfähigkeit gespannter und ungespannter Hölzer*. *Polytechnisches Centralblatt*, Jahrgang 1851, Cols. 1485–8, Leipzig. (Extracted from the *Gewerbeblatt f. d. Grossh. Hessen*, 1851, S. 237.) This paper does not appear to contain more than the statement of the fact that a wooden bar subjected to transverse load supports more when its ends are built-in than when they are simply supported. In the actual case the ends were not built-in but subjected to tractive load. Fink does not work out the theory of this case, but it obviously approximates roughly to built-in ends; the breaking loads were, however, in general *more than double* their values for simply supported ends.

[919.] A. Wöhler: *Notiz über die Berechnung der Durchbiegung elastischer Körper*. *Erbkams Zeitschrift für Bauwesen*, Jahrgang III., S. 433–6, Berlin, 1853. In this paper Wöhler enquires what the unstrained form of the central line of a cantilever must be in order that when it is loaded at its free end with a weight P the central line may become straight.

For a cantilever of uniform cross-section it seems to me we have the unstrained form of the central line given by :

$$y = \frac{P}{6E\omega\kappa^2} (x^3 - 3l^2x + 2l^3),$$

where y is measured vertically upwards from the strained position of the central line and the origin is at the free end.

If the section be not uniform, we have on the Bernoulli-Eulerian hypothesis an equation of the form

$$\frac{d^2y}{dx^2} = \frac{Px}{E\omega\kappa^2}$$

to integrate where $\omega\kappa^2$ is a function of x .

For 'beams of equal resistance' we must have

$$Px/(\omega\kappa^2) = T_0/z,$$

where T_0 is the uniform traction in the fibre at maximum distance z from the neutral axis. Hence

$$\frac{d^2y}{dx^2} = \frac{T_0}{E} \frac{1}{z},$$

or if $T_0/E = n$,

$$d^2y/dx^2 = n/z,$$

which we can integrate as soon as z is given. None of these results agree with Wohler's, who obtains differential equations of the first order only, and integrates them for a number of special cases, which the reader can easily construct for himself (e.g. $y^{m+1} = px^m$, etc.)

[920] C R Bornemann *Ueber relative Festigkeit Polytechnisches Centralblatt*, Jahrgang 1853, Cols 1297–1308 (Extracted from *Der Civilingenieur*, Bd 1, S 18). The author notes the discrepancies which occur in the text-book formulae for the strength of beams (in great part due to the 'paradox' see our Art 930), and proposes to use a stretch limit instead of a stress limit in the 'extreme fibre'. He is, I think, right in preferring a strain- to a stress limit, but otherwise the paper only contributes what must, I think, be regarded as empirical formulae for relative strength.

[921] C R Bornemann *Graphische Tabelle über die relative Festigkeit* *Der Civilingenieur*, Neue Folge, Bd 1, S 18–25 Freiberg, 1854.

Bornemann by means of logarithmic scales, or what Lalanne would term an *abaque* (see *Annales des ponts et chaussées*, T XI, 1846, pp 1–69), represents by a system of parallel straight lines the families of curves given by the formula

$$\text{Bending Moment} = T \times \frac{\omega\kappa^2}{h},$$

for the flexure of beams¹. Here T is the safe limit to tractive

¹ The idea of applying the method of logarithmic coordinates to the graphical representation of the strength of materials as well as the method itself is due to Lalanne. See his *Mémoire sur les tables graphiques et sur la géométrie analytique* *Annales des ponts et chaussées* T XI pp 1–69, 1846 also his book *Méthodes graphiques pour l'expression de lois empiriques ou mathématiques à trois variables* Paris 1878. Louvel gave abac diagrams for the resistance of iron bars in double T in the *Portefeuille des conducteurs des ponts et chaussées* 4 Série Nos 6 and 7. Phillips' formulae for springs (see our Arts 453–508) have been reduced to

stress, $\omega\kappa^2$ is the moment of inertia of the cross-section about the "neutral axis" and h is the distance of the "extreme fibre" from that axis. For example for a beam of rectangular cross-section ($b \times 2h$) we have

$$\text{Bending Moment} = \frac{2T}{3} \times b \times h^2.$$

There would thus be three entries into the graphic table, i.e. bending moment, breadth and height of beam, supposing T a definite constant. Bornemann after some rather lengthy discussion chooses values of the constant T for wrought-iron, cast-iron and wood, and his table contains the system of lines for rectangular beams, with some few lines at a different slope for beams of circular, hollow circular, square and **I** sections. The method is of real worth for considering the relative strength of beams of diverse cross-sections. But I think Bornemann's example of the method is of small value, since T varies greatly with the different kinds of iron and wood and further varies with the shape of the cross-section. The first entry ought not to be M the bending moment, but M/T , in which case the same set of lines answer for all materials. The method has been further discussed by Vogler: *Anleitung zum Entwerfen graphischer Tafeln*, S. 37, Berlin, 1877. I have for some time used a table constructed like Bornemann's, but with M/T as the variable, for calculating beams with either a uniform load or an isolated central load. The body of Bornemann's paper is taken up by details as to the best practical values for the constants in formulae for absolute and relative strength, and to this part of it we have briefly referred in the preceding article.

[922.] O. Ortmann: *Zur Theorie der Widerstandsfähigkeit der Baumaterialien*. *Försters Allgemeine Bauzeitung*, Jahrgang xx., S. 243-62. Wien, 1855.

Ortmann in the Jahrgang VIII. (1843) of this journal (S. 408-40, under the title *Theorie des Widerstandes fester elastischer Körper*) had

graphical *abac* representation by Lévy-Lambert in the *Annales des ponts et chaussées*, T. xx., 1880, 2^e Semestre, pp. 59-65, while Chéry has given similar diagrams for the strength of beams of wood, iron, etc. of the principal forms in use in the *Pratique de la résistance des matériaux dans les constructions*, Paris, 1877, p. 16, Plates 7 to 24. An interesting discussion of the method is given by P. Terrier in his French translation of Favaro's *Calcul graphique*, Paris, 1885, pp. 208-224, with very copious references. See also Lalanne's *Description et usage de l'abaque*, Paris, 1845 and 1851, English translation, London, 1846.

drawn attention to the fact that in many cases of flexure there is a normal thrust on the cross sections of a beam and therefore that in such cases the 'neutral axis' does not pass through the centroids of the cross sections. He says in the later memoir that Morin and Rebhann (see our Arts 876 and 885) have neglected this fact¹. There does not, however, seem any real novelty in Ortmann's own investigations. He attempts to take into account the effect of impulsive stress, but certainly does not get further than, if as far as, Poncelet had done many years previously (see our Art. 988*). Some of the results obtained seem also very questionable both in hypothesis and in method of analysis, and the paper does not seem to require from us more than a note of caution.

[923] With *Ueber den Widerstand der Baumaterialien Organ für die Fortschritte des Eisenbahnwesens*, Bd 8, S 200. Wiesbaden, 1853. This paper contains a general résumé of the theory of the strength of materials combined with a statement of supposed experimental facts. It appears to be based chiefly on Morin's work see our Art 876, and contains assertions with regard to the proportionality of stretch and traction in cast-iron which are certainly incorrect. It has no present value.

[924] A long paper *Ueber zusammengesetzte Festigkeit* was read by Grashof to the *Berliner Bezirksverein* of German engineers on March 7, 1858. It is printed *in extenso* on S 183–225 of the *Zeitschrift des Vereins deutscher Ingenieure*, Jahrgang III, 1859. It follows very much the lines of Weisbach (see our Art 1377*) and contains nothing of intrinsic importance. We shall refer to Grashof's methods later when dealing with his well known treatise on elasticity.

[925] F. Roffiaen *Widerstandsfähigkeit der Baumaterialien Praktische Beispiele für die Stärkebestimmungen der verschiedenen Verbandstücke der Holz- und Eisenkonstruktionen nebst Bemerkungen über Bauten, die aus diesen Materialien ausgeführt sind Forsters Allgemeine Bauzeitung*, Jahrgang XXIV, S 257–320. Wien, 1859. I presume this is a translation of the work referred to in my Art 892, but which was inaccessible to me in the original French. There is, however, no statement that it is a translation.

The first part applies the ordinary theory of elasticity to frames built-up of straight wooden beams, the second to curved wooden arches. In both cases the author appeals to Aidant, see the *Addenda* to our Vol I, pp 4–10. The third part deals with non structures, giving numerical examples for cases of wrought, cast and plate non guides,

¹ This is hardly correct see p 101 of the first edition (1853) of Morin's work.

and later the author passes to structures combining wood and iron (S. 301-4). There does not seem to me any special novelty in these portions of the work, nor any special permanent technical value in the numerical examples worked out. In an *Anhang* (S. 304-20) the author develops a new theory of flexure and applies it to several examples. This theory as detailed on S. 304-5 is very obscure, but it seems to amount to taking the stretch- and squeeze-moduli different, and on this supposition calculating the position of the 'neutral axis' which no longer pass through the centroid of the cross-section. The ultimate resistances to tension and compression are also taken to be in the ratio of these moduli. The application by Roffiaen, however, of the theory seems perfectly arbitrary. Thus his (v) and (xi) S. 305 are quite erroneous, and I do not grasp the meaning of (vi) S. 304, nor its application in paragraph 2 of S. 306. Indeed, what is new in the investigation seems to me wrong. The hypothesis itself is at least as old as 1822: see our Arts. 234*-40*.

[926.] Klose: *Ueber die Festigkeit und die zweckmässigste Form eiserner Träger, Hannoverische Bauzeitung (Architekten- u. Ingenieur-Verein)*, Hannover, 1854, S. 523.

The author at rather needless length of analysis based on Navier's theory of ribs (see our Art. 257*), shows that a cantilever in the form of a circular arc if loaded at the free end perpendicular to the tangent at the built-in end is no stronger than a straight cantilever of the same cross-section and of length equal to half the chord of double the arc of the circular cantilever. This result is only true when the radius of the cantilever is great as compared with the linear dimensions of the cross-section (see our Arts. 519 and 621). Klose tested this theoretical result for four rods six feet long and with cross-sections squares of one inch, supported at their ends and centrally loaded. The details of the experiments show a remarkable agreement between the deflections of the rods for the same weights whether they were of straight or circular central line and this agreement lasted up to rupture, which also occurred at the same load for both types. The circular rib therefore has no advantage as a cantilever over the straight beam, and further has the disadvantage of considerable lateral yielding, the values of which are tabulated in the experiments.

[927.] The second part of the paper deals with the comparative strength of cast-iron beams of two special cross-sections. The first is a **T** in which the web is trapezoidal, and the second a **I** akin to Hodgkinson's strongest section (see our Art 244*). The beams were 14' between the points of support, but not, as I think they ought to have been, of the same height, the former being 8½" and the latter 10"; the areas of the cross-sections were practically equal. Klose found the **I** much the stronger section. But it is remarkable that he found the theoretical value of the stress in the 'extreme fibre' at rupture

was the same for both cross sections. He does not state whether this stress was also equal to the absolute tensile strength of his cast-iron. He applies without hesitation the Bernoulli Eulerian theory of flexure to find the conditions of rupture.

[928] A. Junge *Ueber die Tragkraft gesprengter Balken* *Polytechnisches Centralblatt*, 1855, Cols 844–54 (Extracted from *Der Civilingenieur*, Neue Folge, Bd 2, S 79 Freiberg, 1855)

Der gesprengte Balken besteht aus zwei über einander liegenden Theilen, welche an ihren Enden fest verbunden sind, übrigens aber durch dazwischen gestellte Spreizen auseinander gehalten werden (Col 844)

The present paper investigates whether such a girder, which has initial strain, is theoretically stronger than one in which the two booms are united so as to form a simple girder. Junge supposes the two booms exactly equal. He shows by means of tables for wood and wrought-iron that the limits within which the split beam is stronger are rather narrow.

Die Gefahr die günstigste Spannung zu überschreiten liegt also sehr nahe (Col 854)

Several such girders had had to be removed after a short period of use, and they appear now to have gone out of fashion. They were introduced by Laves of Hannover in a work entitled *Ueber die Anwendung und den Nutzen eines neuen Construction Systems nebst erläuternder Beschreibung desselben*, 1839.

I have not verified Junge's analysis, he assumes that the curvature of the initially strained booms is circular (Col 851)

[929] Baumgarten *Note sur la valeur du coefficient d'élasticité de la fonte à l'appui du rapport de M. M. Collet-Meygret et Desplaces sur le viaduc de Tarascon* *Annales des ponts et chaussées*, 1^{er} Semestre, 1855, pp 225–233 Paris, 1855. This paper gives some results on the flexure of beams of considerable size, the cross sections being T and I, the beams had a varying cross section from middle to end, and might be conceived of as parabolic or as 'solids of equal resistance'. Baumgarten supposes a beam of length $2l$ divided into $2m$ parts of equal length, and the cross section in each of these parts to be uniform for the part, then he gives the following formula for the deflection f under a central load $2P$

$$f = \frac{1}{3Em} \left\{ \frac{3(m-1)m+1}{\omega_1 \kappa_1} + \frac{3(m-2)(m-1)+1}{\omega \kappa} + \frac{3(m-3)(m-2)+1}{\omega \kappa} \right. \\ \left. + \frac{3(m-n)(m-n+1)+1}{\omega_n \kappa_n} + \frac{3(n-2)+1}{\omega_{m-1} \kappa_{m-1}} + \frac{1}{\omega \kappa} \right\},$$

where $\omega_n \kappa_n^2$ is the moment of inertia of the cross-section of the n th part about its central axis.

By means of this formula he finds different values of E for the two pieces on which he has experimented, and both values differ largely from that usually adopted for cast-iron.

An attempt to explain the 'beam paradox' (pp. 231-3), with which Baumgarten concludes his memoir, falls into the old fallacy of supposing the proportionality of stress and strain to last up to rupture: see our Arts. 173, 507, 930-8 and 1053.

[930.] William Henry Barlow. *On the existence of an element of Strength in Beams subjected to Transverse Strain, arising from the Lateral Action of the fibres or particles on each other, and named by the author the "Resistance of Flexure."* *Phil. Trans.* 1855, pp. 225-242. This paper was received on February 23 and read March 29, 1855.

It deals with the "old beam paradox:" see our Arts 173, 507 and 542. Barlow expresses it thus: "the strength of a bar of cast iron subjected to transverse strain cannot be reconciled with the results obtained from experiments on direct tension, if the neutral axis is in the centre of the bar" (p. 225). By a series of experiments (pp. 225-8) Barlow shows (as many previous experimenters: see our Arts. 998*, 1463*(e) and 876) that the neutral line within the limits of experimental error coincides with the central line. He then endeavours to explain by 'lateral adhesion,' i.e. shearing stress, the increased absolute strength. We must here note one or two points: (i) the formula adopted by Barlow from the Bernoulli-Eulerian theory of beams supposes the material to remain elastic up to rupture,—this is certainly not true; (ii) it assumes the elasticity also linear, this again is hardly true for cast-iron; (iii) even if with Saint-Venant we introduce the proper slide terms into the formula they would make no sensible difference except for very short beams; (iv) to account for the 'paradox' we must suppose stress-strain relations other than linear to hold in the neighbourhood of rupture, i.e. such relations as those suggested in our Arts. 1411* and 178. It is to such relations, giving us results *depending not only on the moment of inertia of the cross-section, but more generally on its shape*, that we must look for light on the so-called 'paradox.'

Barlow gives (p. 231) an empirical formula for the breaking strength of 'doubly ribbed open beams'. The cross-sections were

not of sufficient variety to give any evidence that the quantity he terms 'resistance to flexure' is really independent of the shape of the cross-section

[931] W H Barlow *On an Element of Strength in Beams subjected to Transverse Strain, named by the author "The Resistance of Flexure" Second Paper Phil Trans, 1857, pp 463-88* This paper was received March 12 and read March 26, 1857 It is a continuation of the subject dealt with in the memoir referred to in the preceding article

Let T be the breaking tensile stress, W the breaking load, $E\omega\kappa^2$ the flexural rigidity of the beam, h the distance from the neutral axis, of the 'fibre' furthest removed, l the length of the beam, and $1/\rho$ the curvature at the mid-point The beam is supposed weightless, doubly supported and centrally loaded Then we have, assuming the correctness of the Bernoulli-Eulerian theory up to rupture

$$T = Eh/\rho, \quad E\omega\kappa^2/\rho = \frac{1}{4}Wl,$$

$$\text{or} \quad W = 4T\omega\kappa^2/hl \quad (1)$$

Now in his first memoir Barlow assumes that T consists of two parts, the first T_1 due to tensile strength and the second T_2 to what he terms 'resistance to flexure'—produced by 'lateral adhesion' The former part he holds to be constant, the latter to vary when the beam is hollow as the 'depth of metal into the deflection' This value of T_2 seems curious, but as an empirical expression we may perhaps allow it to stand, however little it may have to do with 'lateral adhesion'

[932] In the second memoir, however, Barlow goes much further, he expresses his traction \hat{z} at distance z from the neutral axis by the formula (p 472)

$$\hat{z} = \frac{Ex}{\rho} + T = \frac{T_1 z}{h} + T \quad (11)$$

He then proceeds to take the moment of these tractions at the middle of the beam round the neutral axis, and equates them to the bending moment, or we have

$$\frac{T_1 \omega \kappa}{h} + T \omega \bar{z} = \frac{1}{4}Wl$$

At first sight it would appear that the second term ought to vanish, but Barlow evidently intends that T shall change sign on crossing the

neutral axis so that if ω_1, ω_2 be the areas of cross-section above and below the neutral axis and \bar{x}_1, \bar{x}_2 the *numerical* distances of their centroids from this axis we have:

$$T_1 \frac{\omega \kappa^2}{h} + T_2 (\omega_1 \bar{x}_1 + \omega_2 \bar{x}_2) = \frac{1}{4} WL \dots \dots \dots (iii),$$

or for a section symmetrical about the neutral axis:

$$T_1 \frac{\omega \kappa^2}{h} + T_2 \omega \bar{x}_1 = \frac{1}{4} WL.$$

For a rectangle ($2b \times 2a$), $(\frac{1}{3}T_1 + \frac{1}{2}T_2) 4ab^2 = \frac{1}{4} WL,$

for a circle (b) $(\frac{\pi}{4} T_1 + \frac{4}{3} T_2) b^3 = \frac{1}{4} WL.$

From these and similar results Barlow seeks to find the values of T_1 and T_2 and to ascertain whether they are constant.

[933.] We must now inquire whether there is any ground for the formula (ii).

Since the total longitudinal load is zero, we must have:

$$\frac{T_1 \omega \bar{x}}{h} + T_2 (\omega_1 - \omega_2) = 0.$$

Hence we see that unless $\omega_1 = \omega_2$ the neutral line will not coincide with the central line. W. H. Barlow himself has only dealt with symmetrical sections, but Peter Barlow in an appendix to the paper, pp. 483–8, treats of the non-coincidence of the neutral and central lines in the case of **I** sections. There is no experimental investigation of whether this non-coincidence, a clear result of the theory used, is real or not.

Barlow (p. 472) defines T_2 as “the resistance of flexure acting as a force evenly spread over the surface of the section.” He has previously, by a reasoning which I fail to follow, deduced that this ‘resistance of flexure’ is due to lateral cohesion (p. 472). Now whatever be the experimental value of a formula such as (ii) I think we may safely say: (a) that the quantity T_2 can have nothing whatever to do with shearing strength, (b) that the formula gives a discontinuous change of tractive stress at the neutral line, i.e. suddenly from T_2 to $-T_2$, (c) that the constancy of the value T_2 as a term in the traction, all over the surface and whether the traction is negative or positive, is exceedingly improbable.

[934.] But we may still inquire whether there may not be an approximation to the truth in Barlow’s formula. The first term $T_1 x / \rho$ might be a portion of the traction due to elasticity, the second T_2 , a constant, a portion due to plasticity. Now before rupture it does not seem improbable that a part of the beam may be plastic and

another elastic, although it is perhaps hardly likely that these two stages occur at the same time in all fibres. The outer fibres will be enervated and then tractions more nearly constant, the inner especially in the neighbourhood of the neutral axis will still remain elastic. Thus as a *mean result for the whole cross section* Barlow's expression for the traction does not appear so unreasonable as when we associate it, as its author has done, with any idea of 'lateral cohesion'.

[935] The chief value of the memoir however lies in the tabulation of the results of experiments on the absolute strength of beams of diverse section under flexure. We reproduce some of these results as they cannot fail to be of value to any one investigating a theory of rupture by flexure. So far as the cast-iron beams are concerned, it may be questioned whether an allowance ought not to be made for the 'defect in Hooke's law,' even if we use Barlow's plastico elastic formula. This allowance will probably account for most of the difference see our Art 1053

[936] Cast Iron Beams (Barlow's 'open girders' are omitted)

Form	l in inches	ω in sq inches	Dimensions of cross section etc in inches	T from formula (i) in lbs	T from formula (iii) in lbs	T_1 in lbs
Rectangle	60	2	2×1 height, 2	41,709	15,654	17,971
Square	60	1	side vertical	45,630	17,892	19,399
Square	60	1	diagonal vertical	53,966	17,523	19,213
Circle	60	1	—	51,396	19,158	20,236
I Section	48	2.60	{equal flanges} 2×5 and web 1×5 about	37,508	—	20,942
H Section	48	2.59	{equal flanges} 2×51 and web 98×51 about	43,358	—	18,460
Square	60	4	large 2×2	39,094	—	16,644
Circle	60	5	large $2\frac{1}{2}$ diam	39,560	—	15,902
Circle	60	3.79	large $2\frac{1}{4}$ diam	44,957	—	17,778
Square	60	4	{large diagonal} vertical	47,746	—	16,878

These numbers bring out sufficiently the following points

(1) That T [as calculated from formula (i)] varies with the form of the section. Had we included the 'open girders,' we should have seen that its value varies from 25,000 to 54,000 lbs about. The average tensile strength of the metal is however only 18,750 lbs.

(ii) The values of T_2 and T_1 are by no means constant, but the values of T_1 are much more nearly that of the tensile strength of the material.

(iii) The large bars are relatively weaker than the small: see our Arts. 952*, 1484* and 169 (e) and (f). Barlow takes as mean values:

$$T_2 = 16,573 \text{ lbs. and } T_2/T_1 = .847.$$

The mean value of T_2 is computed from those given in the above table and from the mean results of six series of experiments on 'open girders'.

[937.] Barlow then proceeds to investigate how far other experiments give confirmatory results. He considers:

(a) Hodgkinson's Experiments: *Iron Commissioners' Report*. (See our Art. 1413*.)

Mean ratio of T_2 to $T_1 = .853$. This *average* compares well with Barlow's .847, but the values of T_2/T_1 range from .516 to 1.185, or the ratio must be held to vary with each quality of metal. No information as to variety of cross-section is given.

(b) Wade's Experiments. *American Report on Canon Metal*. (See our Art. 1043.)

Here the cross-sections of the cast-iron bars were square and circular, and the breaking load under flexure and the tensile strength are given. From the former Barlow calculates by his formula the value of T_1 , it agrees with Wade's determination of the tensile strength pretty closely. I suppose, although Barlow does not state it distinctly, that he has taken $T_2/T_1 = .9$.

The following remarks of Barlow following on these experiments may be cited (pp. 479-80):

If the metal were homogeneous and the elasticity perfect, it is probable that the resistance of flexure would be precisely equal to the tensile resistance, instead of bearing the ratio of nine-tenths as found by experiment. It is evident, however, that it varies in different qualities of metal, and that the tensile resistance does not bear a constant ratio to the transverse strength.

Barlow, after showing from Wade's experiments that a decrease in the absolute tensile strength may be accompanied by an increase in the absolute flexural strength, continues:

It is easy to conceive also, that the resistance to flexure might be supposed to maintain nearly the same proportion to the tensile resistance in bodies similarly constituted, as for example crystalline substances, yet great variation may be expected to occur between crystalline and malleable and fibrous substances.

I see no theoretical reason why it should be probable that $T_1 - T_2$ for homogeneous and perfectly elastic bodies.

(c) Peter Barlow's Experiments on Wrought-Iron (pp 480-3)

Here we find W H Barlow no longer treating of absolute strength but of stresses "just sufficient to overcome the elasticity"—which seems to me a very different matter. He remarks that he has done this because the material yields by bending and not by fracture. The mean result is very nearly $T_1/T = 2$. I see, however, no reason for applying formula (11) to this case, and W H Barlow himself admits that the experiments are insufficient. On p 481 he gives experiments confirming the coincidence of neutral and central lines in the case of wrought-iron.

(d) Further results of Hodgkinson's Experiments on Cast-Iron taken from the *Manchester Memoirs*, Vol v see our Art 237*. These are given in the form of an appendix by Peter Barlow (pp 483-8), the experiments in question are those on the cross section of greatest absolute strength. Peter Barlow takes $T_1 = T_2$ owing to the difficulty of finding a mean value for T_1 . This leads to a series of values for T_1 varying from 14,000 to 16,000 lbs, values not varying more among each other than those for the tensile strengths of 50 square cast-iron bars given on p 9 of the *Iron Commissioners' Report* see our Art 1408*. For large iron castings owing to their relative weakness, Barlow remarks, T_1 ought to be taken much less, probably not more than 10,000 lbs.

[938] We may conclude then that

(1) There is no theoretical basis of sufficient validity for Barlow's formula, also that the term containing T_2 cannot arise from "lateral adhesion," and that the name "resistance of flexure" is thoroughly bad, but,

(11) there is sufficient evidence to show that for a considerable range of *cast-iron* beams of varied cross section the formula gives results for the absolute flexural strength accurate enough in practice.

[939] Jouravski *Sur la resistance d'un corps prismatique et d'une piece composee en bois ou en tôle de fer à une force perpendiculaire à leur longueur. Annales des ponts et chaussées, Memoires*, 1856, 2^e Semestre, pp 328-51. Paris, 1856. This is an extract from a work in three volumes 4to on bridges built on Howe's or the American system.

The memoir is an attempt to improve the old Bernoulli Eulerian theory of flexure by introducing the consideration of the lateral adhesion of the fibres. Jouravski remarks that given a rectangular beam its strength will be diminished by dividing it into two equal beams by a horizontal plane, hence there is an element

of strength in the beam due to the lateral adhesion of the fibres, or in our own words there is shearing-stress along the neutral axis of a beam which in itself forms an element of strength. Jouravski's investigation, suggestive as it is, is not, however, correct, for he really supposes this shearing stress to be uniform all along the neutral axis of a cross-section. This of course, as Saint-Venant has shown, is not the case, and the full treatment of the problem has been given by him in his memoir on flexure: see our Art. 69. At the same time Saint-Venant has praised Jouravski's idea and in his *Leçons de Navier* (see our Art. 183 (a) and his p. 390) adapted it to the case of a rectangular beam, the dimensions of which in the plane of flexure are much greater than those perpendicular to that plane. The memoir applies this incomplete theory of the slide-element in flexure to various numerical cases to which, I think, no importance can be attached. See my remarks on the similar investigations of Winkler and Airy in Arts. 661-6.

[940.] J. Dupuit: *Note sur la poussée des pièces droites employées dans les constructions. Comptes rendus*, T. XLV., pp. 881-2. Paris, 1857. The brief extract given here of the memoir does not enable us to judge of its contents. The author apparently finds fault with the ordinary theory of beams, because it does not take account of the fact that the 'fibres' cannot slip over the points of support and states that this produces a great side thrust on the points of support. Further the reactions themselves modify the points of support and therefore their resistance. There is no hint in the paper of how the author proposed to allow for these sources of error and I do not think the paper was ever published in full.

[941.] Fabré: *Sur la résistance des corps fibreux. Comptes rendus*, T. XLVI., p. 624. Paris, 1858. A memoir under this title was presented to the Academy in 1858. The author had concluded from very fine measurements that the ordinary theory of beams is incorrect, the *central line* being always compressed or elongated. I cannot find that the memoir was ever published.

[942.] G. Rebhann: *Relative Widerstandsfähigkeit eines an beiden Enden festgehaltenen prismatischen Trägers. Försters Allgemeine Bauzeitung*. Jahrgang XVIII., S. 130-7. Wien, 1853. This is an application of the Bernoulli-Eulerian theory of beams to ascertain the increased strength obtained by building-in the terminals of a beam. There is no novelty to record: see our Arts. 571-3 and 943-5.

[943.] F. Grashof: *Ueber ein im Princip einfaches Verfahren, die Tragfähigkeit eines auf relative Festigkeit in Anspruch genommenen*

prismatischen Balkens wesentlich zu vergrössern *Zeitschrift des Vereins deutscher Ingenieure*, Jahrgang I, pp 75–80 Berlin, 1857 Grashof, having seen Lamarle's results (see our Art 571) without his analysis, gives an investigation of some special cases where the strength of simple beams would be increased by fixing their terminals at definite slopes

[944] F Grashof *Ueber die relative Festigkeit mit Rücksicht auf deren möglichste Vergrösserung durch angemessene Unterstützung und Einmauerung der Träger bei constantem Querschnitt derselben*. *Zeitschrift des Vereins deutscher Ingenieure*, Jahrgang II, S 22–31, and Jahrgang III, S 23–8, 45–8, 155–160 Berlin, 1858 and 1859 This memoir starts with a criticism of Scheffler's work referred to in the next article It then proceeds to a consideration of the following problem Suppose a simple beam uniformly loaded and having a concentrated load at any one point of it, at what angles must the ends be built in in order to ensure the maximum of strength? It will be observed that this is little more than the simpler case of Lamarle's memoir (see our Arts 571–3) Grashof however works out a very great number of special cases, as when the isolated load is at the centre, the terminals are built-in horizontally, etc, etc There seems to be no novelty of method or result in the paper, and its technical importance is minimised by the difficulty we have already referred to of practically building in the terminals of a beam at a required angle see our Art 573

In the last part of the memoir Grashof deals with continuous beams passing over points of support at different heights, but as he takes here only the case of continuous loading, his analysis is not more general than Lamarle's and is in no way superior to it

[945] H Scheffler *Ueber die Versuchung der Tragfähigkeit der Brückenträger durch angemessene Bestimmung der Höhe und Entfernung der Stützpunkte* *Organ für die Fortschritte des Eisenbahnwesens*, Bd VII S 97 Wiesbaden, 1857 Further *Ueber die Tragfähigkeit der Balken mit eingemauerten Enden*, Ibid Bd XIII S 51, 1858

The first of these papers only deals with a very special case of what Lamarle and afterwards Grashof have treated generally, and in addition the analysis is very cumbersome The second paper is controversial, a poor reply to Grashof's perfectly legitimate criticism

[946] H *Festigkeits und Biegeverhältnisse eines über mehrere Stützpunkte fortlaufenden Trägers* *Der Civilingenieur*, Neue Folge, Bd IV, S 62–73 Freiberg, 1858

A continuous beam is supported on $(n + 1)$ points of support not on the same level and forming n equal spans The beam weighs p lbs per foot-run, and a live load of p' lbs per foot-run together with an isolated load Q cross the beam and occupy successively each span The author finds the deflections and bending moments with great length

of analysis. He considers in particular the case of five spans, and applies his results to various special numerical cases.

[947.] H. *Continuirliche Brückenträger. Der Civilingenieur*, Neue Folge, Bd. iv., S. 142–6. Freiberg, 1858. This memoir deals fully with the case of a beam of uniform cross-section resting on three points of support, when the mid-point of support is lower than the terminals and the live load covers one or both spans. Many numerical details are given for this case for variations of the ratio of live to dead loads, etc.

[948.] H. *Continuirliche Brückenträger. Der Civilingenieur*, Neue Folge, Bd. vi., S. 129–202. Freiberg, 1860. This paper is a continuation of the paper referred to under the same title in our Art. 947. The writer now supposes three unequal spans, the mid-span being longer than the two equal external spans and the mid-points of support lower than the terminals. There is a uniform dead load, and a uniform live load which may cover: (i) the two outside spans, (ii) the mid-span, (iii) all the spans, (iv) one outside span, (v) the mid-span and one outside span. All these separate cases are worked out with great detail and then more than 30 pages of numerical values are given for the reactions and maximum moments in these five different cases of loading for various ratios: (a) of the lengths of the spans, (b) of the live to the dead load, and for various amounts (c) by which the middle points of support may be supposed to be sunk below the terminals. Supposing these portentous tables to be correct we have here the most complete treatment the three-span continuous beam has ever received or is likely to receive.

[949.] E. Winkler: *Beiträge zur Theorie der continuirlichen Brückenträger. Der Civilingenieur*, Neue Folge, Bd. viii., S. 135–182. Freiberg, 1862. This paper may be noted here as it belongs essentially to the same group as those referred to above. It opens with an investigation of results similar to those of Clapeyron, Heppel, etc., and then proceeds to discuss the effect of loading only the r th out of n spans. Winkler presents his results in the form of continued fractions. He then takes the case of equal spans and calculates reactions, deflections, etc. (S. 147–60). Next he passes to the investigation of the most dangerous load system, and then turns to tables of numerical detail for various types of loading. Then he deals by aid of copious tables (S. 171–182) with the case of a continuous beam of four spans. Thus we may say that before 1862, the complete analytical theory of continuous beams of any number of spans and complete numerical details of beams up to four spans had been published¹.

[950.] S. Hughes: *An Inquiry into the Strength of Beams and Girders of all Descriptions, from the most simple and elementary Forms*,

¹ For further investigations with regard to continuous beams belonging to this decade see our Arts. 535, 571–7, 598–607, 889, 890, and 893,

up to the Complex Arrangements which obtain in Girder Bridges of Wrought- and Cast Iron. *The Artizan* Vol xv, pp 145-50, 170-3, 194-8, 217-20, 244-47, (255), 267-71, Vol xvi, pp 3-6, 27-31, (44-5), 79-84, 129-133, 158-160, London, 1857 and 1858. These papers contain a practical treatise on bridge making, involving very little theory, but citing the experimental results of Hodgkinson, Fairbairn and others, and applying them to the details of various girders, beams and bridges. They do not appear, however, to demand any close analysis in our History at the present day.

[951] W R R. *Notiz über die besten Querschnittsform eisener Träger*. *Zeitschrift des Vereins deutscher Ingenieure*, Jahrgang II, S 310. Berlin, 1858. The writer of this note criticises Hodgkinson's and Davis' beams of strongest section (see our Arts 244* and 1023), saying that in practice we do not want to have the beam strongest at rupture, but strongest at receiving set. He supposes that the elastic limit of cast-iron in tension is half that in compression and that both elastic limits are equal for wrought-iron. How he reaches these numbers I do not know. A footnote by Grashof questions their accuracy, but does not seem to notice the relative nature of the elastic limit in general. Compare our Art 875.

[952] Albaret. *Nouvelles Annales de la Construction*, Juin, 1859. I have only seen an extract of this paper entitled *Festigkeit von Metalträgern* in the *Hannoversche Bauzeitung*, 1860, S 523. The author discusses by a method, which is not very intelligible in the extract, the form of the girder which containing a minimum of material can yet safely carry a given load. The paper does not appear to be of any importance.

[953] Callcott Reilly. *On the Longitudinal Stress of the Wrought Iron Plate Girders*. This was a paper read before the British Association in 1860. It is published in the *Civil Engineer and Architect's Journal*, Vol xxiii, pp 261-4 and 294-5, also in *The Artizan*, Vol xviii, pp 209-12 and 220-1. London, 1860. The author supposes the limits of safe tensile and compressive stress to be different, taking for wrought-iron 5 and $3\frac{3}{4}$ (to 4) tons per square inch respectively (pp 262 and 294).

He assumes that these safe limits are reached in compression and tension under the same bending moment. He further supposes the stress to be proportional to the strain and the stretch and squeeze moduli equal (p 262). This fixes the neutral axis, and therefore, if there be no thrust, the position of the centroid of the cross section. For a given bending moment and I section of given total height and given thickness of web, we then have enough equations to determine the arcs of the flanges, if their breadths be given. Or for thin flanges the areas even without the breadths. Reilly concludes his paper with a calculation of the girders for a bridge actually built from designs based on his theory.

[954.] L. Mitgau: *Ueber die relative Tragfähigkeit guss- und schmiede-eiserner Träger mit Rücksicht auf deren Verwendung zu baulichen Zwecken. Zeitschrift für Bauhandwerker*, Jahrgang 1860, S. 121–7, Braunschweig. This paper is of no importance for us, the greater portion of it being occupied with the calculation of the moments of inertia of T and I sections.

[955.] Blacher: *Application du calcul des ressorts. Mémoires et Compte-rendu des travaux de la Société des Ingénieurs civils. Année 1850*, pp. 143–52. Paris, 1850.

This memoir may be considered as quite replaced by that of Phillips (see our Art. 483), for it only treats a very special case of the latter memoir. The formulae for springs cited on pp. 147–9 are due to Clapeyron who had given them to Shintz (*sic*, Schinz?) from whom Blacher obtained them. The assumption from which the memoir starts ("Soit une série de lames d'égale épaisseur et d'égale largeur superposées de manière que l'une repose sur les extrémités de l'autre par l'intermédiaire de petits tasseaux" p. 144) is by no means so general or satisfactory as that of Phillips.

[956.] Schwarz: *Von der rückwirkenden Festigkeit der Körper. Erbkams Zeitschrift für Bauwesen*, Jahrgang IV., S. 518–30. Berlin, 1854.

This memoir after some general remarks on cohesion and elasticity proceeds to deduce a formula for the buckling load P of doubly pivoted struts in the following manner. If $E\omega\kappa^2$ be the flexural rigidity of the strut supposed of length l , then as in Euler's theory (see our Art. 67*):

$$P = \frac{\pi^2 E\omega\kappa^2}{l^2} \dots\dots\dots (i).$$

If there were compression without buckling, we should have as the value for P

$$P = \omega C \dots\dots\dots (ii),$$

where C is the safe compressive stress.

Now if δ be the limiting elastic squeeze and C' the corresponding compressive stress $C' = E\delta$,

$$\text{or} \quad C' = \frac{l^2 P \delta}{\pi^2 \omega \kappa^2} \dots\dots\dots (iii).$$

Now Schwarz argues that the strut has to withstand buckling and compression at the same time, hence we must have

$$C' + C \text{ or } \frac{P}{\omega} \left(1 + \frac{l^2 \delta}{\pi^2 \kappa^2} \right)$$

less than the greatest safe compressive stress, say C_0 . Thus he finds

$$P < C_0 \omega \left(1 + \frac{l^2 \delta}{\pi \kappa^2} \right)$$

This formula is in fact akin to the empirical formula, of Gordon, Rankine and Scheffler, but the above process by which Schwarz deduces it remains a mystery to me

[957] A C Benoit-Duportail *Calcul des essieux pour les chemins de fer Le Technologiste*, 1856, pp 315–25 Paris, 1856
Translated in the *Polytechnisches Centralblatt*, 1856, Cols 705–14
This paper appears to be theoretically correct and is of considerable technical value

Suppose $2P$ to be the load on the axle, b the distance from the mid-point of the wheel to the mid point of the journal on which the load rests, then the bending moment throughout the axle is uniform and equal to Pb . If r be the radius of the axle and T the safe tractive strength of its material, then on the Bernoulli Eulerian theory

$$Pb = \frac{T}{r} \times \pi r^2 \times \frac{r^2}{4} = \frac{T \pi r^3}{4} \quad (1)$$

This formula holds whether the journals are placed inside or outside the wheels, the flexure in the two cases being, however, in opposite senses

According to Benoit-Duportail the value of b lies between 2 and 3, metres, and T varies from 600 to 400 kilogs per sq centimetre. He thus finds for r in centimetres

$$\begin{aligned} r &= 35 \sqrt[3]{P}, \text{ for } b = 2 \text{ m and } T = 600 \text{ kilogs} \\ &= 40 \sqrt[3]{P}, \quad = 25 \text{ m and } T = 500 \\ &= 457 \sqrt[3]{P}, \quad = 3 \text{ m and } T = 400 \\ &= 40 \sqrt[3]{P}, \quad = 2 \text{ m and } T = 400 \end{aligned}$$

The values of r are then tabulated for various loads P (pp 316–7)

[958] The flexure is next calculated, as before on the assumption that the axle has a uniform cross section. Since the flexure is circular this is easily done and for such axles as are in common use the amount is found to be 1.75 mm, which throws the top of the wheel from 3 to 4 millimetres out of the perpendicular (p 317)

Il est évident que lorsque l'essieu tourne, la flexion change de position et que l'essieu prend un mouvement de flexion oscillatoire, analogue à celui qu'on opère pour faciliter la rupture des barres de fer ou des morceaux de bois, qui tend à altérer la qualité du fer. Mais il est à remarquer que

lorsque les trains sont en marche, comme il faut un certain temps pour que la flexion se produise, l'amplitude des oscillations est d'autant moindre que la vitesse est plus grande et les effets d'altération qui se produisent sont beaucoup moins destructifs qu'on ne pourrait le craindre au premier abord (p. 317).

This seems to me to disregard the possibility of an accumulation of stress : see our Arts. 970 and 992.

[959.] The journal has to be treated somewhat differently from the body of the axle. In the first place it may be considered as a cantilever of length l and thus we have for its radius :

$$Pl = \frac{T\pi r^3}{4} \dots\dots\dots (ii).$$

This gives the radius required at the wheel-end or place of maximum stress, the journal being supposed *outside* the wheel.

But there is another point to be considered, namely, the friction of the load, which produces heat. It is found that for an axle that has been some time in use, the frictional surface is about one-third of the circumference. Hence the area of friction $= \frac{2}{3}\pi rl$. Or, if p be the mean pressure, we have, according to our author, $P = p \times 2rl$ about, that is

$$l = \frac{1}{2}P/(pr) \dots\dots\dots (iii).$$

This reasoning is not, I think, satisfactory; p is normal to the journal surface at each point and we ought rather to have

$$P = p \times 2rl \sqrt{3}/2 = p \times 1.7rl \text{ about.}$$

From (ii) and (iii) we find for the dimensions of the journal (p. 318) :

$$\left. \begin{aligned} r &= \sqrt{P} \sqrt{\frac{2}{pT\pi}}, \\ l &= \frac{1}{2p} \sqrt{P} \sqrt{\frac{pT\pi}{2}} \end{aligned} \right\} \dots\dots\dots (iv).$$

Benoit-Duportail states that $p = 25$ kilogs. per sq. centimetre is found by experience to be about the maximum mean pressure which will not over-heat the journal. Putting $T = 600$ kilogs., he then finds :

$$r = .08 \sqrt{P} \text{ in centimetres, and } l = 3.125r \dots\dots\dots (v).$$

The value of l as given by this formula would then be retained for the journal. But the value of r would only be valid after there had been a certain wearing away due to use. The value of r therefore must be increased by from 1/10 to 1/12 of its value (p. 319).

If we had supposed, however, the load distributed uniformly over the length of the journal and not all acting at one end as in the extreme case, we should have had instead of (ii) the equation

$$\frac{1}{2} Pl_1 = \frac{T\pi r_1^3}{4} \dots\dots\dots (vi),$$

which with (iii) leads us when $T = 600$ and $p = 25$ kilogs to

$$r_1 = 0.68 \sqrt{P} \text{ and } l_1 = 4.3 r_1 \quad (\text{vii}),$$

instead of (v)

On the *Chemin de fer du Nord* for certain wagons P equals 3250 kilogs. This gives, correcting Benoit Dupontail's arithmetic

$$r_1 = 3.9 \text{ centimetres, and } l_1 = 16.7 \text{ centimetres}$$

Adding to r_1 a tenth of its value we have

$$r_1 = 4.29 \text{ and } l_1 = 16.7,$$

the values actually taken being $r_1 = 4$ and $l = 17$. Thus the theory leads to results in fair agreement with practice.

For engines and locomotives whose springs are much stiffer, T ought not to be taken so large, but = 400 kilogs, say, and p ought also to be reduced. We then have from (iii) and (iv) (p. 319)

for $p = 20$ kilogs,	$d = 2r = 16 \sqrt{P},$	$l = 2d,$
= 15 kilogs,	$d = 2r = 17.1 \sqrt{P},$	$l = 2.3d,$
= 10 kilogs,	$d = 2r = 18.9 \sqrt{P},$	$l = 2.8d$

Benoit-Dupontail gives a table of the values of d and l for loads ($2P$) from 500 to 12000 kilogs (pp. 320). Then follows with tables an investigation similar to the above for the case when the journals are inside the wheels (pp. 322–3). The memoir concludes with a discussion of the effect of wedging (*calage*) the wheels on to the axle (pp. 324–5).

[960] W. Fairbairn *Tubular Wrought Iron Cranes*. *Institution of Mechanical Engineers Proceedings*, 1857, pp. 87–98. This paper contains details as to the strength and deflection of these cranes: see our Art. 909.

[961] Callon *Rapport a la commission centrale des machines a vapeur sur la reponse des diverses commissions de surveillance des bateaux a vapeur aux questions posees par la circulaire ministerielle du 15 juillet 1853*. *Annales des ponts et chaussees. Memoires* 1856, 2^e semestre, pp. 71–102. Paris, 1856. I only refer to this memoir because in a *Note*, pp. 90–102, it seems to me to give a very doubtful and, I think, erroneous theory of the safe limit for the thickness of the walls of cylindrical boilers. I do not see how the theory of beams can be applied to this case, and if it be applicable I do not understand how (dy/dx) could be neglected as it is on p. 92: see my remarks in Art. 537 on a like treatment of the problem due to Bresse.

[962] F. Gray *Predgold's Formula for the Thickness of Cast Iron Cylinders*. *The Artizan*, Vol. XVII pp. 289–90, London, 1859. Predgold *On the Steam Engine*, §§ 518–20, gives a formula for the proper thickness of cast iron cylinders and pipes subjected to strain arising from

unequal expansion. Thus he supposes one-half of a cylinder to be heated 300° F. higher than the other half. Tredgold's formula and his method are both very questionable. Gray points out a slip in his algebraical work and gives a corrected formula based on the same hypothesis. The whole procedure seems to me so questionable that I place no faith in Gray's corrected version of Tredgold's formula. Winkler has attempted a similar problem, in a manner which I think inadmissible also, but certainly better than Tredgold's: see our Art. 645. The problem is of some importance and ought, I think, to admit of a solution by accurate analysis.

[963.] Mahistre: *Mémoire sur les limites des vitesses qu'on peut imprimer aux trains des chemins de fer, sans avoir à craindre la rupture des rails. Comptes rendus*, T. XLIV., pp. 610-13. Paris, 1857.

This paper after referring to the Portsmouth experiments on the flexure of railway rails under a travelling load (see our Art. 1417*), proceeds to develop a formula for the maximum load which can cross with given velocity a doubly built-in rail without destroying its elastic efficiency. Mahistre treats the railway rails as built-in at the sleepers, and finds by a process which does not seem to me free from doubtful hypotheses the following formula for the maximum load which can travel with velocity V along the rail:

$$P = \frac{(E - 2T_0 \frac{h}{b}) \omega \kappa^2}{l \left(\frac{V^2}{g} + \frac{1}{2} \frac{E}{T_0} b - h \right)},$$

where $2l$ is the length of the rail, b its vertical diameter, $E\omega\kappa^2$ its flexural rigidity, h the height of the centre of gravity of the travelling load above the rail, T_0 the limit to elastic tractive stress, E the stretch-modulus of the material of the rail, and $4P$ the part of the weight of the locomotive which rests on the most charged pair of wheels.

If $2h/b$ be small compared with E/T_0 , as I think it would generally be, this formula reduces to

$$P = E\omega\kappa^2 / l \left(\frac{V^2}{g} + \frac{E}{2T_0} b \right).$$

This may be compared with a formula for P which I have deduced from Saint-Venant's result (xiii^b) for a doubly supported beam given in our Art. 375. Putting the Q of that article = $2P$, I find approximately for P :

$$P = E\omega\kappa^2 / l \left(\frac{4}{3} \frac{V^2}{g} + \frac{E}{2T_0} b \right).$$

Thus the difference occurs in the factor $4/3$ of the term V^2/g .

Mahistre neglects the inertia of the rail; he assumes it at each instant under the transit of the load to take the statical form which would be produced by the force $2P + \frac{2P}{g} \frac{V^2}{r}$, where r is the radius of

curvature of the curve described by the centre of gravity of the load, and he further appears to assume that the centres of curvature of the path of the load and of the curve of deflection of the rail at the point of contact with the wheel must coincide at each instant

I do not think either the first equation of his (1) or his equation (3) holds for a doubly built in rail. They apply rather to *one simply supported*, and this on the assumption that the cross section has its centroid in the mid point of the vertical axis of symmetry. Further I do not follow the argument by which it is shown that the envelope of the successive curves of deflection is a circle, nor if it be a circle do I understand why equation (4) for the deflection and curvature of the strained form *at any instant* must hold. My surprise is rather that the author comes so close to the right result than that he differs from the formula of Phillips and Saint-Venant

[964] Robert Mallet *On the increased Deflection of Girders on Bridges exposed to the Transverse Strain of a rapidly passing Load*. This paper was read at the Institution of Civil Engineers of Ireland and will be found printed in *The Civil Engineer and Architect's Journal*, Vol xxiii pp 109-110 London, 1860. Mallet refers to the labours of Willis and to the experiments of James and Galton, and then adopts Morin's formula for the deflection, which is really due to Cox see our Arts 1417*-24*, 1433* and 881(b). It supposes the beam to take its greatest deflection when the travelling load is at the centre and the deflection then to be that which would be due to a central load equal to the weight of the travelling load, together with a load equal to the instantaneous 'centrifugal force' of the travelling load. If the load statically placed at the centre of the beam would produce a bending moment M_s there, then I find on this theory that the bending moment M_D , when it is travelling with velocity V , is

$$M_D = \frac{M_s}{1 - \frac{M_s V^2}{E \omega \kappa y}},$$

where $E \omega \kappa$ is as usual the flexural rigidity of the beam. Hence if M_0 be the safe bending moment, we must have

$$M_s < \frac{M_0}{1 + \frac{M_0 V^2}{E \omega \kappa y}}$$

But if w be the weight of the travelling load and $2l$ the length of the beam, $M_s = \frac{1}{2} w l$, or,

$$w < \frac{2 M_0 / l}{1 + \frac{M_0 V^2}{E \omega \kappa y}}$$

If $M_0 = T_0 \omega \kappa^2 / h$, we have

$$w < \frac{2T_0 \omega \kappa^2 / (l h)}{1 + \frac{T_0}{E} \frac{V^2}{g h}}.$$

Mallet does not reduce Morin's result to this simple form, but says rather vaguely that it accords with James and Galton's experiments. The above result will be found to agree with that of Mahistre's cited in the previous article, if we remember that $w = 2P$, $h = \frac{1}{2}b$ of the latter's notation: see also our Art. 663. The conclusions, however, of Mahistre and Mallet are erroneous, being founded on a method condemned at a much earlier date by Stokes: see our Art. 1433*. Mallet in a footnote notices Phillips' memoir (see our Art. 552), and commends it strongly to the reader, but does not seem to have noticed that its results contradict those he cites. He considers Willis and Stokes' work as excellent, but "past the usual range of practical men." There is nothing of further importance in the paper.

[965.] Lemoyne: *Note sur l'évaluation du poids équivalent à un cahot en ce qui concerne la résistance d'une poutre de pont; ou plus généralement: Détermination de la charge tranquille équivalente, quant à la flexion d'une pièce élastique reposant, par ses extrémités, sur deux appuis de niveau, au choc d'une masse déterminée tombant d'une hauteur connue sur le milieu de cette pièce. Annales des ponts et chaussées. Mémoires, 1859, 1^{er} semestre, pp. 326-33.*

The method of this paper is not very satisfactory, and the whole matter has since been thoroughly discussed by Saint-Venant (see our Arts. 362-71 and 413).

Lemoyne argues as follows: Let the weight Q dropped from the height h produce the same deflection f as the weight P statically placed upon a bar, then to get a superior limit for the value of P we may suppose the work done in bending the bar in the two cases equal or:

$$Q(h+f) = Pf,$$

but $f = l^3 P / (48 E \omega \kappa^2)$, where l is the length of the bar and $E \omega \kappa^2$ its flexural rigidity, hence we find:

$$P = \frac{Q}{2} \left(1 + \sqrt{1 + \frac{192 E \omega \kappa^2 h}{l^3 Q}} \right) \dots\dots\dots (a).$$

Il est à remarquer de plus, que la relation (a) fournirait seulement, dans la pratique, une limite supérieure du poids à déterminer; car cette expression n'est vraie, théoriquement, que pour le cas impossible de deux corps parfaitement élastiques, ce cas étant le seul où il n'y ait pas une perte de puissance vive par le fait même du choc (p. 329).

To obtain an inferior limit Lemoyne determines the kinetic energy absorbed in the elastic deformation. Let V' be the joint velocity after

impact and W the weight of the ball, then if both W and Q were free we should have by the principle of momentum

$$\frac{Q}{g} \sqrt{2gh} = \frac{W+Q}{g} V'$$

$$\text{Thus,} \quad \frac{1}{2} \frac{W+Q}{g} V'^2 = \frac{Q^2 h}{W+Q}$$

$$\text{Putting} \quad Pf = \frac{Q^2 h}{W+Q} + Qf,$$

we find for an inferior limit of P (p 330)

$$P = \frac{Q}{2} \left(1 + \sqrt{1 + \frac{192 E \omega \kappa^2 h}{l^3 (W+Q)}} \right)$$

Lemoyne's reasoning seems to me very doubtful, in particular with his definitions of P and f I think $\frac{1}{2}Pf$ and not Pf is the work corresponding to P . He gives an example of these limits, and he finds that for a certain case P must lie between 13,260 and 3,210 kilogs, when $Q = 3,000$ kilogs and the drop is 08 metres. A further assumption leads him to limits of 11,000 and 5,142 kilogs. In neither case do the limits seem to me sufficiently close to be of much practical value.

[966] F. Grashof *Ueber die Berechnung der Festigkeit der Schraubengewinde* *Zeitschrift des Vereins deutscher Ingenieure* Jahrgang iv, S 289-92 Berlin, 1860

The author commences with a short historical account of the discussions which had taken place in Germany on the strength of screws. At a meeting in March, 1860, of the Hannoverian *Architekten u. Ingenieur Verein* Wittstein had given a formula for the strength of screws based on the assumption that the thread is a beam under flexure (!). Let a be the width and c the depth of the thread, b the circumference of the screw multiplied by the number of turns of the screw in the matrix, then Wittstein supposed that the tractive strength P of the screw is given by

$$P = mbc^2/a \quad (1),$$

where m is a constant to be deduced by experiments on the rupture of screws and not from pure traction experiments on its material. This formula led to a discussion in which Ruhlmann, Karmarsch, Kuchweger and others took part. Karmarsch, from experiments made by himself twenty years previously, concluded that the resistance of wooden screws was due to the shearing and not to the bending strength of the thread. Thus if S_0 be the absolute shearing strength of the material, we ought to have instead of (1)

$$P = S_0 bc \quad (11)$$

Ruhlmann (*Zeitschrift des Architekten u. Ingenieur Vereins f. d. Konigreich Hannover*, Bd VI Heft 2 u 3, where the details of the

discussions will be found,—a periodical unfortunately inaccessible to me) considers that formulae (i) or (ii) will be true according as the thread does not or does accurately fit the matrix. He then proposes to use a formula given by Navier, in § 154 of his *Leçons*, for combined flexure and shear. This formula is erroneous, so that no weight can be laid on Rühlmann's results. In the course of his paper he refers to certain experiments on wrought-iron made in 1834, the details of which are published on S. 228 of the *Mittheilungen des Gewerbe-Vereins f. d. Königreich Hannover*, 1835, showing that the absolute shearing strength of wrought-iron is from 68 to 80 per cent. of its absolute tractive strength,—a result not very far from the $\frac{4}{5}$ obtained by extending the results of uniconstant isotropic elasticity to the phenomena of cohesion: see our Arts. 879 (d) and 903.

[967.] Such was the state of the problem when Grashof took it up. He considers (ii) to be the correct formula for tightly fitting screws, and that it is impossible to apply (i) to the case of a beam the height of whose cross-section is of the same dimensions as its length. It is necessary, he holds, in the case of a metal screw, which does not fit so closely as a wooden one, to take into account both the flexure and shear of the thread. He supposes the pressure P to be distributed on a cylinder round the spindle of the screw, the radius of which is slightly greater than the mean between the radii of the spindle and the thread. I hardly see that he justifies this assumption (S. 290). He then, after demonstrating at some length the error of Navier's formula,—a fact long before known from Saint-Venant's researches—proceeds to apply Saint-Venant's formula for combined flexure and shear to the case of the thread of a screw. He attributes this formula to Poncelet and says he first found a rational treatment of combined flexure and shear in Laissle and Schübler's work (see our Art. 889)! He then gives a numerical table showing the influence of shear and flexure respectively on short beams. This table is similar to one which had been previously given by Saint-Venant and which we have already cited in a later form (see our Art. 321 (d)). Grashof concludes from his formula,—into which, however, he has not introduced the differences between the stretch and slide moduli, and between the absolute tractive and shearing strengths,—that if a screw thread is not to give way by flexure we must have

$$P < \frac{8}{15} bc T_0 \dots\dots\dots\text{(iii),}$$

where T_0 is the absolute tractive strength, and if it is not to give way by shear we must have :

$$P < \frac{4}{3} bc T_0 \dots\dots\dots\text{(iv).}$$

Thus a slightly loose screw would give way sooner than a tight one. Better results than these would be obtained on the same *hypothesis*—i.e. *that of the thread as a beam*,—from the conclusions of our Art. 321 (d).

I question, however, whether this hypothesis in the least approximates to the facts of the case. Were the thread cut through in several

places parallel to the axis of the screw, would not its strength be weakened? Further, if it is to be treated as a beam, surely in practice its cross section is not uniform and equal to bc ? Lastly if we may suppose these assumptions to make no difference, would not better results be obtained by treating the thread as a very narrow *plate* built-in at one edge and loaded near the parallel edge? In this case we should not obtain a formula like (iii) in which T_0 is the absolute tractive strength. We should have to deal with a plate incapable of contracting in its own plane and the results would be again different.

GROUP C

Experimental Researches on Shaped Material and Structures

[968] The remarks we have made on the papers of the two great engineering Institutions for the earlier period see our (Art 1464*) hold in a slightly modified degree for much of the technical literature of the period 1850–60. The scientist stands aghast at the great mechanical results which have been obtained often by a defective, sometimes by a false theory. Perhaps it is only a consciousness of the large ‘factor of safety’ used which makes a railway journey endurable for a scientist after a perusal of some of the technical papers published in this decade!

[969] The following papers in the *Proceedings of the Institution of Mechanical Engineers* may be just noted

(a) 1850–1, January, pp 19–31 *On Railway Carriage and Waggon Springs* by W. A. Adams, with an additional paper by the same author, April, pp 14–26. These papers are interesting as giving an account of the various buffing and bearing springs then in use. There are details of experiments on the deflection, set and absolute strength of some of these springs. Several of them might be made the subject of interesting theoretical investigations.

(b) 1853, pp 45–56 *On Improved India Rubber Springs for Railway Engines, Carriages, etc* by W. G. Craig. Similar remarks apply to this paper.

(c) 1857, pp 219–226 *Description of a New convex plate laminated Spring* by J. Wilson. The flat plates of the ordinary spring are replaced in this new spring by “grooved or trough plates”. Details of deflection and set in springs will be found on p. 223.

(d) 1858, pp 160–5 *On a new construction of Railway Springs*, by T. Hunt. This gives details of deflection and set.

[970.] *On the Fatigue and consequent Fracture of Metals.* F. Braithwaite. *Institution of Civil Engineers. Minutes of Proceedings*, Vol. XIII. 1853-4, pp. 463-7 (Discussion pp. 467-75). The word 'fatigue' is attributed by Braithwaite to Field (p. 473) and is used by him to denote a progressive destructive action arising from repeated loading. The paper is in very general language and the only evidence brought forward is drawn from numerous "unaccountable" accidents which the author attributes to a wearing-out of material due to repeated stress. Fairbairn in the discussion supported the old view that the variations in stress produce a change in the molecular structure, thus "wrought-iron assuming a crystalline instead of a fibrous arrangement" (p. 469): see our Arts. 1463*-1464* and 881 (b). Sewell held "that fractures were frequently owing to the arrest of the longitudinal wave of vibration by a transverse check." He believed that this would account for the action of fatigue at shoulders and angles (p. 471). This is really a true view although obscurely expressed, the wave of stress is reflected by such 'checks,' and the stress tends to double if not further multiply itself at such points¹. This accumulation of vibratory stress owing to reflection can be easily demonstrated theoretically in the case of longitudinal and torsional vibrations, and I believe is the real reason why a vibrating body *appears* to give way under a stress less than the statical rupture stress. Thus 'fatigue' would only express the constantly increasing set due to an accumulated stress which exceeded the elastic limits. The vague way in which the latter term is used by Hawksley in the discussion is characteristic; he does not seem to have in the least grasped that the vibratory strain under a certain loading may be twice, or even more times, as great as the strain produced by the same load under statical conditions. It is accordingly the maximum vibratory strain and not the statical strain which must be less than the elastic limit, but the vibratory strain can only be deduced from the load by theoretical calculations, which are occasionally of a rather complex character.

[971.] C. R. Bornemann: *Festigkeitsversuche mit dreieckigen Stäben*, *Der Civilingenieur*, Neue Folge, Bd. I., S. 186-195. Freiberg, 1854. This is an attempt by means of experiments on wooden and cast-iron bars of triangular cross-section to ascertain whether the stretch- and squeeze-moduli of such materials are equal. The bars were of equilateral cross-section, and in the case of wood were of deal with the fibres apparently *in the plane of the cross-section and parallel to a median line*. The experiments with the wooden bars were made with the cross-section in three different positions relative to the plane of the load supposed vertical, i.e. (i) with the vertex upwards, (ii) with it downwards, in both cases one side being horizontal, and (iii) with a side vertical. Experiments were then made in which elastic flexure, set and ultimately flexural strength were measured. Similar bars of cast-iron with their

¹ The papers of Thorneycroft and McConnell referred to in our Art. 1464* both draw attention to the fact that axles almost invariably break at the wheel. McConnell attributes this position of the fracture to "the sudden stoppage or reaction of the vibratory wave at that place."

cross sections in the same three positions relative to the load were experimented on. The details of both sets of experiments were found on S 187-92.

Bornemann finds that the relative strength of both wooden and cast-iron beams, calculated by extending the Bernoulli-Eulerian theory to rupture, would depend on the position of the cross section relative to the plane of the load. Further that the elastic flexures in these positions require us to suppose that for cast-iron at least the stretch and squeeze moduli are unequal. He works out a theory of flexure on this hypothesis on S 192-3, which is very similar to the Hodgkinson theory; see our Arts 234* and 925. His general conclusions stated on S 195 are as follows. His experiments

(1) Die bei früheren Festigkeitsversuchen gemachten Beobachtungen bestätigen, nämlich die Proportionalität der Zunahme der Einbiegung mit den Gewichtslagen, innerhalb gewisser Grenzen, dann die stufenweise Zunahme der Einbiegungen bei höheren Belastungen, das Auftreten permanenter Einbiegungen bereits bei sehr geringen Belastungen (z. B. für bei 1/57 der Bruchlast, für Gusseisen bei weniger als 1/20 derselben) bei sehr unbedeutenden Ausdehnungen der extremen Fasern (für bei einer Ausdehnung = 0.0032, und für Gusseisen bei der Ausdehnung = 0.0086), die stärkere Zunahme der permanenten Einbiegungen in der Nähe der Bruchbelastung, das plötzliche Eintreten des Bruches bei eisernen Barren und unter Bildung eigenthümlicher keilförmiger Hebelwirkungen an der Seite der comprimierten Fasern, endlich die Abnahme des Elasticitätsmodulus mit wachsenden Einbiegungen,

(2) Scheint sich aus diesen Versuchen ein Unterschied zwischen Elasticitätsmodulus der comprimierten und demjenigen der ausgedehnten Fasern herauszustellen, welcher aber für Holz wo die entsprechenden Verhältnisse sich wie 1:054:1 verhielten nur sehr unbedeutend sein kann, für Guss dagegen, wo die Elasticitätsmoduli sich wie 1:4939:1 verhielten, übersehen werden konnte, sondern die Annahme einer andern Lage der neutralen Achse und die Einführung anderer Biegemomente nothig machte. Als Elasticitätsmodulus der ausgedehnten Fasern ergab sich für Gusseisen im Mittel 9562500000 Kilogr. [per sq. metre], für Holz 153195 Kilogr. [per sq. metre].

(3) Gleichzeitig ergibt sich aber auch eine Veränderlichkeit der neutralen Achse mit steigenden Belastungen, indem sie sich immer mehr dem Schwerpunkt zu nähern scheint.

(4) Die gewöhnliche Berechnungsweise der Festigkeit wird durch diese Versuche nicht bestätigt, es scheint vielmehr, als ob zwischen den Festigkeitsmodellen der dem Druck und der dem Zug entsprechenden Ungleichheit bestünde, welche zwischen den verschiedenen Materialien gefunden wurde.

The fourth result is of course the old 'beam paradox' see our Arts 173, 178 and 930-8. The possibility of obtaining satisfactory results by making the stretch and squeeze moduli for cast iron different I think, doubtful, since the chief peculiarity of cast iron is the linearity of its stress-strain curve from the very outset see Arts 1111* and 793.

[972.] Eaton Hodgkinson: *Experimental Researches on the Strength of Pillars of Cast Iron from various Parts of the Kingdom*. *Phil. Trans.* 1857, pp. 851–899 with three plates. London, 1858.

This memoir may be treated as a supplement to that of 1840 considered in our Arts. 954*–965*. From the theoretical point of view it does not contribute much additional information, and from the practical it must be looked upon chiefly as modifying the constants obtained in the earlier investigations.

[973.] The pillars in the present researches were upwards of 10 ft. long and from 2·5 to 4 inches in diameter; partly solid and partly hollow. The material was cast-iron and the iron was of a variety of well-known qualities. A description of the testing machine will be found on pp. 851–2 (with plate xxxi); the experiments, made at University College, London, were at the joint cost of the Royal Society and Mr Robert Stephenson. Hodgkinson being unable to determine any point which could be described as that of incipient flexure, confined his attention to rupture loads.

The rupture load of a solid pillar of diameter d and length l , according to Hodgkinson's investigations of 1840 varied as $d^{3.55}/l^{1.7}$. In the present experiments he gives for Low Moor Iron the rupture load w in tons of a hollow pillar of internal and external diameters, d_1 and d inches, l feet long (p. 862):

$$w = 42.347 \frac{d^{3.55} - d_1^{3.55}}{l^{1.68}},$$

while in the researches of 1840 he gave (see our Art. 961*):

$$w = 46.65 \frac{d^{3.55} - d_1^{3.55}}{l^{1.7}}.$$

It is obvious that there is a very considerable difference between these results, and we are compelled to put even less faith in the formula than we might hope to do, when we notice that the powers of the diameters vary from 3.213 to 3.679, and the powers of the lengths from 1.5232 to 1.6724 in the different sets of experiments; still other values of the powers would have arisen, if the results of the experiments of 1840 had been taken into account. Further these empirical formulæ are, we are told, to be limited to pillars of cast-iron, whose lengths are at least 30 times their diameter (pp. 864–6). It may be questioned whether the Gordon-Rankine formula or some of its numerous German

equivalents would not give equally good, perhaps better, results see our Arts 469, 650 and 956

For the different kinds of cast-iron Hodgkinson gives on p 872 a summary of the values of m , where in tons $w = m \frac{d^{3.5}}{l^{.63}}$ for solid pillars m , for d in inches and l in feet, varies from 33.6 up to 49.94. This summary may have value for practical purposes, but we can only afford space to refer to it here.

[974] We may note one or two points of the memoir which have possibly a theoretical bearing

(a) The relative strength of pillars with flat or bedded ends to those with rounded ends was found to be as 3.107 to 1 (p 855 and compare p 854, § 5). The theoretical incipient flexure loads are as 4 to 1. Probably a certain amount of strength was gained by the flattening of the rounded ends under the pressure. With one end flat and one rounded the ratio was as 2 to 1, which agrees with that given by incipient flexure very fairly see our Art 959* and *Corrigenda* to Vol 1 p 2.

(b) Hodgkinson gives a theory of these ratios (pp 855-58), but it is not very novel or sufficient. His remarks on the points of rupture (p 858) seem to suggest that rupture ultimately takes place at the points of maximum elastic stress as given by Euler's theory. These are the points referred to in our Art 959*.

(c) On pp 861-2 the great loss of strength due to removing the external crust is referred to. Hodgkinson thus notes "that to ornament a pillar it would not be prudent to plane it". Further "In experiments upon hollow pillars it is frequently found that the metal on one side is much thinner than on the other, but this does not produce so great a diminution in the strength as might be expected, for the thinner part of a casting is much harder than the thicker, and this usually becomes the compressed side" (p 862).

The considerable differences between the crushing strength of iron at the core and towards the periphery of the casting are again referred to on pp 866-870. Thus if R, R' be the resistances to crushing per square inch at the periphery and the core respectively, then $\frac{R - R'}{R}$ = the defect of resistance at the core, the resistance towards the periphery being taken to be unity. Hence if d be the diameter of the weaker core, d_1 of the pillar, Hodgkinson supposes (see our Art 169, (e))

$$w = \frac{\beta}{l^{.63}} \left(d_1^{3.5} - \frac{R - R'}{R} d^{3.5} \right),$$

where β is a constant. For Low Moor iron $\frac{R - R'}{R} = \frac{1}{4}$ nearly, and from $d = .25d_1$ to $d = .8d_1$, we see that w will vary from

$$998 \frac{\beta d_1^{3.5}}{l^{.63}} \text{ to } 8855 \frac{\beta d_1^{3.5}}{l^{.63}}$$

Thus the weakness of the core may have considerable effect. The reasoning by which Hodgkinson reaches the above formula is not very satisfactory, but it probably roughly expresses the effect of the variation of the strength of the material across the section. The point has been considered in other applications by Saint-Venant and Bresse: see our Arts. 169 (e)-(f) and 515.

Experiments showing the decrease of strength from the periphery to the core of castings are given on pp. 889-92, and might be useful for comparison with further theoretical investigation on this subject, although in many cases the evidence only proves irregularity in the casting; in one case even the greatest strength was near the centre.

(d) In the *Appendix* to the memoir, pp. 893-9, we have some experiments on six cast-iron columns of circular, square and triangular cross-sections. From the few results obtained it would appear that for the same quality of metal, the same weight and length, the circular, square and equilateral triangular cross-sections give loads varying as 55299, 51537, and 61056 respectively, or the *triangular* is distinctly the strongest and the square the weakest. In these cases the ends were *flat*; Hodgkinson seems to hold that this would not be true if the ends were rounded, but the experiment on a cruciform pillar, made in 1840, on which he bases his conclusion does not seem very satisfactory. The ratio of the corresponding *buckling* loads is on Euler's theory $9 : 3\pi : 3.464\pi$, which makes the load for the triangle the greatest, and with roughly about the same ratio to that for the square as Hodgkinson gives for the rupture loads. But this theory applied to rupture makes the square stronger than the circle, which is the reverse of Hodgkinson's experience.

The rupture surfaces of the pillars experimented on are figured. The details of some experiments on wrought-iron columns and timber balks referred to on pp. 852-3 were not, so far as I know, ever published.

[975.] This is the last memoir of Hodgkinson's that we have to note. He died on June 28, 1861, after some years of bad health. An account of his life will be found in the *Mémoires et compte rendu des travaux de la Société des Ingénieurs civils*, Année 1861, pp. 505-10. Paris, 1861. Of this society he was an honorary member. The account is a translation by Love of a notice of the veteran technical elastician which appeared in the *Manchester Courier*, but on what date I do not know.

[976.] D. Treadwell: *On the Strength of Cast-Iron Pillars. Proceedings of the American Academy*, Vol. iv., pp. 366-73. Boston, 1860.

This paper is a mere *résumé* and criticism of earlier work. It refers to the labours of Euler, Rennie, Tredgold and Hodgkinson (see our Arts. 65*, 74*, 185*, 196*, 833*, and 954*-65*). It points out that Hodgkinson's formulæ ought not to be trusted beyond the limits of his

experiments, careful as the latter were Treadwell further remarks that no practical directions founded upon Hodgkinson's experiments have been given in any engineering work¹, and that American architects are governed by Tredgold's formula, which leads to different and in many cases quite incongruous results At Treadwell's suggestion a committee was appointed to draw up rules which should be consistent with the laws of strength for small as well as for large pillars I am unaware whether this committee ever published any report

[977] B B Stoney *On the Strength of Long Pillars Proceedings of the Royal Irish Academy*, Vol VIII, pp 191-4 Dublin, 1864 This gives a very insufficient and unsatisfactory method of deducing a formula for the 'deflecting weight' of long struts It practically only reaches Euler's result in an incomplete form see our Art 74*

[978] G H Love A memoir by this writer may be noted although it belongs to a year outside the present decade It is entitled *Sur la loi de Resistance des piliers d'acier deduite de l'experience pour servir au calcul des tiges de piston, bielles, etc Mémoires et compte rendu des travaux de la Société des Ingenieurs civils*, Année 1861, pp 119-66 Paris, 1861

The memoir commences by noting the want of experiments on the strength of steel columns, and proposes to rectify this by experiments on three columns of steel with rounded ends of one centimetre diameter and of lengths 10, 20 and 30 centimetres respectively From results obtained for these *three columns only*, and by a process which is not very intelligible to me, Love obtains the following empirical formula for the total crushing load P of a steel column

$$P = C\omega \sqrt{l/d - 5.50} \quad (1),$$

where C = the crushing strength of a small block of steel,
 ω = the cross section of the column, supposed circular,
 l = its length and d its diameter

Presumably this formula only holds when $P < C\omega$ or when $l/d > 6.82$, and this only for steel like that of the experiments having an absolute strength not less than 7600 kilogs per sq centimetre

For columns with flat ends Love gives the formula

$$P = C\omega \sqrt{l/d + 35} \quad (11)$$

¹ This seems to me incorrect as Hodgkinson's formulae got at once into the text books—and have unfortunately remained there till to day

For columns of square cross-section Love multiplies the results (i) and (ii) by 1.53 as a factor in analogy with Hodgkinson's results for cast-iron¹.

These formulae may be compared with the empirical expressions for P in the case of columns of wrought-iron of circular cross-section which Love gives on p. 136. They are the following:

$$\text{For flat ends:} \quad P = \frac{C\omega}{1.55 + .0005 (l/d)^2},$$

$$\text{For rounded ends:} \quad P = \frac{C\omega}{.0012 (35 + l/d)^2}.$$

Such formulae may hold fairly closely for a limited range of experiments, but there ought to be great caution in applying them beyond that range, as their extreme diversity of form shows that they have no theoretical justification. I draw attention to them here only because such formulae are still frequently quoted in practical treatises on bridge-design often without the necessary note of caution; for example in Résal's *Ponts Métalliques*, Paris, 1885, p. 12. Love's insistence (p. 142 footnote) on the generality of his formulae does not seem to me warranted.

[979]. The remainder of the memoir consists of practical applications of these formulae and of a criticism of Euler's expression for the buckling load of struts (see our Arts. 74* and 649), which had been dogmatically applied to rupture.

Love concludes with throwing down the gauntlet to the theoretical elasticians in the following words:

Au reste, je reviendrai sur cette question dans un écrit auquel je mets en ce moment la dernière main, et qui traite de l'influence de la méthode spéculative en général, et de la spéculation mathématique en particulier sur le progrès des sciences d'application; et j'espère montrer que cette méthode, qui, en France, trône encore dans toutes les sciences et qui empêche l'avènement de la méthode baconienne, a été et continue d'être le plus grand obstacle aux progrès des sciences et de la société (p. 163).

[980.] William Fairbairn: *On the Resistance of Tubes to Collapse*. *Phil. Trans.*, 1858, pp. 389–413, with two plates. London, 1859. This memoir was read on May 20, 1858.

The experiments recorded in the memoir were undertaken at the joint request of the Royal Society and the British Association. The author thus describes their aim:

¹ I find by Art. 974 (d), that, if $w = \beta d^{1.5}/l^{1.63}$ and $w' = \beta' l^{1.5}/l^{1.63}$ for columns of circular and square cross-section respectively, then $\beta' = 1.42\beta$ and not 1.53 β .

Their object is to determine the laws which govern the strength of cylindrical vessels exposed to a uniform external force, and their immediate practical application in proportioning more accurately the flues of boilers for raising steam, which have hitherto been constructed on merely empirical data (p 389)

After referring to the great increase in the number of boiler-explosions owing to the rise of working pressure from 10 to 50 and even 150 lbs per sq inch, Fairbairn goes on to remark that it is impossible to treat flues, the ends of which are supported by rigid rings or securely fastened frames, as cylindrical tubes of indefinite length, or as tubes whose strength is unaffected by their length. He states that practical engineers have supposed boiler-flues to be equally strong at all parts of their length notwithstanding their built-in terminals, but that this is very far indeed, from the fact. Thus flues 35 feet long were found to be distorted under considerably less force than those 25 feet long (p 390)

Pp 390-2 describe the apparatus by which a large external pressure was applied to a tube. The air inside the tube was maintained at the atmospheric pressure by means of a small connecting pipe which also allowed the air to rush out on the collapse of the tube.

[981] The tubes to be experimented on were composed of single thin plates bent to the required form on a mandril and then riveted. They were also brazed to prevent leakage into the interior. The tubes were closed by cast-iron terminals, to which they were securely riveted and brazed. They were supported at one end by a rod from the cast-iron terminal of the tube to the lower cover of the hydraulic cylinder, and the other terminal was united by a pipe to the upper cover of the cylinder. Fairbairn seems to think that this rod and pipe screwed tightly up to the covers hindered the buckling action of the pressure on the cast-iron terminals of the tube, but the great increase of strength in one experiment in which an iron rod was placed inside the tube between the cast-iron terminals so as to prevent their approach appears to me¹ to indicate that the pressure on those terminals may in some cases have acted as a buckling force, and the collapse may not have been entirely due to the lateral pressure on the tube (cf Fairbairn's

¹ Fairbairn regards the increase as due to a thinning left in by mistake

experiment M. and second ftm. p. 393). This buckling action of the pressure would not occur in ordinary boiler flues.

[1882.] The first series of experiments were on tubes of 4, 6, 8, 10 and 12 inch diameters, and from 19 to 60 inches in length (pp. 392-6). The general conclusion is that the 'pressure of collapse' varies inversely as the length. The tubes appear in these cases to have been lap-jointed(?) and made of plates of .043 inches thickness. The forms of the collapsed tubes together with their cross-sections at positions of greatest collapse are depicted. The latter are generally star-shaped and of surprising regularity (up to even five angles).

The two tubes treated next were made of equal shape and size, but the one with a butt-joint and the other with a lap-joint. The one with a lap-joint showed more than $\frac{1}{3}$ less strength than that with a butt-joint, proving how much a slight deviation from the true circular form reduces the strength (pp. 396-7), and therefore how important it is to adhere to that form.

Fairbairn, as I have remarked, considered that his arrangement maintained a constant distance between the cast-iron ends of his tubes. He now gives some experiments in which the ends were left free to approach; in these no internal rod was placed inside the tube, nor were its ends connected with the covers of the enclosing cylinder. In these cases the pressure of collapse did not vary so exactly with the inverse of the length as in the previous results (pp. 397-8).

The experiments we have referred to up to this point were on tubes made of thin wrought-iron plates. The next three were on steel and iron tubes of somewhat different forms, and in each case with an internal longitudinal stay between the ends (pp. 399-400). These do not appear to be very conclusive. They were followed by two on elliptic tubes, which showed a great weakness as compared with circular tubes of like construction and size. Thus the strength was found to be less by one-half when a tube of circular section 60" in length, 12" diameter, and .043" thickness of plate was compared with one of the same length and thickness, but of elliptic cross-section 14" x 10 $\frac{1}{4}$ ". The experiments were, however, too few to be really of theoretical value.

[1883.] Fairbairn next turned to experiments on the strength of tubes subjected to internal pressure. The results are not very satisfactory for the data were too few. He concluded, however, that the strength was in this case, for lengths greater than one to two feet, nearly independent of the length for wrought-iron tubes; the difficulty arising from the fact that the tubes invariably gave way at the riveted joint was not overcome. The conclusion as to the bursting pressure being independent of the length was confirmed by experiments on leaden pipes (pp. 401-3).

[1884.] Pp. 403-10 are entitled: *Generalisation of the Results of the Experiments*. Fairbairn states that T. Tate and W. Unwin assisted

him in this matter. He assumes the following purely empirical formula for tubes collapsing under external pressure

$$p = C\tau^n / (ld),$$

where p = pressure in lbs per sq inch at collapse, τ = thickness of plate of tube in inches, d its diameter in inches (whether internal or external not stated, but the difference is a small percentage), and l its length in feet, C and n being constants to be determined from the experimental data (p 404)

For sheet iron tubes Fairbairn gives as the mean of his experiments

$$C = 806,300 \text{ and } n = 2.19$$

Approximately therefore we may take in practice

$$p = 806,300 \tau^2 / (ld)$$

Fairbairn considers that l ought to be limited in the more exact formula to values between 1.5 and 10 feet

For very thin tubes of 12" diameter, the divergence, however, is considerable, and Fairbairn accordingly gives the following formula as a closer approximation to the results of his experiments (p 408)

$$p = 806,300 \frac{\tau^{2.19}}{ld} - 0.02 \frac{d}{\tau}$$

Here the second term on the right is negligible for all but very thin tubes

It may well be doubted whether the experiments made by Fairbairn really permit of the generalisations involved in these formulae, and I feel inclined to lay still less stress on the formulae suggested for elliptic tubes, for riveted tubes subjected to internal pressure and for lead pipes given on pp 409-10. These are all based on the result of only two or three experiments, which cannot be considered as sufficing in such difficult and delicate matters

[985] On pp 410-13 Fairbairn states the practical conclusions as to boiler construction which may be drawn from his experiments. He points out that boiler flues are generally dangerously weak as compared with the outer shell of the boiler. Both have to resist the same pressure, but the rupture pressure of the former is given by

$$p = 806,300 \tau^{2.19} / (ld),$$

and that of the latter by $p' = 60,000 \tau / d$. Hence we have for tubes of the same thickness and diameter

$$p' / p = \frac{1}{13.44} \frac{l}{\tau^{1.19}}$$

So that the maximum internal pressure p' is greater than the maximum external pressure p , whenever (l in feet and τ in inches)

$$l > 13.44 \tau^{1.19}$$

In order to equalise the strengths of the shell and flues, Fairbairn suggests (1) that butt joints with longitudinal covering plates should be used, and (2) that strong angle iron ribs in the form of rings

conclusive experiments on the relative resistances to impact by a falling mass, to blows from a hammer and to torsion of hollow and solid railway wagon axles.

[990.] Kaumann: *Versuche über die Durchbiegung und die Elasticitätsgrenze für Axen der Eisenbahnfahrzeuge. Erbkams Zeitschrift für Bauwesen*, Jahrgang v., S. 412. Berlin, 1855. *Polytechnisches Centralblatt*, Jahrgang 1855, Cols. 1107—1110. The axles were clamped at any chosen cross-section and loaded as cantilevers. The flexures and the elastic limits were then noted. The paper contains nothing of permanent value.

[991.] A. von Burg: *Ueber die von dem Civil-Ingenieur Hrn. Kohn angestellten Versuche, um den Einfluss oft wiederholter Torsionen auf den Molekularzustand des Schmiedeeisens auszumitteln. Wiener Sitzungsberichte*. Bd. VI., S. 149—52. Wien, 1851. This paper contains a very brief and insufficient account of Kohn's experiments on repeated small torsions. Another account is given in the *Zeitschrift des österr. Ingenieur-Vereins*, Jahrgang iii., 1851, S. 35. But the most satisfactory description of the experiments and apparatus will be found in the memoir discussed in the following article.

[992.] A. Schrötter: *Ist die krystallinische Textur des Eisens von Einfluss auf sein Vermögen magnetisch zu werden? Wiener Sitzungsberichte*. Bd. XXIII., S. 472—81. Wien, 1857.

This paper gives a very good account of the manner in which Kohn's experiments were made. In the first series a rotating wheel had three teeth, each producing a small torsion in the bar or spindle under test and then suddenly releasing it from all load. In the second series the wheel was replaced by an eccentric, and thus the torsion was gradually imposed and removed. More than 32,000 torsions were given in the course of an hour, that is to say as many as nine a second. It seems to me, then, very probable that there may have been an 'accumulation of strain,' i.e. it does not follow that because each individual total torsion gave a *mean* torsion which was below the elastic limit, that the bar or spindle was never subjected at any one point to strain beyond the elastic limit¹. Waves of torsional strain would move

¹ I have calculated the value of this accumulation of strain, which can easily amount to two or three times that due to the individual total torsions supposing them to be applied statically. My results were communicated to the *Cambridge Philosophical Society* in 1888, but have not hitherto been published.

backwards and forwards along the bar and would hardly become insignificant in $1/9$ of a second. Seven bars were first experimented on and then broken at different stages by a hydraulic press after the loading had been repeated from 32,000 up to over 128,000,000 times. Each bar was bent into a right-angular form ABC , A was built-in, B was embraced by a socket which allowed free rotation of the bar, AB was the vertical part of the bar receiving torsion by means of the horizontal bar BC , which was acted upon at C by the toothed wheel or eccentric. The cross-sections after rupture were examined with a lens. The seven bars gave the following results with the toothed wheel

(i) After 32,400 torsions no change was observable in either AB or BC

(ii) After 129,600 torsions no change was visible to the naked eye, but in AB the lens showed the fibrous structure already broken and as *ein Aggregat von feinen Nadeln*

(iii) After 388,800 torsions the change in AB was visible to the naked eye and the rupture surface was *grobkornig*

(iv) After 3,888,000 torsions, the whole length of AB was affected, especially at the middle section, which we are told is the place of greatest torsion. But why it should be so, is not shown, and it does not seem theoretically probable

(v) After 23,328,000 torsions the rupture surfaces in AB were *sehr grobkornig* but showed still no *Blättchen*

In all these cases the horizontal arm BC had shown no change in its rupture surfaces owing to the flexural vibrations it was subjected to

(vi) After 78,732,000 torsions the bar AB showed, especially when ruptured at its central cross section, a remarkable change, the rupture surfaces were similar to those of cast zinc, and at the same time the horizontal arm BC began to alter its structure

(vii) After 128,309,000 repeated torsions (occupying thirteen months) the bar AB showed no further change at its centre, only sections nearer to the ends began also to be *grossblättriger*. The horizontal arm BC also advanced in its structural changes

Similar results were obtained with the eccentric, only the number of torsions had to be greater to produce the same changes

[993] Schrotter concludes from these results

(i) That repeated torsions can change the structure of a bar from fibrous to crystalline and then to *blättrig*, and that the absolute strength decreases during these changes

(ii) That the number of torsions required depends upon their magnitude. (He deduces this from the fact that the changes occur

first at the centre of the bar AB , according to him the place of maximum torsion, but if we do not accept this hypothesis, the statement is still doubtless true.)

(iii) Impacts increase the effect of torsion, or without torsion produce ultimately the same structural changes.

(iv) The changes were due to mechanical action and not to the influence of variations in temperature.

The general conclusion then to be drawn from these results is the gradual destruction of wrought-iron by change of structure due to *rapidly* repeated loading or repeated vibratory impacts.

[994.] Schrötter applied to the *k. k. Handelsministerium* with a view to the institution of experiments to ascertain whether the magnetic properties of a bar of iron were changed by several million repeated torsions. If they were so, a ready means would have been found for testing the loss of strength due to such loading. These experiments were ultimately undertaken by Miltzer on five bars which had been subjected respectively to no strain, and in round numbers to 4, 23, 29 and 79 million repeated torsions, and an account of these experiments is given on S. 477–80. The conclusions to be drawn from these experiments—supposing we adopt the theory that repeated loading changes iron from fibrous to crystalline are:—

That this important molecular change corresponds to no marked alteration in the capacity of the bar either: (i) to be magnetised by an electric current, or, (ii) to retain magnetism on the cessation of the current.

Miltzer's field appears to have been a high one. A *few* torsions certainly change magnetic properties in a weak field and this without appreciable change of the mechanical properties: see our Arts. 714, (12)–(14), and 811–4.

[995.] *Ueber Gussstahl-Achsen. Dinglers Polytechnisches Journal*, Bd. 146, S. 65–8. Stuttgart, 1857. This paper gives the details of experiments made at the *Gussstahlfabrik des Bochumer Vereins für Bergbau und Gussstahlfabrication* on cast-steel railway axles. A weight of 1403 pounds was dropped from heights of from 3 to 36 feet upon the axles supported at points 3 feet apart. The flexural sets were noted, and after each few blows the top and bottom fibres of the axle were reversed. With this reversal 5 or 6 blows from 36 feet destroyed the axles tested.

[996.] H. Résal: *Note sur les formules à employer dans les épreuves des essieux de l'artillerie. Annales des mines*, Tome XIII., pp. 497–503. Paris, 1858.

The axles were tested by dropping a given weight upon them while they were simply supported at their ends. Résal gives a theory of this sort of impact, but as his theory depends solely on the principle of work and on Cox's hypothesis that the beam retains under central

impact the statical form of the elastic line, it is not very satisfactory. The whole matter has been more thoroughly investigated by Saint-Venant see our Arts 362-71 and 410


[997] Wohler *Bericht über die Versuche, welche auf der Königl. Niederschlesisch-Märkischen Eisenbahn mit Apparaten zum Messen der Biegung und Verdrehung von Eisenbahnwagen-Achsen während der Fahrt, angestellt wurden* *Erbkams Zeitschrift für Bauwesen*, Jahrgang viii, S 642-52 Berlin, 1858

This paper describes the first investigations of Wohler on the repeated loading of railway axles, and not only is of historical interest as leading up to his later more important researches, but contains in itself much that is of considerable value. It should be read in conjunction with the memoir on the theory of axles referred to in our Arts 957-9

[998] Wohler designed two pieces of apparatus to measure respectively the flexure and torsion of the axles of railway wagons performing their usual service. The first apparatus, designed to measure flexure, recorded automatically the maximum approach and separation of two opposite points on the wheels, and by halving this it is obviously easy, supposing the flexure of the wheels insensible, to calculate the maximum flexure of the axle. The amount through which the point on each wheel was shifted was measured by a separate instrument, which recorded the shift by a needle scratching a slip of zinc. Wohler remarks

Beide Apparate zum Messen der Biegung sind so construirt, dass 1 Zoll Zeiger Ausschlag während der Fahrt einer Bewegung ac am Umfange des Rades von $\frac{3}{16}$ Zoll oder einer Abweichung am von der normalen Lage von $\frac{3}{32}$ Zoll entspricht

Die Seitenkraft, welche am Umfange des Rades angebracht werden muss, um eine gleiche Biegung der Achse, also einen einseitigen Zeiger Ausschlag von $\frac{1}{2}$ Zoll hervorzubringen, ist für die Achsen von $3\frac{3}{4}$ Zoll Durchmesser in der Nähe, mit Rädern von $36\frac{1}{4}$ Zoll Durchmesser, = $23\frac{1}{2}$ Centner¹, und für die Achsen von 5 Zoll Durchmesser in der Nähe, mit Rädern von $36\frac{3}{4}$ Zoll Durchmesser, = $70\frac{1}{2}$ Centner (S 641)



¹ The Centner = one hundredweight or presumably 100 Prussian lbs = 103 English lbs

This *Seitenkraft* was ascertained by connecting opposite points on the rims of the wheels by a chain containing a dynamometer and then pulling them together. This does not seem to me an entirely satisfactory process. In the first place the axle is really bent by a couple on either journal. This couple changes, owing to unevenness in the permanent way, jolting, etc. during the journey. The ordinary load produces a certain flexure in the axle when the wagon is at rest; the same load applied, as it is, in *alternate* directions during the rapid rotation of the axle, we should expect to produce at least *twice* the flexure of the statical couple even if the way were perfectly level. Wöhler does not distinguish between the flexure produced by the ordinary load applied in alternate directions and the flexure which may arise by way of variation due to unevenness in the way, etc. Further, his dynamometer did not act as a couple applied to the journals would have done, but it would include in the shifts measured by his apparatus the flexure of the wheels themselves. Thus while it would measure the load corresponding to flexure produced by side pressure on the flanges of the wheels, it does not seem to me to have suitably recorded the flexure of the axle due to statical dead load or to variations in the journal couples due to motion. Indeed Wöhler appears to neglect the flexure due to statical dead-load, otherwise he ought surely to have stated whether the dynamometer was applied while the dead-load was on the journals and in what plane it was applied, as it might tend to increase or decrease the dead-load flexure according to the position of that plane. If the flexure due to dead-load was negligible, as compared with the vibratory flexure, then this ought certainly to have been stated. Was there no motion of the recording needle on the zinc when the axle was *slowly* turned round?

[999.] The apparatus for torsion measured only what might be termed the *integral* torsion of the axle, i.e. the angle one wheel had been rotated relative to the other. But if the inertia of the axle itself be taken into account, and this might be necessary with an axle of 5 inch diameter, then any impulsive couple applied simultaneously to both wheels would produce a torsion in the axle relative to the central cross-section, which would not be measured

by Wohler's apparatus¹ It ought to have been shown that this torsion was in itself negligible As first one wheel and then the other may lag, Wohler's apparatus records twice the maximum integral torsion

Der Apparat an der Achse von $3\frac{3}{4}$ Zoll Durchmesser ist so construiert dass 1 Zoll Zeiger-Ausschlag einer Bewegung von 321 Zoll am Umfange des Rades von $36\frac{1}{4}$ Zoll Durchmesser entspricht, gegen die normale Lage des Rades betragt also die Grosse der Bogen-Abweichung 160 Zoll, oder der Torsionswinkel 30 Minuten

Zu einer solchen Verdrehung ist eine am Umfange des Rades wirkende Kraft von $18\frac{3}{4}$ Centner erforderlich

Bei dem Apparat der Achsen von 5 Zoll Durchmesser in der Nabe, deren Rader $36\frac{3}{4}$ Zoll Durchmesser haben, ist auf 1 Zoll Zeiger Ausschlag die Bewegung am Umfange des Rades = 228 Zoll, die Abweichung gegen die normale Lage also 114 Zoll, und der Torsionswinkel = 21 Minuten Um eine solche Verdrehung hervorzubringen, ist eine am Umfange des Rades wirkende Kraft von 44 Centner erforderlich (S 642)

[1000] Wohler, having now measured the motion of his recording needles in terms of the force applied to the rim of the wheels, is able at once to reduce their *half*-maximum records to equivalent loads, and then to calculate from these loads the stresses in the axles The journeys were made from Breslau, chiefly to Berlin and back, but also to Liegnitz, Lissa and Frankfurt The wagons were four- and six-wheeled coal and covered goods wagons, and with two exceptions ran with goods trains The axles were $3\frac{3}{4}$ " steel and 5" iron axles The wagons were not reversed before the return journey so that the axle experimented on was sometimes a fore- and sometimes a hind-axle The weight of the wagons, their loads and dimensions are all recorded

Wohler gives no details of the calculations by which he deduces the flexural stress ('Faserspannung') from the equivalent load Thus he says that a rim load of 72 centners on the wheel of $36\frac{1}{4}$ " diameter for an axle of $3\frac{3}{4}$ " diameter produces a maximum stress of 252 centners per square inch This can be easily verified if it be noted that T' the effective stress is connected with C the rim load by the formula

$$T' = \frac{16}{\pi} \frac{d}{\Delta^3} \times C,$$

¹ I have calculated the numerical value of this torsion in the paper referred to in the footnote of our p 669 It is there shown to be practically small but the torsional differences noted by Wohler were also small

where Δ is the diameter of the axle and d of the wheel, the longitudinal stress due to C being neglected. For the torsion of the same wheel, Wöhler says a rim-load of $29\frac{1}{16}$ centners produces a '*Spannung der äussersten Fasern*' of 52 centners.

Now if S be the *shear* and not the traction at the 'outer fibre' I find

$$S = \frac{8}{\pi} \frac{d}{\Delta^3} \times C,$$

and S has the value 52 centners.

So that there is a radical difference between the two stresses of 252 and 52 centners both of which Wöhler speaks of as *Faserspannung*. He proceeds as follows :

Die Möglichkeit des Falles vorausgesetzt, dass die grössten Kräfte auf Biegung und auf Verdrehung gleichzeitig wirkten, ist dann nach den vorstehend ermittelten Zahlen die grösste aus diesem Zusammenwirken resultirende *Faserspannung der Achse* $= \sqrt{252^2 + 52^2} = 257$ Centner pro □ Zoll (S. 644).

I do not understand why the maximum stress at any point should be the square root of the sum of the squares of the maximum traction and shear.

The maximum stretch s_0 is, I think, given by

$$s_0 = \sqrt{\frac{T^2}{E^2} + \frac{1}{4} \frac{S^2}{\mu^2}},$$

and therefore the maximum traction, which is not of course in the direction of the 'fibre', by

$$T_0 = Es_0 = \sqrt{T^2 + \frac{1}{4} \frac{E^2}{\mu^2} S^2};$$

or, for uniconstant isotropy,

$$T_0 = \sqrt{T^2 + \frac{2}{16} \frac{E^2}{\mu^2} S^2}.$$

In Wöhler's results the smallness of S as compared with T enables us practically to neglect its effect on the maximum stress.

Wöhler remarks that the maximum stress of 257 centners in these cast-steel axles of $3\frac{3}{4}$ " diameter would have produced set in iron axles, the elastic limit of which he takes at 180 centners per □".

The above results were for four-wheeled wagons. For six-wheeled wagons he found that these stresses were increased in the ratio of 6 : 5 ; while for covered four-wheeled as compared with open four-wheeled wagons they were increased as 10 : 9.

For the 5" diameter axle the maximum traction was 156 centners and the maximum shear 35 centners, so that the result appears rather close to the elastic limit of iron as stated by Wöhler above. Further, with these axles the maximum stress seems to have been often repeated. Wohler reduces these stresses to percentages of the total load of wagon and cargo (S. 646).

[1001] The number of repetitions of the maximum stress does not, Wohler considers, exceed one per German mile¹, and he reckons the life of an axle at 200,000 miles. Hence he reduces his problem to the following one: To how great recurring positive and negative stresses can an axle of given dimensions be subjected 200,000 times without its breaking? He describes (S 647–8) the method by which he proposes to answer experimentally this problem. Thus we see the origin of his later experiments on repeated loading. Two points are to be noticed in the problem as Wohler states it. First, he supposes that all loads less than the maximum (and therefore unrecorded by his apparatus) do not contribute to the destruction of the axle. Secondly, he takes no account of the rapidity with which the loads are repeated. Would 200,000 loadings and reloadings of an axle in a day represent the same wear as 200,000 like maximum loadings occurring while the axle was running 200,000 miles, that is, spread out over its whole life? —I believe not. A load repeated many times a minute may lead to a vibratory accumulation of stress, this accumulation is impossible if the same load recurs only at long intervals. For both these reasons Wohler's latter experiments do not seem to me so useful as they might otherwise have been.

The memoir concludes with tables of the numerical details of the experiments (S 647–52).

[1002] Wohler *Versuche zur Ermittlung der auf die Eisenbahnwagen-Achsen einwirkenden Kräfte und der Widerstandsfähigkeit der Wagen-Achsen*. *Erbkams Zeitschrift für Bauwesen*, Jahrgang x, S 583–616. Berlin, 1860. The first portion of this memoir (S 583–6) is entitled *Versuche zur Ermittlung der auf die Wagen-Achsen einwirkenden Kräfte*, and it details experiments made with a slightly modified form of the apparatus referred to in our Arts 998–1000, necessitated by its application to the carriages of passenger trains moving at a greater speed. Only flexure experiments were made as it was considered that the first set of experiments had demonstrated that the torsional stress was of small account. In the case of the axles of passenger carriages the maximum stress in a 4 5" iron axle was found to be 173 centners per sq. in., and it was reckoned that the mean stress was from 80 to 110 centners.

¹ About five English miles.

Ein Durchmesser der Achse von 4·5 Zoll in der Nabe darf daher bei Wagen der Art, wie der benutzte, für vollkommen ausreichend erachtet werden (S. 586).

The details of the experiments on the axles of passenger carriages are given on S. 603-4. Further experiments, confirmatory of the previous ones, on the $3\frac{3}{4}$ " steel and 5" iron axles of goods wagons are given on S. 601-2.

[1003.] The second part of the paper is entitled: *Versuche zur Ermittlung der Widerstandsfähigkeit der Wagen-Achsen* (S. 586-600 with tables of results S. 605-16).

These are Wöhler's first series of experiments on repeated loading, and we postpone their consideration for the present, in order to deal with his complete researches in the decade 1860-70. The present experiments are on repeated flexure and the stress changed from zero to its maximum positive value through zero to its maximum negative value, and then back to zero again, once in about every four seconds (S. 586). Other matters in the memoir, not exactly bearing on repeated loading, are the erroneous treatment of the stretch-squeeze ratio on S. 592 where it is assumed that the volume of a bar under flexure does not change, the deduction of the form of the strained cross-section, and a not very lucid discussion of the relation of set to elastic strain. Wöhler holds that elastic strain is always in linear proportion to stress, and is in itself quite independent of the amount of set (S. 600).

GROUP D.

Memoirs relating more especially to Bridge Structure.

[1004.] F. W. Schwedler: *Theorie der Brückenbalkensysteme*. *Erbkams Zeitschrift für Bauwesen*, Jahrgang I., S. 114-123, 162-173, 265-278. Berlin, 1851.

The first part of this paper is purely theoretical, but does not present any novelty; the second deals with braced girders in general; and the third applies the rather complex formulæ obtained to special systems (Neville's and Town's girders, and to Stephenson's and Fairbairn's tubes). There are no numerical examples, and I doubt some of the statements made (e.g. S. 277) and see little advantage in others.

[1005] A series of papers also by Schwedler on the analytical calculation of stress in the members of latticed girders (*gitterförmige Träger*) will be found in *Zeitschrift des Vereins deutscher Ingenieure*, Jahrgang III, S 37, 96, 135, 233, 297 (Berlin, 1859), but they have little real bearing on the theories of elasticity or of the strength of materials

[1006] Baensch *Zur Theorie der Brückenbalkensysteme* *Erbskams Zeitschrift für Bauwesen*, Jahrgang VII, S 35-50, 145-156, 289-308 Berlin, 1857 This memoir professes to be a continuation of F W Schwedler's paper in the volume for 1851 of the same *Zeitschrift* see our Art. 1004 It applies the Bernoulli Eulerian theory of beams to various cases of simple beams, to a few continuous beams, and to some cases of braced girders There is a great deal of analysis in the paper, but from the theoretical standpoint no novelty It may well be questioned whether practically it would not be easier to work out *ab initio* the theory of any given girder than to endeavour to apply formulæ obtained in a memoir of this type for a great variety of special cases, none of which may really fit the exact type of girder it is required to construct

[1007] *Institution of Civil Engineers Minutes of Proceedings* Vol XI, pp 227-232, 1851-52 Appendix to a paper by A S Jee entitled *Description of an Iron Viaduct erected at Manchester*

This Appendix gives the details of experiments on cast iron girders of varying cross section so far as deflection and set are concerned—these were of **I** section, also the details of experiments on wrought iron tubular girders—these latter might be described as **I** girders in which the upper flange was replaced by a tube of circular section to prevent buckling

Further experiments by J Hawkshaw on the absolute strength, deflection, etc of other **I** cast iron girders will be found on pp 242-3

[1008] *British Association, 1852, Belfast Meeting, Transactions*, pp 126-7 T M Gladstone gave some notes on the superior safety of malleable to cast-iron girders He considered the reduction in weight compensated for the difference in price He also treated of the proper relation between depth and span for a particular **I** section, apparently however for the case of a special load

[1009] Poncelet *Examen critique et historique des principales théories ou solutions concernant l'équilibre des voûtes Comptes rendus*, T XXXV, pp 494-502, pp 531-540, and pp 577-587 Paris, 1852

This is a very valuable criticism of the various theories of the arch propounded up to 1852, and is of peculiar interest as noting the extent to which these theories had influenced the practice of the

De Clercq, Winkler, nor Wöhler take into account in their analysis (see our Arts. 1017, 1026 and 1028). In all cases the theoretical stresses in the bracing bars are calculated and tabulated. The experiments show the great increase of strength due to multiple-bracing and to the riveting together of the bracing bars. Lohse does not consider his experiments numerous enough for him to propound any general formula, but the numerical details and the general results are perhaps more likely to be of practical service than the lengthy analytical investigations to which we have previously referred.

[1020]. G. Wolters: *Résumé des résultats obtenus dans les épreuves de quelques ponts en fer. Annales des travaux publics de Belgique*, Tome xv., pp. 145-75. Bruxelles, 1856-7. This is translated into German under the title *Bericht über die Ergebnisse der Belastungsproben einiger eiserner Brücken* in the *Zeitschrift des österreichischen Ingenieur-Vereins*, Jahrgang x., S. 185-195. Wien, 1858. It gives details of experimental determinations of the deflection of various railway bridges in Flanders. The girders of the bridges were chiefly of cast-iron with openings in the web; there was one of plate-iron. The results do not seem to have any permanent theoretical importance.

[1021.] In the same volume of the *Annales* is an article by Houbotte entitled: *Expériences sur la résistance des longerons en tôle* (pp. 403-26). It is translated into German in the same volume of the *Zeitschrift*, S. 195-201. The girders were of plate-iron, and the object of the experiments described was to test the best relative dimensions for the flanges and web in the case of girders of **I** section. The span of the model girders was from 1.5 m. to 3 m. and their heights varied from 2 to 4.9 m. The load upon them was gradually increased up to rupture during a period amounting in some cases to several weeks; the duration of load, the elastic and set deflections were all noted. There is also one set of experiments on a girder in which the web was replaced by bracing. Houbotte concludes from this experiment that the bracing is more efficient than the plate-web. The rupture occurred in the plate girders by buckling of the web. Houbotte endeavours to construct a formula which will give the proper strength for the web of such a girder, but neither the range of experiments nor his method of obtaining his formula seems very satisfactory.

[1022.] A number of articles by J. Langer on wooden and iron lattice girders, the latter in the form of arches with braced ribs, etc. will be found in the *Zeitschrift des österreichischen Ingenieur-Vereins*, Jahrgang x., S. 113, 135, 152. Wien, 1858-9. Jahrgang xi., S. 69, 127, 153, 186, 206. Wien, 1859. These give a lengthy theory of the braced arch. Further projects for braced arches will be found in Jahrgang xii., S. 29, 91, 125 and 193. In several of these projects,

graphical methods might now be usefully employed. The designs would form very good exercises in the calculation of stresses for advanced engineering students even at the present day.

[1023] Thomas Davies *Wrought and Cast Iron Beams* *The Civil Engineer and Architect's Journal*, Vol. xx, pp. 20–23, and pp. 41–44. London, 1857. This paper was read at a meeting of the Architectural Institute in Edinburgh, February, 1856.

It commences with some account of the want of confidence felt in cast-iron beams, and of the superiority of malleable iron beams owing to their lightness and sensible yielding before rupture. Fairbairn having given in his work on cast- and wrought iron only one experiment on a "plate beam" (one of I section?) Davies proposes to supply this want of information with regard to the strength and elastic properties of wrought-iron beams, in order that they may be more generally understood and adopted.

The experiments given in the first part of the paper may have technical, but they hardly have theoretical or physical value, the load was applied over as much as $\frac{1}{6}$ of the length of the beam, and was brought into play by putting on the top flange iron railway bars "requiring two men at each end to lift them." The author agrees with Tate that the upper and lower flanges of a wrought iron beam should have practically equal areas (p. 23).

The second portion of the paper criticises the results of Hodgkinson's experiments on the beam of greatest strength—see our Arts. 244*, 875 and 1016. The writer contends that the ratio of the sectional area of the flanges ought to be as 3.5 or 3 to 1 and not 6 to 1 as suggested by Hodgkinson. He enters into no theoretical investigation of the strength of such beams, nor does he adduce any experimental evidence beyond Hodgkinson's. He considers Hodgkinson's results erroneous because the latter left out of account the difference in the thicknesses of the webs of his individual beams when deducing conclusions from his experiments. It seems to me that Hodgkinson was right and quite justified in doing this, as the web added little to the flexural strength of the beam. Thus the ratio of the areas of the flanges ought to be nearly that of the compressive to the tensile strength of cast-iron, i.e. according to Hodgkinson about 6 to 1.

[1024] Decomble *Sur les meilleures formes à donner aux poutres droites en fonte* *Annales des ponts et chaussées*, 2^e Semestre, pp. 257–319. Paris, 1857.

This is a long memoir investigating a theory of the solid of greatest resistance, when the tensile and compressive strengths of the material are supposed different, and the solid is designed so that the ruptures are stretched and squeezed 'fibres' occur at the same load. Apart from the assumption involved in applying the theory of elasticity to the phenomenon of rupture, the discussion seems in several points very doubtful, and all that can be reached of value by a theory of this

kind has been better given by Saint-Venant in his *Leçons de Navier*, pp. 102, 142–56, and our Arts. 176, 177, (b). There are, however, a number of interesting experiments on the rupture of cast-iron beams of various shapes and cross-sections, which may possibly have practical value still. The editors of the *Annales* remark in a note appended to the memoir :

Quoique la partie théorique du mémoire précédent soit en opposition, sur plusieurs points, avec les principes généralement admis, la commission des *Annales* a cru devoir le publier tel qu'il a été présenté par l'auteur, à raison des détails intéressants qu'il renferme sur les poutres en fonte et sur le moulage de la fonte en général (p. 319).

[1025.] *British Association. Report of Twenty-Seventh* (Dublin) *Meeting*, 1857.

The titles of two articles in this *Report* may be noticed: C. Vignoles: *On the Adaption of Suspension Bridges to sustain the passage of Railway Trains*, pp. 154–158. P. W. Barlow: *On the Mechanical Effect of combining Girders and Suspension Chains, and a comparison of the weight of Metal in Ordinary and Suspension Girders, to produce equal deflections with a given load*, pp. 238–48. Both these papers discuss the adaption or modification of suspension bridges when built for the transit of railway trains. They turn principally on stiffening the platform till it becomes a girder, or on special arrangements of the suspending bars. The bridges at Niagara and elsewhere built as girder suspension-bridges, had gone far to destroy the old mistrust in suspension-bridges for railway traffic; and the authors of the above papers endeavour to show that equal strength may be obtained with far less material from a suspension-girder than from a pure girder bridge.

[1026.] G. A. De Clercq: *Note sur les phénomènes de la flexion des poutres en treillis. Annales des travaux publics de Belgique*, T. xv., pp. 198–214. Bruxelles, 1856–7.

This is another of those memoirs which deal with the lattice-girders, which were rapidly taking the place of the older double-T girders with a solid web. The writer of the memoir supposes the bracing bars rigidly attached to the booms, and deduces by what does not seem to me very conclusive reasoning, that a bracing bar after flexure will take the form of a spiral of Archimedes (p. 201). C. Winkler (see our Art. 1028) had, I think, read De Clercq before writing the second part of his paper; he extends, however, the latter's results. The present paper is clearly written as compared with Winkler's, but it deals with a simpler case. At the same time to consider the special conclusions deduced by both these writers from their somewhat doubtful hypotheses would carry us beyond our limits.

[1027.] C. Knoll: *Zur Theorie der Gitterbalken. Eisenbahn-Zeitung*, Jahrgang xvi., S. 13–5. Stuttgart, 1859. This is an analytical

calculation of the stresses in the bracing of lattice girders with straight parallel booms

[1028] C Winkler *Theorie der eisernen Gitterträger* Forsters *Allgemeine Bauzeitung* Jahrgang xxiv, S 191–222 Wien, 1859

This memoir on lattice-girders is divided into two parts. The first deals with the stresses in the booms and bracing bars when the bracing bars are not riveted to each other. In this case we have only to consider the flexure of the booms, for the bracing bars are, if buckling be excluded, in pure tensile or compressive stress. Winkler proceeds analytically to the discussion of the stresses, and points out an error of Scheffler's (see our Art 651). The treatment appears sound, and the results, although having only special technical interest and application, may still be of service (S 191–9).

In the second part of the memoir the bracing bars are supposed riveted or pinned where they cross each other, and the result is that these bars are now subjected to flexure. The calculations, here of course necessarily analytical, become more complex, and I confine myself to referring to Winkler's analysis which I have not verified (S 199–206). How far his fundamental hypotheses—similar to those of De Clercq (see our Art 1026),—approach the truth, especially for the second case stated on S 199–200, I have no means of judging, they seem to me somewhat bold, not to say dubious. The memoir concludes with the application of the results obtained to a number of numerical cases of lattice girders (pp 206–22). The *exact* treatment of these lattice-girders, in which the frames have a great number of supernumerary bars, would be an extremely difficult analytical problem.

[1029] B B Stoney *On the Application of some new Formulae to the Calculation of Strains in braced Girders* *Proceedings of the Royal Irish Academy*, Vol VII, pp 165–172 Dublin, 1862. This paper was read in 1859.

Pp 165–9 deal by the simplest statical methods with the stresses in the diagonal bracing of a Warren girder when some or all of the nodes at the upper boom are loaded. There is nothing that calls for special comment.

Pp 169–72 treat of *Lattice Girders* and use only ordinary statical processes. The discussion, however, seems to me obscure, especially the final paragraph. It is in many cases impossible to find the *exact* stresses in lattice girders without appeal to the theory of elasticity, and this point does not seem to have been recognised by Stoney.

[1030] Another paper by B B Stoney may be just referred to here: it is entitled *On the Relative Deflection of Lattice and Plate Girders* and is published in the *Transactions of the Royal Academy*, Vol xxiv, pp 189–93 of Part I, *Science* Dublin, 1871. The paper was read June 23, 1862. It does not seem to contain anything of sufficient theoretical interest or experimental value to require special notice.

[1031.] J. G. Lynde: *Experiments on the Strength of Cast-Iron Girders*. This paper was read before the Manchester Literary and Philosophical Society. An abstract of it will be found in *The Civil Engineer and Architect's Journal*, Vol. xxii., pp. 386-7. London, 1859.

Lynde made experiments on 89 girders, cast on their sides, and of the form recommended by Hodgkinson as that of strongest section (see our Art. 244*). One girder only was tested up to rupture, and Lynde remarks that no permanent set was visible up to that point (!). The girders were of large size (30 ft. 9 in. in span).

Hodgkinson (*Experimental Researches on Cast-Iron*, Art. 146) had given the following formula for W , the breaking central load in tons:

$$W = \frac{2}{3dl} \{bd^3 - (b - b') d'^3\},$$

where: l = span in feet,

b = breadth of bottom flange in inches,

b' = thickness of web in inches,

d = whole depth in inches,

d' = depth from the top of the beam to the upper side of the bottom flange in inches.

Lynde's single experiment on rupture would go to show that the coefficient $2/3$ is too large for a large beam and should be replaced by $\cdot 625$, as suggested by Hodgkinson himself in his Art. 147 for *large* beams.

[1032.] Marqfoy: *Mémoire sur les essais des ponts en tôle par l'électricité*. *Annales des ponts et chaussées*, 1859, 2^e Semestre, pp. 74-89. Paris, 1859. This paper describes an apparatus for recording the deflection at various points of bridges under a rapidly moving load.

[1033.] Noyon: *Notice sur la restauration et la consolidation de la suspension du pont de la Roche-Bernard*. This paper is in the same volume of the *Annales*, pp. 249-329. It gives an account of the accident to this suspension bridge (see our Art. 936*) and also details of numerous experiments on the absolute strength of iron wire and cables.

[1034.] In the same periodical in the volume for 1860, 2^e Semestre, are two articles on bridges which touch the limits of our subject. The first by Jouravski, entitled, *Remarques sur les pontres en treillis et les pontres pleines en tôle*, pp. 113-34, discusses in general terms the vibrations which occur in such bridges and their strength; the second by Manton, *Étude de la partie métallique du pont construit sur le canal Saint-Denis...* pp. 161-251, gives a very full theoretical determination of the stresses etc. in all the different parts of a particular bridge.

[1035.] W. Fairbairn: *Experiments to determine the Effect of Vibratory Action and long-continued Changes of Load upon*

Wrought-iron Girders, pp 45-8 *British Association, Report of Thirtieth (Oxford) Meeting, 1860*

The experiments were made on a double-T plate girder of 20 feet span, the flanges being built up of plates and angle-irons, the total depth of section was 16" and the calculated breaking weight 12 tons. The load was applied at the mid-section of the girder in a gradual manner at the rate of about eight changes per minute with the following results

Load	Number of loadings	Total number of loadings	Mean Deflection
About 3 tons	596,790	596,790	17"
About 3 5 tons	403,210	1,000,000	22"
About 4 8 tons	5,175	1,005,175	35" (broke)

The beam was repaired after the last load and 1,500,000 additional loadings were given to it with a load of about 3 tons without its giving way

It would appear, therefore, that with a load of this magnitude the structure undergoes no deterioration in its molecular structure, and provided a sufficient margin of strength is given, say from five to six times the working load, there is every reason to believe, from the results of the above experiments, that girders composed of good material and of sound workmanship are indestructible so far as regards mere vibratory action (p 48)

It will be noted that Fairbairn's experiments differ from Wohler's in their *slowness of repetition*, there was very little opportunity for accumulation of stress

[1036] P Fink *Allgemeine Betrachtungen über Biegezugfestigkeit und Biegezugwiderstand zur Erzielung eines einheitlichen Standpunktes für die Beurtheilung verschiedener Bruchsysteme Zeitschrift des österreichischen Ingenieur Vereins, Jahrgang VII, S 40, 69-77, 204-211* Wien, 1860 This paper does not seem to convey any information beyond what may be deduced from the ordinary Bernoulli Eulerian theory of beams when the load is not perpendicular to the axis. I have made no attempt to investigate the accuracy of the lengthy formulae with which the moment bounds

GROUP E.

Researches on the Strength of Cannon and of Materials for Ordnance.

[1037.] *Reports of Experiments on the Strength and other Properties of Metals for Cannon, with a Description of the Machines for testing Metals, and of the Classification of Cannon in Service, by Officers of the Ordnance Department, U. S. Army.* Philadelphia, 1856. This folio volume of 428 pages is the first batch of a series of valuable technical researches in elasticity due to the United States Government. The more important portion of the present work is due to Major W. Wade, and it is sometimes cited as Wade: *On the Strength of Metals for Cannon.* A further group of reports by Rodman will be dealt with in the period 1860–70. The value for us of these reports lies not in their details as to cast-iron and bronze ordnance, which probably have little more than historical interest at the present day, but in the numerous experimental investigations on the strength of materials which are embraced in their pages. We can only afford space to note briefly some few of the facts recorded.

[1038.] The first report deals with cast-iron, and particularly, with the influence of the time of fusion and the number of meltings upon the strength. We mark the following conclusions:

(a) A prolonged exposure of liquid iron to intense heat augments its absolute strength. The strength increases as the time of exposure up to some not well ascertained limit between 3 and 4 hours (?). This result does not seem to be based on a sufficiently large range of experiments. The experiments made were on 8 cast-iron guns tested up to bursting (pp. 11–17).

(b) In experiments on the transverse strength of cast-iron bars it was found that the absolute strength as deduced from bars of circular cross-section was uniformly much higher than that from those of square cross-section cast from the same kind of iron. This is part of the old 'paradox in the theory of beams.' Casting at a high temperature gave greater strength than casting at a low one; a gradual increase of strength even up to 60 p.c. was found to result from increasing the

time of fusion, this increase of strength was accompanied by a decrease of set, the set being measured for a given load somewhat less than the minimum breaking load (pp 21-8). On p 44 further evidence is given of the increase in both tensile and transverse strength by increasing the period of fusion. It is also shown that rapid cooling increases transverse strength in small castings, and slow cooling increases tensile strength in large ones (p 45).

(c) Some attempts will be found on pp 77-88 to connect the tensile strength of a bar, the hydrostatic rupture pressure in a cylinder and the impulsive rupture pressure due to the discharge of powder in the same cylinder with one another. As no theory is proposed for this comparison, the experiments are rather vaguely directed and lead to no very definite conclusions. Wade takes for the transverse strength of a beam of length l and rectangular cross section $b \times d$, when centrally loaded with w , the expression $wl/4bd^2$ or $1/6$ of the greatest traction in the extreme fibre. He has for mean results on p 80 tensile strength of cast-iron = 22,133, transverse strength of cast-iron = 7370. Thus we should have for the rupture stress in the extreme fibre 44,220 or almost *double* the tensile strength. This is a good example of the so called 'paradox in the theory of beams'. The absolute strength calculated from flexure experiments upon a rectangular beam is by this misapplied theory double the tensile strength of the material. see our Arts 173, 178, 930, 1043, 1049-53, etc.

Wade's process of calculating the resistance of a circular cylinder to hydrostatic pressure—i.e. by multiplying the pressure per square inch by the radius and dividing by the thickness of the cylinder—can hardly be considered satisfactory, when radius and thickness are commensurable. This is well brought out by the Table on p 87, where the ratio of this resistance to the tensile strength varies greatly with the ratio of the thickness to the radius of the bore. But I doubt the accuracy even of Wade's experimental numbers, for when the ratio of the thickness to the radius of the bore remains constant, the internal bursting pressure does not bear the same ratio to the tensile strength, but varies from 329 to 602.

Further details of experiments on the bursting of musket barrels by hydrostatic pressure are given on pp 92-107, but I have not been able to apply any theory (e.g. the formula in the footnote of our Vol. 1 p 550) to the numbers given because the proper details are not recorded.

(d) Some experiments on the effect which slow cooling and casting under atmospheric pressure have on the bursting strength of guns are given on pp 129-34. They are neither numerous nor scientific enough to yield results of much value.

(e) A further report on the manufacture of 24 pounder iron cannon does not throw more light on the influence of the times of melting and fusion (pp 145-8). For the proof bars of these castings the mean

ratio of rupture stress in 'extreme fibre' to tensile strength = 1.65, so that it is considerably less than in the experiments considered under (c).

(f) The influence of height and bulk of the sinking head in bronze gun-metal castings on both density and tenacity is referred to on pp. 152-5 and may be compared with the more definite results of a somewhat later British Report: see our Art. 1050.

(g) On pp. 183-221 we have some interesting details of the relative durability of guns when cast solid and when cast hollow, in the latter case the interior was cooled by a flow of cold water. The hollow cast guns appear to have stood longer service than the solid cast guns, but the tenacity of specimens taken from the body of the former after bursting was not sensibly greater than that of specimens from the latter. This fact led Wade to suppose the difference in endurance to be due to differences in initial stress resulting from the different modes of cooling. Rodman (pp. 209-13) gives a not very lucid theory of initial stress deduced from an erroneous hypothesis of Barlow. The most interesting part, however, of this report is perhaps embraced by pp. 217-221, where Wade shows how experience and probability tend to demonstrate that initial stress due to cooling ultimately subsides. He cites a number of cases in which bodies held in a state of constraint obtain a gradually increasing set, apparently relieving them from this state, and he tries to show that guns retained after manufacture for long periods before proof, sustain a far greater proof than those tested directly. He accounts in this way for the hollow cast guns having greater endurance than the solid cast guns. The process of internal cooling he supposes produced less initial stress although no greater tenacity. Some of the details he gives are of interest in their bearing on elastic after-strain.

[1039.] The next portion of the volume (pp. 223-322) is entitled: *Report on the Strength and other Properties of Metals and on the Manufacture of Bronze and Iron Cannon*, 1854. This is the final report due to Major Wade. We proceed to note some points in it.

(a) The effect produced by remelting iron and by retaining it in fusion exposed to an intense heat for a long time is very fully considered on pp. 223-46. The quality of iron is as a rule very much improved by remelting and long continued fusion, but the effects vary from one kind of iron to another. The order of densities is almost invariably the order of tenacities or at any rate up to a certain limit of density¹. As a sample of the sort of results reached, I cite the following (p. 234):

¹ This limit of increase of tenacity with increase of density does not seem to have been clearly proven. Thus on p. 244 it is supposed that Greenwood iron attains its maximum tenacity with a density of 7.27, but it was found later (pp. 246-7) that a density of 7.307 gave even higher tenacities: see our Art. 1000.

	Density	Tenacity in lbs per sq in
Amenia pig iron, 1st fusion	6 948	11420
Same iron, remelted, 6 hours in 2nd fusion	7 172	26310
Another parcel of Amenia iron, 2nd fusion	7 184	26237
Same iron remelted, 3rd fusion	7 322	34728

Thus it was found that the mass per cubic foot could be increased as much as 20lbs and the tenacity in the ratio of 2.8 or even 3 to 1.

As a relation between small and large castings, Wade states that at least for one kind of iron (Greenwood) the strength of proof bars at any fusion may without material error be taken as an approximate measure of the strength of gun heads made of the same iron at the next fusion (p. 243).

(b) On pp. 248-9 we have a number of experimental details on transverse strength. It is not easy to identify the bars which correspond to those treated for tenacity. But it would seem as if the ratio of rupture stress in 'the extreme fibre' to tenacity was as low as 1.6 or even less—see our Arts 936, 1038 (c), 1043 and 1052-3.

(c) We have next a series of experiments on torsion (pp. 250-6). So far as rupture is concerned what Wade records is really the value of $\frac{1}{16}\pi T_3$ for bars of circular cross-section or the S_3 of our Art 1051 (c), T_3 being the absolute shearing strength. Or, if T_3 be taken $= \frac{4}{5}T$, the tensile strength T , he records what ought to equal $15708T_3$. If T'_2 be the value of T calculated from this, I find from Wade's summary of results on pp. 241 and 251 by recalculating his numbers, that for various kinds of cast iron the ratio of T'/T varies from 1.6 to 1.8, the mean value being very nearly 1.7. Or, with the notation of our Art 1051, $S_3/S = 267$, this differs but slightly from the mean value as found from the British cast iron torsion experiments—see our Art 1053.

Besides the absolute torsional strength, the torsional elastic strain and set were noted for a variety of loads as well as the load which produced an angular set of $\frac{1}{2}$ in a length of bar equal to about 8 times the diameter. This appears to have been about $\frac{7}{16}$ of the rupture load.

Wade also made experiments on the torsional strength of wrought iron and bronze. His mean value for $\frac{1}{16}\pi T'$ for wrought iron is 5465 and for bronze 5511 lbs per sq. in.

(d) Then follow experiments on the torsional strain and rupture of prisms of square, circular and circular annulus cross sections. The mean results are given on p. 256. The mean strength of prisms of square cross section is about 811 times the mean strength of those of circular cross section of equal area. If Saint Venant's theory of the fail limit (see our Arts 18 and 30) held up to rupture the ratio ought to be 735. For the strength of a hollow circular cylinder, the ratio of the internal diameter of which to the external diameter is ξ , I find on

Coulomb's theory $\frac{1 + \xi^2}{\sqrt{1 - \xi^2}}$ times the strength of the solid cylinder of equal area. This gives the ratios of the strengths for $\xi = \frac{1}{2}$ and $\frac{3}{4}$ as 1.44 and 1.7. Wade finds for the corresponding ratios in these cases 1.22 and 1.45, thus considerably less than the theory of the fail-limit would give if extended to the rupture of cast-iron.

(e) On pp. 257-9 we have details of experiments on the crushing strength of various cast-irons and steels. For cast-iron the ratio of the mean crushing strength to the mean tensile strength is about 4.56. If the theory of uni-constant elasticity be extended up to rupture then the ratio should be 4. The cast-iron was in small cylinders the lengths of which were generally two and a half times their diameters and the fracture-surfaces made angles of 52° to 59.6° with the bases. Probably the ends were held in by the friction of the bed-plates and the strength would thus appear to be increased. I expect the ratio of crushing to tensile strength, if both could be ascertained accurately, is not very far from 4 for cast-iron.

For cast-steel Wade gives (p. 258) the following values of the crushing strength in lbs. per sq. inch :

Not hardened	198,944
Hardened ; low temper ; chipping chisels.....	354,544
Hardened ; mean temper ; turning tools	391,985
Hardened ; high temper ; tools for turning hard steel... ..	372,598

He does not give the tensile strength of these steels which were all samples cut from the same bar.

[1040.] (f) Pp. 259-67 deal with the *Hardness of Metals*. These pages were translated into French and published as a tract entitled : *Expériences sur la dureté des métaux* (Paris, Corréard, 1861), but without the name of author or editor. Wade commences with the following statement :

The comparative softness, or hardness of metals, is determined by the bulk of the cavities or indentations, made by equal pressures ; the softness being as the bulk directly, and the hardness, as the bulk inversely (p. 259).

The form of the indenting instrument was a pyramid on a rhomboidal base. The longer diagonal of the base measured 1", the shorter .2", and the height of the pyramid .1". The planes of the sides intersected at the penetrating edge (point ?) at an angle of 90° . Such is Wade's description of the instrument, but it seems to me that the real height is about .098", the difference is perhaps in the angle and probably within the limits of experimental error. According to the author the apparatus would have been improved by making the longest diagonal 1.25" instead of 1", and causing the faces to meet at 60° instead of 90° . Such a pyramid would make a longer indentation and mark minute differences more accurately (p. 266). A cone with a vertical angle of 90° made a cavity about equal in bulk to that produced by the

pyramid under an equal pressure¹ Wade found that for the same material the cavities made by his instrument under different pressures were nearly as the pressures raised to the power of $3/2$. The *nearly* however neglects a divergence of about 17 per cent for large pressures, although the accuracy for small pressures is remarkable. This suggests that the empirical law of Wade may be near the truth for indentations only producing *set*, but becomes increasingly inaccurate as the loads produce *separation* of the material. This want of distinction between *set* and *separation* of the particles of the material—Wade measures in each case the indentation due to a pressure of 10,000 lbs—seems to me the most serious objection to the process. It has obvious advantages, however, over the scratching methods (see our Arts 836–44), and if Wade's law of relation between the volume of the indentation and the pressure were a correct one for *set*, we could obviously avoid such pressures as produce separation and get a scientific measure of hardness. The method does not, however, seem applicable to the variation of hardness with direction in crystals, or again to what Hugueny has termed tangential hardness.

Hertz's theory of hardness makes, I think, the depth of the indentation which a sphere would make on a plane vary as the (pressure) ^{$\frac{2}{3}$} . Hence for small indentations the volume would vary approximately as the (pressure) ^{$\frac{4}{3}$} . This applied to Wade's numbers gives results more discordant than his $\frac{3}{2}$, but this is natural as a pyramid obviously has greater penetrating power than a sphere. Thus the general bearing of Hertz's investigation seems to confirm Wade's mode of experimenting.

[1041] Suppose l to be the length of indentation when the whole volume V of the pyramid ($V = 3 \frac{1}{2}$ cubic tenths of an inch, $l = 10$ tenths of an inch with Wade's instrument) is sunk in a material under the given pressure p_0 , then if l' be the length of the indentation for any other substance under p_0 , Wade takes as a measure of the hardness of that substance $V^{3/4}/l^{1/4}$ (p. 260). But this does not seem to me what he really intended, although he actually calculates his hardnesses from it. For he prints, l being measured in tenths of an inch,

$$10 \text{ bulk } 3 \cdot 333 \quad l^3 \text{ bulk}$$

and he defines, as we have seen, hardness to vary inversely as bulk, we should thus have if H, H' be the two hardnesses

$$10^3 \frac{1}{H} \quad l^3 \frac{1}{H'},$$

$$\text{or} \quad H = H' \frac{10^3}{l}$$

But Wade taking hardness to be *equal* to the inverse of bulk, makes a slip in inverting his ratio and really puts $H = 3 \cdot 5$, when it would seem more natural to put it $1/(3 \cdot 5)$. He has thus chosen to term the hardness

¹ This is Wade's statement but it is I think hardly justified by the numbers in

of the material into which p_0 drives the whole volume of the pyramid 3·3, or, hardness varying inversely as bulk to take an arbitrary coefficient of variation

$$= (3\cdot3)^3 = 11\cdot1.$$

To add confusion to his numbers he remarks (p. 259) :

The maximum indentation of the instrument 3·3 cubic tenths, is therefore assumed as the type of extreme softness ; and as the 0 of hardness (!!).

Wade's numbers would, perhaps, be more intelligible if divided by 11·1. This, however, would still leave them dependent on Wade's particular pyramid. He suggests that a good standard of comparison might be obtained by finding the hardness of the silver coin of some given country and reducing all other hardnesses to this easily obtainable standard.

[1042.] As samples of his numbers we quote from p. 265 the following mean results :

	Density.	Hardness.
Cast-iron, proof-bars, 1st fusion	7·032	8·48
2nd "	7·086	12·16
3rd "	7·198	19·66
4th "	7·301	29·52
Bronze { Seville		5·18
{ Boston		4·73
Wrought-iron		11·03

[1043.] For any one investigating the relations which hold theoretically between density, tenacity, transverse strength, torsional strength, compressive strength and hardness, the table on p. 267 for upwards of 20 specimens of cast-iron would be invaluable. Want of space, however, compels me to cite here only the results for groups of 4 specimens arranged according to their densities (p. 268); but the inaccessibility¹ of these American Reports justifies at least this table in which I have corrected some of the numbers—

Group	Density	Strengths in lbs. per sq. inch				Hardness	Ratio of crushing to tensile strength
		Tensile	Transverse	Torsional	Crushing		
1	7·087	20877	6084	6176	99770	12·16	4·78
2	7·182	30670	7587	8341	139834	18·03	4·56
3	7·246	35633	8806	9659	158018	25·42	4·13
4	7·270	39508	9158	9827	159930	25·59	4·05
5	7·340	32458	9274	9065	167030	30·51	5·15
Mean	7·225	31829	8182	8614	144916	22·34	4·55

¹ I sought in vain for copies of these and other American Reports in England. I owe the copies I have used to the kindness of General S. V. Ben'et, Chief of Ordnance, War Office.

Here except for the tensile and torsional strengths of Group 5, all the strengths and hardnesses increase with the density, although the laws of increase are not obvious. The ratio of compressive to tensile strength appears to decrease with the density till we come to the last group, where it suddenly increases. It must be remembered that Wade stands by the transverse strength $\frac{1}{8}$ of the 'tension in the extreme fibre' of a rectangular bar at rupture, and by the torsional strength $\pi/16$ of the shearing stress at the circumference of a bar of circular cross section at rupture see our Arts 1049-53.

Thus with the notation of our Art 1051, we have

$$S_1/S_2 = 257, \quad S_3/S_2 = 271, \quad S_4/S_2 = 4.55$$

numbers greater in the last two cases, but in the first case considerably smaller than those of the British experiments.

[1044] (g) Wade next records some experiments on the rupture of hollow cylindrical rings. These rings were burst by applying force to a conical frustum made of hardened cast steel inserted in them. By means of a shield of cast steel cut into segments and internally tapered to fit the frustum, the friction between the ring and the frustum was reduced to a minimum (p. 269-70). Wade found that when the external diameter was about double of the internal diameter the ratio of the tenacity computed from what he terms the 'central force' on the frustum to the tenacity obtained by a pure tensile test was for both cast-iron and bronze about as 4:1, when the ratio of the diameters was as 21:16 then the ratio of these tenacities was about as 2:6:1. Wade does not explain how he calculates the tenacity from the 'central force,' and he remarks that the divergence in the values of the tenacities is probably due to the friction. His theory is in general so weak, that it very possibly has failed him in the reduction of his numbers. Lunc's formula (see our Art 1013^x, fn.) cannot be applied, when as in this case there is no longitudinal load on the cylinder. I find, however, that for a cylinder of isotropic material of radii a and b subjected to an internal pressure p , the maximum stretch s_0 would occur at the inner surface, $r = a$, and be given by

$$s_0 = \frac{p}{2\mu(b-a)} \left\{ \frac{\lambda + 2\mu}{3\lambda + 2\mu} a + b \right\},$$

whence, if we put $s_0 = T'/k$, T' being the tensile strength, and assume uniconstant isotropy, we have

$$T' = \frac{p}{k} \frac{3a + 5b}{b - a}$$

$$1.92p, \text{ if } b/a = 2,$$

$$1.02p, \text{ if } b/a = 21/16$$

It is, however, unlikely that Wade calculated the tenacity from the internal pressure and then from the 'central force' by any such formula.

as this. His method of calculation being unknown, the numbers he gives cannot be modified or used to test any theory.

(h) On pp. 272-4 will be found the details of experiments made with this conical frustum to test Barlow's hypothesis that the area of the cross-section of cylinders subjected to internal pressure does not change. The experiments were far too crude to efficiently demonstrate the erroneous nature of Barlow's assumption: see our Arts. 901, 1069 and 1076-7.

(i) We may note how Wade on pp. 274-5 draws attention to the very considerable ranges of density, hardness, tensile and compressive strengths to be found for different kinds of the same metal, and therefore to the importance of testing in every case samples of the metals which it is proposed to use for any given purpose.

[1045.] Wade after suggesting on pp. 278-80 chemical tests of the various types of iron which possess owing to repeated meltings such different elastic and cohesive properties, turns to the subject of bronze guns to which he devotes pp. 281-304. In these pages a great deal of information will be found as to the effect of position in the casting or of the size of the casting on the tenacity and density; thus gun-head samples have hardly half the strength of small bars cast with the guns, and as a rule less strength than small bars cast in quite different moulds. There is a good deal of interesting detail as to the exact effect of casting, but we cannot afford the space needful for discussions here.

pp. 305-22 contain a full account of Wade's testing machine for compressive, transverse and torsional strains. The description is of considerable historical interest as the machine has been the model of a good many others, even in this country. Following our usual rule we refrain, however, from discussing apparatus and refer the reader to the original paper, or to W. C. Unwin: *The Testing of Materials of Construction*, p. 127. London, 1888.

[1047.] The remaining Reports of the volume may be briefly noticed.

(a) On pp. 323-46 we have a report by Lieutenant Walbach on the tensile strength and density of specimens taken from the muzzles of nearly 3000 iron guns. He found that for metal of a high class with a tenacity of nearly 30,000 lbs. per sq. in. and a density of 7.21 there was a colour, structure and fracture quite different from those of a metal of a low class with tenacity of between 19,000 and 20,000 and a density of about 7.05. As a sample of the type of difference we may take the fracture described in the first case as "close and even, not hackly" and in the second as "rough, uneven and hackly" (p. 339). Some remarks on p. 344 on the general relation between increased density and increased strength are not without interest, but the whole Report has not much *physical* importance.

(b) This report is followed by one on the extreme proof by continuous firing of test guns (pp 350-68), its contents appear only of interest for the art of gunnery

(c) The volume concludes with three reports on the chemical analysis of specimens of cast-iron gun metal (pp 370-428) In the first two reports by taking averages and classifying cast-iron into three classes it is shown that with decreasing density and tensile strength there is a decrease of combined carbon and an increase of silicium, and various suggestions are made as to the relation between the physical properties and chemical constitution of the metal (pp 377-387) The effect of hot and cold blast on these properties is also noted (pp 388-9)¹ But in the Third Report (p 394) the writers remark on the discordance which exists between the laws suggested connecting physical properties with chemical constitution and the results of their more elaborate investigations They go so far as to throw doubt on the exactness of the physical investigations of density and tenacity and sum up with the words

the limited extent of our investigations prevents, at present, the establishment of any laws as to the relation of chemical composition and physical structure, in gun metal (p 394)

On p 396 they give the chemical analysis of 32 specimens of cast iron, but as they now suppress all data of tenacity and density, the results are not suggestive for further research on the relations between chemical composition and physical structure

[1048] Cast-Iron Experiments *Report relative to a Series of Mechanical Experiments made under the direction of the Superintendent, Royal Gun Factories, and of Chemical Analysis under the Chemist to the War Department, upon various British Irons, Ores etc, with a view to an Acquaintance, as far as possible, with the most suitable Varieties for the Manufacture of Cast-Iron Ordnance, with an Appendix, containing similar Examinations of several Foreign and other Irons, carried on by order of the Secretary of State for War dated 9 June, 1856* London 1856

This Report appears to have been returned in June, 1858 although some of the experiments in the Appendix are dated as late as February 3, 1859, and so perhaps were added while the Report was being printed The experiments were carried out under the superintendence of Colonel F Eardley Wilmot, R A by the proofmaster Mr M Kimby We need here only consider the

¹ In the Table of *Analysis* p 388 in the 4th column for the *Total Carbon* of the *Cold Blast* read 0417 for 0407

mechanical experiments and not the chemical analyses of the various irons and ores, which form the second part of the *Report*.

The *Report* is a folio volume consisting almost entirely of the numerical results of experiments on a great variety of cast-irons from all parts of the United Kingdom and some few foreign irons. The experiments are fairly comprehensive, but appear to have been made without any special regard to theory. They are thus very inferior in value to those of the *Iron Commissioners' Report* or of Kirkaldy on wrought-iron and steel.

A brief *résumé* of the results to be drawn from these experiments will be found in the *Mechanic's Magazine, New Series*, Vol. II., pp. 162-3, and another in the *Civil Engineer and Architect's Journal*, Vol. 22, pp. 397-8. Both, London, 1859.

[1049.] Experiments were made on the tensile, flexural, torsional and crushing strengths of a great number of specimens and with a view of testing the bearing of the results I cite the following table from p. 2 :

Strengths of Cast-Iron in lbs. per sq. inch.

	Specific Gravity of 850 specimens	Tensile, of 850 specimens: S_2	Transverse, of 564 specimens: S_1	Torsional, of 276 specimens: S_3	Crushing, of 273 specimens: S_4
Maximum	7.340	34,279	11,321	9,773	140,056
n	6.822	9,417	2,586	3,705	44,563
Mean ¹	7.140	23,257	7,102	6,056	91,061
Ratio of Strengths (from General Mean)	—	1	.305 (S_1/S_2)	.260 (S_3/S_2)	.3915 (S_4/S_2)

The difference between the maximum and minimum values fully justifies the remarks of the *Report* that :

The term "cast-iron" as describing any specific material does not convey to the mind of those connected with such experiments any more positive quality than what may be gathered from the use of the term "wood" in speaking of that material. The remarkable range of the various qualities of different samples is scarcely more marked in the latter than in the former; and in addition, the same iron treated in a different manner, as regards the apparently simple process of melting or cooling assumes a different character.

¹ In all cases of 51 samples or parcels.

No attempt was made to ascertain the result of mixing various brands of iron nor the special treatment which would improve the quality of any particular iron. Eighteen bars were cast of each iron, 22" long and of cross section 2" square, nine were cast vertically and nine horizontally, three of each of these sets of bars were covered with sand to delay cooling as much as possible and kept in the mould till thoroughly cooled, three were cast 'in the usual way,' three were turned out of the mould as soon as set and exposed to currents of air. These processes are described in the tables as 'slow,' 'gradual' and 'quick' casting. The results of these various modes of casting show a distinct superiority of the bars cast horizontally over those cast vertically, and in a less marked degree of those cooled quickly over those cooled gradually or slowly.

It is to this rapid cooling and condensation that the superior strength of a two inch bar, cast from a portion of the metal of which a gun is made is due (p 4)

[1050] Experiments were further made to show that the length of 'dead head' does not add to the resisting power of metal. These experiments were made on cast iron and 'on bronze or brass gun metal'. In the former case a cylinder 26' long and 7" diameter was cast vertically, and discs were cut from the top, centre and bottom, or at intervals of about 12', out of these discs tensile specimens were taken. In the case of bronze there was 30" distance between the specimens as they stood in the casting. The following results were obtained (p 3)

	Cast Iron (mean results)		Bronze	
	Tensile Strength	Specific Gravity	Tensile Strength	Specific Gravity
Top	29 778	7 217	35,600	8 539
Centre	27,650	7 263	38 704	8 545 ¹
Bottom	28,648	7 324	49 401	8 814

Thus although the tensile strength of the cast iron varied with the pressure at casting, it did not, like the bronze, show a uniform increase with increase of pressure.

[1051] Of the 18 bars referred to above, 12 were submitted to transverse test and 6 to torsional test, a tensile specimen and a small cylinder for specific gravity being taken from the end of the transverse specimen after the test, and a crushing specimen from the end of the torsional specimen after test.

¹ So in Report but possibly a misprint for 8 645

We will briefly note how the experiments were made in order to render the table in our Art. 1049 intelligible.

(a) *Transverse Strength.* The rectangular bars "were ground in the centre, so as to present a regular surface; this being necessary for obtaining a correct measure of fracture". The area of fracture was measured by taking the mean of three breadths, centre, top and bottom of the section, and multiplying by the mean height found in the same manner. When a load of 5000 lbs. had been applied, it was removed and the permanent set measured, and this repeated for each additional 5000 lbs. up to fracture; the deflections were also noted for the same increments of load. If L be the length, B the breadth, D the depth of the bar and W the central breaking weight, the report tabulates

$$S_1 = \frac{LW}{4BD^2}$$

as a measure of transverse strength. If T_1 be the *apparent* tensile strength in the 'extreme fibre' supposing the Euler-Bernoulli theory applied up to rupture:

$$T_1 = \frac{3LW}{2BD^2} = 6S_1,$$

i.e. *six* times the quantity recorded in the table in our Art. 1049.

(b) *Tensile Strength.* The specimens here were unfortunately made of varying diameter in order apparently to ensure breaking at a given central section: see our Art. 1146. Thus although the extensions measured after a stress of 15000 lbs. at every additional 5000, are of no real value owing to the irregular form of the specimen, the results are only of value for the breaking load. If the rupture be T_2 , the tables of the Report record:

$$S_2 = T_2.$$

(c) *Torsional Strength.* The test pieces were cylindrical in the centre and square at the ends for the purpose of fastening them, one end being "keyed to the standing part of the machine, the other to the moveable levers" (p. 9). From this description it appears to me not improbable that the pieces were subjected to both flexure and torsion, in which case the measure of strength adopted would not give a sound result. The tables tabulate: $S_3 = RW/d^3$, where R is the arm at which the weight W is applied and d the diameter. If we apply the theory of elastic torsion up to rupture, let T_3 be the absolute shearing strength, then by our Art. 18,

$$T_3 = \frac{16}{\pi} \cdot \frac{RW}{d^3} = \frac{16}{\pi} S_3.$$

(d) *Crushing Strength.* The specimens were 6" in diameter and 13" in length and were taken from bars which had been subjected

to the torsional test. It does not appear to have been noticed that this previous strain nearly up to torsional rupture may probably have had a sensible influence on the crushing strength. The squeeze of the material at 15,000 lbs and the set at this load were noted and these quantities measured again with every addition of 5000 lbs. The rupture surfaces correspond fairly closely to fig 5 of the frontispiece to our first volume. They show, however, that the bedded terminals were hindered by the friction from expanding fully. The tables of the Report record S_4 , where $S_4 = T_4$ the ultimate crushing strength.

There are pictures of five samples of fracture surfaces under the above different kinds of stress on pp 8-10, and the work concludes with a number of diagrams representing, but not very clearly, the mean results of the tables of experiments. Tables *A* and *B* (pp 154-6) give a *résumé* of the chief results for all the different kinds of cast-iron employed.

[1052] We may note a few theoretical considerations, which flow from the formulae in the preceding article and from the table in our Art 1049.

If uniconstant isotropy could be supposed to hold for cast-iron up to rupture, we should have the absolute shearing strength to the absolute tensile strength as 4/5, or

$$T_3 = \frac{4}{5}T$$

Further T_4 would be given by

$$T_4 = 4T,$$

and

$$T_1 = T,$$

whence we ought to find

$$S_1 = 16S,$$

$$S = 157S,$$

$$S_4 = 4S$$

Of these results only the last is at all in accordance with the mean results of the table, which gives

$$S_4 = 3.915S$$

This confirms the statement often made in the course of our work that for *practical* purposes the relation between the tensile and crushing strengths of cast iron may be taken to be that deduced from supposing uniconstant isotropic elasticity to hold up to rupture.

Instead of the first result the table gives

$$S_1 = 30.5S$$

or

$$T_1 = 1.37T$$

instead of $T_1 = T$. This is the so called paradox in the theory of beams; see our Arts 930-1. Recent experiments have given the ratio of T_1/T

for rectangular sections = 1.74, for circular sections = 2.03, showing that it varies with the form of the section.

If the result $S_3 = .260S_2$ as given by the tables be correct, it shows that the ordinary theory of torsion certainly cannot be applied to cast-iron up to rupture, for there is little doubt that the shearing strength of cast-iron does not differ largely from the tensile strength.

If we express the above ratios in terms of the crushing strength as unity we have from data supplied in the Report :

	Crushing Strength	Tensile Strength	Transverse Strength	Torsional Strength
Elastic Theory	1	.25	.042	.039
General Means	1	.255	.078	.067
Butterley Iron (p. 181)	1	.201	.063	.038
New York Iron (p. 175)	1	.379	.097	.067
Charcoal Iron (p. 171)	1	.266	.093	.088
Blaenavon Iron (p. 147)	1	.183	.052	.022

The last four examples have been taken at random from the tables in the Report to show the great variations in the ratios of the different types of strength, and to demonstrate how rash it is to apply the ordinary theory of elasticity to determine the rupture stresses of a material like cast-iron.

[1053.] Let us apply the stress-strain relation which Saint-Venant has based on Hodgkinson's results and which does not assume Hooke's Law. For a rectangular beam under flexure, the method is discussed in Art. 178. Let m_1 be not put equal to m_2 , but their ratio taken as that of the ultimate tensile and crushing strengths. We shall follow Saint-Venant then put for cast-iron $m_1 = 1$ and $m_2 = 4$ whence we find (*Leçons de Navier*, Table, p. 182):

$$T_1 = 1.81 T_2.$$

Further taking $m = 4$ in the corresponding torsion-formula in our Art. 184, we find:

$$T_3 = 1.037 T_2.$$

Whence reducing to the S -notation of the present discussion we have:

	S_1/S_2	S_3/S_2	S_4/S_2
Saint-Venant's theory	.302	.204	4
Mean results of experiments	.305	.260	3.915

Thus we see that for practical purposes, Saint-Venant's formulæ with the above values of the constants may be used, failing direct experiments, to find fairly good *mean* results for the transverse strength of cast iron

[1054] Robert Mallet *On the Physical Conditions involved in the Construction of Artillery, and on some hitherto unexplained Causes of the Destruction of Cannon in Service* *Transactions of the Royal Irish Academy*, Vol XXIII, Part I, *Science*, pp 141–436 Dublin, 1856 This paper was read on June 25, 1855 A review and at the same time a criticism of the portions of Mallet's memoir bearing on the strength of materials will be found in Vol XIX, pp 325, 366, 389, 401 and Vol XX, pp 29–31 of the *Civil Engineer and Architect's Journal* London, 1856–7

This long memoir contains a great deal of interesting information with regard to the physical properties of the metals, notably iron Some of the statements made, seem to me wanting in scientific precision, but it is quite possible that they may be much more intelligible to one having a more intimate acquaintance with the appearance and the rupture surfaces of large masses of material We shall note only one or two points referred to by the writer in his earlier chapters

[1055] *On the Bursting of Guns from internal Pressure* The memoir notices that rupture invariably appears to have begun at some point on the inside, the gun opening out along one half a longitudinal section through this point the opposite half being subjected in part to traction and in part to contraction,—this produces a characteristic point of inflexion in this half of the surface of rupture (p 146)

[1056] *Molecular Constitution of Crystalline Bodies*

It is a law (though one which I do not find noticed by writers on physics) of the molecular aggregation of crystalline solids, that when the particles consolidate under the influence of heat in motion, their crystals arrange and group themselves with their principal axes, in lines perpendicular to the cooling or heating surfaces of the solid that is, in the lines of direction of the heat wave in motion, which is the direction of least pressure within the mass (p 147)

Mallet lays considerable stress upon this law and discusses it at some length in pp 147–9 and Note E, pp 353–57 If the law be true, it obviously has a very great bearing on the influences of the various processes of working on the strength of materials It is not always quite obvious what is meant by *crystalline structure* and its opposite *fibrous condition* in the writings of technical elasticians, or whether they are

distinctly related to molecular crystallisation. There is obviously a distinction between an *amorphic body or solid of confused crystallisation* (as expressed by Saint-Venant: see our Arts. 115 and 117 (c)) and a body in a 'longitudinally fibrous' condition as produced by drawing or rolling, but Mallet describes both as presenting no crystallisation (pp. 148-9). Thus he notes an experiment with a plate of rolled zinc which is nearly "homogeneous in structure [isotropic in structure?], or, if not so, presents fibres and laminae in the plane of the plate." This plate is laid upon a cast-iron plate which is then heated nearly up to the melting point of the zinc. The zinc is then said to assume a "crystalline structure,—the crystals now having their principal axes all cutting perpendicularly through the plate from side to side; in other words, *the planes of internal structure being in this.....case absolutely turned round 180° of angular direction.*" I suppose the 180° to be a slip for 90°.

The words "internal structure" here seem to point as much to *crystalline* as to elastic structure, and Mallet would seem to associate a 'fibrous condition' with crystalline axes in the direction of the fibre, and a 'crystalline condition' with crystalline axes perpendicular to the greatest dimension of a wire or plate. Now 'initial stress' due to working may produce aeolotropy, but it does not seem necessary to assume, that such stress really connotes an arrangement of crystalline axes in or perpendicular to the lines of initial stress. Indeed I think the identification of elastic aeolotropy having one or more planes of symmetry with crystalline structure, which is assumed by some English writers, is not without danger. That crystalline structure connotes a certain elastic structure may be perfectly true, but I do not see why the converse must necessarily hold. The passage of heat through a material, perhaps, changes its tensile strength, *when the temperature is thereby raised nearly to fusing point* (words omitted in Mallet's statement of his law, but which was apparently a condition of the experiments he quotes): see however our Arts. 692* (8), 876*, 953*, 968*, 1301*, and 1524*. What Mallet adds to this statement is, that the direction in which the heat is propagated through the metal affects the directions of greatest and least tensile strength and may interchange the two. At the same time it is not improbable that a much smaller change of temperature will produce a change in elastic structure, and alter the magnitude of the elastic constants and the directions of the planes of elastic symmetry.

If Mallet's law be true it would follow that many processes of annealing so far from producing isotropy may merely change the nature of the aeolotropy, and that further without very great precautions in the process of annealing, the question of rari-constant isotropy cannot be tested by experiments on annealed bodies, originally of fibrous structure. The process of annealing so far from producing Saint-Venant's 'amorphic' condition in place of the 'fibrous,' may produce Mallet's 'crystalline structure.' Mallet asserts (pp. 147-8) that a heat far below that of fusion will change an amorphic into a crystalline body, and that when a body cools "the principal axes of the crystals will

always be found arranged in lines perpendicular to the bounding planes of the mass, that is to say, in the lines of direction in which the wave of heat has passed outwards from the mass in the act of consolidation (p 147, § 10)." He adds nothing as to the *rate* at which the cooling is supposed to take place. The bearing of this remark, if true, on the labours of those experimenters who discard *rare constant isotropy* on account of the evidence of multi constancy found in *annealed wires* will be obvious to the reader.

One word more as to certain expressions used by Mallet in the statement of his law. He identifies the direction of the heat wave, I presume he means heat *flow*, with that of "least pressure within the mass" (pp 147 and 353). I do not understand exactly what this pressure denotes. In the second page cited Mallet speaks of it as the "pressure due to distortion or change of form by contraction or expansion." But this does not make it much clearer. Does he mean the direction of least initial traction? Even then I do not understand why the heat-flow always passes in this direction. According to the mode in which we apply heat to the body, it seems to me we can alter the direction of the heat-flow. If we could not, it is difficult to understand how the heat-flow could change the direction (in Mallet's phraseology) of the crystals, whose 'principal,' 'symmetric' or 'longest' axes are always in the direction in which the heat-flow has passed (p 353). By "consolidation of particles" Mallet refers not only to a previously fused solid solidifying by cooling, but to the action of heat applied to the external surfaces of a body raised to a temperature even less than that of fusion (pp 147-8).

[1057] Chapter IV of the memoir is entitled *Molecular Constitution of Cast Iron* (pp 149-152). Mallet, after remarking that according to his previous law "the planes of crystallisation group themselves perpendicularly to the surfaces of the external contour", goes on to infer that when the contour presents either a re-entering angle, or a sharp change in direction, then a plane exists in the neighbourhood of the angle, in which there is *confused crystallisation*, this confused crystallisation he considers a source of weakness and he terms the plane a *plane of weakness*.

Experiments seem to prove that such *planes of weakness*, ultimately of rupture, do really exist where Mallet has placed them, but I much doubt if they are due to "confused crystallisation." More probably they connote an *initial stress* due to the peculiarity of the cooling in these parts. Indeed if we followed Mallet's idea as it appears exemplified in an experiment on lead on p 148 (s 12), it would seem that parallelism and not confusion of the directions of the crystalline axes would be a source of decreased tensile strength in directions perpendicular to the axes and so parallel to the surface of the casting.

[1058] Chapter V is termed *Physical conditions induced in Moulding and Casting* (pp 152-162). In this chapter Mallet points out that the size of the 'crystal' in the casting (and therefore its weak-

ness) depends on the length of time the casting takes to cool. Hence the temperature of the molten metal ought to be only just above that requisite for fusion. He remarks also on the state of internal (initial) stress produced in large castings due to the different rates of cooling of adjacent parts. This points again rather to initial stress than to 'confused crystallisation' as a source of weakness. He cites Savart's memoir of 1819 (see our Art. 332*) and a memoir by Bolley upon the molecular properties of zinc (*Annalen der Chemie und Pharmacie*, Bd. xcv. S. 294) in support of his views. As an example of the evil of a long period of solidifying Mallet points out that a small bar which is part of a large casting and thus cools slowly is found not to be so strong as a bar of the same size cast alone under the same 'head' of metal (p. 162).

[1059.] We may note that on pp. 154-5 Mallet rejects Fairbairn's theory that a certain number of repeated meltings increases the strength of cast-iron (see our Art. 1098):

Indeed, these experiments (Fairbairn's), rightly considered, only prove what was well known before—that by continually remelting and casting into *small* pieces (i.e. imperfectly chilling) any cast-iron, we may gradually cause all its suspended carbon (in the state of graphite) to exude, as Karsten long ago proved, and so gradually convert the metal into an imperfect steel, with increased hardness and cohesion, and diminished fusibility, but with properties altogether unworkable and useless. No such result can occur when the metal is cast into large masses, nor any such improvement by repeated meltings, but very much the contrary (p. 154).

[1060.] Chapter VI. on the *Effects of Bulk and Fluid Pressure* and Chapter VII. on the *Quality of Metal* in reference to strength refer to practical points of casting and need not detain us. We merely remark that increase of bulk produces decrease, increase of 'head' or fluid pressure produces increase of both density and strength, while British irons show a tensile strength comparing favourably with foreign makes (pp. 162-172).

Chapter X. on the effect which heating the inside of a cylinder has in producing strain and ultimately rupture of the material is not very satisfactory from the theoretical point of view. With the aid of a somewhat more extended analysis more approximate results might I think have been obtained.

[1061.] Chapter XVIII. is entitled: *The General Relations of Elasticity to the Construction of Guns* (pp. 194-220). So far as the theory of elasticity is concerned this is not a very satisfactory chapter. Thus on p. 194 (§ 114) it is pointed out that 'linear' and 'cubic elasticity' have not a constant ratio, while in the following section (§ 115) the relation between them, and on p. 216 (§ 144) the relation between the slide- and stretch-moduli are given on the rari-constant hypothesis without a word of qualification. Similarly the thermal statements at the conclusion of § 114 and in § 116 strike me as very obscure. The following pages (pp. 198-207) are occupied with a reproduction of Poncelet's results on the cohesive and elastic resilience of bars, taken

from the *Mécanique industrielle* (see our Arts. 981*-2*, 988*-991*) Mallet only reproduces those results which neglect the influence of the inertia of the metal, and makes no statement that he has done so. His application of these results for the longitudinal resilience of bars to the case of the cylinder of a gun in § 130, p. 208, seems to me quite unjustifiable. The elastic resilience of a massive hollow cylinder subject to internal impulsive pressure presents no great difficulties of analysis, but it certainly cannot be deduced from that of a bar without inertia, by supposing the latter bent into a ring!

[1062] On pp 211-219 are tables of the elastic strength and the coefficients of elastic and cohesive resilience of metals, chiefly extracted from Poncelet's *Mécanique industrielle*. Mallet draws attention, as Poncelet had already done to the importance of considering these coefficients of resilience rather than the cohesive strength of a material when we are judging its suitability for ordnance. At the same time I think he should have brought out more clearly that it is rather the elastic than the cohesive resilience which must be taken as a measure of suitability, otherwise the gun would rapidly lose its form and efficiency. Had he done so the disproportion in the efficiencies of cast steel and wrought iron of extreme ductility would not have appeared anything like so great as exhibited in the areas of the curves on p. 213. Thus in Table X, p. 219 'strong and rigid' wrought-iron bar has a greater elastic resilience than wrought iron of 'mean strength and ductility,' while the cohesive resilience of the latter is much greater than that of the former. Similarly gun-metal has a less elastic resilience than either cast iron or wrought-iron bar, but an immensely greater cohesive resilience. At the same time we must remark that Mallet's tables are not quite in accord (e.g. the results in Tables VII and X), this is perhaps due to the assumption of uniform isotropy in the calculation of some of the results.

[1063] Chapters XIX. and XX. of Mallet's memoir are devoted to the physical properties of gun metal or bronze (pp 220-241). A table on p. 222 giving the physical properties and in particular the tensile strengths of various alloys of copper with zinc or tin is extracted from the author's *Second Report upon the action of Air and Water upon Cast Iron, Wrought Iron and Steel*¹, *Transaction of the British Association*, Tenth (Glasgow) Meeting, 1840, pp 221-305. London 1841.

¹ These reports (1834-43) escaped my notice in working up the material for Vol. I. but only pp 302-8 of the Second Report really concern us. On pp 306-7 are the tables referred to (see also *Proceedings of the Fourth Irish Academy* Vol. II. pp 95-6. Dublin 1844). They give the specific gravity, tensile strength, hardness, order of ductility, order of malleability at 60° F., order of fusibility (the author does not state how these orders were determined), nature of the fracture and commercial name where known of 21 alloys of copper and zinc and 14 of copper and tin together with those of copper, zinc and tin themselves. On pp 302-4 are details of the fracture and specific gravity of various kinds of cast iron, on p. 304 of increase of density in cast iron due to solidification under a considerable head of water (4 to 14 feet) on p. 305 of decrease of density with the increase in bulk of a

[1064.] Chapter XXI. (pp. 242-3) deals with cast-steel. It contains a reference to Ignaz von Mitis' experiments, but nothing of importance for our present purposes: see our Art. 693*.

[1065.] Chapter XXII. is entitled: *Molecular Constitution of Wrought-Iron, and the Law of Direction of its Crystals or Fibre* (pp. 244-248). Here we have the same general statements as to crystalline axes to which I have objected in Art. 1056. On p. 245 the general law is stated:

In wrought, as in cast iron, the principal axes of the crystals, tend to assume the directions of least pressure throughout the mass while exposed to pressure and heat in progress of manufacture.

It appears by the remarks upon this law, that Mallet understands by the 'direction of least pressure' that in which the stress applied in the process of working is least, i.e. the direction of the 'fibres'¹ in a bar, plate or wire. Here again it seems to me that it would be safer to talk of an aeolotropy symmetrical with regard to certain planes rather than of the direction of the crystalline axes. Mallet notes (pp. 246-7) that in the case of a bar of wrought-iron of large cross-section, heat as well as working stress plays a part in determining the direction of the crystalline (elastic?) axes, and that the process of cooling tends to place these in directions perpendicular to the surface of the bar.

[1066.] Chapters XXIII.-XXV. (pp. 248-256) deal principally with the characteristics presented by large masses of forged iron. The author speaks of these masses as possessing confused crystallisation, or in other words being *amorphous*. He disputes the accuracy of Fairbairn's results cited in our Art. 1497* (ii), and refers to some experiments of Clarke's (*The Britannia and Conway Tubular Bridges*, Vol. I. p. 377) which gave for the mean tensile strength per sq. inch: with the fibres 20 tons, across the fibres 17 tons. Mallet holds that the tensile strength of bars cut out of a large mass of forged iron in *any* direction would also give a tensile strength of about 17 tons (pp. 249 and 253).

[1067.] Chapter XXVI. (pp. 256-260) deals with the point referred to in our Arts. 1463*-4*, 881 (b) and 970, namely the possibility of a change in wrought-iron from a 'fibrous to a crystalline state' by repeated loading or impacts. Mallet's general conclusion on this point is given on p. 257. He holds that no strain or impact which does not produce permanent change of form is capable of affecting any molecular alteration however often repeated, but:

It does appear certain from many well-observed phenomena, that instantaneous changes of molecular structure and reversals or transposition of casting; on p. 308, of the specific gravity and fracture of a number of wrought-irons and steels.

¹ Mallet, p. 248, says: "I have used the term 'fibre' as being already long in use, and conveying well the character of this particular form of crystallisation to the eye; but it should be clearly understood that the 'fibre' of the toughest and best iron is nothing more than the *crystalline arrangement* of inorganic matter."

the crystalline axes can be produced in wrought iron at ordinary temperature, by the violent application of mechanical force, producing suddenly change of form at one or more points of the surface of the mass

He instances the effect of the blacksmith's 'nicking' with a blunt chisel the side of a bar of the toughest iron, which can then be easily broken, although without the 'nick,' it might have been sharply bent double without fracture. There is an attempt to explain this on the 'theory of direction of crystalline axes' see our Art 1056

[1068] Chapter XXVII (pp 260-266) is concerned with the rupture of wrought iron plates by impulses, such as the blow of a shot. In § 229 Mallet obtains a formula for the velocity V of the body which will certainly produce fracture. If u be the 'velocity of force transmission,' by which we are to understand the velocity of sound waves, and s_0 be the limit of safe stretch or squeeze, then if

$$V = u \times s_0$$

there will certainly be rupture. This is a result of Young's for *longitudinal impact* of beams (see his *Lectures on Natural Philosophy*, Vol. 1 p 144), but I do not understand how it can be straightway applied to the transverse impact of plates. Mallet applies it, however, taking $u = 13,000$ ft per second, $s_0 = \frac{1}{25}$, and deducing that V is only one-third to one-fourth that of cannon shot, so that the inevitable destruction of the iron plate follows. It is needless to add that in explaining the nature of the fracture of plates by shot he appeals to his crystalline law (pp 265-6) see our Art 1056. The subject of the rupture velocity for transverse impact on plates has been treated by Boussinesq in a memoir of 1882 (*Comptes rendus*, Vol xcv 1882, p 123 see also his *Application des Potentiels* pp 487-90), which we shall consider in its proper place

[1069] After some chapters relating more closely to the construction of artillery, Mallet in Chapter XXXIII (pp 280-296) returns to our subject, dealing with the problem of constructing a gun by placing cylindrical rings of wrought-iron over each other, each new ring being shrunk on to the series of rings which form its core. It is well known that a hollow cylinder subject to internal pressure, if homogeneous and without initial stress, will only sustain a certain definite pressure, however its thickness may be increased see our Arts 1013* (with footnote) and 1474*. Mallet proposes to raise this limiting pressure by putting the material into an initial state of stress. The theory of this initial state of stress is given in a Note by Dr Hart appended to the memoir to which note we shall return.

On pp 284-5 Mallet cites five different formulæ for the relation between thickness, safe tractive load and internal pressure. None of these agree with that I have given on p 500 of Vol 1 still less do they agree among themselves. Mallet makes no attempt to select any one of them as the correct one. He states with Barlow (*Transactions*

of *Institution of Civil Engineers*, Vol. i. p. 136) that there is no thickness which will withstand an internal pressure equal to the safe tensile load. Dr Hart's formula gives the same result. As a matter of fact for uni-constant isotropy the thickness τ for internal pressure p and internal diameter d is given by :

$$\tau = \frac{d}{2} \left\{ \sqrt{\frac{4T_0 + 2p}{4T_0 - 5p}} - 1 \right\},$$

whence we find $p = \frac{4}{5}T_0$ as the limiting possible pressure.

[1070.] Chapter XXXIV. (pp. 296—9) is entitled : *On the Relations between Annealing and Tenacity*. It is based principally on Baudrimont's results : see our Arts. 830*-1* and 1524*. But there is very little evidence accessible on these points :

A rich reward awaits the physicist who, in a comprehensive manner, shall first, experimentally, attack the question of the molecular changes produced by hardening and annealing ; it has been as yet almost unattempted (p. 297).

[1071.] The memoir concludes with a long series of notes, partly historical and partly statistical, of considerable general interest. I may draw attention to the following :

(a) Note S. (pp. 392—396). *Physical Constants of the Materials for Gun-founding*. This note gives some tables of information with regard to the ultimate strength of cast- and wrought-iron, cast-steel and bronze extracted from the *Ordnance Reports, United States Army*, 1856, and on the compression of bronze gun-metal from some experiments of Colonel F. E. Wilmot at Woolwich Arsenal made at Mallet's request (April, 1856). See our Arts. 1037—47 and 1050.

(b) Note W. (pp. 399—406). This note by Dr Hart professes to give the theory of the stress in a number of superposed metal cylinders (see our Art. 1069), but I have been unable to follow the analysis. If it be correct, which I very much doubt, at least the author should have clearly stated the meanings of the symbols he employs. After saying that the cylinder may be conceived as split up into 'cylindrical laminae,' he continues :

Let r be the radius of any of these cylinders, and $2P$ the corresponding force, the length of the cylinder being unity. Also let $r+u$ be the radius of the same cylinder when extended, then (according to the common theory) :

$$\frac{dP}{dr} = -k \frac{u}{r}.$$

It would appear from what follows that the author means by the 'corresponding force $2P$ ' the expression which we should denote by $-2r \cdot \widehat{rr}$ and his equation then becomes

$$\frac{d\widehat{rr}}{dr} + \frac{\widehat{rr} - ku/r}{r} = 0.$$

This obviously assumes that the meridional traction $\widehat{\phi\phi}$ is equal to ku/r : see our Art. 120.

Similarly the second equation on p 400 is

$$P = -k'r \frac{du}{dr}$$

or

$$\hat{r}r = k' \frac{du}{dr}$$

Thus it would seem that the author has either supposed the material to have no dilatation, or else assumed that the meridional and radial tractions are each proportional solely to the stretches in the same directions! The error is exactly that of Scheffler see our Art 655

[1072] On the whole Mallet's memoir presents much of interest and importance, but is painfully weak in analysis and even in elementary dynamical notions (e g equation (58), p 269)

[1073] British Association *Report of Twenty-fifth (Glasgow) Meeting* London, 1856 *Provisional Report of the Committee appointed to institute an inquiry into the best means of ascertaining those properties of metals and effects of various modes of treating them which are of importance to the durability and efficiency of Artillery*, pp 100-8 This does not appear to contribute anything of theoretical or permanent importance to the subject of our history, or to the science of gunnery

[1074] *Expériences faites en 1856 avec deux canons à bombes en fonte de fer Extrait du rapport fait sur ces expériences par M von Borries Annales des travaux publics de Belgique*, T xv pp 427-56 Bruxelles, 1856-7 This is a translation of a portion of a report to the Prussian Government on the strength of two Belgian cast iron cannon made at Liege The cannon were tested to bursting There is nothing that calls for special notice in the report

[1075] D Treadwell *On the Practicability of Constructing Cannon of Great Caliber, capable of enduring long continued Use under full Charges Memoirs of the American Academy*, Vol vi Part i pp 1-19 Cambridge and Boston U S, 1857 This memoir, after criticising the current methods of constructing guns of large size, proposes to form the caliber and breech of cast-iron, but to place outside these parts rings or hoops in one, two or more layers of wrought iron, every hoop is formed with a screw or thread upon its inside to fit to a corresponding screw or thread formed upon the body of the gun first, and afterwards upon each layer that is embraced by another layer These hoops are made a little, say $\frac{1}{1000}$ th part of their diameters less upon their insides than the parts they enclose, and are placed on hot, being then allowed to shrink and compress This method of constructing cannon appears to have been first suggested by Treadwell, and a process of building up guns by wrought iron hoops has been largely used see our Arts 1069, and 1076-82 The memoir gives a few details of the relative strength of such cannon and of cast

iron cannon (pp. 13–16), and concludes by describing a process of avoiding ‘lodgment’ (pp. 16–18), and with a condemnation of the European process of ‘piling or fagoting’ for building up wrought-iron cannon.

[1076.] James Atkinson Longridge: *On the construction of Artillery, and other Vessels to resist great Internal Pressure. Institution of Civil Engineers. Minutes of Proceedings.* Vol. xix. pp. 283–460 (with discussion). London, 1860. This is one of the numerous practical papers on artillery which contain statements with a good deal of bearing on physical and theoretical elasticity. There are frequent references in the course of the paper to Mallet’s researches: see our Arts. 1054–72.

The author commences by saying that he intends to limit his remarks to methods of making a gun ‘which gunpowder cannot burst.’ He refers then to the difficulty of making the cylinders of large hydraulic presses sufficiently strong to resist a pressure of 3 or 4 tons per square inch, and refers to what he terms the explanation of this difficulty given by Professor Barlow, “with the clearness which distinguishes all the works of that accomplished mathematician.” We have had occasion to mention this matter once or twice: see our Arts. 655, 901 and 1069.

[1077.] Barlow’s formula for the strength of hydraulic presses, which at one time had worked its way into all hydraulic text-books for practical engineers, depends on the assumption that the volume of the cylinder does not change owing to pressure¹. It was superseded in Germany ultimately by a formula due to Brix, based on the assumption that the thickness of the wall of the cylinder is not changed by the pressure. These two formulae, equally absurd in theory, maintained their places in the text-books long after Lamé had given more correct results²: see our Arts. 1012*–13* and footnote p. 550.

Our author proposes to make guns to withstand a very great internal pressure by placing coils of metal round the inner cylinder of the gun having initial stresses. Blakely, Sir William Armstrong and Mallet had, unknown to the author, been working on the same lines.

[1078.] The memoir commences by pointing out the extreme difficulty of making heavy guns of cast-iron, wrought-iron or steel. It notices how initial stresses are produced by cooling when metal is cast in large masses: see our Arts. 879 (f), 1039, 1056–8 and 1060. Further the difficulties inherent in the construction of wrought-iron and

¹ See Barlow’s erroneous theory in a paper entitled: *On the force excited by Hydraulic Pressure in a Bramah Press. Institution of Civil Engineers, Transactions*, Vol. i., pp. 133–9. London, 1836.

² Ruhlmann in his *Vorträge über Geschichte der technischen Mechanik*, Bd. i. S. 320, after remarking on the doubtful character of Barlow’s formula, states that Brix’s ‘deserves much more confidence,’—apparently because it does not give a limit to the pressure possible for an infinite thickness. This approval was given so late as 1885!

steel guns are noticed, especially difficulties of good welding and hammering are referred to (pp 287-96) The author then turns to the processes of construction suggested by Mallet and Blakely, consisting in putting on hoops of wrought-iron round the gun tube, which being put on hot, give, when cool, an initial tension. He considers that these processes of building up a gun are not satisfactory, because (i) they really would require an infinite number of infinitely thin hoops, and (ii) there is great practical difficulty in constructing the hoops with just the theoretically right radii. Longridge shows (pp 301-3) that an error in workmanship of only $\frac{1}{500}$ of an inch in the radius of a hoop may make a very serious difference in the stress in the material when the internal pressure is applied. There is a mathematical theory of the proper values of the radii of the successive hoops given in the Appendix (pp 329-335) by C H Brooks to which we shall return later. In a diagram on p 297 curves of the stress across an axial section of a hollow cylinder are given. These curves are plotted out for the formulae of both Barlow and Hart (see our Arts 1071 and 1077), so that in both cases they must be considered erroneous. The real curve would be obtained by plotting out, for values of r , the values of $\frac{p}{2}$, the meridional traction, which can be deduced from the results of our Art. 120, or for isotropy from those of our Art 1012*. Subtract the ordinates of this curve from a constant traction equal to the maximum to which we propose to subject the gun, and we have the initial tractions, which each point of the cylinder ought to be subjected to on the theory of Mallet and Longridge in order that we may have the strongest gun. There are I think obvious objections to this theory, of which I need only mention one, namely that it is not an equality of *stress*, but of *strain* (i.e. u/r see our Art 1080) that we ought to strive for, and that the former does not connote the latter see our Arts 1567*, 5(c) and 321.

In order to obtain the exact traction initially required Longridge discards a finite and limited number of hoops, and proposes to use coils of wire, which he holds can be put on with the exact stress indicated by theory (p 301). In the case of his experimental cylinders he put on his coils of wire with an initial tension deduced from Barlow's theory (p 306). It is, therefore, difficult to believe that he constructed the strongest possible cylinder, even if we assume that the results for solid cylinders could be legitimately applied to wire coils, and that the test for maximum strength is equality of stress, not of strain, across an axial section.

Pp 307-19 give details of the author's experiments on cylinders and guns bound with coils of steel or non wire. Pp 319-21 give the details of the construction of a small hydraulic press cylinder built up in this manner and of experiments upon it.

[1079] An Appendix to the paper (pp 322-337) contains various mathematical investigations. Thus on the force of gun powder wherein it is shown that the pressure exerted can be 17 to 25 tons

per square inch. Remembering that this is more or less of an impulsive pressure applied to the inside of the cylinder, and therefore theoretically might correspond in straining effect to a steady pressure of 34 to 50 tons, it would be little wonder if most guns ultimately burst by being thus continually strained beyond their elastic limit. It would not indeed much alter matters if the real impulsive pressure only reached a moiety of the above large value.

[1080.] The next portion of the *Appendix*, which is of interest for our present purpose is entitled: *Conditions of Stress of a Cylinder built up of Concentric Rings* (pp. 329–35) by Mr C. H. Brooks.

This investigation starts from expressions for the inner and outer meridian tractions in a hollow cylinder which agree with the values obtained from Lamé's formula (see our Art. 1012*). So far the theory seems likely to be more complete than Hart's, but, alas! the next stage is entirely erroneous. Brooks makes the following statement, which I cite with our notation:

Now if $\widehat{\phi\phi}$ be the tension at any radius r , and E the modulus of extension, then the extension of that radius is $\widehat{\phi\phi} \cdot r/E$ (p. 330).

This is the error into which Scheffler, Hart, and Virgile (see our Arts. 122, 655 with ftn. and 1071 (b)) have all fallen, and which it still seems impossible to root out of the mind of the technical elastician.

Lamé's formula quoted by Brooks from Rankine involves a longitudinal traction in the cylinder, and thus if u be the radial shift, and the external and internal radii of the cylinder be r_1 and r_0 , we easily find (see our Art. 1012*):

$$E \frac{u}{r} = \frac{E}{3\lambda + 2\mu} \frac{r_0^2 P_0 - r_1^2 P_1}{r_1^2 - r_0^2} + \frac{E}{2\mu} \frac{r_0^2 r_1^2 (P_0 - P_1)}{r^2 (r_1^2 - r_0^2)},$$

$$\text{while} \quad \widehat{\phi\phi} = \frac{r_0^2 P_0 - r_1^2 P_1}{r_1^2 - r_0^2} + \frac{r_0^2 r_1^2 (P_0 - P_1)}{r^2 (r_1^2 - r_0^2)}.$$

Whence in order that $u = \widehat{\phi\phi} \cdot r/E$ we must have $E = 3\lambda + 2\mu = 2\mu$, an absurdity. Thus we need not inquire into the accuracy of the remainder of Brooks' investigation.

In the discussion which followed the author refers to Lamé's formula as the basis of Dr Hart's and Mr Brooks' investigations but he does not see how hopelessly the latter have misapplied it (p. 341).

[1081.] Pp. 338–460 are occupied by the discussion which was extremely long and somewhat discursive. I may draw attention to the remarks: p. 345, on the want of longitudinal strength in wire-bound cylinders—another obvious reason why Lamé's formula should not be applied to them; p. 358, on the difficulty of forging large masses without flaw; p. 360, that the pressure of gun-powder could reach 30 tons per sq. inch; p. 364, that there is less internal stress in large castings after they have been kept a long time, showing a very slow after-strain effect; pp. 385–7, on cooling hollow cast-iron cylinders from the inside and so

obtaining an initial negative traction in the inner shells, p 388, on a method of testing the pressure produced at various distances along the bore of a gun on discharge and so calculating the strength of material required at the corresponding sections, p 443 and footnote, on the absolute tensile strength of cast-iron before and after remelting, also on its general average (p 444), pp 444-5, on the apparently slight influence of chemical identity on the identity of mechanical properties in iron. The impression made on my mind after reading the paper is the general want even so late as 1860 of theoretical training among practical engineers. The apparently universal acceptance in the discussion without the least enquiry of an erroneous theory is remarkable, and the need that experiments on the strength of materials should be conducted by those who have a real knowledge of the theory of the elasticity becomes very obvious. For example, throughout no distinction seems to have been drawn between impulsive external load and the resulting maximum internal stress, thus the absolute tensile strength of the material is spoken of as if it were the limit to be given to the internal pressure, which is quite false, were we even to suppose the gun to be elastic up to rupture, and its efficiency not destroyed by set.

[1082] T. A. Blakely *A mode of constructing Cannon, whereby the Strain produced by firing is distributed throughout the Mass of Metal*. This paper was printed in the *Journal of the United Service Institution*, whence it was reprinted in the *Civil Engineer and Architect's Journal*, Vol 22, pp 45-50, 81-3 London, 1859. *Idem* *Strength of Guns and other Cylinders*. Extract of a paper read at the United Service Institution. *Civil Engineer and Architect's Journal*, Vol 22, pp 245-7 London, 1859.

The first of these papers contributes but little to our knowledge of stress in cylindrical bodies. The author quotes erroneous results of Bailow's and notes that a press or gun will only stand a certain limit of internal pressure, whatever its thickness. The whole theory of pressure in cylindrical bodies had been some time previously correctly worked out by Lamé and it is not to the credit of our Ordnance Department at that date, that its scientific knowledge should have extended no further than the range exhibited in this paper. Blakely notes experiments showing that cylinders subjected to internal pressure first rupture on the inside. His object in the paper is to advocate that system of building up guns which consists in putting on rings of metal of a diameter slightly smaller than that of the inner cylinder or tube over which they are placed. He suggests wrought-iron hoops over a cast iron tube. There is considerable reference to the investigations of Mallet and Longridge see our Arts 1054 and 1076.

In the second paper Blakely cites results from the *American Reports of Experiments on Metals for Cannon* in order to show that a gun built up of hoops shrunk over each other must be much stronger than a solid cylinder. The experiments cited are those of the work referred to in our Art 1037.

[1083.] J. Cavalli: *Mémoire sur la théorie de la résistance statique et dynamique des solides surtout aux impulsions comme celles du tir des canons. Mémoire della R. Accad. delle Scienze di Torino. Serie II. T. xxii. pp. 157–233 with three plates. Torino, 1865.* The memoir was read on January 22, 1860.

This is one of several memoirs which were called forth by the publicity given to the results of Hodgkinson's experiments in the treatises of Love and others: see our Arts. 894, etc. The memoir is not without value although it contains some rather doubtful theoretical investigations. Considering the title of the paper and the fact that the major portion of it is devoted to the discussion of implements designed for the destruction of human life, it is a curious sign of the perverseness of even the scientific mind in 1860 to find the preface closing with the following words:

La connaissance du calcul de ces vitesses, avec les principes les plus élémentaires de la mécanique rationnelle et des sciences en général, fourniront aux constructeurs le seul guide infaillible pour réussir dans les grandes et nouvelles constructions, que le Tout-Puissant ait donné à l'intelligence des hommes pour qu'ils sachent bien s'en servir dans les études et les travaux auxquels tout mortel doit se livrer à l'avantage de son espèce, fuyant l'oisiveté pour justifier son passage sur la terre (p. 168).

[1084.] Cavalli's memoir opens with a *Préface* which occupies pp. 157–168. It commences by quoting with approval certain principles stated by Love. These principles are chiefly deduced from Hodgkinson's experiments and may be summed up as follows:

(i) There is no exact proportionality between stress and strain for cast-iron.

(ii) Set begins for cast-iron with even the smallest loads, and the term elastic limit has thus no real meaning.

(iii) Both cast- and wrought-iron subjected to impact or vibration can support indefinitely loads very near to those capable of producing immediate rupture (p. 159).

The third conclusion seems to me founded on very doubtful evidence, the second is true only if the body has not been reduced to a state of ease, while the first will probably now be generally admitted.

Cavalli next proposes to replace the *elastic limit* by what he terms *la limite de stabilité*. This limit is, I think, what I have termed the yield-point (see our Vol. i. p. 889), as the following words indicate:

Dans mes expériences à la flexion des barreaux on reconnaît nettement les flexions partagées en deux parties, retournantes les unes, restantes les autres dès leur commencement jusqu'à la rupture, et que chaque partie suit une loi différente mais régulière, dès la plus petite charge jusqu'à celle momentanée produisant la rupture. On découvre encore qu'il y a un terme

intermédiaire de la série de ces charges que les barreaux cessent de soutenir d'une manière stable, et où un mouvement de lassitude très insensible d'abord commence et s'accroît ensuite rapidement au fur et à mesure qu'on se rapproche à la charge de la rupture, quoique le temps de l'essai soit très-court (p 160)

Cavalli's experiments were made partly on flexure, partly on compression, and stress strain curves were traced automatically. After each small increase of load the load was removed, and we thus have a very accurate representation of the relations of elasticity and set to increasing load. Cavalli's curves figured on Plates II and III are extremely instructive and are I think the earliest of their kind. Plate II contains load flexure diagrams for bronze, cast iron and cast-steel, Plate III contains compression diagrams for the same three materials. Roughly speaking these diagrams bring out the following points (a) that both elastic strain and set follow laws the graphical representations of which give extremely regular curves, (b) that the state of ease can be extended almost up to absolute strength, (c) that the elasticity remains practically the same throughout this extension, (d) that there is a point at which set begins to increase with great rapidity see our Vol 1, pp 887-9, (5)-(8). With regard to (d) we note that for a considerable range of stresses the set curve is almost a straight line close to and parallel to the stress axis, then it begins to slope more and more to this axis. The point at which this change takes place Cavalli calls the 'limit of stability' and he considers it ought to replace the 'elastic limit'. It seems to me that it is an important limit the knowledge of which is essential, but that it does not replace the 'elastic limit,' which notwithstanding Cavalli's statements (e.g. p 162) has a real existence, only every stress exceeding the limit to the state of ease alters its value. In order to ascertain the exact point at which the bar ceases to sustain its load stably, Cavalli takes the limit of stability to be the point which is midway¹ between the point at which it is doubtful whether the curve of set has ceased to be parallel to the stress axis and the point at which there is no doubt such parallelism has ceased (p 181). He terms this point the limit of stability, because he holds apparently that for any load beyond this limit, the bar will continue to yield till after a longer or shorter time it ruptures (p 175). Thus he considers the limit of stability to be the proper measure of strength for permanent loading, while for impulsive loading, lasting only during a very brief interval, it is allowable to pass this limit of stability, provided the stress still remains sufficiently below the absolute strength (pp 176-7). This of course is the legitimate result of principle (iii) stated above, but that principle itself seems to me doubtful. Owing to the above statements we have associated Cavalli's 'limit of stability' with our yield point although in some respects it seems to be closer to the point half way between B and C on the diagrammatic stress strain curve of our Vol 1, p 890.

¹ Cavalli has 'le point intermédiaire le plus près du second des dits points' but this is very indefinite.

[1085.] Cavalli now notes that while in most cases the curve giving the relation between the elastic stress and strain is practically linear, that between the set strain and stress is represented by a curve which although perfectly regular has yet to be determined analytically. The sum of the areas of these stress-strain curves, however, gives the work done on the bar up to any given load, and Cavalli accordingly divides this work into two parts which we may term "elastic strain energy" and "ductile strain energy" (*travail élastique et travail ductile*). The energy which the body can absorb of the former kind, increases as the state of ease is extended; the energy of the latter kind is a definite quantity and can only be used once, although it may be consumed in parts on different occasions. Cavalli holds that the elastic and ductile strain energies are the true measures of the practical strength of materials; he expresses them in terms of the kinetic energy of a particle, of mass equal to that of the material, moving with velocities V (for the elastic strain energy) and W (for the united elastic and ductile strain energies). The values of V and W (*vitesses d'impulsion*) thus measure the *resilience* of the material, and their values at the limits of stability and rupture are tabulated on pp. 230–3 of the memoir for a considerable number of bars of bronze, cast-iron and cast-steel (wrought and unwrought), as ascertained by flexural and compressional experiments.

The above sufficiently indicates the general lines of Cavalli's investigations so far as they appear of real novelty or service, but a detailed criticism of his rather lengthy theoretical statements may be of service to other investigators, and I devote the next few articles to it.

[1086.] § I. of the memoir (pp. 168–75) is entitled: *De l'existence de la limite de stabilité au lieu de la limite d'élasticité*. This opens with a statement of the old 'paradox in the theory of beams': see our Arts. 173, 507, 542, 930–8, 1043 and 1051–3. Given a beam of rectangular cross-section of height h and breadth b , then if M be the breaking bending-moment, the absolute strength T (as deduced from an extension of the Bernoulli-Eulerian theory to rupture) is given by

$$T = 6 \frac{M}{bh^2}.$$

Now Hodgkinson found that for cast-iron bars the factor 6 must be replaced by 2.63, or if T_2 and T_1 be the absolute strengths as calculated from traction and flexure respectively we have:

$$T_2/T_1 = .438, \text{ or (in the notation of Arts. 1051–3) } S_1/S_2 = .380.$$

But the American experiments on the metals for cannon (see our Art. 1043) show that the ratio of T_2 to T_1 varies with the density of the cast-iron, increasing up to a certain density and then rather strangely decreasing. Cavalli holds this decrease to be a result of defective experimental method (possible failure of exactly axial application of

load which often occurs in *pure traction* experiments see our Art 1249* and Cavalli's memoir, pp 169-70 and 160), and after rectifying the results, he obtains values of the ratio increasing from 57 to 72 with the density¹ He uses this variation as a general argument against the ordinary theory of beams and as in some way suggesting the importance of his own investigations into the 'limit of stability,' because he supposes it to show the inapplicability of the theory based on the 'limit of elasticity' He passes rather abruptly from this discussion to a description of his testing machine and automatic apparatus for drawing stress strain diagrams (pp 172-5)

[1087] § II of the memoir (pp 175-87) is entitled *Discussion des nouveaux principes à admettre, et déduction de la mesure du travail élastique et ductile, et de la vitesse d'impulsion que les solides peuvent supporter* In this section the author first states and criticises the conclusions of Love, Hodgkinson, Belanger and Moir, and then states his own theory of resilience as the true test of resistance especially for the case of impulsive loading He qualifies his previous statements as to the limit of rupture being the superior limit for impulsive stress (see the principle (iii) of our Art 1084) by the rather vague reservation that the impulses must not succeed each other too rapidly, nor last for too long a time without interval of repose (p 178) The following remarks indicate Cavalli's standpoint and deserve quotation

Lorsqu'une seule portion du travail ductile l'épuiserait à chaque impulsion, le nombre ou la somme de ces impulsions ne devra pas dépasser la limite du travail ductile total, de sorte que ce nombre d'impulsions que le prisme pourra supporter à la limite prescrite se trouvera restreint

Le choix entre les différents matériaux à employer dans les constructions se trouva par ces conditions soumis à un calcul qu'il faut savoir faire. On ne pourra pas dire d'avance qu'on doit dans telle sorte de construction employer les matériaux plus ductiles qu'élastiques et *vice versa* dans telle autre sorte de construction, on s'exposerait par un tel procédé à bien des méprises, comme l'abus des constructions toutes en fonte a fait ressortir et comme il arriverait par l'abus de tout faire en fer forge (p 179)

[1088] To apply his theory Cavalli proceeds thus Let F be the load and x the elastic, y the 'ductile' deflection immediately under the load, then the elastic strain energy $= \frac{1}{2}Fx$, while the ductile strain energy $= \frac{1}{2}F\tau y$, where $\frac{1}{2}\tau y$ is the mean ordinate of the ductile stress-strain (or really of the load deflection) curve Now Cavalli's experiments were made on the flexure of a cantilever of length l and rectangular cross section $b \times h$, hence, if T_0 be the maximum elastic stress in the beam

$$T_0 = 6 \frac{FL}{bh^2} \quad \text{and} \quad \tau = \frac{4FL}{Ebh^2},$$

¹ The mean of the American results as rectified by Cavalli gives $T/T_0 = 0.6$ the ratio as deduced from the hypothesis proposed by the Editor in a paper on the Flexure of Beams *Quarterly Journal of Mathematics* Vol XXIV p 105 1890 is for the case of a rectangular section 667

or,
$$\frac{1}{2}Fx = \frac{1}{18} \frac{T_0^2}{E} b h L.$$

If D be the density of the material, Cavalli equates this to $\frac{1}{18} b h L D \times V^2$ and so finds :

$$V^2 = \frac{T_0^2}{ED}.$$

Thus Cavalli's V is at once determined by the density of the material and the *modulus of resilience* : see our Art. 363.

If W be the velocity corresponding to both elastic and ductile strain energies

$$\frac{1}{18} b h L D \times W^2 = \frac{1}{2} Fx + \frac{1}{2} F\tau y,$$

whence we have

$$W = V \sqrt{1 + \tau \frac{y}{x}},$$

where τ and y/x have to be determined by experiment for each material. According to Cavalli's results τ decreases by about a half between the limits of stability and rupture, so that Hodgkinson's experiments on cast-iron which made $y \propto F^2$ and give $\tau = 2/3$ cannot be accepted as generally true : see pp. 185-6 of the memoir and our Arts. 969* and 1411*.

[1089.] The reason apparently why Cavalli takes $\frac{1}{18} M V^2$ instead of $\frac{1}{2} M V^2$ as suggested by his definition of V (see our Art. 1085), is that he supposes $\frac{1}{2} M V^2$ to be the resilience of longitudinal elasticity. $\frac{1}{2} Fx$ in this case is equal to $\frac{1}{2} \frac{T_0^2}{E} b h L$ and this is nine times the above value. The following are Cavalli's *mean* results in metres per second¹ (p. 184) :

Material		At Limit of Stability		At Rupture	
		<i>V</i>	<i>W</i>	<i>V</i>	<i>W</i>
Bronze	{ Extension	5.44	6.16	18.00	29.50
	{ Compression	14.03	15.43	34.74	48.80
Cast-Iron	{ Extension	8.16	8.79	16.4	18.3
	{ Compression	27.45	27.78	80.54	87.43

This table may be used to obtain the moduli of resilience, which are equal to $D V^2$ or $D W^2$ as the case may be.

¹ The second number in the first column of the table in the footnote, p. 184, should be 4.93 and not 5.60, I think.

Cavalli in some rather obscure reasoning on p 186 appears to state that any portion of a body may receive a blow which gives it a velocity V (or W as the case may be) without ultimate (or immediate) danger. For example, the velocity given to the parts of the inner surface of a cannon ought not to exceed the value W . But I am unable to follow the argument, nor do I understand how the velocity, which if attributed to the entire mass would give an amount of energy equivalent to the strain energy, is necessarily the velocity with which any part will commence vibrating. It must be noted that throughout Cavalli neglects the inertia of the vibrating parts, i.e. proceeds statically, and although this may give the maximum total flexure or compression fairly correctly, Saint-Venant has shown, that for the case of transverse impact at least it is very far from giving the correct value of the maximum strain, which depends on relative flexure or relative compression see our Arts 371, 406 and 412

[1090] § III (pp 187-96) is entitled *De la position des fibres invariables dans les prismes soumis à la flexion*. This section rejects Hodgkinson's stress strain relation for cast iron, and asserts that the neutral axis does not pass through the centroid of the section because the stretch and squeeze moduli are unequal. This had in fact been previously discussed by Hodgkinson (see our Art 234*), and there is nothing new or of real value in Cavalli's results. By taking P and Q as the resistances per unit area to extension and compression respectively and supposing the material perfectly elastic, Cavalli finds that the ratio Q/P must be in some cases as much as 6, if the absolute strengths as given by tractive and flexural experiments are to agree. He does not seem to have noticed that with his definitions and on his hypotheses this would have made the squeeze-modulus six times the stretch modulus (pp 189-93).¹ Morin's hypothesis, which our author condemns,—i.e. that the resistances to compression and extension only begin to vary after the elastic limit is passed,—is certainly more reasonable than this.

Cavalli quotes a formula due to Roffiaen for the strength of a prism under flexure (see our Arts 892 and 925), and applies his own results to a prism of circular cross section. The treatment in both cases is obscure, not to say inadmissible.

[1091] § IV of the memoir is entitled *Essai theorique de la resistance vive elastique et ductile des prismes par la vitesse d'impulsion des solides, suivi d'exemples pratiques* (pp 196-229).

This introduces Tredgold's modulus of resilience $\frac{1}{2} E$ but attributes it to Poncelet. The investigation of the longitudinal resilience on p 198 is obscure, because it is not obvious why Cavalli concentrates the mass of the rod at the free end. The results for a frustum of a cone on p 199 seem to me still more doubtful. In treating of the flexure of a cantilever Cavalli concentrates *half* its mass at the free end (pp 199-202) and applies his theory of the shifted neutral axis. In all these cases the inertia of the bar is neglected but it has

have pointed out, the greatest influence on the maximum strain. On pp. 204-5, there is an unsatisfactory attempt to determine the time over which an impulse must be spread, in order that the whole and not a part of the bar may sustain the work due to the impulse. Cavalli finds that when the time of the maximum safe impulse is less than

$$t_1 = \frac{\pi x_1}{2V},$$

where x_1 is the maximum shift of the free end and V the velocity discussed in our Art. 1088, then even with this impulse the bar will be injured at the part to which the blow is applied.

[1092.] Cavalli next passes to practical examples chiefly dealing with problems in gunnery and with the penetration of shot into iron-plates (p. 205 to the end).

As a sample of the somewhat loose style of reasoning as well as of grammar adopted in these pages, I cite the following example, which does not belong to the theory of gunnery :

Prenons à calculer un pont en poutres simples de fer sur un chemin de fer pendant le passage des trains : ces poutres fléchiront pour se redresser après le passage. De même que dans le calcul statique on ne considère que la moitié de la charge concentrée au milieu, l'autre moitié de la charge étant portée par les culées, l'on pourra considérer aussi ici que la moitié de la masse totale du pont et de la charge est concentrée au milieu, et tombant de la hauteur de la flexion entière ; soit pour plus de simplicité dans le calcul, que pour avoir égard aux secousses que l'irrégularité du mouvement du train causera au pont (pp. 215-6).

Considering the attention this problem had already received from Willis, Stokes and Phillips (see our Arts. 1276*-91*, 1418*-22*, 378-82 and 552-60), Cavalli's treatment is somewhat antiquated.

Without entering into an analysis of these individual problems, we may conclude our notice of Cavalli's memoir with citing a remark he makes on the testing of cannon. After noting that every impulse which exceeds the existing elastic limit uses up some of the reserve of ductile strain-energy in the material, and that every successive impulse uses up more of this surplus energy until either by raising the elastic limit the elastic strain-energy alone suffices, or the gun at last bursts, he continues :

L'épreuve des canons par des tirs surtout plus forts que ceux ordinaires, outre d'être embarrassante et très-coûteuse, prouve seulement qu'après ces tirs les canons qui l'ont subie sont moins bons qu'auparavant, sans pouvoir, pour plusieurs causes confirmées par l'expérience, nous rassurer d'après leur résistance sur celle des autres canons (p. 227).

To the memoir are affixed the tables of experimental results referred to in our Art. 1085.

GROUP F

Strength of Iron and Steel

[1093] *A Series of Experiments on the Comparative Strength of Different Kinds of Cast-Iron, in their simple state as cast from the Pig, and also in their compounded state as Mixtures, made under the directions of Robert Stephenson, Esq, with a view to the selection of the most suitable for the various purposes required in the construction of the High Level Bridge* The experiments were made at Gateshead, September, 1846, to February, 1847, and the results are published in the *Civil Engineer and Architect's Journal*, Vol XIII, pp 194—199 London, 1850 Only the numerical results—consisting of the loads and deflections through a certain range up to the breaking load, together with the initial series of sets—are given No general conclusions are drawn nor is there any graphical representation of results

[1094] *Rapport d'une Commission nommée par le gouvernement anglais, pour faire une enquête sur l'emploi du fer et de la fonte dans les constructions dépendant des chemins de fer Annales des ponts et chaussées Mémoires*, 1851, 1^{er} Semestre, pp 193—220 Paris, 1851 This is a translation by Busche of the report attached to the evidence of the Iron Commissioners see our Art 1406*

[1095] In the volume of the *Annales des ponts et chaussées* for 1855, *Mémoires*, 1^{er} Semestre, pp 1—127 will be found a French translation of E Hodgkinson's *Experimental Researches* (see our Arts 966*—73*) by E Puel Even at the present day the results of Hodgkinson's experiments reduced to French measure are not without special value

[1096] Dehaigne *Galvanisation du fer avantages de l'emploi de fils galvanisés dans les ponts suspendus Annales des ponts et chaussées Mémoires*, 1851, 1^{er} Semestre, pp 25—28 Paris, 1851 On pp 280—8 will be found details of experiments on the absolute strength of iron wire before and after galvanisation, and it is shown that the iron loses nothing of its strength or ductility by the process some of the experiments show indeed a great increase of strength owing to galvanisation

[1097.] *British Association, 1852, Belfast Meeting, Transactions*, p. 125. Notice of some experiments by Fairbairn then in progress to test the effect of repeated meltings on the strength of metals—and further to test the effect of temperature on unwrought iron plates.

[1098.] The experiments on the effect of repeated meltings referred to in the previous article form the subject of a paper communicated to the *British Association* in 1853, and printed on pp. 87–116 of the Report of the Hull Meeting for that year. The paper is entitled: *On the Mechanical Properties of Metals as derived from repeated Meltings, exhibiting the Maximum Point of Strength and the Causes of Deterioration*.

Fairbairn commences by thus stating the object of his investigation, undertaken at the request of the Association:

It is a generally acknowledged opinion, that iron is improved up to the second, third and probably the fourth meltings; but that opinion, as far as I know, has not been founded upon any well-grounded fact, but rather deduced from observation, or from those appearances which indicate greater purity and increased strength in the metal.

Those appearances have, in almost every instance, been satisfactory as regards the strength; and the questions we have been called upon to solve in this investigation, are, to what extent can these improvements be carried without injury to the material; and what are the conditions which bear more directly upon the crystalline structure, and the forces of cohesion by which they (*sic*) are united (p. 87).

[1099.] The first set of experiments were on the resistance of rectangular bars (in all cases of nearly 1 inch square cross-section and of 4 ft. 6 inches span) to a central transverse load. 18 successive meltings were undertaken of which the 17th melting was a failure, "the iron being too stiff to run into bars." Fairbairn reduces his results to a standard beam of 1 inch square cross-section and 4 ft. 6 in. span. He terms the product of the breaking load into the ultimate deflection, the *power of resisting impact*. He considers it *proportional* to the resilience, and it is entered in the table below as Proportional Resilience. The experiments were made on "Eglinton Iron, No. 3, Hot-blast." After each melting the rupture-surfaces were microscopically examined and presented interesting changes, in some cases figured in the memoir. Their general appearance is described in rather vague language, as: 'finely grained texture,' 'crystals of greatly increased density,' 'fine frosty appearance,' etc. One noteworthy change is the appearance of an internal core in the last meltings differing much in structure from the rest of the metal.

I reproduce the following summary of results (pp 107-8)

No of Meltings	Specific Gravity	Mean rupture load in lbs	Mean ultimate deflection in inches	Proportional resilience
1	6 949	490 0	1 440	705 6
2	6 970	441 9	1 446	639 0
3	6 886	401 6	1 486	596 7
4	6 938	413 4	1 260	520 8
5	6 842	431 6	1 503	648 6
6	6 771	438 7	1 320	579 0
7	6 879	449 1	1 440	646 7
8	7 025	491 3	1 703	861 2
9	7 102	546 5	1 620	885 3
10	7 108	566 9	1 626	921 8
11	7 113	651 9	1 636	1066 5
12	7 160	692 1	1 666	1153 0
13	7 134	634 8	1 646	1044 9
14	7 530	603 4	1 513	912 9
15	7 248	371 1	643	238 6
16	7 330	351 3	566	198 8
17	lost			
18	7 385	312 7	476	148 8

It will be noted that the transverse strength decreases from the 1st to the 3rd melting and then increases to the 12th melting after which it rapidly decreases. The resilience also reaches its maximum at the 12th melting, but I should not feel inclined to lay much stress on any results obtained by a measurement of ultimate deflections.

[1100] A second series of experiments was made on the compressive strength of the same iron after 18 meltings (pp 109-113). The following results were obtained.

No of Meltings	Compressive strength in tons per sq inch	No of Meltings	Compressive strength in tons per sq inch
1	44 0	10	57 7
2	43 6	11	61 8
3	41 1	12	73 1
4	40 7	13	*66 0
5	41 1	14	95 9
6	41 1	15	76 7
7	40 9	16	70 5
8	41 1	17	lost
9	50 1	18	55 0

* In Experiment 13 the cube was not properly bedded, and so the result is erroneous. It would probably, Fairbairn says, have given 80 to 85 tons per sq inch.

Up to the eighth melting it will be observed that the ordinary power of resistance to a crushing force, namely, about 40 tons to the square inch, is indicated. Afterwards, as the metal increases in strength, from the eighth to the thirteenth melting, a very considerable change has taken place, and we have 60 instead of 40 tons as the crushing force. Subsequently, as the hardness increases, but not the [transverse] strength, double the power is required to produce [crushing] fracture (p. 115).

Plate 3 at the end of the *B. A. Report* figures the rupture surfaces of the blocks crushed in the experiments.

The results are compared with those of Rennie, Rondelet and Hodgkinson: see our Arts. 185*-7*, 696*, and 948*-51*. The memoir concludes with a chemical analysis of the iron after different meltings by F. C. Calvert (pp. 115-116). From this analysis it appears that silicium increases, while sulphur and carbon fluctuate in percentage with the number of meltings.

[1101.] *British Association*, Report of Liverpool Meeting, 1854, *Transactions*, pp. 151-152. Letter of William Hawkes: *On the Strength of Iron after repeated Meltings*. The writer had made experiments on "Corbys Hall Iron, No. 1, Hot-blast" with 29 successive meltings. His results do not present the regularity of change which marks Fairbairn's experiments: see our Art. 1099. They do indeed give a minimum and maximum of strength after the 6th and 12th meltings respectively, but these are followed again by a minimum at the 14th, a maximum at the 18th, a minimum at the 21st, and a maximum at the 24th, while the strength at the 29th is greater than after the first melting. There is thus no sign of deterioration following on any number of meltings, such as was manifested in Fairbairn's results: see our Arts. 1059 and 1099.

[1102.] F. C. Calvert: *On the Increased Strength of Cast-Iron produced by the use of improved Coke, with a Series of Experiments* by W. Fairbairn, *Institution of Civil Engineers, Minutes of Proceedings*, Vol. XII., pp. 352-381. London, 1853. Evidence is given in this paper as to the amount of influence which the method of preparation has on the elasticity, set and absolute strength of cast-iron.

[1103.] J. Jones: *Table of Pressures necessary for Punching Plate-Iron of various Thicknesses. The Practicual Mechanic's Journal*, Vol. VI., p. 183. London and Glasgow, 1853-4. This table contains numerical details of apparently very careful experiments on punching plate-iron. It would still be of considerable service to any investigator wishing to test a theory of absolute shearing strength: see our Art. 184 (b). No theory is attempted in the paper itself.

[1104.] C. R. Bornemann: *Notiz über John Jones' Versuche über den Kraftbedarf zum Lochen von Kesselblechen. Dinglers*

Polytechnisches Journal, Bd 140, S 327-32 Stuttgart, 1856
The details of Jones' experiments on punching holes of various diameters in iron boiler-plates had been cited in the *Polytechnisches Centralblatt* for 1854 (see our Art 1103) Bornemann gives a *résumé* of them, calculating the mean values, and he suggests the following empirical formula

$$P = 62725 - 2822 \cdot 34\alpha,$$

where P is the punching stress per unit-area of sheared surface and α is the area of the sheared surface, P being measured in pounds per sq inch and α in sq inches For a circular hole of diameter b in a plate of thickness τ , the total load $L = \pi b \times \tau \times P$ and $\alpha = \pi b \times \tau$ or

$$\begin{aligned} L &= (62725 - 2822 \cdot 34\pi b\tau) \pi b\tau \text{ lbs,} \\ &= (197056 - 27856b\tau) b\tau \text{ lbs} \end{aligned}$$

Bornemann obtains the numerical coefficients by means of the method of least squares and he then compares the result with earlier investigations on punching strength,—e g those of E Cresy (*Encyclopædia of Civil Engineering*, New Impression, Vol II, pp 1035 and 1708 London, 1861), which give considerably smaller values for L , of Fairbairn (*locus?*), of Gouin et Cie (see our Art 1108) In round numbers we have for the punching strength in kilogrammes per square millimetre Jones, 42, Cresy, 31, Fairbairn, 37, Gouin et Cie 32 Bornemann concludes with the following table for English plate-iron

Resistance to punching	42	kilogrammes per sq millimetre,
, , traction	40	” ” ”
” ” shearing	32	” ” ”
” , crushing	25	

The last number 25 I do not understand, as I should have expected the crushing strength to be greater than this

[1105] J D Moiries Stirling *On Iron, and some Improvements in its Manufacture Institution of Mechanical Engineers, Proc edn of* 1853, pp 19-33 London, 1853 This paper contains experiments on the transverse and tensile strengths of cast and wrought iron with the details of some experiments by Owen on the comparative strength of ordinary and 'toughened' cast iron girders (p 23 and Plate 4)

[1106.] Brame: *Note sur l'application de la tôle à la construction de quelques ponts du chemin de fer de ceinture. Annales des ponts et chaussées. Mémoires*, 1853, 1^{er} Semestre, pp. 78—111. Paris, 1853. This contains some account of experiments by Brame on iron-plate with references to those of Hodgkinson, Fairbairn, Gouin et Cie., etc. see our Arts. 1477*, 1497* and 1108.

[1107.] Kirchweger: *Ueber die Prüfung des Stabeisens. Polytechnisches Centralblatt*, 1854, Cols. 1110—6. Leipzig, 1854. (Extracted from *Mittheilungen des Gewerbevereins für das Königreich Hannover*, 1853, S. 240.) This paper gives details of German experiments on the strength of English iron plates used for the girders of railway bridges. The plates were tested by boring rivet holes in them, which were then driven asunder by a conical steel wedge upon which a given weight was allowed to fall repeatedly from a definite height. The number of blows required for rupture was taken as a measure of the strength.

[1108.] Gouin et Cie. (*Expériences sur la résistance à la traction de tôles de diverses provenances et sur celle des rivets*). These are described in an article by Mathieu and Lavalley on the *Pont de Clichy* in the *Mémoires...de la Société des Ingénieurs civils*, Année 1852, pp. 153—7. Paris, 1852. A German translation appeared in the *Polytechnisches Centralblatt*, Jahrgang 1854, Cols. 525—6. The first part of the experiments deals with the absolute tensile strength of iron-plate parallel and perpendicular to the direction of the rolling. For charcoal raw iron there was on the average a fall from 3313 to 3240 kilog. per sq. centimetre; for coke raw iron a fall from 3657 to 2906. Hence the rolling has far less influence when the iron is prepared in the former fashion: see our Arts. 1497*, 879 (d) and 902.

The second part of the experiments deals with the absolute shearing strength of iron rivets of 8 to 16 millimetres diameter. The shearing strength averaged about 3200 kilogs. per sq. centimetre as compared with about 4000 kilogs. tensile strength, or very nearly in the $\frac{4}{5}$ ratio obtained by extending uni-constant isotropy to the rupture of wrought-iron.

[1109.] Collet-Meygret et Desplaces: *Rapport sur les épreuves faites à l'occasion de la réception du viaduc en fonte construit sur le Rhône, entre Tarascon et Beaucaire, pour le passage du chemin de fer, et sur les observations qui ont servi à constater les mouvements des arches sous l'influence de la température et des charges, soit permanentes, soit accidentelles; suivi de considérations sur le mode de résistance et sur l'emploi de la fonte dans les grands travaux publics. Annales des ponts et chaussées. Mémoires*, 1854, 1^{er} Semestre, pp. 257—367. Paris, 1854.

This memoir contains an account of the viaduct over the Rhone at Tarascon, the arches of which were made of cast-iron.

The description is of interest, as these arches have been dealt with theoretically by Bresse see our Arts 520 (a) and 527 It is also, I think, the first bridge in which the strains due to changes of temperature were carefully measured (pp 274-291) The exact deflections due to dead and live load were also very accurately ascertained (p 280 and pp 292-307) The diminution of the compressibility of the iron with the increase of the load, i.e. the non-proportionality of stress and strain within the elastic limit, seems to have been noted on the large scale of this bridge see our Arts 1411* and 935

[1110] On pp 307-19 we have a comparison of theory and experiment The authors give the following formula for the deflection f (deduced in *Note A*, pp 360-4)

$$f = \frac{p^2 r^4}{E \omega \kappa^2} \times 000,004,855,$$

where p = the weight of the arch per unit run of the horizontal, r the radius of its central axis, E its stretch modulus and $\omega \kappa^2$ the usual moment of inertia of the cross section about the 'central axis' The values of f obtained from this formula were far from agreeing with those found by direct experiment The authors accordingly argue that E ought only to be given one half the value previously adopted for it from traction experiments (p 320) It must be remarked, however, that their theory of arched ribs is very far from satisfactory and that it ought to be replaced by Bresse's investigation see our Arts 514-31

This discrepancy in their theory leads the authors to consider the details of a number of French and English experiments on cast iron They show that its *tensile strength* varies with its quality and the dimensions of the test-piece to a very wide extent, and hence they appear to argue (p 329) that its stretch modulus can also have values varying from 6,000,000,000 to 12,000,000,000 kilogrammes per sq metre This does not seem very convincing, especially as the table (p 327) of tensile strengths has been deduced from flexure experiments see our Art 1052 A more satisfactory investigation by direct experiment of the values of E follows on pp 330-46 These values were found to vary from less than 3,000,000,000 to more than 12,000,000,000 kilogrammes per sq metre, according to the material of the bar The authors conclude that

1° les barreaux de fonte des diverses usines essayés dans les mêmes circonstances donnent des valeurs de E peu différentes

2° un barreau donne pour E des valeurs sensiblement différentes suivant qu'il est posé à plat ou de champ

3° les barreaux d'une même usine donnent des valeurs de E très différentes suivant les conditions des assemblages, posés sur deux appuis et chargés au milieu, ils donnent des valeurs de E plus grandes que lorsque étant posés sur

deux appuis ils sont chargés à leurs extrémités, ou lorsqu'étant encastrés par un bout ils sont chargés à l'autre bout, et, dans ce cas, ils donnent des valeurs de E plus grandes que lorsqu'ils sont chargés debout, c'est-à-dire comprimés dans le sens de leur longueur (p. 337).

As a result of these conclusions Collet-Meygret and Desplaces consider that the best value of the stretch-modulus for the iron of the Tarascon viaduct ought to be obtained by comparing direct experiment on the bridge itself with the formula referred to above. They consider that it is the manner in which the iron is employed in the structure rather than its particular 'manufacture' which determines the value of its stretch-modulus.

[1111.] They especially note the difference between the elasticity of the core and periphery in the case of cast-iron bars and conclude :

1° que de deux pièces semblables de la même fonte, la plus grosse donnera la plus faible valeur de E .

2° qu'une même pièce chargée de la même manière et sous les mêmes assemblages donnera, lorsqu'elle sera présentée sous différentes faces, des valeurs de E différentes, dépendantes du moment d'inertie de sa section, comparé au moment d'inertie de son périmètre.

3° que dans une même pièce de fonte on trouvera pour E une valeur d'autant moindre que dans les joints d'assemblage et par le mode de chargement, on laissera libre une plus grande portion du périmètre, de manière qu'une plus grande partie du métal extérieur, le moins élastique, soit entraînée par le métal intérieur, le plus élastique, au lieu de le retenir (pp. 340-1).

The authors suppose the periphery to have a thickness of .005 metres, a stretch-modulus ϵ and an absolute tractive strength τ . Then if E and T be the like quantities for the core, they find from experiments on cast-iron bars such as were used in the Rhone viaduct in kilogs. per sq. metre,

$$\begin{array}{ll} \tau > 40,000,000, & \epsilon > 12,000,000,000, \\ T < 20,000,000, & E < 3,000,000,000. \end{array}$$

Their remarks on the experiments leading to these results and the conclusions to be drawn from them are of considerable interest: see their pp. 341-6 and our Arts. 169 (e)-(f) and 974 (c). Similar differences probably hold for the temperature effect on the core and on the periphery, but the authors remark that as various physicists give values for the stretch per degree centigrade of iron, whether it be cast or wrought, varying only between .000,011 and .000,013, it is safe to neglect these differences and adopt the number .000,012,2 to represent this stretch.

[1112.] With this value of the stretch or thermal coefficient and with the modified value of the stretch-modulus the authors (pp. 346-58) analyse the various elements of flexure due to temperature, to live and to dead load. They sum up their conclusions on pp. 358-60. Their

remark, that the values of the elastic constants found by physicists experimenting on small bars of metal cannot be safely adopted for large masses of the same metal such as occur in great engineering structures, deserves from its obvious truth more attention than it has sometimes received (p 359) To the memoir are appended (pp 360-7) various notes which do not call for special mention here

[1113] G Weber *Versuche über die Cohäsions und Torsionskraft des für Geschütze bestimmten Krupp'schen Gussstahls* *Dinglers Polytechnisches Journal*, Bd 135, S 401-17 Stuttgart, 1855

This memoir opens with some interesting details of the chemical constitution of gun metal used in 1663 and later, and shows how the earlier metal would certainly not have stood the strength of modern (?) powder Weber then proceeds to details of the tensile and the torsional strengths of steel (manufactured by Krupp, and in England, Salzburg and the Tyrol) of wrought-iron and of bronze or gun metal There is an interesting figure (Tab VI, Fig 2) giving a good picture of the stricture of a bar of Krupp's cast-steel for guns It shows exceedingly well the relative amount of stricture at each cross section and the total change at rupture of each dimension of the bar The whole paper is an advertisement for Krupp, but probably a well deserved advertisement

[1114] Details of various experiments on the strength and elasticity of steel with reference to the peculiar difficulties of casting it so that its quality is uniform throughout the piece, and with comparison of results obtained for wrought-iron will be found in the *Polytechnisches Centralblatt*, Jahrgang 1856, Cols 1275-6, Jahrgang 1857, Cols 35-44 (*Annales des Mines*, T VIII, pp 373-88, 1855) and Jahrgang 1857, Cols 1128-38 All these have special reference to steel prepared by Uchatius' process With regard to the strength and stricture of wrought-iron prepared by the Bessemer process an account of some experiments made at Woolwich will be found in *The Mechanic's Magazine*, 1856, p 270

[1115] William Fairbairn *On the Tensile Strength of Wrought-Iron at various Temperatures* *British Association*, Cheltenham Meeting, 1856, *Report* pp 405-422

These experiments are of very considerable interest, as in many structures of wrought-iron the material is subjected to very high temperatures or to a considerable range of temperatures Fairbairn's first series are on the tensile strength of boiler plates with and against the fibres From 0 to 395 Fahr there seem to be only very slight fluctuations in the strength in the direction of the fibre, and these are not improbably due to experimental errors, or to weaknesses in the individual pieces Roughly the strength fluctuates from 18 to 22 tons per sq inch without any

apparently regular variation with the temperature. I have little doubt that some of the fluctuation is due to want of exactly central pull in the arrangement adopted by Fairbairn. For tensile strength across the fibre there is a rise from about 18·7 to 20·4 tons per sq. inch for a change of temperature from 0° to 212°, a fall to 18·8 at 340° and to 15·3 at visible red heat, the latter result being considered by Fairbairn as too high. Here again the only safe conclusion seems to be that at “a dull red heat just perceptible in day-light” the tensile strength is much reduced. At what heat the maximum is reached is not rendered clear by the experiments (pp. 413–4).

[1116.] The second series of experiments relate to the tensile strength of rivet-iron. Here there was a more marked relation between strength and temperature. The experiments were on temperatures from -30° to 435° and at ‘red heat.’ There was an increase here from 28·2 tons at -30° to 37·5 at 325° , and at least a steady increase from 28·1 tons at 60° to 37·5 at 325° . After this there was a slight diminution at 435° , and a great drop to tons (marked “too high”) at red heat (p. 420).

The memoir concludes with a comparison of the increase in strength due to rise of temperature with that due to repeated fracture, and with some remarks on the stretch in bars of different lengths, which do not seem to me of much scientific value: see pp. 421–2 and our Art. 1503*.

[1117.] William Bell: *On the Laws of the Strength of Wrought- and Cast-Iron*, *Institution of Civil Engineers, Minutes of Proceedings*, Vol. xvi., pp. 65–81. London, 1857. A résumé of this paper will be found in the *Mechanic's Magazine*, Vol. 65, pp. 579–81. London, 1856. It is an endeavour to demonstrate from the many experiments which have been made on cast- and wrought-iron beams under flexure that theory and experiment are after all not so discordant as some have supposed. We may sum up the author's conclusions as follows:

(i) For slight strains theory and experiment coincide.

(ii) The ordinary theory of rupture practically coincides with experiment for wrought-iron beams, especially those of large size. [It should only do this if Hooke's Law practically holds for wrought-iron up to rupture.]

(iii) There is no reason for supposing the neutral axis shifts its position to any extent worth noticing before rupture

(iv) There is a divergence between theory and experiment in the case of small cast iron bars whose transverse strength is compared with their direct tensile strength, but the coincidence between these strengths for large girders is nearly exact

I think the latter statement requires further demonstration. We should not expect such equality because Hooke's Law does not hold for cast-iron, even in the case of small strains, and certainly not up to rupture

(v) That one of the chief failures of the ordinary theory occurs for cast-iron struts (rounded ends for length < 20 diameters, and flat ends for length < 50 diameters, p 67)

[1118] The author remarks that according to Hodgkinson the ratio of the tensile and compressive strengths of wrought iron may for practical purposes be taken as unity. In the case of cast-iron he apparently prefers a traction stretch relation of the form (')

$$\widehat{xx} = q + Es_x,$$

where q is a constant, to Hodgkinson's

$$\widehat{xx} = as_x - bs_x^2$$

[1119] In the discussion P W Barlow laid stress on W H Barlow's 'explanation' of the paradox in the resistance of beams under flexure (see our Arts 931), and W T Doyne on his modification of Hodgkinson's rule for the section of the beam of maximum strength, see our Arts 1016 and 1023. R Sheppard communicated a method of noting the permanent set due to flexure by drawing lines on the faces of a beam of lead

[1120] On p 83 ftn of the same volume will be found some details of the tensile, transverse and crushing strengths of some iron manufactured in India

[1121] H Wiebe *Ueber die Festigkeit der Bleche und der Vermetungen* *Zeitschrift des Vereins deutscher Ingenieure* Jahrgang 1, S 255-268 Berlin, 1857. This paper gives details of the experiments of Fairbairn, Clark, and Goum et Cie on riveted iron plates see our Arts 1497*, 902, 1066 and 1108

[1122] B Dahlmann *Die absolute Festigkeit verschiedener Eisen und Stahlarten des konygl wuertemb Huttenwerks Friedrichthal* *Dinglers Polytechnisches Journal*, Bd 143, S 94-7 Stuttgart, 1857. Details are given of the absolute strength of cast iron and steel made at a particular foundry, and as individual results they form only an advertisement of the same foundry

[1123.] M. Meissner: *Mittheilung von Versuchen, welche zur Ermittlung der absoluten Festigkeit von Eisen- u. Stahlarten in April 1858 ausgeführt worden sind. Polytechnisches Centralblatt, Jahrgang 1858, Cols. 1195–9. Leipzig, 1858.* (Extracted from the *Zeitschrift d. österr. Ingenieur-Vereins*, 1858, S. 88.) This paper merely contains details of the absolute tensile strength of various kinds of iron and steel, which might be useful, as others of the same type, to anyone writing a history of the gradual improvements in the preparation of iron and steel, but the results are of no permanent practical value and have no bearing on theory.

[1124.] *Vergleichende Zerreißversuche mit den Pöhlmann'schen, Webster-Horsfall'schen und Miller'schen Clavier-Stahlseilen. Dinglers Polytechnisches Journal, Bd. 147, S. 460–1. Stuttgart, 1858.* (Extracted from *Verhandlungen des nieder-österreichischen Gewerbevereins*, Jahrgang 1858, S. 54.) This contains details of the comparative strength of the steel pianoforte wires of different manufacturers, and is of no general interest at the present time.

[1125.] C. E. Browning: *On the Extension and Permanent Set of Wrought-Iron when strained tensibly. The Engineer*, Vol. v. pp. 317 and 352. London, 1858. These two letters propound the thesis that the strength of wrought-iron is increased by straining it to rupture. The writer apparently considers that the density and strength are alike increased by the drawing in of the cross-section in set, but the experiments he cites are certainly not conclusive, as it might well be argued that the material would give way first at its *weakest* cross-section, and thus might expect a greater load at successive ruptures: see our Art. 1503*. The proposal in the second letter to subject all the bars of braced girders and the cables of suspension bridges to a stress of 20 tons per square inch before using them, as a means of increasing their strength and reducing the weight of structures would hardly meet with favour, we think, from practical engineers.

[1126.] Völckers: *Ueber Festigkeit der Bleche, Zeitschrift des Vereins deutscher Ingenieure. Jahrgang II., S. 17–20. Berlin, 1858.* This paper contains the details of some experiments on the absolute tensile strength of iron plate with and across the fibre,—Völckers found with the fibre 100, across 91·3, in the diagonal 93·2 to represent the relative strengths of one kind of iron plate,—and on the loss of strength due to riveting. Völckers found the loss of strength due to punching rivet holes to be as 59·4 to 100, while Fairbairn had given it as 56 : 100: see our Art. 1500*. The author also gives some account of experiments on the loss of strength by heating. He concludes that there is little reduction of absolute strength up to about 300° C., but that temperatures from 500° to 700° C. enormously reduce the strength, the reduction amounting to one-half and even more. The memoir concludes with a comparison of the formulæ of the Prussian, French and Austrian Governments for the thickness of cylindrical boilers. If n be the number

of atmospheres internal pressures, τ the thickness in Prussian inches, d the diameter in Prussian feet, these formulae were

$$\text{Prussian, } \tau = 0.18d(n-1) + 1$$

$$\text{French, } \tau = 0.214d(n-1) + 113, \quad (\text{see our Art 879 (c)})$$

$$\text{Austrian, } \tau = 0.216d(n-1) + 114$$

Volckers compares these formulae with the results obtained by him for the strength of riveted plates and concludes that even the Prussian formula gives theoretically sevenfold safety (p 20)

[1127] Another series of experiments on plate iron by C Schönmann will be found on S 304-6 of the same Jahrgang of the *Zeitschrift (Resultate von Blech Versuchen)*. The effects of temperature and of rivet holes in reducing strength were considered. Numerical results are given, but no general conclusions are drawn. Further experiments by Krieme of a like kind will be found on S 173 of the *Zeitschrift*, Jahrgang III, 1859

[1128] Robert Mallet *On the Coefficients T_e and T_r of Elasticity and of Rupture in Wrought Iron, in relation to the Volume of the Metallic Mass, its Metallurgic Treatment, and the Axial Direction of its constituent Crystals*. Institution of Civil Engineers, *Minutes of Proceedings*, Vol XVIII, pp 296-348 (with discussion) London, 1859. This is an interesting paper dealing principally with the influence of the bulk of a forging on its elastic and cohesive properties. The author on p 298 states the three principal points of his inquiry as follows

(i) What difference does the same wrought iron afford to forces of tension and of compression, when prepared by rolling, or by hammering under the steam hammer, the bars being in both cases large?

(ii) How much weaker, per unit of section, is the iron of very massive hammer forgings than the original, or ingot iron, of which the mass was made up?

(iii) What is the average, or safe measure of strength, per unit of section of the iron composing such very massive forgings, as compared with the acknowledged mean strength of good British bar iron in moderate market sizes?

Mallet holds the proper measure of strength in a bar of iron to be the "work done, whether by extension, compression, rupture, or crushing, by any force applied to it". Thus his T_e = the elastic resilience of the body = $\frac{1}{2} E s_0$, where s_0 is the limiting elastic stretch or squeeze, = $\frac{1}{2} s_0 P_0$, where $P_0 = E s_0$.

"The value of the coefficient T_r ," he continues, "is arrived at in the same way by substituting the corresponding values for P_0 and s_0 , due to the moment of crushing or of rupture" (p 299). This seems to me to suppose that the proportionality of stress and strain lasts up to rupture, which is indeed far from true for many materials. It would seem better to define T_r as the work done in rupturing a body, without expressing it in terms of the final stress and strain.

I find that Mallet calculates his value of T_r from the assumption

that its value is half the product of the final strain into the final stress (see his Appendix, Tables I. and II., together with the remarks, p. 332). Thus it cannot be taken as a basis for some of the conclusions he draws from it. I think his own diagrams, pp. 318–19, should have shown him his error in this respect.

Mallet attributes the introduction of these coefficients T_e and T_r to Poncelet (see our Art. 982* and compare Art. 999* however) and remarks that for all crystalline substances, notably wrought-iron (see our Art. 1065), their values will depend on the direction of the stress which produces rupture.

[1129.] He compares the strength of bars cut in different directions from massive forgings, and concludes generally that the latter are weaker than the rolled bars of moderate size of which the heavy forgings were built up. He likewise shows how the molecular arrangement far more than the metallurgical constitution affects the elasticity and strength of different kinds of iron.

Probably his *résumé* of the elasticities and strengths of cast- and wrought-irons, especially in regard to the longitudinal and transverse elasticities and strengths of large forgings would be useful even to-day: see Table V. of the Appendix. It is certainly of great interest to the theoretical elastician to see how far the distribution of elasticity depends on 'working,' and how widely the ordinary materials of construction diverge from isotropy.

[1130.] A. R. von Burg: *Untersuchungen über die Festigkeit von Stahlblechen, welche in dem Eisenwerke des Herrn Franz Mayr in Leoben für Dampfkessel erzeugt werden. Sitzungsberichte der mathematisch-naturwissenschaftlichen Classe d. k. Akademie der Wissenschaften*, Bd. 35, S. 452–74. Wien, 1859.

This memoir busies itself¹ with the safe use of cast-steel as a material then being adopted for boilers. Howell in England had introduced a 'homogeneous patent iron' especially intended for boilers, and the experiments detailed in this paper are on cast-steel plates (*Gussstahlbleche*) prepared by F. Mayr for a similar purpose and tested by the Vienna Polytechnic Institute at the request of the *Handelsministerium*. The experiments go to show that the tensile strength of cast-steel plates is roundly double that of iron plates, both being of Austrian manufacture, and these experiments are shown to be well in accord with those of Fairbairn, Clark and Gouin et Cie.: see our Arts. 1497*, 902, 1066, and 1108. They give a tensile strength in the direction of the rolling (*Längenrichtung, Richtung des Walzens*)

¹ v. Burg gives an interesting foot-note on S. 454 on the difficulty of determining the exact factors in iron and steel which cause their very different elastic properties. All this difference is not due to the quantity of carbon (varying from .625 to 1.9 p.c.), but has probably much to do with the state of crystallisation (Dalton attributed the difference almost entirely to the latter). Fuchs supposes iron dimorphic, consisting of a mixture of tesseral and rhombohedral crystals: wrought-iron is chiefly tesseral, raw-iron rhombohedral. He attributes the difference between tempered and untempered steel to a transition from one form of crystallisation to the other. By annealing with increasing heat the tesseral replaces the rhombohedral crystallisation.

slightly greater than in the direction transverse to it (*Querrichtung*), this agrees with the results for iron plates, of Clark, Gouin et Cie and von Burg himself, but not with the rather doubtful conclusions of Fairbairn as to Yorkshire and Staffordshire plates. The stricture was also greater and rupture more gradual in the case of bars cut in the direction of the rolling. Von Burg concludes his paper with some remarks on the elastic limit for steel plates, which are not, however, based on his own experiments. *Ausgluhen* for two hours over a charcoal fire did not reduce on cooling the strength of steel more than 2 p c (S 463-6)

[1131] K Karmarsch *Ueber die absolute Festigkeit der Metall drahte* Polytechnisches Centralblatt, Jahrgang 1859, Cols. 1272-76 Leipzig, 1859 (Extracted from the *Mittheilungen d Gewerbe Vereins f d Konereich Hannover*, 1859, S 137)

The writer begins by referring to his experiments of 1824 (see our Art 748*) in which he had shown that the process of drawing alters in a remarkable manner the absolute strength of metal in the form of wires

Die Ursache der beruhrten Erscheinung liegt unstreitig in Folgendem. Wenn ein Draht feiner und feiner gezogen wird, vermindert sich seine Festigkeit—d h die zum Abreissen desselben erforderliche Zugkraft—nach Verhaltniss seiner Querschnittsfläche oder des Quadrats seines Durchmessers. Zugleich aber findet ein Zuwachs an Festigkeit dadurch statt, dass das Metall zunachst an der Oberfläche, vermoge des Drucks in den Ziehlochern verdichtet, wohl in der Textur vortheilhaft verändert wird. Da diese Wirkung unmittelbar am Umkreise des Querschnitts vor sich geht, so steht ihre Grosse im Verhaltniss dieses Umkreises oder, was eben so viel sagen will, des Durchmessers

Man darf sich daher die Festigkeit F eines Drahtes vom Durchmesser D als aus zwei Theilen zusammengesetzt vorstellen, von welchen der eine von dem Durchmesser, der andere von der zweiten Potenz des Durchmessers abhängig ist, d h man kann

$$F = aD^2 + bD$$

setzen, worin a und b aus der Erfahrung abgeleitete Coefficienten sind (Col 1273)

Karmarsch then determines the constants a and b for a great variety of metal wires, but his method of selecting the results from which a and b are to be determined seems to me very unsatisfactory. He ought to have proceeded by the method of least squares, but he calculates a and b from a number of selected experiments by taking the arithmetical means

The process of annealing reduces the values of both a and b . The coefficient b can amount in the case of ordinary iron or platinum wire to as much as one half of a and sinks in the case of lead to zero or to an insensible quantity. The relation of the absolute strengths of annealed and unannealed wires is not the same for the same metal, but varies with the diameter of the wire. Further for wires of the

same diameter but of different metals it varies from a maximum with platinum to a minimum with iron.

[1132.] *Admiralty Experiments on the Various Makes of Iron and Steel. Transactions of the Institution of Naval Architects.* Vol. I., pp. 169–70. London, 1860. Also *The Mechanic's Magazine, New Series*, Vol. III., pp. 156–7. London, 1860.

This paper records the results of a number of experiments on cast and puddled steel and on cable iron in the form of bolts and links as used for cables made at Woolwich Dockyard in 1859. With a side weld and $1\frac{1}{8}$ in. chain the best puddled steel bore 39 to 41 tons, while the best iron bore $41\frac{1}{4}$ to $43\frac{3}{8}$ tons. The difficulty of properly welding the steel seems to have told against the strength of steel as compared with iron cables in the experiments on links: see our Art. 1147. The numerical details might still be of service to any one working out a theory of the absolute strength of chain-cables: see our Art. 641.

[1133.] F. Schnirch: *Resultate einiger Versuche über die Festigkeit des Schmiedeisens und einiger Steingattungen.* *Zeitschrift des österreichischen Ingenieur-Vereins*, Jahrgang XII., S. 2–3. Wien, 1860. This paper contains nothing of permanent value.

[1134.] H. Tresca: *Procès-verbal des expériences faites sur la résistance des tôles en acier fondu pour chaudières.* *Annales des Mines, Mémoires*, T. XIX. pp. 345–65. Paris, 1861. This is attached to a *Rapport* by a Commission appointed to consider *les conditions spéciales d'épaisseur pour les tôles d'acier fondu employées dans la construction des chaudières à vapeur*, which occupies pp. 311–44 of the same volume. The Commission consisted of the engineers Combes, Lorieux and Couche, and they experimented on a boiler of cast steel plate presented by MM. Pétin et Gaudet to the Exhibition of 1855. The experiments on the material of this boiler and on plates of like material showed that the ductility and absolute strength of a plate were in inverse ratio; they also exhibited the now well-recognised phenomenon of stricture. There are details (pp. 324–6) of further experiments on the strength and ductility of various kinds of steel plates and the evidence of various engineers with regard to their practical efficiency. At the request of the Commission further experiments were made by Tresca on bars cut from plates prepared by Pétin et Gaudet. These bars were tested for extension and absolute strength, and in various conditions as regards

tempering and annealing Tresca gives (Plate VI) stress-strain diagrams, which show the rapid increase of stretch after the elastic limit is passed For an untempered bar this limit was reached at a tensile stress T_1 of about 2477 kilogs per sq centimetre, the stretch-modulus being $E=19,674,000,000$ kilogs per sq metre and the elastic limit a stretch of $s_1=001259$ Corresponding to rupture we have a traction T_2 of about 4873, with a stretch of $s_2=05493$ On the other hand after tempering and annealing we find for another bar with the same units,

$$T_1=6528, \quad s_1=00331, \quad E=19,722,000,000, \\ T_2=8820, \quad s_2=00473$$

Thus the elastic limit and the absolute strength are much raised by the process, but the stretch-modulus remains practically constant Tresca was among the first to notice these facts and also to give well-drawn traction-stretch diagrams showing the life-history of individual material see our Art 1084 and Vol I p 889

Without entering more fully into the details of his individual experiments we may briefly indicate his conclusions

1° Maximum stretch before rupture

	Aciers doux	Aciers rifs
Before tempering	about 04	about 06
Tempered and } Annealed	about 005	about 004

2° Stretch modulus in kilogs per sq metre

	Aciers doux	Aciers rifs
Before tempering	$17,273 \times 10^6$	$20,764 \times 10^6$
After tempering	$19,906 \times 10^6$	$19,199 \times 10^6$

Thus the stretch modulus varies far less than the maximum stretch

ractions at elastic limit in kilogs. per sq. centimetre :

	Aciers doux	Aciers vifs
Before tempering	2400	2532
After tempering	7440	5056

tretches at elastic limit :

	Aciers doux	Aciers vifs
Before tempering	·001,368	·001,236
After tempering	·003,767	·002,618

lastic resilience (= area of elastic stress-strain diagram) :

	Aciers doux	Aciers vifs
mpering	1·641 kilogs. per sq. cm.	1·565 kilogs. per sq. cm.
npering	about nine times the above.	about four times the above.

bsolute strength, means in kilogs. per sq. cm. :

	Aciers doux	Aciers vifs
Before tempering	5748	5318
After tempering	8562	7234

Tresca's memoir pp. 361-5, and compare with the results of
and Wertheim cited in our Arts. 848*-58* and 1292*-1301*.

35.] 'Lloyd's' *Experiments upon Iron Plates and Modes of
g applicable to the Construction of Ships: Transactions of
stitution of Naval Architects*, Vol. I., pp. 99-104. London,

1860 This paper contains the details of a series of experiments on riveted joints made for 'Lloyd's' under the superintendence of W T Mumford, surveyor, in 1857 The experiments were arranged solely with a view to acquiring special information for iron shipbuilders, and seem both from the mode of experimenting and the comparative paucity of experiments, 22 in all, to be of little theoretical or even permanent practical interest With two exceptions the joints were all butt-joints, the rivets were placed in single and double rows, being spaced at three, four, and four and a half diameters apart In both lap- and butt-joints spacing the back row exactly behind the front row gave better results than spacing midway, and four diameters apart seems to have been the best spacing Lap-joint, double riveting, four diameters apart, reduced the strength of the plate in the ratio of 69.5 to 100, while butt-joint, double riveting four diameters apart, reduced the strength in the ratio of 76.5 to 100, in both cases the back rows were exactly behind the front-rows

[1136] J Daglish *On the Strength of Wire Ropes and Chains The Engineer*, Vol XI, pp 51 and 67 London, 1861 This contains the details of a paper read before the *Northern Institute of Mining Engineers* with the discussion upon it A further paper entitled *On the cause of the Loss of Strength in Iron Wire when heated* will also be found on p 67 These papers give some account of experiments on the absolute strength of wire ropes and iron chains They show the reduction in strength produced by heating, by splicing and by ordinary socket joints in the case of wires The experiments on chains do not give details of the links ($\frac{3}{4}$ inch wrought-iron chains bore 15 to 24 tons) They show, however, the remarkable result that chains after being once tested and having borne a load of 18 to 22 tons may afterwards *break* with a less load of 16 to 20 tons This does not tend to confirm the contention of Browning see our Art 1125 Daglish supposes the considerable weakening effect of heating wire ropes to a red heat as compared with the slight effect of the same treatment on chains to be due to the fact that the former are cold and the latter hot rolled He does not believe, however, that the increased density due to drawing is the real cause of this difference in strength, for this difference in density he tries to show does not disappear on heating either wire or cold rolled iron to red heat Such a process changes the density but sometimes increases, sometimes decreases it

[1137] David Kirkaldy *Experiments on the Comparative Tensile Strength of Steel and Wrought-Iron* (made for Messrs

Napier and Sons). These are published in the *Transactions of the Institution of Engineers in Scotland*, Vol. II., 1859. A short *résumé* of Kirkaldy's results was also communicated to the British Association and will be found in the *Transactions of the Twenty-Ninth (Aberdeen) Meeting*, 1859, pp. 242-3. They were reprinted *in extenso* in *The Artizan*, Vol. XVIII., pp. 8-20 (pp. 9-20 are erroneously paged 321-332). London, 1860. The results are given in the above publications without comment and consist almost entirely of tables of numerical data. The experiments are some of the most comprehensive and thorough ever made on steel and wrought-iron.

The object sought in instituting the series of experiments about to be described was to ascertain the comparative strength of various kinds of steel and wrought-iron when subjected to a tensile strain, with the view of substituting homogeneous metal or steel for wrought-iron in the construction of machinery, boilers, steam ships, etc.

Upwards of 540 specimens were tested and these were "indiscriminately collected from engineers' or merchants' stores except those marked *samples* which were obtained from the makers¹." The object of this precaution was to avoid especially prepared test pieces. The experiments themselves made by perfectly reliable interested engineers for their own practical information among the first to give full details of stricture and fracture, are of as great theoretical as practical interest. We shall not, however, attempt to analyse them in the above form, but note that all these results as well as others were embodied by Kirkaldy shortly afterwards in a work, the title of which is given in the following article.

[1138.] David Kirkaldy : *Results of an Experimental Inquiry into the Tensile Strength and other Properties of various kinds of Wrought-Iron and Steel*. 1st edition, 1862, 2nd edition, 1864, Glasgow. This work, although falling a little outside our present period, to a great extent embraces experiments conducted several years previously and referred to in the preceding article. Our references will be to the pages (1-227 and xvi plates) of the

¹ An attempt was made to suppress the publication of the results on the ground that the specimens had not been procured directly, and legal proceedings were threatened. That the attempt failed does not really affect the arguments in favour of an independent Government testing house.

second edition The treatise may be said to do, and do in a more thorough manner, for wrought iron and steel what the English and American experiments had already done for cast-iron see our Arts 1406*, 1037 and 1048

[1139] Pp 9-17 deal with the mode of collecting specimens (see our Art 1137), with the form of the testing apparatus (see Plate I, it was a somewhat primitive directly loaded lever machine), with the preparation of the specimens and the measurement of their extension under stress (by a large pair of compasses with their points inserted in marks made by a centre-punch in the bar) and with the method in which the results are tabulated The method of experimenting was throughout based on the desire to reach broad technical conclusions, rather than to make delicate physical measurements, and the methods adopted appear occasionally to have been rather rough and ready when judged from the physical standpoint The experiments were directed to ascertain breaking stress, structure, nature of rupture, rate of elongation under increasing stress, influence of treatment and of shape, strength of welded joints, effect of gradual and sudden stress on steel and iron in both bar and plate Tables F-K give a summary of the numerical results, Plates II to V give reproductions of the rupture surfaces, and Plates VI to XIII represent the results graphically We proceed in the following articles to give a brief *résumé* of some of the results of Kirkaldy's experiments together with the inferences which may be drawn from them

[1140] Section VIII (§§ 29-70) deals with the tensile strength and structure of wrought-iron It opens with an historical account of the experiments on iron of Muschenbroeck, Lamé, Telford, Brunel, Fairbairn, Wade, Lloyd, etc (see our Arts 28* (δ), 1001*-4*, 1494*-1503*, 1037, and 1135) and points out the great divergence in the recorded results This is attributed partly to difference in quality and partly to difference in methods of experimenting and stating experimental results Kirkaldy remarks of these earlier researches

In all former experiments the ultimate strength or breaking weight per square inch of the specimen's original area alone is given and the various pieces are rated accordingly, the one that stands highest being considered the best

It seems most remarkable that an element of the highest importance should have been so long overlooked, namely, the *contraction* of the specimen's area [i.e. *Stricture*] when subjected to considerable strain [i.e. stress] and the still greater contraction, at the point of rupture which takes place in a greater or lesser degree as the material is soft or hard and the consequent influence this reduction must have on the amount of weight sustained by the

specimen before breaking. The apparent mystery of a very inferior description of iron suspending, under a steady load, fully a third more than a very superior kind, vanishes at once when we find that the former had the benefit of retaining to the last its original area only slightly decreased; whilst the latter on breaking was reduced to very nearly a fourth of its original area—the one a hard and brittle iron, liable to snap suddenly under a jerk or blow, the other very soft and tough, impossible to break otherwise than by tearing slowly asunder (pp. 23-4).

Kirkaldy is of course quite right in drawing attention to the importance of taking into account not only the absolute strength per unit of original area, but also the elongation and stricture in measuring the value of a certain class of metal, but the introduction of the words 'superior' and 'inferior' above would appear to suggest some test of the superiority or inferiority of the metal *not relative to the purpose to which it is to be applied*. In most cases the element of ultimate resilience will of course be of considerable importance: see our Arts. 1085 and 1128.

Kirkaldy following up the ideas suggested in the above quotation gives for bars full details of their total elongation, their general reduction of section other than at the section of fracture, their reduction at the section of rupture (or the stricture), and also of their absolute strength calculated to original, reduced and rupture sections. Further, the nature of the rupture is recorded. Similar details are then given for plates.

[1141.] Kirkaldy takes as his test of relative merit the absolute strength conjointly with the stricture, and it becomes important to ascertain what influence different methods of working have on one or both of these properties. He notes the following points:

(i) The size of the bar in rolled iron has far more influence on the absolute strength of 'inferior' iron than of iron of 'superior' quality.

(ii) Removing the skin does not alter the strength, or rough rolled bars are not stronger than turned ones: see our Art. 858*.

(iii) Reducing rolled bars by forging slightly increases the absolute strength, but decreases the stricture.

(iv) The absolute strength and stricture of iron-plates is greater in the direction in which they are rolled than across it (pp. 26-30): see our Arts. 1497*, 902 and 1108.

After dealing with *rolled* iron Kirkaldy turns to *hammered* iron and criticises the loose use of the term *scrap-iron*. He shows among other things, that the absolute strength and stricture are greater in specimens cut lengthwise than in those cut crosswise from crankshafts.

[1142] Section IX (pp 33-5) deals with steel, and Kirkaldy insists on the same conjoint test (Art 1141) of the value of different parcels. He states that the absolute strength and structure of *puddled* steel plates are greater in the direction in which they are rolled, as in the case of iron plates, while the converse holds for *cast* steel plates (p 92)

[1143] Section X (pp 35-60) discusses with a criticism of the results of other writers the appearance of the rupture surfaces in iron. Kirkaldy enters into the history of the controversy as to the change from fibrous to crystalline structure by vibration see our Arts 1463*-4*, 881 (b) and 992. He cites the opinions of McConnell, Thomeycroft and Stephenson, as well as that of Roebling, the engineer of the Brooklyn bridge, who does not appear to have believed in the change. Kirkaldy himself considers that the nature of the rupture surface depends largely on the mode of rupture, and not on previous vibration. He holds that

the appearance of the same bar may be completely changed from wholly fibrous to wholly crystalline, without calling in the assistance of any of those agents already referred to—viz, vibration, percussion, heat, magnetism, etc., and that may be done in three different ways—1st, by altering the shape of the specimen so as to render it more liable to snap, 2nd, by treatment making it harder, and 3rd, by applying the strain [stress] so suddenly as to render it more liable to snap from having less time to stretch (p 53)

The *act of breaking* is really the determining cause and Kirkaldy's best demonstration of this was the actual breaking of the same bar with crystalline and fibrous fractures within a few inches of each other (pp 53-4). Kirkaldy considers however, that any process of working that decreases the structure of a specimen renders it more liable to *snap* or to take a crystalline fracture¹

After considering the evidence brought forward by Kirkaldy and others with regard to crystalline and fibrous fractures, I am inclined to think that the difference really lies in the *extent* of the material which is subjected to a stress equal or nearly equal to the rupture stress. When only the material between two very close cross sections is subjected to such stress then we get a crystalline fracture such as occurs in snapping, when a considerable extent of the material as in pure tensile strain is subjected to this limiting stress then the rupture is fibrous. This view would account for the crystalline fracture occurring in cases of vibration, for in such cases there is generally an 'accumulation of stress' due to stress waves at some particular cross sections only. Almost the same result arises from the sudden blow of a hammer which also leads to a crystalline fracture.

¹ In this section Kirkaldy refers to the action of dilute hydrochloric acid in removing the impurities from the surface of a specimen and exposing more clearly to view the metallic portion and its texture. A like application to any planed section of a specimen which has been subjected to large stresses producing set will often bring to view the directions of maximum and minimum strain.

Section XI. (pp. 61–2) is devoted to the appearance of the rupture surfaces in steel. These are classified as *granular*, *granular and crystalline*, *crystalline and fibrous*, *granular and fibrous*, *fibrous*. The distinction between a fibrous and granular fracture is always due according to Kirkaldy to the slowness or suddenness of the act of breaking.

[1144.] Section XII. (pp. 62–9) is entitled: *Rate of Elongation under Increasing Strains* [? Stresses]. Kirkaldy holds that a slow application of load (i.e. one that leaves time to measure the stretches) does not lessen the absolute strength. I think Kirkaldy cannot be instituting a comparison with (p. 63) the sudden application of load, or else its slow application would certainly be remarkable not for lessening but *increasing* the apparent absolute strength: see our Arts. 988*, 970, *tc.*

The set and the ultimate stretches were measured, and Kirkaldy remarks that most of the specimens extended uniformly along their lengths nearly up to rupture just before which stricture began usually at one, sometimes at two, and in a few exceptional cases at three different places. The lateral dimensions of the specimens formed an important element in determining the value of the ultimate stretches (p. 69), i.e. in modifying the amount of stricture.

[1145.] Section XIII. (pp. 69–74) deals with the *Influence of various Kinds of Treatment*. Here Kirkaldy considers a number of interesting and practically valuable methods of altering the absolute strength and stricture of iron and steel. I remark that:

(i) The strength of steel is reduced by hardening in water, but is greatly increased by hardening in oil. This increase varies from 11·8 to 79 per cent. as we pass from soft steels slightly heated to hard steels highly heated (p. 70). The higher the temperature at which the 'hardening' takes place, the greater the increase provided the steel is not 'burnt.' Kirkaldy argues that the steel was also 'toughened' because when under great stresses it might be "repeatedly struck [without breaking] with a rivet-hammer" (p. 70). I do not understand exactly what Kirkaldy means by 'toughened' here.

Further, steel plates hardened in oil and riveted are fully equal in strength to unriveted soft plates, or the hardening in oil more than counterbalances the loss of strength by riveting (p. 71).

(ii) In the course of the investigations on riveted steel plates, it is pointed out that the absolute shearing strength of steel rivets is about $\frac{1}{4}$ of the tensile strength. According to the uni-constant theory extended to rupture the former should be $\frac{1}{3}$ of the latter. As a mean from 17 rivets we find that the shearing is to the tensile strength as 63,796 is to 86,450 lbs. per sq. in., $\frac{1}{5}$ of the latter would have been 69,160 lbs. (p. 71). Kirkaldy questions whether the usual rule for iron rivets—that the diameter of the rivet should equal the combined thicknesses of the two plates to be joined—is a correct one.

(iii) 'Case hardened' iron bolts have less absolute strength than whole iron bolts. Iron highly heated and *suddenly* cooled in water has a greater absolute strength than before, but it is more liable to snap, i.e. exhibits less stricture. Iron like steel, when heated and *slowly* cooled loses in absolute strength see our Arts. 692*, 1301* and 1353*. Cold-rolling increases the absolute strength but diminishes the stricture. Kirkaldy holds (cf. our Arts 1136 and 1149) that the specific gravity is not raised by cold-rolling. Galvanising or tinning iron plates did not increase the strength of plates of the thickness ($\frac{3}{16}$ " to $\frac{1}{8}$ ") experimented on (pp 73-4)

[1146] Section XIV (pp 74-7) discusses the effect of altering the shape of specimens. Kirkaldy states that we cannot compare the strengths of metals as given by different experimenters as we do not know the shape of their specimens, and instances Wilmot's Woolwich experiments, which are cited in Fairbairn's treatise on *Iron* (see our Art 911), as diverging essentially from his own for Bessemer Steel (Wilmot's mean value for the absolute strength is 153,677 lbs. per sq. inch, Kirkaldy's, 111,460 lbs.) This divergence Kirkaldy shows to have arisen from the fact that the minimum cross section in the test-pieces for the Woolwich machine occurred *only at one point*. He cites experiments to prove that grooving increases the absolute strength and decreases the stricture (see our Art 1503*). This seems to me probable as it is very unlikely that the groove would be formed at the weakest cross section, and the maximum stresses being confined to the neighbourhood of the groove there will arise according to the view expressed above (see our Art 1143) a crystalline fracture, or at any rate one with less stricture.

[1147] Section XV deals with the comparative strength of screwed and chased bolts (pp 77-80), and Section XVI with the strength of welded joints (pp 80-2). In the first case the strength of screwed bolts is found to be nearly proportional to their areas, with a slight difference in favour of the smaller area. The strength of the bolt is greater for a screw made with old than for one made with new dies, a result attributed by Kirkaldy to the hardening effect of an old and blunt die (p 78). The loss in strength due to screwing is given in Table Q (pp 174-9), or varies from about 75 p.c. for Govan bolts with old dies (about 178 p.c. with new dies) to about 23 p.c. for 'Glasgow B Best' with old dies (about 33 p.c. with new dies). The results for the welding of iron are very inconclusive. In some cases the welded joint bore nearly as much as the uncut bar and in other cases the strength was reduced fully one third (p 80). Heating to the welding point and then cooling slowly without hammering was found to reduce the stricture very largely, but not the absolute strength. The welding of steel bars owing to their liability of being burnt is difficult and uncertain see our Art 1132.

[1148] Section XVII is concerned with *Suddenly Applied Strain* (pp 82-6). Kirkaldy arrives at the conclusion that the backing-

stress is considerably less when the load is suddenly applied, "though some have imagined that the reverse is the case" (p. 95). The decrease is, however, only about 18·5 p.c. instead of 50 p.c., so I imagine Kirkaldy's trigger apparatus did not really apply the load instantaneously. Like other experimentalists he does not distinguish in the case of sudden loading between the real breaking stress and the apparent load per unit area of cross-section.

He notes that the stricture is in the case of sudden application of load much reduced (p. 84). Turning to the effect of frost we find that the absolute strength is reduced when iron is frozen. *Provided the stress be suddenly applied*, there is a reduction of about 3·6 p.c. When the stress is gradually applied there is little difference. Kirkaldy attributes this to the warming of the iron by the drawing out of the specimen (p. 86). The experiments were not, however, nearly sufficient in number to be very conclusive. The difference between sudden and gradual loadings may, perhaps, explain the divergence between the conclusions reached by Joule and Kirkaldy: see our Art. 697 (c).

[1149.] Section XVIII. deals with the specific gravities of iron and steel (pp. 87–91). Kirkaldy found that the specific gravity of iron indicates generally its 'quality,' that it is *decreased* by wire drawing, cold rolling, and for some kinds by hot rolling in the ordinary way: see our Arts. 732 and 1136. It is also decreased by being drawn out by a severe tensile stress. In the case of steel, 'highly converted' steel has not the greatest density. Cast steel is denser than puddled steel, which is even less dense than some of the superior descriptions of wrought-iron (pp. 91 and 95).

[1150.] Section XIX. (pp. 91–100) gives a summary of the conclusions contained in the volume, and some general remarks on their practical application. Kirkaldy asserts that the truest measure of the quality of iron or steel is the breaking stress per unit area of the fractured surface (i.e. of the stricture) and appears to lay the greatest importance on this mode of comparison.

On pp. 106–187 we have the tables of numerical results which it is impossible to condense or analyse here; their importance has been long recognised by technical elasticians. For the absolute strength of wrought-iron we may, however, reproduce the mean results as given on p. 96 since they may be of service for later reference in our own work:

Strength in lbs. per square inch of original area.

	Highest	Lowest	Mean	
188 Bars, rolled	68,848	44,584	57,555	= 25 $\frac{1}{4}$ tons
72 Angle iron, etc.	63,715	37,909	54,729	= 24 $\frac{1}{2}$ "
167 Plates (length-ways)	62,544	37,474	50,737	= 21 $\frac{1}{4}$ "
160 Plates (cross-ways)	60,756	32,450	46,171	

[1151] In the *Appendix* will be found a series of extracts from articles and letters in *The Engineer* and other papers, which are not without interest as showing the general state of knowledge with regard to the elasticity of iron and steel about 1860. The volume concludes with plates of Kinkaldy's simple apparatus, and with more or less suggestive diagrams of the surfaces of rupture, showing the reduction in transverse diameter not only at the stricture, but also at other cross sections of the specimens. There are graphical representations of some of the numerical results, and on Plate XIV are given the distorted forms (approximately elliptical) after strain of circles drawn on the unstrained faces of a bar. These were obtained with a view of showing the relative longitudinal stretch and lateral squeeze. I find just about the strictured portion of a bar of cast steel from measurement of the semi diameter that the circle of 1" diameter has been converted into an oval of 1.125" longitudinal and of .889" lateral diameter. Hence the longitudinal stretch is 125 and the lateral squeeze 111, or the stretch-squeeze ratio η for the set of this bar equals 89, which is far from agreeing with the 25 which the uniform theory gives for η in the case of *elastic strain*.

GROUP G

Strength of Materials, other than Iron and Steel

[1152] L. G. Peleaux *Apparatus for testing and ascertaining the strength of yarn, thread, wire strings, or fabrics*. *London Journal of Arts (Conjoined Series)* Vol 43, pp 325-8. London, 1853. This contains a description of a patent for a testing machine. In order to prevent too great a shock upon the rupture of the material tested, one of the clamps holding the material sets in motion a fly wheel on the release of the load and thus the shock is deadened.

[1153] Houbotte. A testing machine invented by this engineer will be found described on p 432 of the *Annales des travaux publics de Belgique*, T. VIII, 1854-5, or *Polytechnisches Centralblatt*, Jahrgang 1855, Cols 1237-40. Leipzig, 1855. The machine was designed to ascertain the crushing strength of stone. Its peculiar novelty seems to be the gradual application of load by filling slowly a reservoir of water supported by the loading lever of the machine. Houbotte gives the details of various experiments on the crushing of stone blocks. He further made some few not very conclusive experiments on the increase of strength due to lateral support.

[1154] T. Dunn. *On chain Cable and Timber Testing Machines*. *Institution of Civil Engineers. Minutes of Proceedings*, Vol XVI pp 301-308. London, 1857. This gives an account of a testing

machine made by Messrs Dunn and of some experiments made with it on bars and chains. This apparently was the first introduction into general use of fairly cheap testing machines. We refer in our Art. 1158 to the use made of one of these machines by Captain Fowke in the Paris Exhibition of 1855.

[1155.] W. Fairbairn: *On the Density of various Bodies when subjected to enormous compressing Forces.* *British Association*, Report of Liverpool Meeting, 1854, *Transactions*, p. 56. The author states that he has applied pressures of 90,000 lbs. per sq. inch to various substances. "Under this enormous pressure, clay and some other substances had acquired all the density, consistency and hardness of some of our hardest and densest rocks."

[1156.] W. Fairbairn: *Solidification of Bodies under Pressure: The Civil Engineer and Architect's Journal*, Vol. xvii., p. 394. London, 1854. The author gives further particulars of the experiments referred to in our Art. 1155. The tensile and compressive strengths of spermaceti and tin were found to be much increased by solidification under pressure.

Thus a bar of the former substance solidified under a pressure of 40,793 lbs. per sq. inch carried 7·52 lbs. per sq. inch more compressive stress than when solidified under a pressure of 6421 lbs. The tensile strength was again as 1 to 0·876 in favour of the more compressed bar.

Further three bars of tin were allowed to solidify, the first at the of the atmosphere, the second at 908 lbs., and the third at per sq. inch. Between the two last there was an increase of strength in the ratio of ·706 to 1, or an increase of about $\frac{1}{3}$ solidified under six times the pressure.

Since the specific gravity of the metals increases at a less rate than the strength Fairbairn hopes from compression to insure not only greater strength but greater economy.

[1157.] Marcq: *Expériences faites sur différentes pièces de bois, à l'effet d'en déterminer le coefficient d'élasticité.* *Annales des travaux publics de Belgique*, Tome xiv., pp. 279–301. Bruxelles, 1855–6. This paper gives details of experiments on the flexure of various kinds of wood, such as may be bought in the market and not specially prepared for the purpose of experiment in small blocks as in the researches of Wertheim and Chevandier (see our Art. 1312*). Nothing is said about the state of moisture of the wood, or the position of rings and fibres relative to the plane of flexure; presumably the latter were always parallel to that plane, as the pieces were long. The author believed that he had found a real limit of elasticity up to which the flexures were proportional to the loads. This limit of elasticity, as measured by the load, bore to the rupture load the ratio ·43 for oak to ·33 for beech. After the limit of elasticity was passed the flexures increased more rapidly than the loads till the rupture load was approached, when this law was no longer true. For beams of large cross-section the

stretch modulus was less than for pieces of small section, where the fibres are more continuous (p 281) A load if removed and then after a short interval re applied produced a greater flexure than on the first application This seems a rather doubtful statement especially as it is not stated whether the load was above or below the elastic limit, when originally applied

Either a stretch of 0006 or a traction of 600,000 kilogs per sq metre may be taken as a safe limit of loading for all kinds of wood, even the poorest

I do not cite here the values of the stretch moduli for the various kinds of wood (pp 298-9) as the stretch modulus of wood varies from tree to tree and with the state of dryness of the wood

[1158] Francis Fowke *Results of a series of Experiments on the Strength and Resistance of Various Woods Reports on the Paris Universal Exhibition, Presented to both Houses of Parliament by Command of Her Majesty* Part I, pp 402-525 London, 1856 This report contains the details of a long series of experiments on the specimens of various woods from Australia, British Guiana and Jamaica exhibited at the exhibition The experiments were made with the aid of a hydraulic testing machine made by Dunn of Manchester see our Art 1154 The experiments were directed to ascertaining the following data (i) the specific gravity of wood, (ii) the rupture strength under flexure, (iii) the crushing load in the direction of the fibre, (iv) the crushing load transverse to the direction of the fibre The deflections for various loads are given, but as there is no reference to set, it is not certain that they give the true values of the stretch-moduli In many cases the deflections are not proportional to the loads Tables giving the final results for upwards of 80 specimens of wood will be found on pp 514-25, and these might even now be useful for commercial purposes

[1159] Captain Fowke made further experiments on a much greater variety of woods exhibited at the International Exhibition of 1862 His results were published in 1867 by the Science and Art Department in a work entitled *Tables of the Results of a Series of Experiments on the Strength of British, Colonial and other Woods* The Report of 1855 was reprinted at the conclusion of this work

Upwards of 3000 specimens were tested with a hydraulic machine due to Messrs Hayward, Tyler and Co Each specimen was as nearly as possible 16 inches long and of square cross-

section, 2" side. The bearings for flexure seem to have been 12" apart. The same series of experiments were made as at Paris, and an additional series was undertaken to ascertain the elasticity. The woods came from a wider range of colonies and from some European countries.

Table VIII. gives the deflection, divided into set and elastic strain, at every 1,120 lbs. (pp. 213-242). The stretch-moduli are not actually reckoned out. The elastic strains were not proportional to the loads, and it seems probable that elastic after-strain was not recognised and allowed for.

The work contains the most extensive series of experiments on wood hitherto made, and may for many purposes still be useful, but the experiments were conducted in a manner rather calculated to further commercial purposes than to put to the test any theories of the distributions of elasticity in wood: see out Arts. 1229*, and 308-15.

[1160.] *H. R. Storer: On Gutta Percha Tubes. Silliman's American Journal of Science and Arts. Second Series, Vol. 21, pp. 445-6. New Haven, 1856.* (Extracted from the *Proceedings Boston Society Nat. Hist.*, Vol. v., p. 268.) This paper gives details of the bursting strength of gutta percha tubes under water pressure. The tubes varied in diameter from 1" internal, $1\frac{3}{16}$ " external, to $\frac{1}{4}$ " internal, $\frac{5}{8}$ " external diameter, and the bursting pressures varied from 266 lbs. to 760 lbs. per square inch. The smaller tubes had the greater strength.

[1161.] *C. F. Dietzel: Ueber die Elasticität des vulkanisirten Kautschuks und Bemerkungen über die Elasticität fester Körper überhaupt. Polytechnisches Centralblatt, Jahrgang 1857, Cols. 689-94. Leipzig, 1857.* This paper commences by general remarks on the influence of temperature, elastic after-strain etc. on elastic phenomena. It then criticises Boileau's experiments (see our Art. 851) on the ground that they left out of account the influence of after-strain. Dietzel gives an account of two series of experiments of his own on a vulcanised caoutchouc thread, in which he carefully distinguished fore-strain, after-strain and set. The loads were gradually increased from 1 to 29 grammes, and 24 hours were allowed for the action of the elastic after-strain. He found roughly speaking that the elastic after-strains were proportional to the loads, but that the elastic fore-strains were far from being so, increasing in a much more rapid ratio than the loads. This was not due to the decrease in cross-section due to the increasing sets. The elastic after-strain developed in 24 hours decreased from about $\frac{1}{4}$ of the fore-strain down to about $\frac{1}{12}$ as the loads increased from 1 to 29 grammes. Dietzel remarks that Gerstner's Law (see our Art. 806*) does not appear to hold for vulcanised caoutchouc.

[1162] A von Burg *Versuche über die Festigkeit des Aluminiums und der Aluminiumbronze (Legierung von 90 proc Kupfer und 10 proc Aluminium)* Polytechnisches Centralblatt, Jahrgang 1859, cols 619–20 Leipzig, 1859 (Extracted from *Mittheilungen d. nieder-österreich. Gewerbe Vereins*, 1858, S 530)

Cast bars of aluminium gave an absolute strength of 10 96 kilogrammes per square-millimetre Cold hammered bars gave an absolute strength of 20 26, or reduced to the section of stricture, 28 67 kilogrammes per square millimetre The aluminium bronze had an absolute strength of 64 59 in one specimen and 49 62 in a second, the first being hot-hammered and the second only cast Thus the absolute strength lies between those of iron and steel¹

[1163] C Fabian *Ueber die Dehnbarkeit des Aluminiums* Dinglers Polytechnisches Journal, Bd 154, S 437–8 Stuttgart, 1860 Demonstration of the extensibility of aluminium by beating it into extremely fine leaves See also the *Répertoire de chimie appliquée*, 1859, p 435, where the discovery is attributed to the Parisian goldsmith Degousse, who had beaten aluminium to leaves as thin as those of gold or silver

[1164] Morin and Tresca *Détermination du coefficient d'élasticité de l'aluminium* Annales des mines, T XVIII, pp 63–6 Paris, 1860 This is an extract from the *Annales du Conservatoire des arts et métiers*, No 2, presumably of the same year

The authors after referring to the experiments of von Burg on the absolute strength of aluminium and aluminium bronze consisting of 90 p c copper and 10 p c aluminium (see our Art 1162) remark that his results are not sufficient for the purposes of construction in the former material They have accordingly determined its stretch modulus They find from flexure experiments that the stretch modulus may be taken as equal to 6,757,000,000 kilogs per sq mm and that the elastic limit was reached at about 8 16 kilogs per sq mm For good iron we have $E = 20,000,000,000$ and the traction at the elastic limit 20 kilogs, while the density is about 7 7 as compared with the 2 5 of aluminium Thus the comparative serviceability of the two metals is indicated

[1165] William Fairbairn *Experiments to determine the Properties of some mixtures of Cast Iron and Nickel* Memoirs of the Literary and Philosophical Society of Manchester Vol XV, pp 104–112 Manchester, 1860 This memoir read March 2, 1858, gives the results of experiments on the resistance to flexure of a mixture of cast iron and 2 5 p c of nickel This investigation was undertaken owing to

¹ Wertheim found for the absolute strength of steel wire 96 to 100 kil. per sq mm, and for iron wire 62 to 50 thus the value for aluminium bronze 64 59 is a little less than that of very strong iron

² See also *Repertory of Patent Inventions*, London, Vol 32, p 106

the fact that this percentage of nickel had been found in meteoric iron, which is "above all other, the most ductile." The ingots prepared, however, for these experiments were found to be widely different; for their "power to resist impact" was nearly one half less than those composed of pure iron. In this memoir the "power to resist impact" is, as in that discussed in our Arts. 1098-9, measured by the product of ultimate deflection and rupture load. The general result of two series of experiments is that the admixture of nickel reduces the strength of the cast-iron: see our Art. 1189.

[1166.] W. M. Ellis: *Results of Experiments on the Tensile Strength of Copper, Iron, Gun Metal, Yellow Metal and Bolts. The Artizan*, Vol. XVIII., p. 124. London, 1860. This is merely a table of the numerical results of experiments made by Ellis for the United States Government. The exact nature of the metals is not stated. As mean results for tensile strength we find:

Copper.....	36,000 lbs. per sq. inch,
Iron.....	52,250 " "
Gun metal (9 copper, 1 tin)	17,400 " "
Yellow metal (19 copper, 6 spelter)....	48,700 " "

[1167.] *Einige Bemerkungen zur Tragfähigkeit hölzerner Balken. Zeitschrift für Bauhandwerker*, Jahrgang 1860, S. 161-5. This paper gives some details of the best methods of cutting beams out of the tree, having regard to the variation of strength with the direction of the axis of the beam. It considers further the most advantageous forms of simple wooden trusses, etc.

[1168.] Vicat: *Mémoire sur l'emploi des ciments éventés comparés aux ciments vifs suivi de quelques observations sur les ciments brûlés ou cuits jusqu'à ramollissement. Annales des ponts et chaussées, Mémoires* 1851, 1^{er} semestre, pp. 236-254. Paris, 1851. This paper gives some interesting practical details of the cohesion, absolute strength, etc., of various kinds of cements before and after immersion in water for various periods of time.

[1169.] J. M. Rendel: *Experiments on the relative Resistance to 'compression' of Portland and Roman Cement, etc. Institution of Civil Engineers. Minutes of Proceedings*, Vol. XI., pp. 497-502. London, 1851-2. This contains further experiments on the 'adhesive', 'cohesive', and 'cross-strain' strengths of cement. The paper is printed as an appendix to one by G. F. White on the subject of Portland cements. It deals solely with the strength of these cements under various kinds of stress, and has only practical value.

[1170.] J. Manger: *Untersuchungen über die Festigkeit von reinen und gemischten Cementen. Erbkams Zeitschrift für Bauwesen. Jahrgang* IX., S. 523-34. Berlin, 1859.

This paper gives details of the strengths of Medina and Portland

cement Specimens in the shape of small bars only 4" long between the supports were tested by flexure I doubt the possibility of calculating by use of the Bernoulli-Eulerian formula the absolute strength from flexure experiments in which the length of the bar was not even four times the diameter, even if we suppose stress proportional to strain up to rupture For the rest Manger's numerical results have no permanent interest He concludes his memoir with a number of results as to the time various kinds of cement take to become hard.

[1171] Tacke *Versuche über die Festigkeit thönerner Röhren gegen inneren Wasserdruck Hannöversche Bauzeitung (Architecten- u Ingenieur-Verein)* S 308 Hannover, 1854

This is an interesting experimental paper on the internal pressure at which earthenware pipes burst. The pipes were tested by water pressure, either 'dry', that is without previous soaking, or 'wet', that is after soaking for four days in warm water, they were from 2 to 3 feet long, 2 to 9 inches diameter and $1\frac{1}{8}$ down to $\frac{1}{2}$ inch thickness In the case of some materials the strength of the pipes was enormously reduced by the process of soaking, in others it did not appear to have much influence. The following are some of the results

	Substance of Pipe	Length in feet.	Diameter in inches.	Thickness in inch.	Condition.	Bursting Pres- sure in Cologne pounds* per sq inch.
1	{ Ordinary glazed } { earthenware }	2	4	$\frac{5}{8}$	dry	94
2	" "	2	6	$\frac{5}{8}$		46
3	" "	2	4	$\frac{11}{16}$,	110
4	{ 'Porphyrmasse' } { burnt without glaze }	3+	2	$1\frac{1}{8}$	"	142
5	" "	3	3	$\frac{1}{2}$		230
6	" "	3	4	$\frac{1}{2}$		122
	(had two supporting rings)					
7	Same as (5)	3	3	$\frac{1}{2}$	wet	242
8	'Chamottthon' (ra- ther porous and yellow glaze)		6	$\frac{1}{2}$		45
9	" "		4	$1\frac{1}{2}$	dry	166
10	" "		3			90
11	{ Same material, } { black glaze }		9	$1\frac{1}{2}$	wet	42 (T. d.)
12			6		dry	112
13			4	$\frac{3}{4}$		102
14			6		wet	10
15			4	-		34

* A Cologne lb = 500 grammes

+ Saxon feet the other appear to be in inches

These results might be useful in testing how far the theory of our Arts. 1012*-1013*, footnote, may be applied to rupture. The writer concludes that pipes of more than 6" diameter ought to be made of cast-iron.

[1172.] Kraft: *Ueber die nothwendige Stärke thönerner Wasserleitungsröhren*. *Polytechnisches Centralblatt*, Jahrgang 1859, Cols. 1445-6. Leipzig, 1859. (Extracted from the *Gewerbeblatt aus Württemberg*, 1859, Nr. 30.) This paper gives an empirical formula for the thickness of the sides of pipes, which is said to be based on experiments made in Ravensburg on pipes for the water supply. The formula, which is accompanied by a numerical table, is the following:

$$d = \frac{1}{2} w (a + 1),$$

where d is the thickness of the side of the pipe in *lines* (*Linien*), w is the internal diameter (*Lichtweite*) in inches (*Zoll*) and a is the internal water pressure in inches.

[1173.] *Institution of Civil Engineers, Minutes of Proceedings*, Vol. xix., p. 276. London, 1859-60. Some details of experiments on the power of bricks to resist a crushing force will be found in an Appendix to a paper on the Netherton Tunnel.

[1174.] *Lateral Strength of Stone*. *The Civil Engineer and Architect's Journal*, Vol. xiii., pp. 269-270. London, 1850. Some account of experiments made in 1848 for Chester Railway Station on the flexural strength and ultimate deflection of slate and stone are here recorded. Only unreduced numerical results are given.

[1175.] W. R. Johnson: *Comparison of Experiments on American and Foreign Building Stones to determine their relative Strength and Durability*. *Silliman's American Journal of Science and Arts*. Second Series, Vol. xi., pp. 1-17. New Haven, 1851.

This memoir contains a general *résumé* of European investigations on the crushing strength of various kinds of stone together with accounts of experiments by C. G. Page, Dougherty and R. Mills on American stones. The American experiments were made on 2" cubes, and the absolute crushing strengths as well as those relative to alum sandstone taken as 100 are recorded. Good tables in English measure are given of the results of Rennie (see our Arts. 185*-6*), Daniel and Wheatstone, W. Wyatt in England; Rondelet (see our Art. 696*), Gauthey, Soufflot and Perronet (see our Art. 28* (ξ)) in France. See especially pp. 14-15 of the memoir. Noting the discordance of the results obtained, Johnson concludes that the resistance to crushing must be some function of the number of units in the base of the column crushed, increasing with that number. He suggests the following law:

That the crushing strength of a cube varies as the product of the area of the base into the cube root of that area.

He tests this law by some ten cases, which he remarks do not conclusively prove it, but afford "a pretty strong presumption in its favor" (p 17)

[1176] Mohn *Versuche über das Gleichgewicht und die rückwirkende Festigkeit von natürlichen Bausteinen* Notizblatt des Architekten und Ingenieur-Vereins, Bd 1, S 360 Hannover, 1853

This paper contains details of experiments on the crushing strength of stone cubes, the sides of which were four Hannoverian inches long In order to test the stones in a frozen condition some were placed in warm water and after becoming saturated submitted to a frost of 10° R. for several days In some cases the strength appears to have been somewhat decreased by this freezing process, but no general law is obvious The numerical results are somewhat irregular and have little more than local and temporal interest

[1177] Hodgkinson *On the Elasticity of Stone and Crystalline Bodies* British Association, Report of Hull Meeting 1853, *Transactions*, pp 36-37 Hodgkinson refers again to the "defect of elasticity" in stone and cast-iron It is not quite obvious what he means by "defect," but it is I imagine 'set' and not perfect elasticity with "defect of Hooke's Law" See our Arts 969*, 1411* and Vol 1 p 891 He refers to Lamé's "profound work" and remarks that its results do not apply to the bodies of which he is speaking—some of which are of primary technical importance

[1178] *Strength and Density of Building Stone* The Edinburgh New Philosophical Journal, Vol LVII, p 371 Edinburgh, 1854 A few numerical details of the crushing strengths of sandstones, marbles and granites, extracted from a report on experiments made at Washington, U S, are here published

[1179] Michelot *Recherches statistiques sur les matériaux de construction employés dans le département de la Seine* Annales des ponts et chaussées, *Mémoires* 1855, 2^e semestre, pp 189-212 Paris, 1855 This is only a report by Belgrand on a long memoir by Michelot, which as far as I am aware was never published It refers on p 209 to some experiments on the crushing of stone

[1180] Henry *On the Mode of testing Building Material and an account of the Marble used in the Extension of the United States Capitol* Silliman's American Journal of Science and Arts, Vol 22 pp 30-55 New Haven, 1856 (Extracted from the *Proceedings of the American Association for the Advancement of Science*, August, 1855, *Provisional Meeting*) This paper describes the apparatus used by an American Commission to test the marble used in extending the Capitol There is

e that calls for general note here, except perhaps the statement on 3 that in crushing cubes the manner in which the ends are bedded fundamental factor in the apparent crushing strength. If the bases he cube are free to expand, as is approximately the case if they bedded on thin plates of lead, the crushing strength appears far than if they be bedded on steel.

For example, one of the cubes, precisely similar to another which stood a pressure of upwards of 60,000 lbs. when placed in immediate contact with the steel bed-plates, gave way at about 30,000 lbs. a lead interposed. This remarkable fact was verified in a series experiments, embracing samples of nearly all the marbles under trial, in no case did a single exception occur to vary the result.

Some remarks on cohesion and molecular attraction with which the air closes do not seem very lucid (pp. 36—38).

[1181.] A. Brix: *Zerdrückungs-Versuche zur Ermittlung der wirkenden Festigkeit verschiedener Bausteine. Verhandlungen des Vereins zur Beförderung des Gewerbfleisses in Preussen, 1855, Lief. 2. Polytechnisches Journal, Bd. 137, pp. 393—4. Stuttgart, 1855.* This paper gives details of the crushing strength of various kinds of man stone. The loads at cracking and at crushing are given in each case. Details of earlier experiments by Brix will be found in the *Verhandlungen* 1853, S. 1, 137, 203, and in the *Polytechnisches Journal* 1853, Cols. 1308—9.

[1182.] W. Fairbairn: *On the Comparative Value of various kinds of Stone, as exhibited by their Powers of Resisting Compression. Memoirs of the Manchester Literary and Philosophical Society, Vol. 14, pp. 31—47. Manchester, 1857.* This memoir was read April 1, 1856. It contains numerical values for the crushing loads of various kinds of granite, limestone and sandstone, and a comparison of these results with those of Rennie for stone, Hodgkinson for stone and wood, James Clarke for brickwork, and Fairbairn himself for cast-iron: see Arts. 185*, 1445* and 953*.

There are three plates of rupture-surfaces. While the sandstones fractured in wedges, the limestones formed longitudinal cracks or cleavages. The strength of stone was about as "10 to 8 in favour of the stone being crushed upon its bed to the same when crushed he line of cleavage." This applied to both sandstone and limestone (39).

[1183.] Knight: *Strength of Building Stone. The Builder, Vol. II., p. 579. London, 1860.* Details are given in this paper of the crushing strengths of various colonial building stones; they are taken from a treatise by Knight, presumably published in Victoria. Some account of experiments on the transverse strength of stone are also given.

[1184] G Cavalli *Memoria sul delineamento equilibrato degli Archi in muratura e in armatura Memorie dell' Accademia di Torino, Serie Seconda, Tomo XIX, pp 143-200 Turin, 1861* This memoir was read in 1858 It contains on pp 183-7 values of the crushing strengths of a very great variety of Italian stones

GROUP H

Miscellaneous Minor Memoirs on topics related to the Strength of Materials

[1185] Bolley *Ueber das Krystallwuchs und Sprosswerden des Schmiedeeisens durch fortgesetzte Erschütterungen Dinglers Polytechnisches Journal, Bd 120, S 75-7 Stuttgart, 1851* Extracted from *Schweizerisches Gewerbeblatt* 1850, No 5 This contains evidence in favour of the change of wrought-iron from the fibrous to the crystal line (*kornig*) condition by repeated impacts

[1186] P W Brix *Ausdehnung des Gusseisens bei wiederholtem Erhitzen Mittheilungen des Gewerbe Vereins für das Königreich Hannover, Neue Folge, Jahrgang 1853, Cols 214-5 Hannover, 1853*

This short extract from a work on fuel by Brix contains some interesting statements with regard to the set produced in cast-iron bars by heating them The fact that cast iron after heating does not return to its old volume was first noted by Prinsep in the *Edinburgh Journal of Science*, Vol x, pp 356-7, 1829 Brix found that by continually heating a cast iron bar there was after each heating more set, but in decreasing increments The thermal set appears in this to resemble after strain Set produced by heating in a moderate fire 17 and more days gave an extension of 2 to 3 p c This fact deserves further investigation as its physical and practical consequences seem of much interest

[1187] L Dufour *Tenacite des fils metalliques qui ont ete par courus par des courants voltaïques Bibliotheque universelle de Geneve Archives des sciences physiques et naturelles, T 27, pp 156-8 Geneve, 1854*

Wertheim had noted the change in the stretch modulus produced by sending an electric current through a loaded wire see our Art 1306* Dufour proposes to investigate the changes in absolute strength, if any, produced by passing a current for a long time

rough a wire. His results are not very conclusive. He finds a loss of strength in copper and a slight gain of strength in iron wire, the currents having run as long as 19 days. A much greater number of experiments would have to be undertaken to reach results of real value.

[1188.] Florimond: *Note sur les aimants de fer de fonte trempée et sur la fragilité des fils de laiton exposés à l'air sous l'influence de certaines variations de température. Bulletin de l'Académie Royale de Belgique*, 2^{me} Série, T. VII., pp. 368–71. Bruxelles, 1859.

This paper merely puts on record that in 1848 “après quelques jours gelée suivi d'un brouillard” the brass wires which bind the telegraph wires ruptured and the pieces falling to the earth broke into small pieces of excessive fragility. In 1858 a similar phenomenon occurred with the brass ropes which worked the bells at the church of St Pierre Louvain. Attempts to reproduce the phenomenon artificially failed. Florimond inquires what may be the peculiar crystallisation or disintegration produced by these atmospherical changes in brass.

[1189.] Bri-Brachion (? Sir W. Armstrong): *The Cause and Prevention of the Deterioration of Wrought-Iron. The Chemical News*, vol. II., pp. 183–4. London, 1860.

The author cites the fact that iron crystallises in cubes or octahedrons, and states his belief that such crystallisation takes place without melting and slow cooling, namely by the influence of frequently repeated vibrations. He quotes two French chemical writers on this effect (Pelouze and Frémy) and refers to the stock examples of railway axles and steam boilers. He then remarks that any impurity tends to hinder crystallisation. Hence he considers pure iron should not be used for structures subjected to frequent vibrations. To test whether iron is pure or not, he suggests magnetisation, pure iron losing immediately its magnetisation, but impure iron retaining it. He has himself tried as ‘impurities’ carbon, manganese, cobalt, zinc, bismuth, tin and nickel, but his experiments lead him to believe that nickel is the most efficient, as it is not removed in the puddling process. As an example of the unsatisfactory nature of pure iron, he gives an experiment with a pure iron bar which was successfully tested with 80 lbs. before being submitted to vibration, but after the vibratory experiment it broke with a ‘highly crystalline fracture’ in three pieces simply falling to the ground. Compare our Art. 1165.

[1190.] W. Lüders: *Ueber die Aeusserung der Elasticität an elastischen Eisenstäben und Stahlstäben und über eine beim Biegen dieser Stäbe beobachtete Molecularbewegung: Dinglers Polytechnisches Journal*, Bd. 155, S. 18. Stuttgart, 1860. *Polytechnisches Centralblatt*, Organ 1860, Cols. 950–4. Leipzig, 1860. Lüders had noted that Magdeburger bar-iron and on various soft kinds of cast-steel the surface after flexure is covered by a network of orthogonal systems

of curves These curves by means of a weak solution of nitric acid could be etched, and this process even repeated after several filings of the surface At the same time these lines only exhibit themselves at places where the material has received great strain Similar *Luders' Curves* were shown to the Editor on I-bars of wrought iron a few years ago¹, and apparently corresponded very nearly with the lines of strain in beams under flexure as figured in the text-books It would appear then that if a bar be bent beyond the elastic limit mechanical changes take place along the lines of strain and exhibit themselves in a system of orthogonal curves on the scale at the surface of the beam, or even further in, if the strain has been great, and acid be applied. Lüders attributes these curves to a *Molekularbewegung*, but does not associate them with the lines of strain He had in one specimen found a third system of curves diagonal to the rectangular elements of the other two He had observed these curves of strain after flexure in bars of pure tin (*tesserales Form*)

[1191] *Summary* The decade with which we have been dealing in this chapter is one of the most fruitful in the history of elastic theory and practice Besides the large number of memoirs which have been dealt with in the last five hundred pages, it must be remembered that several of the most important publications of Lamé, of Saint-Venant and of the older German elasticians, considered in previous chapters or in the following chapter of our *History*, really date from this period. Nor is the advance confined to any one branch of our subject There is to be noted the beginnings of a real union between theory and technical practice in France and Germany, which has continued to bear fruit even to the present day, when its full value is also being realised in England by the establishment of numerous technical schools in which instruction in the strength of materials is given and research is scientifically carried on In the department of physical elasticity we have to note that while great progress was made in the collection of facts, there was still too wide a divorce between theory and experiment This is very obvious in the elaborate physical researches of Kupffer and Wertheim Yet while these and other investigators to some extent failed to conduct their experimental inquiries in the

¹ Still more recently Mr J B Hunter, M I C E has sent me some splendid photographs and specimens of Luders curves produced by rust round holes punched in the steel plates of dredger buckets see frontispiece to Part II I look forward to these curves being used as a powerful mode of graphically analysing strain

anner best calculated to advance scientific theory, they undoubtedly by their researches in such branches as thermo-elasticity, after-strain, and magneto-elasticity gave a great impulse further theoretical and physical work. The development in this period of our knowledge of the physical properties of elastic materials showed the insufficiency of much of the accepted elasticity theory, but for the establishment of a truer and more comprehensive theory we shall probably have to wait until we gain a wider acquaintance with the nature of intermolecular action and the part played by the ether in varying and adjusting that action.

In the technical researches of the period we find that the special problems of bridge structure and gun-making, notably the introduction of lattice-girders and composite cannon, largely influenced the direction of investigation, and incidentally led to the discovery of many important physical properties of iron and steel. On the technical side the researches of Bresse, Phillips and Kirkaldy form each in their peculiar fields models of what investigation in technical elasticity should be, and emphasise the special merits of the French and English systems of engineering training. In the sphere of terminology a great service was rendered by Rankine owing to his introduction or precise definition of a number of useful names for important elastic coefficients and conceptions. On the whole while the number of memoirs published was alarmingly great, the proportion which may be classified as absolutely worthless is extremely small. In many cases they contain important facts which have been forgotten in later decades only in order to be rediscovered in recent times. This is largely owing to the want of any easily accessible record.

Cambridge

PRINTED BY C J CLAY, M A AND SONS,

AT THE UNIVERSITY PRESS